

STORMWATER MANAGEMENT GUIDEBOOK

February 2019

DRAFT FOR PUBLIC COMMENT



PROPOSED PRINCIPAL PROPOSED PR

Prepared Under:

Grant No. 2015-1508-WPD

Grant No. 2018-1819-SWR

Prepared for:

District Department of the Energy and Environment Watershed Protection Regulatory Review Division

DISTRICT OF COLUMBIA

1200 First Street NE Washington, DC 20002 https://doee.dc.gov/

Prepared by:

Center for Watershed Protection, Inc.

8390 Main Street

3290 North Ridge Road, Suite 290 Ellicott City, MD 21043





PROPOSED PERIOD



PROPOSED PER IIIS ION

Acknowledgements

A major undertaking such as this requires the dedication and cooperative efforts of many individuals. Dr. Hamid Karimi, former Deputy Director of Natural Resources; Sheila Besse, former-Associate Director of Watershed Protection; Jeff Seltzer, former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-ManagementNatural Resources; and Timothy Karikari, Branch Chief of former-Management

Project Manger

Rebecca C. Stack, DDOE formerly DOEE-Technical Services

Julienne Bautista, DOEE-Building Permit Plan Review

James Dunbar, DOEE-Building Permit Plan Review

Lead Authors

Greg Hoffmann, P.E., Center for Watershed Protection

Rebecca C. Stack, DDOE formerly DOEE-Technical Services

Brian Van Wye, DDOE Stormwater Management DOEE-Regulatory Review

Editor

Laura Gardner, P.E., Center for Watershed Protection

Editors

Sherry Schwechten, DDOE Stormwater Management formerly DOEE-Natural Resources Administration

Scott Drew, DOEE-Natural Resources Administration

Geoffrey Brown, DOEE-Natural Resources Administration

Contributors and Peer Reviewers

Joseph Battiata, P.E., formerly Center for Watershed Protection

Erik Bethke, formerly DOEE-Regulatory Review Division

Evan Branosky, DDOEformerly DOEE-Stormwater Management

Gerald Brock, Ph.D., George Washington University

Josh Burch, DDOE Planning and DOEE-Restoration

Collin R. Burrell, DDOE Water Quality

Walter Caldwell, DDOEDOEE-Inspection and Enforcement

Walter Caldwell, DOEE-Inspection and Enforcement

Jonathan Champion, DDOE Stormwater Management DOEE-Planning and Reporting

Reid Christianson P.E., Ph.D., formerly Center for Watershed Protection

Laine Cidlowski, DC Office of Planning

Luke Cole, formerly DOEE-Water Quality Division

Richard DeGrandchamp, Ph.D., University of Colorado/Scientia Veritas

Elias Demessie, DOE-Technical Services P.E., CFM, DOEE-Building Permit Plan Review

Rebecca Diehl, DOEE-Water Quality Division

Diane Douglas, DDOE Water Quality DOEE-Standards and TMDLs

Clara Elias, DOEE-Watershed Protection Division

Matthew Espie, DDOE Stormwater Management-DOEE-Water Resource Protection and Mitigation

Erin Fenton, formerly DOEE

Alex Forasté, Williamsburg Environmental Group, Inc.

Laura Gardner, Center for Watershed Protection

Matt Johnson, DOEE-Regulatory Review Division

Timothy Karikari, P.E., CPESC, CFM, DDOE Technical Services DOEE-Building Permit Plan Review

Melissa Keeley, Ph.D., George Washington University

Tim Klien, DDOEformerly DOEE-Inspection and Enforcement

Cecilia Lane, DOEE-Restoration

Sarah Lawson, Ph.D., Rainwater Management Solutions

Leah Lemoine, DDOE formerly DOEE-Planning and Restoration

Susan Libes, Ph.D., Coastal Carolina University, Conway, SC

Kelly (Collins) Lindow, P.E., (formerly Center for Watershed Protection)/RK&K

Dennis Lye, Ph.D., US EPA

Massoud Massoumi, DDOE Technical Services DOEE-Building Permit Plan Review

Abdi Musse, P.E., DDOE Technical Services DOEE-Building Permit Plan Review

Lillian Peterson, formerly DOEE-Inspection and Enforcement Division

Phetmano Phannavong, P.E., C.F.M., DDOE Technical Services DOEE-Water Resource Protection and Mitigation

Philip C. Reidy, P.E., Geosyntec Consultants

Stephen Reiling, DDOE Planning and DOEE-Restoration

PROPOSED PREVIOUS PROPOSED PRO $\underline{\textbf{Emily Rice, } \underline{\textbf{DDOE Stormwater Management}}\underline{\textbf{DOEE-Partnering and Environmental Conservation}}$

Tom Schueler, Chesapeake Bay Stormwater Network

Jeff Seltzer, P.E., DOOE Stormwater Management DOEE-Water Quality

Tanya Spano, MWCOG-Water Resources

Bill Stack, P.E., Center for Watershed Protection

 $Meredith\ Upchurch,\ \underline{formerly\ }DDOT\text{-}Stormwater$

Matt Watkins, DOEE-Inspection and Enforcement Division

June M. Weintraub, ScD, San Francisco Department of Public Health

PROPOSED PENISION PROPOSED PRO

Preface

Technical information and notices regarding future-updates to the District of Columbia Stormwater Management Guidebook will be available at

http://ddoe.dc.gov/publication/stormwater_guidebook. Notices regarding future versions of the manual will be posted on this website. Future versionshttps://doee.dc.gov/swguidebook. Revisions are expected to occur, at most, once aper year.

PROPOSED PENISION PROPOSED PRO

Contents

Acknowledgements	vi
Preface —ix	
List of Tables - xxxii	
List of Figures xxxvi	
List of Equations	xliii
Chapter 1 Introduction to the Stormwater Management Guidebook	1
1.1—Introduction	1
1.2 Purpose and Scope	1
1.3 Impacts of Urban Runoff	2
1.3.1—Hydrologic Impacts	2
1.3.2 Water Quality Impacts	4
1.4 References	6
Chapter 2 — Minimum Control Requirements	
2.1—District of Columbia Stormwater Management Performance Requirements	
2.2 Stormwater Retention Volume	
2.3 Water Quality Treatment Volume	
2.4 from eachdrainage areaseparate sewer syste eachdrainage areaModeslExtreme	
Requirements	
2.5 Minimum Criteria for Determining Extreme Flood Requirements	40
2.6 Additional Stormwater Management Requirements	41
2.7 Acceptable Urban BMP Options	49
Chapter 3 Stormwater Best Management Practices (BMPs)	54
3.1—Standard Best Management Practice Design Guidance Format	
3.2 Green Roofs	55
3.2.1 Green Roof Feasibility Criteria	55
3.2.2 Green Roof Conveyance Criteria	57
3.2.3 Green Roof Pretreatment Criteria	57
3.2.4 Green Roof Design Criteria	 57
3.2.5 Green Roof Landscaping Criteria	65
3.2.6 Green Roof Construction Sequence	
3.2.7 Green Roof Maintenance Criteria	69
3.2.8 Green Roof Stormwater Compliance Calculations	70

3.2.9	References	 71
3.3 Ra	inwater Harvesting	 73
3.3.1	Rainwater Harvesting Feasibility Criteria	 75
3.3.2	Rainwater Harvesting Conveyance Criteria	 78
3.3.3	Rainwater Harvesting Pretreatment Criteria	 78
3.3.4	Rainwater Harvesting Design Criteria	81
3.3.5	Rainwater Harvesting Landscaping Criteria	 96
3.3.6	Rainwater Harvesting Construction Sequence.	96
3.3.7	Rainwater Harvesting Maintenance Criteria	97
3.3.8	Rainwater Harvesting: Stormwater Compliance Calculations	99
3.3.9	References	99
	pervious Surface Disconnection	
	Impervious Surface Disconnection Feasibility Criteria	
3.4.2	- Impervious Surface Disconnection Conveyance Criteria	108
	Impervious Surface Disconnection Pretreatment Criteria	
3.4.4	Impervious Surface Disconnection Design Criteria	108
3.4.5	Impervious Surface Disconnection Landscaping Criteria	111
3.4.6	Impervious Surface Disconnection Construction Sequence	112
3.4.7	Impervious Surface Disconnection Maintenance Criteria	113
3.4.8	Impervious Surface Impervious Surface Disconnection Stormwater Complian	
	Calculations	114
3.4.9	References	115
	rmeable Pavement Systems	
3.5.1	Permeable Pavement Feasibility Criteria	119
3.5.2	Permeable Pavement Conveyance Criteria	122
3.5.3	Permeable Pavement Pretreatment Criteria	122
3.5.4	Permeable Pavement Design Criteria	122
3.5.5	Permeable Pavement Landscaping Criteria	130
3.5.6	Permeable Pavement Construction Sequence	131
3.5.7	Permeable Pavement Maintenance Criteria	136
3.5.8	Permeable Pavement Stormwater Compliance Calculations	138

3.5.9	References	139
3.6 Bi	oretention	141
3.6.1	Bioretention Feasibility Criteria	144
3.6.2	Bioretention Conveyance Criteria	147
3.6.3	Bioretention Pretreatment Criteria	149
3.6.4	Bioretention Design Criteria	151
3.6.5	Bioretention Landscaping Criteria	168
3.6.6	Bioretention Construction Sequence	172
3.6.7	Bioretention Maintenance Criteria	175
3.6.8	Bioretention Stormwater Compliance Calculations	177
3.6.9	References	178
3.7 Fi	Itering Systems	181
3.7.1	Filtering Feasibility Criteria	190
3.7.2	Filtering Conveyance Criteria	191
3.7.3	Filtering Pretreatment Criteria	191
3.7.4	Filtering Design Criteria	192
3.7.5	Filtering Landscaping Criteria	197
3.7.6	Filter Construction Sequence	197
	Filtering Maintenance Criteria	
3.7.8	Filtering Volume Compliance Calculations	201
3.7.9	References	201
3.8 In:	filtration	203
3.8.1	—Infiltration Feasibility Criteria	206
3.8.2	—Infiltration Conveyance Criteria	208
3.8.3	Infiltration Pretreatment Criteria.	208
3.8.4	Infiltration Design Criteria	209
3.8.5	Infiltration Landscaping Criteria.	213
3.8.6	—Infiltration Construction Sequence	214
3.8.7	Infiltration Maintenance Criteria	216
3.8.8	Infiltration Stormwater Compliance Calculations	217
3.8.9	References	218

3.9 Open Channel Systems	219
3.9.1 Open Channel Feasibility Criteria	222
3.9.2 Open Channel Conveyance Criteria	225
3.9.3 Open Channel Pretreatment Criteria	225
3.9.4 Open Channel Design Criteria	226
3.9.5 Open Channel Landscaping Criteria	235
3.9.6 Open Channel Construction Sequence	236
3.9.7 Open Channel Maintenance Criteria	238
3.9.8 Open Channel Stormwater Compliance Calculations	241
3.9.9 References	242
3.10 Ponds	
3.10.1—Pond Feasibility Criteria	248
3.10.2—Pond Conveyance Criteria	
3.10.3 Pond Pretreatment Criteria	251
3.10.4 Pond Design Criteria	251
3.10.5 Pond Landscaping Criteria	
3.10.6 Pond Construction Sequence	257
3.10.7—Pond Maintenance Criteria	259
3.10.8 Pond Stormwater Compliance Calculations	261
3.10.9—References	261
3.11—Stormwater Wetlands	264
3.11.1—Stormwater Wetland Feasibility Criteria	266
3.11.2 Stormwater Wetland Conveyance Criteria	268
3.11.3 Stormwater Wedand Pretreatment Criteria	269
3.11.4 Stormwater Wetland Design Criteria	269
3.11.5 Stormwater Wetland Construction Sequence	272
3.11.6 Stormwater Wetland Landscaping Criteria	275
3.11.7—Stormwater Wetland Maintenance Criteria	279
3.11.8 Stormwater Wetland Stormwater Compliance Calculations	281
3.11.9 References	282
3.12 Storage Practices	283

3.12.1—Storage Feasibility Criteria	285
3.12.2—Storage Conveyance Criteria	287
3.12.3 Storage Pretreatment Criteria	288
3.12.4 Storage Design Criteria	289
3.12.5—Storage Landscaping Criteria	2 91
3.12.6 Storage Construction Sequence	291
3.12.7—Storage Maintenance Criteria	293
3.12.8 Storage Volume Compliance Calculations	295
3.12.9 References	295
3.13 Proprietary Practices	297
3.13.1—Proprietary Practice Feasibility Criteria	
3.13.2 Proprietary Practice Conveyance Criteria	297
3.13.3 Proprietary Practice Pretreatment Criteria	297
3.13.4 Proprietary Practice Design Criteria	297
3.13.5 Proprietary Practice Landscaping Criteria	298
3.13.6 Proprietary Practice Construction Sequence	298
3.13.7—Proprietary Practice Maintenance Criteria	298
3.13.8 Proprietary Practice Stormwater Compliance Calculations	299
3.14 Tree Planting and Preservation	301
3.14.1—Preserving Existing Trees During Construction	301
3.14.2—Planting Trees	303
3.14.3 Tree Inspection Criteria	309
3.14.4 Tree Maintenance Criteria	309
3.14.5 Tree Stormwater Compliance Calculations	310
3.14.6 References	311
<u>Chapter 4</u> <u>Selecting and Locating the Most Effective Stormwater Best Management Pract</u> 315	i ce System
4.1 Choosing Stormwater Management Best Practices (BMPs)	315
4.2 Regulatory Compliance	
4.3 Land Use Factors	
4.4 Physical Feasibility Factors	
4.5 Community and Environmental Factors	3 22

4.6 Location and Permitting Considerations	327
4.7 References	329
Chapter 5 Administration of Stormwater Management Rules	330
5.1 Administration	Error! Bookmark not defined.
5.1.1 Approval Requirements	Error! Bookmark not defined.
5.1.2 Fees	Error! Bookmark not defined.
5.2 Stormwater Management Plans	Error! Bookmark not defined.
5.2.1 Submittal and Review Process of Stormwater Mo	anagement PlansError!
Bookmark not defined.	
5.2.2 SWMP Submittal Documents	Error! Bookmark not defined.
5.2.3 SWMP Components	Error! Bookmark not defined.
5.2.4 Resubmission of Stormwater Management Plans	346
5.3 Construction Inspection Requirements	348
5.3.1 Inspection Schedule and Reports	348
5.3.2 Inspection Requirements Before and During Con	astruction 349
5.3.3 Final Construction Inspection Reports	351
5.3.4 Inspection for Preventive Maintenance	351
5.4 Maintenance	352
5.4.1 Maintenance Responsibility	352
5.4.2 Maintenance Agreement	353
5.5 Exemptions	
5.6 Supporting Forms	354
Chapter 6 Use of Off-Site Retention by Regulated Sites	305
6.1 Off Site Retention Overview	305
6.2 Off Site Retention via Stormwater Retention Credits	308
6.3 Off Site Retention via In Lieu Fee	311
6.4 Forms for Use of Off-site Retention	312
Chapter 7 Generation, Certification, Trading, and Retirement o	f Stormwater Retention Credits 313
7.1 Stormwater Retention Credits Overview	313
7.2 Eligibility Requirements	313
7.2.1 Eligibility Requirements: Retention Volume	316
7.2.2 Eligibility Requirements: Design and Installation	318
7.2.3 Eligibility Requirements: Inspection	319

7.2.4 Eligibility Requirements: Maintenance	319
7.3 Certification of Stormwater Retention Credits	319
7.4 Format of SRC Serial Numbers	322
7.5—Failure to Maintain Retention after Certification of Stormwater Retention Cre	dits 322
7.6—Buying and Selling Stormwater Retention Credits	323
7.7 Voluntary Retirement of Stormwater Retention Credits	323
7.8—Quitting the Obligation to Maintain Retention for Stormwater Retention Cred	its323
7.9 Calculation of Stormwater Retention Credits	324
7.11—Stormwater Retention Credit Calculation Scenarios	329
7.12—Forms for Stormwater Retention Credits	339
Appendix A Compliance Calculations and Design Examples	A-1
A.1 Stormwater Database and General Retention Compliance Calculator Error!	ookmark
not defined.	
A.2 Stormwater Database Instructions Error! Bookmark no	
A.3 General Retention Compliance Calculator Instructions	
A.4 Design Examples	
Appendix B—Maximum Extent Practicable Process for Existing Public Right of Way	
B.1—Maximum Extent Practicable: Overview	
B.2—Public Right of Way Projects	B-1
B.3 Codes.	B-4
B.4 PROW Design Considerations	B-5
B.4.1—Considerations in the Planning Process (limited to Type 1)	B-5
B.4.2 Site Assessment Considerations for the Retention Standard in PROW Pro	jectsB-5
B.4.3 Fundamental Tenets of MEP for PROW	B-10
B.4.4 Minor Disturbances in the PROW Error! Bookmark no	t defined.
B.4.5 Potential Design Modifications for Infiltration Based PROW BMPs	Error!
Bookmark not defined.	
B.5—Design Process for PROW	B-12
B.6 Summary of MEP Type 1 Submission Process	B-17
B.7—References	
Appendix C Off-Site Retention Forms for Regulated Sites	
Appendix D—Stormwater Retention Credit Forms (Certification, Trading, and Retirement)	D-1
Appendix E Relief for Extraordinarily Difficult Site Conditions	E-1
E.1—Relief from Extraordinarily Difficult Site Conditions	E-1

E.2—Submission requirements for Relief from Extraordinarily Difficult Site Conditions.	E-2
E.3 Review of Requests for Relief from Extraordinarily Difficult Site Conditions	E-4
Appendix F Stormwater Conveyance System Design	F-1
F.1—Introduction	F-1
F.2—Clearance with Other Utilities	F-1
F.3—Design of Stormwater Conveyance Systems	F-1
F.4 Gutters	F-2
F.5 Inlets	F-3
F.6 Street Capacity (Spread)	.F-3
	F-3
F.8 Open Channels	.F-4
F.9 Pipe Systems	
F.10 Culverts	F-6
F.11—Hydraulic Grade Line	
F.12 Manholes and Inlets	
Appendix G Design of Flow Control Structures	
G.1—Design of Flow Control Structures	
G.1.1—Circular Orifices	
G.1.2—Flow Under Gates	
G.1.3 Weirs	
Appendix H — Acceptable Hydrologic Methods and Models	
H.1—Acceptable Hydrologic Methods and Models	
H.2 Urban Hydrology for Small Watersheds TR 55	
H.3 Storage Indication Routing	
H.4 HEC 1, WinTR 55, TR 20, and SWMM Computer Models	
H.5—Rational Method	
H.6 Stormwater Volume Peak Discharge	
H.7—References	
Appendix I Rooftop Storage Design Guidance and Criteria	
I.1—Rooftop Storage Design Guidance and Criteria	
Appendix J Soil Compost Amendment Requirements	J-1
J.1 Introduction	
J.2 Physical Feasibility and Design Applications.	J-1
J.3—Design Criteria	J-1

J.4 Construction Sequence	J-3
J.5 Maintenance	
J.6 References	
ppendix K Construction Inspection Checklists	
ppendix L — Maintenance Inspection Checklists	
ppendix M—Rainwater Harvesting Treatment and Management F	
efined.	
M.1—Introduction	Error! Bookmark not defined.
M.2—Pathogen Reduction Targets	Error! Bookmark not defined.
M.3—Treatment Process	Error! Bookmark not defined.
M.3.1—Filtration	Error! Bookmark not defined.
M.3.2 Disinfection	Error! Bookmark not defined.
M.3.3 Treatment Trains	Error! Bookmark not defined.
M.4 Volatile Organic Compounds	Error! Bookmark not defined.
M.5 Storage and Distribution Management Practices	Error! Bookmark not defined.
M.6 Commissioning	Error! Bookmark not defined.
M.7—Operational Monitoring and Reporting	Error! Bookmark not defined.
M.8 Field Verification	Error! Bookmark not defined.
M.9 Design Report	Error! Bookmark not defined.
M.10 Treatment Design Examples	Error! Bookmark not defined.
M.10.1—Example 1: Rooftop Runoff for Landscape Irrigi	
defined.	
M.10.2—Example 2: General Runoft for Indoor Use	Error! Bookmark not defined.
M.10.3 Example 3: Roof Runoff for Cooling Towers	Error! Bookmark not defined.
M.10.4—References	Error! Bookmark not defined.
ppendix N Land Cover Designations	
N.1—General Notes	N-1
N.2 Existing Natural Cover Requirements	N-1
N.3 Planting Requirements for the Creation of Natural Co	
N.4 Stormwater Management Plans and Natural Cover	
N.5 Construction Requirements for Natural Cover Design	
N.6 Maintenance Requirements for Natural Cover Design	
N.7. Compacted Cover Designation	

Appendix O — Geotechnical Information Requirements for Underground BMPs	O-1
O.1 General Notes Pertinent to All Geotechnical Testing	O-1
O.2 Initial Feasibility Assessment	O-2
O.3 Test Pit/Boring Requirements for Infiltration Tests	O-2
O.4 Infiltration Testing Requirements	O-3
O.5—Saturated Hydraulic Conductivity Calculations	O-5
O.6 Infiltration Restrictions	O-6
Appendix P Stormwater Hotspots	P-1
P.1 Stormwater Hotspots	P-1
P.2 Stormwater Hotspot Cover Sheet	P-3
P.3 Stormwater Hotspot Checklist	P-5
P.4 Hotspot Operation Pollution Prevention Profile Sheets	P-11
H-1 Vehicle Maintenance and RepairError! Bookmark not	defined.
H 2 Vehicle FuelingError! Bookmark not	defined.
H 3 Vehicle WashingError! Bookmark not	defined.
H 4 Outdoor Materials Loading and UnloadingError! Bookmark not	defined.
H 5 Outdoor or Bulk Material Storage Error! Bookmark not	defined.
Appendix Q Pollution Prevention Through Good Housekeeping	Q-1
Appendix Q Pollution Prevention Through Good Housekeeping	
	Q-1
Q.1—Pollution Prevention.	Q-1
Q.1—Pollution Prevention	Q-1 Q-1 R-1
Q.1—Pollution Prevention	Q-1 Q-1 R-1
Q.1—Pollution Prevention	Q-1 Q-1 R-1 R-1
Q.1—Pollution Prevention	Q-1 Q-1R-1R-1R-3
Q.1—Pollution Prevention	Q-1 Q-1 R-1 R-1 R-1 R-1 R-3
Q.1 — Pollution Prevention	Q-1 Q-1 R-1 R-1 R-1 R-3 S-1
Q.1—Pollution Prevention	Q-1 Q-1 Q-1 R-1 R-1 R-1 R-3 S-1 S-1
Q.1 — Pollution Prevention	Q-1 Q-1 R-1 R-1 R-3 S-1 S-1 S-1 S-2
Q.1 — Pollution Prevention	Q-1 Q-1 Q-1 R-1 R-1 R-3 S-1 S-1 S-1 S-2 S-3
Q.1 — Pollution Prevention Q.2 — Stormwater Management Plan (SWMP) Good Housekeeping Stamp Notes	Q-1 Q-1 Q-1 R-1 R-1 R-3 S-1 S-1 S-2 S-3 S-3

Appendix T-	—Underground Sand Filter Design ExampleError! Bookmark	not defined.
Appendix U	Resources	V-1
Appendix V	Definitions	W-1
Chapter 1	Introduction to the Stormwater Management Guidebook	1
1.1 Intr	roduction	<u></u> 1
1.2 Pur	rpose and Scope	<u></u> 1
<u>1.3 Imp</u>	pacts of Urban Runoff	2
1.3.1	Hydrologic Impacts	2
1.3.2	Water Quality Impacts	4
	ferences	
	Minimum Control Requirements	
2.1 Dis	strict of Columbia Stormwater Management Requirements	<u></u> 7
2.2 Reg	gulated Site Definition and Examples	<u></u> 9
2.3 Sto	ormwater Retention Volume	18
2.4 Wa	ater Quality Treatment Volume	<u></u> 24
	equirements and Compliance Flow Charts	
2.6 Co1	ontrol of 2-Year Storm	36
2.7 Co1	ontrol of 15-Year Storm	<u></u> 39
2.8 Ext	treme Flood Requirements	<u></u> 39
2.9 Mii	inimum Criteria for Determining Extreme Flood Requirements	<u></u> 40
2.10 Hyd	drology Methods	<u></u> 41
	Iditional Stormwater Management Requirements	
2.12 Exe	emptions	43
2.12.1	Detention for Major Substantial Improvement	43
2.12.2	Disturbance for BMP Installation	<u>43</u>
2.12.3	Affordable Housing	44
2.12.4	Trails	44
2.12.5	Athletic Playing Fields, Permeable Athletic Tracks, and Permeable Play	vground
	Surfaces	
2.12.6	Small Structures at Parks	<u></u> 45
2.12.7	Utility Work	45

Chapter 2	Stormwater Best Management Practices (BMPs)	40
Chapter 3 3.1 St	andard Stormwater Best Management Practice Design Guidance Format	
	reen Roofs	
3.2.1	Green Roof Feasibility Criteria	
3.2.2	Green Roof Conveyance Criteria	57
3.2.3	Green Roof Pretreatment Criteria	57
3.2.4	Green Roof Design Criteria	
3.2.5	Green Roof Landscaping Criteria	65
3.2.6	Green Roof Construction Sequence.	
3.2.7	Green Roof Maintenance Criteria	
3.2.8	Green Roof Stormwater Compliance Calculations	<u></u> 70
3.2.9	References	<u></u> 71
3.3 Ra	ainwater Harvesting.	<u></u> 73
3.3.1	Rainwater Harvesting Feasibility Criteria	<u></u> 75
3.3.2	Rainwater Harvesting Conveyance Criteria.	<u></u> 78
3.3.3	Rainwater Harvesting Pretreatment Criteria	<u></u> 78
3.3.4	Rainwater Harvesting Design Criteria	<u></u> 81
3.3.5	Rainwater Harvesting Landscaping Criteria	<u></u> 96
3.3.6	Rainwater Harvesting Construction Sequence.	<u></u> 96
3.3.7	Rainwater Harvesting Maintenance Criteria	<u></u> 97
3.3.8	Rainwater Harvesting: Stormwater Compliance Calculations	<u></u> 99
3.3.9	References	<u></u> 99
3.4 In	npervious Surface Disconnection	101
3.4.1	Impervious Surface Disconnection Feasibility Criteria	104
3.4.2	Impervious Surface Disconnection Conveyance Criteria	108
3.4.3	Impervious Surface Disconnection Pretreatment Criteria	108
3.4.4	Impervious Surface Disconnection Design Criteria	108
3.4.5	Impervious Surface Disconnection Landscaping Criteria	<u></u> 111
3.4.6	Impervious Surface Disconnection Construction Sequence	112
3.4.7	Impervious Surface Disconnection Maintenance Criteria	113
3.4.8	Impervious Surface Disconnection Stormwater Compliance Calculations	<u></u> 114

3.4.9	References	<u></u> 115
3.5 Pe	ermeable Pavement Systems	<u></u> 117
3.5.1	Permeable Pavement Feasibility Criteria	<u></u> 119
3.5.2	Permeable Pavement Conveyance Criteria	122
3.5.3	Permeable Pavement Pretreatment Criteria	<u></u> 122
3.5.4	Permeable Pavement Design Criteria	122
3.5.5	Permeable Pavement Landscaping Criteria	130
3.5.6	Permeable Pavement Construction Sequence	131
3.5.7	Permeable Pavement Maintenance Criteria	<u></u> 136
3.5.8	Permeable Pavement Stormwater Compliance Calculations	138
3.5.9	References	<u></u> 139
3.6 Bi	oretention	<u></u> 141
3.6.1	Bioretention Feasibility Criteria	<u></u> 144
3.6.2	Bioretention Conveyance Criteria	<u></u> 147
3.6.3	Bioretention Pretreatment Criteria	<u></u> 149
3.6.4	Bioretention Design Criteria	
3.6.5	Bioretention Landscaping Criteria	<u></u> 168
3.6.6	Bioretention Construction Sequence	<u></u> 172
3.6.7	Bioretention Maintenance Criteria	<u></u> 175
3.6.8	Bioretention Stormwater Compliance Calculations	177
3.6.9	References	<u></u> 178
3.7 Fil	Itering Systems	<u></u> 181
3.7.1	Filtering Feasibility Criteria	<u></u> 190
3.7.2	Filtering Conveyance Criteria	<u></u> 191
3.7.3	Filtering Pretreatment Criteria	<u></u> 191
3.7.4	Filtering Design Criteria	<u></u> 192
3.7.5	Filtering Landscaping Criteria	<u></u> 197
3.7.6	Filter Construction Sequence	<u></u> 197
3.7.7	Filtering Maintenance Criteria	<u></u> 198
3.7.8	Filtering Volume Compliance Calculations.	<u></u> 201
3.7.9	References	201

3.8 Infiltration	203
3.8.1 Infiltration Feasibility Criteria	206
3.8.2 Infiltration Conveyance Criteria	208
3.8.3 Infiltration Pretreatment Criteria	208
3.8.4 Infiltration Design Criteria	209
3.8.5 Infiltration Landscaping Criteria	<u></u> 213
3.8.6 Infiltration Construction Sequence	214
3.8.7 Infiltration Maintenance Criteria	216
3.8.8 Infiltration Stormwater Compliance Calculations	217
3.8.9 References	218
3.9 Open Channel Systems	219
3.9.1 Open Channel Feasibility Criteria	222
3.9.2 Open Channel Conveyance Criteria	225
3.9.3 Open Channel Pretreatment Criteria	225
3.9.4 Open Channel Design Criteria.	226
3.9.5 Open Channel Landscaping Criteria	<u></u> 235
3.9.6 Open Channel Construction Sequence	236
3.9.7 Open Channel Maintenance Criteria	238
3.9.8 Open Channel Stormwater Compliance Calculations	<u></u> 241
3.9.9 References	242
3.10 Ponds	245
3.10.1 Pond Feasibility Criteria	248
3.10.2 Pond Conveyance Criteria	250
3.10.3 Pond Pretreatment Criteria	<u></u> 251
3.10.4 Pond Design Criteria	<u></u> 251
3.10.5 Pond Landscaping Criteria	<u></u> 256
3.10.6 Pond Construction Sequence	257
3.10.7 Pond Maintenance Criteria	<u></u> 259
3.10.8 Pond Stormwater Compliance Calculations	<u></u> 261
3.10.9 References	<u></u> 261
3.11 Stormwater Wetlands	264

3.11.1	Stormwater Wetland Feasibility Criteria	<u></u> 266
3.11.2	Stormwater Wetland Conveyance Criteria	<u></u> 268
3.11.3	Stormwater Wetland Pretreatment Criteria.	<u></u> 269
3.11.4	Stormwater Wetland Design Criteria	269
3.11.5	Stormwater Wetland Construction Sequence	272
3.11.6	Stormwater Wetland Landscaping Criteria	<u></u> 275
3.11.7	Stormwater Wetland Maintenance Criteria	<u></u> 279
3.11.8	Stormwater Wetland Stormwater Compliance Calculations	281
3.11.9	References	<u></u> 282
3.12 St	orage Practices	_283
3.12.1	Storage Feasibility Criteria	285
3.12.2	Storage Conveyance Criteria	<u></u> 287
3.12.3	Storage Pretreatment Criteria	<u></u> 288
3.12.4	Storage Design Criteria	<u></u> 289
3.12.5	Storage Landscaping Criteria.	<u></u> 291
3.12.6	Storage Construction Sequence	<u></u> 291
3.12.7	Storage Maintenance Criteria	<u></u> 293
3.12.8	Storage Volume Compliance Calculations	<u></u> 295
3.12.9	References	<u></u> 295
3.13 Pr	oprietary Practices	<u></u> 297
3.13.1	Proprietary Practice Feasibility Criteria.	<u></u> 297
3.13.2	Proprietary Practice Conveyance Criteria	<u></u> 297
3.13.3	Proprietary Practice Pretreatment Criteria	<u></u> 297
3.13.4	Proprietary Practice Design Criteria	<u></u> 297
3.13.5	Proprietary Practice Landscaping Criteria	<u></u> 298
3.13.6	Proprietary Practice Construction Sequence	<u></u> 298
3.13.7	Proprietary Practice Maintenance Criteria	<u></u> 298
3.13.8	Proprietary Practice Stormwater Compliance Calculations	<u></u> 299
3.14 Tr	ee Planting and Preservation	<u></u> 301
3.14.1	Preserving Existing Trees During Construction	<u></u> 301
3.14.2	Planting Trees	303

3.14.3	Tree Inspection Criteria	309
3.14.4	Tree Maintenance Criteria	309
3.14.5	Tree Stormwater Compliance Calculations	310
3.14.6	References	311
Chapter 4 System	Selecting and Locating the Most Effective Stormwater Best Manage315	ement Practice
4.1 Ch	oosing Stormwater Management Best Practices (BMPs)	<u></u> 315
4.2 Re	gulatory Compliance	<u></u> 316
4.3 La	nd Use Factors	317
4.4 Ph	ysical Feasibility Factors	319
4.5 Co	mmunity and Environmental Factors	322
4.6 Lo	cation and Permitting Considerations.	327
4.7 Re	ferences	329
Chapter 5	Administration of Stormwater Management Rules	330
5.1 Ad	ministration	330
5.1.1		
5.1.2		
5.2 Sto	ormwater Management Plans	
5.2.1		
5.2.2	SWMP Submittal Documents	
5.2.3	SWMP Components	
5.2.4	Resubmission of Stormwater Management Plans.	
5.3 Co	nstruction Inspection Requirements	348
5.3.1	Inspection Schedule and Reports	
5.3.2	Inspection Requirements Before and During Construction	349
5.3.3	Final Construction Inspection Reports	351
5.3.4	Inspection for Preventive Maintenance	352
5.4 Ma	uintenance	352
5.4.1	Maintenance Responsibility	352
5.4.2	Maintenance Agreement	353
5.5 Su	pporting Forms	353
Chapter 6	Use of Off-Site Retention by Regulated Sites	
	f-Site Retention Overview	

6.2 Minimum On-Site Retention Requirement30	06
6.3 Off-Site Retention via Stormwater Retention Credits3	08
6.4 Off-Site Retention via In-Lieu Fee3	11
6.5 Forms for Use of Off-Site Retention3	12
Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention	
Credits 313	
7.1 Stormwater Retention Credits Overview	
7.2 Eligibility Requirements3	13
7.2.2 Eligibility Requirements: Retention Volume	16
7.2.3 Eligibility Requirements: Design and Installation	18
7.2.4 Eligibility Requirements: Inspection	19
7.2.5 Eligibility Requirements: Maintenance3.	
7.3 Certification of Stormwater Retention Credits3	19
7.3.1 Certification of SRCs: Process	19
7.3.2 Certification of SRCs: DOEE-Funded Projects	21
7.4 Format of SRC Serial Numbers32	22
7.5 Failure to Maintain Retention after Certification of Stormwater Retention Credits 32	22
7.6 Buying and Selling Stormwater Retention Credits on the Market	23
7.7 Voluntary Retirement of Stormwater Retention Credits	23
7.8 Quitting the Obligation to Maintain Retention for Stormwater Retention Credits 32	23
7.9 Calculation of Stormwater Retention Credits	24
7.10 Stormwater Retention Credit Calculation Scenarios	29
7.11 Forms for Stormwater Retention Credits	39
Appendix A Compliance Calculations and Design ExamplesA	1 -1
A.1 Stormwater Database and General Retention Compliance Calculator	1 -1
A.2 Compliance Calculations and Concepts	1 -2
A.3 Design ExamplesA-	14
Appendix B Maximum Extent Practicable Process for Existing Public Right-of-Way	3-1
B.1 Maximum Extent Practicable: Overview	3-1
B.2 Public Right-of-Way ProjectsB	3-1
B.3 Codes	3-4
B.4 PROW Design Considerations	3-5
B.4.1 Considerations in the Planning Process (limited to Type 1)B	3-5
B.4.2 Site Assessment Considerations for the Retention Standard in PROW Projects B	3-5

B.4	.3 Fundamental Tenets of MEP for PROW	_B-10
B.4	.4 Minor Disturbances in the PROW	_B-11
B.4	.5 Potential Design Modifications for Infiltration-Based PROW BMPs	_B-11
B.5		
B.6	Summary of MEP Type 1 Submission Process	
B.7	References	
Append	ix C Off-Site Retention Forms for Regulated Sites	<u></u> C-1
Append	ix D Stormwater Retention Credit Forms (Certification, Trading, and Retirement).	<u></u> D-1
Append	ix E Relief from Extraordinarily Difficult Site Conditions	E-1
<u>E.1</u>	Relief from Extraordinarily Difficult Site Conditions	<u></u> E-1
E.2	Submission requirements for Relief from Extraordinarily Difficult Site Conditions	E-2
E.3	Review of Requests for Relief from Extraordinarily Difficult Site Conditions	
Append	ix F Stormwater Conveyance System Design	
F.1	Introduction	
F.2	Clearance with Other Utilities	<u>.</u> F-1
<u>F.3</u>	Design of Stormwater Conveyance Systems	
<u>F.4</u>	Gutters	
<u>F.5</u>	Inlets	
<u>F.6</u>	Street Capacity (Spread)	
<u>F.7</u>	Manhole and Inlet Energy Losses	
F.8	Open Channels	
F.9	Pipe Systems	F-5
F.10	Culverts	F-6
F.11	Hydraulic Grade Line	<u>.</u> F-9
F.12	Manholes and Inlets	<u></u> F-9
Append	ix G Design of Flow Control Structures	<u></u> G-1
G.1	Circular Orifices.	<u></u> G-1
G.2	Weirs	<u></u> G-2
Append	ix H Acceptable Hydrologic Methods and Models	<u></u> H-1
H.1	Acceptable Hydrologic Methods and Models.	<u></u> H-1
H.2	Urban Hydrology for Small Watersheds TR-55	<u></u> H-2
<u>H.3</u>	Storage-Indication Routing.	<u></u> H-5
<u>H.4</u>	HEC-1, WinTR-55, TR-20, and SWMM Computer Models	<u></u> H-6
H.5	Rational Method	<u></u> H-6

H.6 Stormwater Volume Peak Discharge	H-7
H.7 References	H-9
Appendix I Rooftop Storage Design Guidance and Criteria	I-1
Appendix J Soil Compost Amendment Requirements	J-1
J.1 Introduction	J-1
J.2 Physical Feasibility and Design Applications	J-1
J.3 Design Criteria	J-1
J.4 Construction Sequence	J-3
J.5 Maintenance	J-4
J.6 References	J-5
Appendix K Construction Inspection Checklists	
Appendix L Maintenance Inspection Checklists	_ /
Appendix M Rainwater Harvesting Treatment and Management Requirements	
M.1 Introduction	
M.2 Pathogen Reduction Targets	
M.3 Treatment Process	
M.3.1 Filtration	M-6
M.3.2 Disinfection	
M.3.3 Treatment Trains	M-17
M.4 Volatile Organic Compounds	M-17
M.5 Storage and Distribution Management Practices	
M.6 Commissioning	M-21
M.7 Operational Monitoring and Reporting	M-21
M.8 Field Verification	M-21
M.9 Design Report	M-22
M.10 Treatment Design Examples	M-22
M.10.1 Example 1: Rooftop Runoff for Landscape Irrigation	M-22
M.10.2 Example 2: General Runoff for Indoor Use	M-28
M.10.3 Example 3: Roof Runoff for Cooling Towers	M-29
M.11 References	M-30
Appendix N Land Cover Designations	N-1
N.1 General Notes	
N.2 Existing Natural Cover Requirements	N-1
N.3 Planting Requirements for the Creation of Natural Cover	N-1

<u>N.4</u>	Stormwater Management Plans and Natural Cover	N-2
N.5	Construction Requirements for Natural Cover Designation	N-3
N.6	Maintenance Requirements for Natural Cover Designation	N-4
N.7	Compacted Cover Designation	N-4
N.8 I	mpervious Cover Designation	N-1
Append	ix O Geotechnical Information Requirements for Underground BMPs	O-1
0.1	General Notes Pertinent to All Geotechnical Testing	O-1
<u>O.2</u>	Initial Feasibility Assessment	O-2
0.3	Test Pit/Boring Requirements for Infiltration Tests	O-2
0.4	Infiltration Testing Requirements	
0.5	Saturated Hydraulic Conductivity Calculations	O-5
0.6	Infiltration Restrictions	O-6
Append	ix P Stormwater Hotspots	P-1
P.1	Stormwater Hotspots	P-1
P.2	Stormwater Hotspot Cover Sheet.	P-3
P.3	Stormwater Hotspot Checklist	P-5
P.4	Hotspot Operation Pollution Prevention Profile Sheets	
Append	ix Q Pollution Prevention Through Good Housekeeping	Q-1
<u>Q.1</u>	Pollution Prevention.	Q-1
<u>Q.2</u>	Stormwater Management Plan (SWMP) Good Housekeeping Stamp Notes.	
Append	ix R Integrated Pest Management	R-1
R.1	Integrated Pest Management	R-1
R.2	Components of an Integrated Pest Management Plan	R-1
R.3	Sample Form for an Integrated Pest Management Plan	R-3
Append	ix S Proprietary Practices Approval Process	S-1
S.1	Proprietary Practice Consideration Overview	S-1
S.2	Types of Manufactured Treatment Devices	S-1
S.3	Proprietary Practice Approval Process – Background	S-2
<u>S.4</u>	MTD Current Approval Status	S-3
S.5	MTD Approval Status Renewal	
S.6	MTD Application Fees	S-4
S.7	References	

Appendix T Underg	round Sand Filter Design Example	<u></u> T-1
Appendix U Site Dra	ninage Area and BMP Design Diagrams	U-1
U.1 Design Diag	ram Overview	<u></u> U-1
U.2 Site Drainag	e Area Diagrams	<u></u> U-1
U.3 Determining	When BMP Performance is Considered to be On-Site	<u></u> U-5
Appendix V Resource	ees	V-1
Appendix W Definiti	ons	_W-1
W.1 References		W-11
	PROPOSITION PRINCIPAL PROPOSITION PROPOSIT	5

List of Tables

Table 1.1 Common Pollutants in Urban Stormwater Runoff and Their Sources (SWQTF, 19	
Table 2.1 Sizing Criteria for Stormwater Management Performance Requirements	8
Table 3.1 Extensive Green Roof Material Specifications	
Table 3.2 Ground Covers Appropriate for Green Roofs in the District of Columbia	
Table 3.3 Typical Maintenance Activities Associated with Green Roofs	 70
Table 3.4 Green Roof Design Performance	 71
Table 3.5 Advantages and Disadvantages of Typical Cistern Materials (Source: Cabell Brain	
Center, 2007; Cabell Brand Center, 2009)	83
Table 3.6 Design Specifications for Rainwater Harvesting Systems	84
Table 3.7 Typical Maintenance Tasks for Rainwater Harvesting Systems	97
Table 3.8 Feasibility Criteria for Simple Disconnection	106
Table 3.9 Recommended Vegetation for Pervious Disconnection Areas	112
Table 3.10 Disconnection Retention Value and Pollutant Removal	
Table 3.11 Permeable Pavement Specifications for a Variety of Typical Surface Materials.	126
Table 3.12 Material Specifications for Typical Layers Beneath the Pavement Surface	127
Table 3.13 Typical Maintenance Tasks for Permeable Pavement Practices	 137
Table 3.14 Enhanced Permeable Pavement Retention Value and Pollutant Removal	138
Table 3.15 Standard Permeable Pavement Retention Value and Pollutant Removal	139
Table 3.16 Maximum Contributing Drainage Area to Bioretention	145
Table 3.17 Filter Media Grain Size Distribution	153
Table 3.18 Summary of Filter Media Criteria for Bioretention.	155
Table 3.19 Determining Maximum Filter Media Depth (feet)	156
Table 3.20 Bioretention Material Specifications	159
Table 3.21 Herbaceous Plants Appropriate for Bioretention Areas in the District	169
Table 3.22 Woody Plants Appropriate for Bioretention Areas in the District	170
Table 3.23 Typical Maintenance Tasks for Bioretention Practices	175
Table 3.24 Enhanced Bioretention Retention Value and Pollutant Removal	177
Table 3.25 Standard Bioretention Design Retention Value and Pollutant Removal	177
Table 3.26 Filtering Practice Material Specifications	195
Table 3.27 Typical Annual Maintenance Activities for Filtering Practices	200
Table 3.28 Filter Retention Value and Pollutant Removal	201
Table 3.29 Infiltration Material Specifications	210
Table 3.30 Maximum Facility Depth for Infiltration Practices	212
Table 3.31 Typical Maintenance Activities for Infiltration Practices	216
Table 3.32 Infiltration Retention Value and Pollutant Removal	 217
Table 3.33 Typical Check Dam Spacing to Achieve Effective Channel Slope	227
Table 3.34 Grass Channel Material Specifications	229
Table 3.35 Dry Swale Material Specifications	230
Table 3.36 Recommended Vegetation for Open Channels	
Table 3.37 Typical Maintenance Activities and Schedule for Open Channels	
Table 3.38 Grass Channel Retention Value and Pollutant Removal	
Table 3.39 Grass Channel on Amended Soils Retention Value and Pollutant Removal	241
Table 3.40 Dry Swale Retention Value and Pollutant Removal	241
Table 3.41 Wet Swale Retention Value and Pollutant Removal	242

Table 3.42 Clay Liner Specifications	253
Table 3.43 Pond Maintenance Tasks and Frequency	
Table 3.44 Pond Retention Value and Pollutant Removal	261
Table 3.45 Popular, Versatile, and Available Native Trees and Shrubs for Stormwater W	
Table 3.46 Popular, Versatile, and Available Native Emergent and Submergent Vegetati	
Stormwater Wetlands.	
Table 3.47 Stormwater Wetland Retention Value and Pollutant Removal	
Table 3.48 Typical Maintenance Activities for Storage Practices	
Table 3.49 Storage Retention Value and Pollutant Removal	
Table 3.50 Selecting Priority Trees and Forests for Preservation	
Table 3.51 Methods for Addressing Urban Planting Constraints	
Table 3.52 Tree Planting Techniques	
Table 3.53 Preserved Tree Retention Value and Pollutant Removal	311
Table 3.54 Planted Tree Retention Value and Pollutant Removal	311
Table 4.1 BMP Selection Based on Regulatory Criteria	317
Table 4.2 BMP Selection Based on Land Use Screening Factors	318
Table 4.3 BMP Selection Based on Physical Feasibility Screening Factors	320
Table 4.4 Selection of Infiltration BMPs Based on Measured Saturated Hydraulic Condu	ıctivity
	322
Table 4.5 BMP Selection Based on Community and Environmental Factors	324
Table 4.6 Location and Permitting Considerations	327
Table 1.1 Common Pollutants in Urban Stormwater Runoff and Their Sources	<u></u> 5
Table 2.1 Sizing Criteria for Stormwater Management Performance Requirements	8
Table 3.1 Extensive Green Roof Material Specifications	<u></u> 61
Table 3.2 Ground Covers Appropriate for Green Roofs in the District of Columbia	
Table 3.3 Typical Maintenance Activities Associated with Green Roofs	
Table 3.4 Unirrigated Green Roof Design Performance	
Table 3.5 Disconnection Retention Value and Pollutant Removal	
Table 3.6 Typical Maintenance Tasks for Permeable Pavement Practices	
Table 3.7 Enhanced Permeable Pavement Retention Value and Pollutant Removal	138
Table 3.8 Standard Permeable Pavement Retention Value and Pollutant Removal	<u></u> 139
Table 3.9 Maximum Contributing Drainage Area to Bioretention	
Table 3.10 Filter Media Grain Size Distribution	<u></u> 153
Table 3.11 Summary of Filter Media Criteria for Bioretention	
Table 3.12 Bioretention Material Specifications	
Table 3.13 Herbaceous Plants Appropriate for Bioretention Areas in the District	
Table 3.14 Woody Plants Appropriate for Bioretention Areas in the District	<u></u> 170
Table 3.15 Typical Maintenance Tasks for Bioretention Practices	175
Table 3.16 Filtering Practice Material Specifications.	195
Table 3.17 Typical Annual Maintenance Activities for Filtering Practices	
Table 3.18 Filter Retention Value and Pollutant Removal	
Table 3.19 Maximum Facility Depth for Infiltration Practices	
Table 3.20 Typical Maintenance Activities for Infiltration Practices	
Table 3.21 Infiltration Retention Value and Pollutant Removal	21/
Table 3.22 Typical Check Dam Spacing to Achieve Effective Channel Slope	<u></u> 221

Table 3.23 Grass Channel Material Specifications	229
Table 3.24 Dry Swale Material Specifications	
Table 3.25 Recommended Vegetation for Open Channels	
Table 3.26 Typical Maintenance Activities and Schedule for Open Channels	
Table 3.27 Grass Channel Retention Value and Pollutant Removal	
Table 3.28 Dry Swale Retention Value and Pollutant Removal	
Table 3.29 Wet Swale Retention Value and Pollutant Removal	
Table 3.30 Clay Liner Specifications	<u></u> 253
Table 3.31 Pond Maintenance Tasks and Frequency	
Table 3.32 Pond Retention Value and Pollutant Removal	<u></u> 261
Table 3.33 Popular, Versatile, and Available Native Trees and Shrubs for Stormwater W	/etlands
Table 3.34 Popular, Versatile, and Available Native Emergent and Submergent Vegetati	2/0
Stormwater Wetlands	
Table 3.35 Stormwater Wetland Retention Value and Pollutant Removal	281
Table 3.36 Typical Maintenance Activities for Storage Practices	
Table 3.37 Storage Retention Value and Pollutant Removal	295
Table 3.38 Selecting Priority Trees and Forests for Preservation	
Table 3.39 Methods for Addressing Urban Planting Constraints	
Table 3.40 Tree Planting Techniques	
Table 3.41 Preserved Tree Retention Value and Pollutant Removal	
Table 3.42 Planted Tree Retention Value and Pollutant Removal	311
Table 4.1 BMP Selection Based on Regulatory Criteria	317
Table 4.2 BMP Selection Based on Land Use Screening Factors	
Table 4.3 BMP Selection Based on Physical Feasibility Screening Factors	
Table 4.4 Selection of Infiltration BMPs Based on Measured Saturated Hydraulic Condu	
Table 4.5 BMP Selection Based on Community and Environmental Factors	
Table 4.6 Location and Permitting Considerations	<u></u> 327
Table A.1 Land Cover Guidance for General Retention Compliance Calculator and Stormwater Database, consult Appendix N for more details	۸ 6
Table F.1 Manning's Roughness Coefficient (n) Values for Various Channel Materials	
Table F.2 Minimum Structure Loss to Use in Hydraulic Grade Line Calculation	F-4
Table H.1 Runoff Coefficient Lactors for Typical District of Columbia Land Uses	H-6
Table J.1 Method to Determine Compost and Incorporation Depths	J-2
Table M.1 Likelihood Exposure will Occur	
Table M.2 Magnitude of Health Risk	M-6
Table M.3 Characterizing Threat to Public Health	
Table M.4 Chemicals of Interest for Baseline Investigations	
Table M.5 Types of Stormwater Use and Routes of Exposure	
Table M.6 Exposure Assumptions Based on Stormwater Use and Exposure Conditions	
Table M.7 Categorizing Exposures Based on Stormwater Use: Severe, High, Medium, and Low	

Table M.8 Risk based Chemical Concentrations for Sites Categorized as Severe, High, Medium, and Low Exposures	
Table M.9 Risk Based Microbial Levels for Sites Categorized As Severe, High, Medium, and Low Exposures	-M-28
Table O.1 Number of Infiltration Tests Required per BMP	O-3
Table F.1 Manning's Roughness Coefficient (n) Values for Various Channel Materials	
Table F.2 Minimum Structure Loss to Use in Hydraulic Grade Line Calculation	
Table H.1 Runoff Coefficient Factors for Typical District of Columbia Land Uses	
Table M.1 Ninety-Fifth Percentile Log ₁₀ Pathogen Reduction Targets (LRT) to Meet 10 ⁻⁴	3 2
(infection) ppy Benchmarks for Healthy Adults ^a	
Table M.2 Typical Values for Pathogen Reduction Using Filtration Processes	
Table M.3 Typical Values for Various Levels of the Inactivation of Enteric Virus in Filtered Secondary Effluent with Selected Disinfection Processes	
Table M.4 Typical Values for Various Levels of the Inactivation of Parasitic Protozoa in	_IVI- /
Filtered Secondary Effluent with Selected Disinfection Processes	M-10
Table M.5 Typical Values for Various Levels of the Inactivation of Enteric Bacteria in Filter	
Secondary Effluent with Selected Disinfection Processes.	M-15
Table M.6 Volatile Organic Compound Maximum Concentrations Table O.1 Number of Infiltration Tests Required per BMP	M-17
Table P.1 Pollution Prevention Considerations for Vehicle Maintenance and Repair	
Record Strip	

List of Figures

	3
Figure 1.2 Changes in streamflow resulting from urbanization (Schueler, 1987)	4
Figure 2.12.1 Map of Anacostia Waterfront Development Zone.	9
Figure 2.22.2 Map of District of Columbia MS4 and CSS areas.	
Figure 2.32.3 Determining the regulatory event used to calculate the SWRv	
Figure 2.42.4 Determining if overall retention requirements have been met, outside the AWD	Z.
Figure 2.52.5 Determining if overall retention and water quality treatment requirements have	. 10
been met, inside the AWDZ for regulated activity governed by the Anacostia Waterfront	
Environmental Standards Amendment Act of 2012.	17
Figure 2.62.6 Determining if minimum retention and water quality treatment requirements ha	
been met.	10
Figure 3.1 Design Requirements for structures constructed above green roofs.	27
Figure 3.1 Design Requirements for structures constructed above green roots	. 46
Figure 3.2 Example of a rainwater harvesting system detail. Figure 3.3 Diagram of a first flush diverter. (Texas Water Development Board, 2005)	. 40
Figure 3.4 Diagram of a roof washer. (Texas Water Development Board, 2005)	
Figure 3.5 Cistern Design 1: Storage associated with the design storm volume only	. 56
Figure 3.6 Cistern Design 2: Storage associated with design storm, channel protection, and flo	
volume	. 57
Figure 3.7 Cistern Design 3: Constant drawdown version where storage is associated with	
design storm, channel protection, and flood volume.	. 58
Figure 3.8 Incremental design volumes associated with cistern sizing.	
Figure 3.9 Example of retention value percentage achieved versus storage for non-potable use	
	-62
Figure 3.10 Design requirements for rooftop and impervious surfaces	. 71
Figure 3.11 Cross section of a standard permeable pavement design.	. 71 . 79
Figure 3.11 Cross section of a standard permeable pavement design	. 71 . 79
Figure 3.11 Cross section of a standard permeable pavement design	. 71 . 79 . 80
Figure 3.11 Cross section of a standard permeable pavement design	. 71 . 79 . 80
Figure 3.11 Cross section of a standard permeable pavement design	.71 .79 .80 .80
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain. Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain. Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design.	.71 .79 .80 .80
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain. Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration	.71 .79 .80 .80 .83 101
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer.	.71 .79 .80 .80 .83 101
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain.	.71 .79 .80 .80 .83 101 101 102
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on-line bioretention area.	.71 .79 .80 .83 101 101 102 106
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer.	.71 .79 .80 .83 101 101 102 106
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on line bioretention area. Figure 3.19 Observation well/cleanout device. Figure 3.20 Example of tree box cross section.	.71 .79 .80 .83 101 102 106 115 118
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on line bioretention area. Figure 3.19 Observation well/cleanout device. Figure 3.20 Example of tree box cross section.	.71 .79 .80 .83 101 102 106 115 118
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain. Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain. Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on line bioretention area. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of tree box cross section with compacted media extending below sideware.	.71 .79 .80 .80 .83 101 101 102 106 115 118 alk.
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain. Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain. Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on line bioretention area. Figure 3.19 Observation well/cleanout device. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of tree box cross section with compacted media extending below sideware.	.71 .79 .80 .83 101 104 106 115 118 hlk.
Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design with an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on-line bioretention area. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of a stormwater planter (B 4). Figure 3.23 Typical schematic for a surface sand filter (F 2).	.71 .79 .80 .83 101 102 106 115 118 119 120
Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design with an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on-line bioretention area. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of a stormwater planter (B 4). Figure 3.23 Typical schematic for a surface sand filter (F 2).	.71 .79 .80 .83 101 102 106 115 118 119 120
Figure 3.11 Cross section of a standard permeable pavement design. Figure 3.12 Cross section of an enhanced permeable pavement design with an underdrain. Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain. Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on line bioretention area. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of a stormwater planter (B 4).	.71 .79 .80 .83 101 102 106 115 118
Figure 3.11 Cross section of an enhanced permeable pavement design with an underdrain Figure 3.12 Cross section of an enhanced standard permeable pavement design with an underdrain Figure 3.13 Cross section of an enhanced standard permeable pavement design without an underdrain Figure 3.14 Use of flow barriers to encourage infiltration on sloped sites. Figure 3.15 Example of standard bioretention design. Figure 3.16 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer. Figure 3.17 Example of enhanced bioretention design without an underdrain. Figure 3.18 Example of an overflow structure in an on-line bioretention area. Figure 3.20 Example of tree box cross section. Figure 3.21 Example of tree box cross section with compacted media extending below sidews. Figure 3.22 Example of a stormwater planter (B-4). Figure 3.23 Typical schematic for a surface sand filter (F 2). Figure 3.24 Part A Example of a three chamber underground sand filter (F 3) for separate	.71 .79 .80 .83 101 102 106 115 118 hlk. 119 120 135

Figure 3.26 Part C Example of a three chamber underground sand filter (F 3) for separate	
sewer areas. Note: Material specifications are indicated in Table 3.26.	138
Figure 3.27 Part A Example of a three chamber underground sand filter (F 3) for combine	ed
sewer areas. Note: Material specifications are indicated in Table 3.26	139
Figure 3.28 Part B Example of a three chamber underground sand filter (F 3) for combine	
sewer areas. Note: Material specifications are indicated in Table 3.26	140
Figure 3.29 Part C Example of a three chamber underground sand filter (F 3) for combine	d
sewer areas. Note: Material specifications are indicated in Table 3.26	141
Figure 3.30 Example of a perimeter sand filter (F 4).	
Figure 3.31 Example of an infiltration trench.	155
Figure 3.32 Infiltration section with supplemental pipe storage	156
Figure 3.33 Example of an infiltration basin.	
Figure 3.34 Grass channel typical plan, profile, and section views (O-1)	171
Figure 3.35 Example of a dry swale (O 2).	172
Figure 3.36 Example of a wet swale (O 3).	173
Figure 3.37 Design schematics for a wet pond (C 2).	194
Figure 3.38 Typical extended detention pond (C 3) details	195
Figure 3.39 Example of extended detention shallow wetland	
Figure 3.40 Cross section of a typical stormwater wetland	214
Figure 3.41 Interior wetland zones: (I) Deep Pool (depth 48 to 18 inches), (II) Transition 2	Zone
(depth 18 to 6 inches), (III and IV) High Marsh Zone (depth 6 to 16 inches), (IV) Tempor	
Inundation Area, and (V) Upper Bank (adapted from Hunt et al., 2007)	214
Figure 3.42 Example of an underground detention vault and/or tank (S-1)	232
Figure 3.43 Example of a dry detention pond (S 2).	233
Figure 3.44 Tree planting guidelines. (Adapted from Flott, 2004 and ISA, 2003b)	
Figure 3.45 The specifications for planting on a steep slope, require creating a level planting	
surface.	
Figure 5.3 Construction inspection and maintenance process	
Figure 5.4 Utility trench exemption example with building in LOD.	293
Figure 5.5 Utility trench exemption example with building and sidewalk in LOD	293
Figure 5.6 Utility trench exemption example solely for utility work	294
Figure 5.7 DC Water/DOEE Storm Sewer Verification form.	
Figure 5.8 As Built Certification By Professional Engineer form.	
Figure 5.9 Statement By Professional Engineer Registered In the District of Columbia form	
Figure 5.10 Statement By Person Responsible For Maintenance form	
Figure 5.11 Statement By Person Responsible For Achieving Off Site Retention form	
Figure 5.13 Application for vesting status.	
Figure 5.14 Declaration of Covenants template.	303
Figure 7.1 Retention volume eligible to earn SRCs.	319
Figure B.1 Diagram of typical residential public right of way in the District of Columbia	
(DDOT Public Realm Design Manual 2011)	B-2
Figure C.1 Application to Use Stormwater Retention Credits for Off-Site Retention	
Volume.	C 2
Figure C.2 Notification of In Lieu Fee Payment to Meet Off Site Retention Volume	C 5
Figure D.1 Application for Certification of Stormwater Retention Credits.	

Figure D.2 Application for Transfer of Stormwater Retention Credit Ownership	D-7
Figure D.3 Application to Retire Stormwater Retention Credits	D 10
Figure F.1 Typical nomograph for culverts under outlet control.	F9
Figure G.1 Absolute downstream control of flow under gate.	G 2
Figure H.1 Approximate detention basin routing for rainfall types I, IA, II and III	
Figure I.1 Rooftop stormwater detention.	
Figure I.2 Typical rainfall ponding ring sections	<u> </u>
Figure K.1 Green Roof Construction Inspection Report.	
Figure K.2 Rainwater Harvesting Construction Inspection Report.	
Figure K.3 Impervious Surface Disconnection Construction Inspection Report.	
Figure K.4 Permeable Pavement System Construction Inspection Report	
Figure K.5 Bioretention Construction Inspection Report	
Figure K.6 Filtering System Construction Inspection Report.	
Figure K.7 Infiltration Practice Construction Inspection Report.	
Figure K.8 Open Channel System Construction Inspection Report.	V 16
Figure K.o. Open d and Stammy stem Constitution inspection Report.	V 10
Figure K.9 Pond and Stormwater Wetland Practice Construction Inspection Report	
Figure K.10 Storage Practice and Underground Detention Construction Inspection Report	
Figure K.11 Generic Structural BMP Construction Inspection Report.	K 20
Figure K.12 Tree Planting and Preservation Construction Inspection Report	
Figure K.13 Stormwater Facility Leak Test Form.	K 24
Figure L.1 Green Roof Maintenance Inspection Report.	
Figure L.2 Rainwater Harvesting Maintenance Inspection Report	
Figure L.3 Impervious Cover Surface Disconnection Maintenance Inspection Report	
Figure L.4 Permeable Pavement Maintenance Inspection Report	
Figure L.5 Bioretention Maintenance Inspection Report.	
Figure L.6 Filtering Ssystem Maintenance Inspection Report.	
Figure L.7 Infiltration Practice Maintenance Inspection Report.	
Figure L.8 Open Channel Systems Maintenance Inspection Report	L 16
Figure L.9 Ponds and Wetlands Maintenance Inspection Report	L 18
Figure L.10 Storage Practice and Underground Detention Facilities Maintenance Inspect	ion
Report	
Figure L.11 Stormwater Management Facilities GenericMaintenance Inspection Report	L 22
Figure L.12 Tree Planting and Preservation Maintenance Inspection Report	
Figure L.13 Maintenance Service Completion Inspection Report	
Figure M.1 Example 1 Treatment Schematic.	
Figure M.2 Example 2 Treatment Schematic.	
Figure O.1 Infiltration restrictions related to site contamination.	
Figure R.1 Sample form for an Integrated Pest Management Plan.	
1 igure K.1 Sumpre form for an integrated 1 est wanagement 1 ian	IX J
Figure 1.1 Changes in the water balance resulting from urbanization (FISRWG, 1998)	3
Figure 1.2 Changes in streamflow resulting from urbanization (Schueler, 1987)	4
Figure 2.1 Map of the Anacostia Waterfront Development Zone.	9
Figure 2.2 Map of District of Columbia MS4 and CSS areas	23
Figure 2.3 Determining the regulatory event used to calculate the SWRv	

Figure 2.4 Determining if the site is an AWDZ site.	<u>.</u> 31
Figure 2.5 Determining if the minimum SDA requirements have been met	.32
Figure 2.6 Determining if minimum retention and water quality treatment requirements have been	
met	
Figure 2.7 Map of drainage types in the District. The Tidal MS4 areas in blue may be exempt from	
2-year detention requirements.	<u>.</u> 38
Figure 2.8 Utility trench exemption example with building in LOD.	
Figure 2.9 Utility trench exemption example with building and sidewalk in LOD.	
Figure 2.10 Utility trench exemption example solely for utility work	
Figure 3.1 Typical layers for a green roof. Note: the relative placement of various layers may vary	7
depending on the type and design of the green roof system.	_58
Figure 3.2 Design requirements for structures constructed above green roofs.	
Figure 3.3 Example of a rainwater harvesting system detail.	
Figure 3.4 Diagram of a first flush diverter. (Texas Water Development Board, 2005)	
Figure 3.5 Diagram of a roof washer. (Texas Water Development Board, 2005)	
Figure 3.6 Cistern Design 1: Storage associated with the design storm volume only.	<u>.</u> 86
Figure 3.7 Cistern Design 2: Storage associated with design storm, channel protection, and flood	
volume.	<u>.</u> 87
Figure 3.8 Cistern Design 3: Constant drawdown version where storage is associated with design	
storm, channel protection, and flood volume	
Figure 3.9 Incremental design volumes associated with cistern sizing.	
Figure 3.10 Example of retention value percentage achieved versus storage for non-potable uses.	
Figure 3.11 Design requirements for rooftop and impervious surfaces.	
Figure 3.12 Cross section of a standard permeable pavement design.	
Figure 3.13 Cross section of an enhanced permeable pavement design with an underdrain1	118
Figure 3.14 Cross section of an enhanced standard permeable pavement design without an	110
underdrain.	
Figure 3.15 Use of flow barriers to encourage infiltration on sloped sites	
Figure 3.16 Example of standard bioretention design.	142
Figure 3.17 Example of an enhanced bioretention design with an underdrain and infiltration	1.42
sump/storage layer	
Figure 3.18 Example of enhanced bioretention design without an underdrain	
Figure 3.20 Observation well/cleanout device	
Figure 3.21 Example of tree box cross section.	
Figure 3.22 Example of tree box cross section with compacted media extending below sidewalk. 1	
Figure 3.23 Example of a stormwater planter (B-4).	
Figure 3.24 Typical schematic for a surface sand filter (F-2)	192
Note: Material specifications are indicated in Table 3.27.	182
Figure 3.25 Part A – Example of a three-chamber underground sand filter (F-3) for separate sewer	102
areas. Note: Material specifications are indicated in Table 3.27.	183
Figure 3.26 Part B – Example of a three-chamber underground sand filter (F-3) for separate sewer	
areas. Note: Material specifications are indicated in Table 3.27.	-
Figure 3.27 Part C – Example of a three-chamber underground sand filter (F-3) for separate sewer	
areas. Note: Material specifications are indicated in Table 3.27	
Figure 3.28 Part A – Example of a three-chamber underground sand filter (F-3) for combined sew	er
areas. Note: Material specifications are indicated in Table 3.27.	
Figure 3.29 Part B – Example of a three-chamber underground sand filter (F-3) for combined sewer	er
areas. Note: Material specifications are indicated in Table 3.27.	187

Figure 3.30 Part C – Example of a three-chamber underground sand filter (F-3) for combined see	
areas. Note: Material specifications are indicated in Table 3.27.	
Figure 3.31 Example of a perimeter sand filter (F-4).	<u></u> 189
Note: Material specifications are indicated in Table 3.27.	
Figure 3.32 Example of an infiltration trench.	<u></u> 204
Figure 3.33 Infiltration section with supplemental pipe storage.	
Figure 3.34 Example of an infiltration basin.	205
Figure 3.35 Grass channel typical plan, profile, and section views (O-1)	
Figure 3.36 Example of a dry swale (O-2).	
Figure 3.37 Example of a wet swale (O-3).	
Figure 3.38 Design schematics for a wet pond (C-2).	
Figure 3.39 Typical extended detention pond (C-3) details.	
Figure 3.40 Example of extended detention shallow wetland.	
Figure 3.41 Cross section of a typical stormwater wetland.	
Figure 3.42 Interior wetland zones: (I) Deep Pool (depth -48 to -18 inches), (II) Transition Zone	
(depth -18 to -6 inches), (III and IV) High Marsh Zone (depth -6 to +6 inches), (IV) Temporary	
Inundation Area, and (V) Upper Bank (adapted from Hunt et al., 2007)	
Figure 3.43 Example of an underground detention vault and/or tank (S-1)	
Figure 3.44 Example of a dry detention pond (S-2).	
Figure 3.45 Tree planting guidelines. (Adapted from Flott, 2004 and ISA, 2003b)	307
Figure 3.46 The specifications for planting on a steep slope, require creating a level planting sur	face.
	308
Figure 5.1 Fees.	332
Figure 5.2 Plan review process.	338
Figure 5.3 Construction inspection and maintenance process	340
Figure 5.4 DC Water/DOEE Storm Sewer Verification form.	369
Figure 5.5 As-Built Certification By Professional Engineer form.	370
Figure 5.6 Statement By Professional Engineer Registered In the District of Columbia form	
Figure 5.7 Statement By Person Responsible For Maintenance form	372
Figure 5.8 Statement By Person Responsible For Achieving Off-Site Retention form	373
Figure 5.9 Anacostia Waterfront Development Zone Site form	374
Figure 5.10 Application for exempt land-disturbing activity.	
Figure 5.11 Declaration of Covenants Template.	380
Figure 5.12 Amendment to Seclaration of Covenants.	
Figure 5.13 Termination and Release of Declaration of Covenants	
Figure 7.1 SRC Eligibility Cutoff Dates.	315
Figure 7.2 Retention volume eligible to earn SRCs.	
Figure 7.3 Scenario 1.	
Figure 7.4 Land Cover Type.	332
Figure 7.5 BMP Design Information.	333
Figure 7.6 Scenario 2.	338
Figure 7.7 Land Cover and Pre-Project BMP Information.	
Figure 7.8 BMP Design Information.	
Figure A.1 Approximate detention basin routing for rainfall types I, IA, II and III.	
Figure B.1 Diagram of typical residential public right-of-way in the District of Columbia (DDO)	
Public Realm Design Manual 2011).	
Figure C.1 Application to Use Stormwater Retention Credits for Off-Site Retention Volume	
Figure C.2 Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume	

Figure D.1 Application for Certification of Stormwater Retention Credits	D-3
Figure D.2 Application for Transfer of Stormwater Retention Credit Ownership.	
Figure D.3 Application to Retire Stormwater Retention Credits.	D-20
Figure F.1 Typical nomograph for culverts under outlet control.	
Figure H.1 Approximate detention basin routing for rainfall types I, IA, II and III.	
Figure I.1 Rooftop stormwater detention	
Figure I.2 Typical rainfall ponding ring sections.	
Figure K.1 Green Roof Construction Inspection Report.	
Figure K.2 Rainwater Harvesting Construction Inspection Report.	
Figure K.3 Impervious Surface Disconnection Construction Inspection Report	
Figure K.4 Permeable Pavement System Construction Inspection Report.	_
Figure K.5 Bioretention Construction Inspection Report.	
Figure K.6 Sand Filter Construction Inspection Report.	
Figure K.7 Infiltration Device Construction Inspection Report	
Figure K.8 Open Channel System Construction Inspection Report	
Figure K.9 Pond, Wetland, and Storage Practices Construction Inspection Report	
Figure K.10 Stormwater Management Facilities Inspection Report.	_K-32
Figure K.11 Tree Planting and Preservation Construction Inspection Report	
Figure K.12 Stormwater Management Standard Testing Record.	_K-38
Figure K.13 Green Area Ratio Landscape Checklist	_K-39
Figure L.1 Green Roof Maintenance Inspection Report.	
Figure L.2 Rainwater Harvesting Maintenance Inspection Report	
Figure L.3 Impervious Cover Surface Disconnection Maintenance Inspection Report	
Figure L.4 Permeable Pavement Maintenance Inspection Report.	
Figure L.5 Bioretention Maintenance Inspection Report.	
Figure L.6 Sandfilter Maintenance Inspection Report.	_L-17
Figure L.7 Infiltration Facilities Maintenance Inspection Report.	
Figure L.8 Open Channel Systems Maintenance Inspection Report	
Figure L.9 Pond and Wetland Maintenance Inspection Report.	
Figure L.10 Storage and Underground Detention Maintenance Inspection Report	
Figure L.10 (continued)	
Figure L.11 Stormwater Management Facilities Maintenance Inspection Report	
Figure L.12 Tree Planting and Preservation Maintenance Inspection Report.	
Figure L.13 Maintenance Service Completion Inspection Report.	
Figure M.1 Example 1 Treatment Schematic.	-
Figure M.2 Example 2 Treatment Schematic.	
Figure O.1 Infiltration restrictions related to site contamination.	
Figure P.1 Vehicle yard.	
Figure P.2 Covered Retail Gas Operation Without Containment for Potential Spills.	
Figure P.3 Containment System Preventing Wash Water from Entering the Storm Drain	
Figure P.4 Unloading Area of Warehouse.	
Figure P.5 Mulch Stored Outdoors at a Garden Center	
Figure P.6 Secondary Containment of Storage Drums Behind a Car Repair Shop.	
Figure R.1 Sample form for an Integrated Pest Management Plan.	
Figure T.1 Sand filter schematic with steps shown.	
Figure U.1 Site Drainage Areas on a single lot.	
Figure U.2 Site Drainage Areas on projects with multiple lots.	
Figure U.3 Site Drainage Areas on campuses.	
Figure U.4 Single lot: BMP and CDA are entirely within the LOD.	<u></u> U-8

Figure U.5 Single lot: CDA is partially outside the LOD, but within the lot.	U-9
Figure U.6 Single lot: CDA is partially in the PROW.	<u>U</u> -10
Figure U.7 Single lot: CDA includes area on an adjacent lot.	<u>U-11</u>
Figure U.8 Single lot: BMP and CDA are entirely outside the LOD	U-12
Figure U.9 Single lot: BMP and CDA are outside primary LOD.	U-13
Figure U.10 Single lot: BMP is outside primary LOD; CDA includes area within primary LO	<u>D.</u> U-14
Figure U.11 Single lot: Tree planting.	U-15
Figure U.12 Single lot: Tree preservation	U-16
Figure U.13 Many lots: BMP and CDA are entirely within the LOD.	U-17
Figure U.14 Many lots: CDA is partially outside the LOD, but within the disturbed lots	U-18
Figure U.15 Many lots: CDA is partially in the PROW	U-19
Figure U.16 Many lots: CDA includes area on an adjacent lot.	U-20
Figure U.17 Many lots: BMP and CDA are entirely outside the LOD.	U-21
Figure U.18 Many lots: BMP and CDA are on an adjacent, undisturbed lot	U-22
Figure U.19 Many lots: BMP and CDA are outside primary LOD.	U-23
Figure U.20 Many lots: BMP is outside primary LOD; CDA includes area within primary LO	<u>D</u> U-
24	
24 Figure U.21 Many lots: Tree planting.	U-25
Figure U.21 Many lots: Tree planting	U-25 U-26
Figure U.21 Many lots: Tree planting	U-25 U-26 U-27
Figure U.21 Many lots: Tree planting	U-25 U-26 U-27 U-28
Figure U.21 Many lots: Tree planting	U-25 U-26 U-27 U-28
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting.	U-25 U-26 U-27 U-28 U-29 U-30
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation.	U-25 U-26 U-27 U-28 U-29 U-30 U-31
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation. Figure U.28 PROW: BMP and CDA are entirely within the LOD.	U-25 U-26 U-27 U-28 U-29 U-30 U-31 U-32
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation. Figure U.28 PROW: BMP and CDA are entirely within the LOD. Figure U.29 PROW: CDA is partially outside the LOD, but within the PROW.	U-25 U-26 U-27 U-28 U-29 U-30 U-31 U-32 U-33
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation. Figure U.28 PROW: BMP and CDA are entirely within the LOD. Figure U.29 PROW: CDA is partially outside the LOD, but within the PROW. Figure U.30 PROW: CDA is partially in an adjacent lot.	U-25 U-26 U-27 U-28 U-29 U-30 U-31 U-32 U-33 U-34
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation. Figure U.28 PROW: BMP and CDA are entirely within the LOD. Figure U.29 PROW: CDA is partially outside the LOD, but within the PROW. Figure U.30 PROW: CDA is partially in an adjacent lot.	U-25 U-26 U-27 U-28 U-29 U-30 U-31 U-32 U-33 U-34
Figure U.21 Many lots: Tree planting. Figure U.22 Many lots: Tree preservation. Figure U.23 Campus: BMP and CDA are entirely within the LOD. Figure U.24 Campus: CDA is partially outside the LOD. Figure U.25 Campus: BMP and CDA are entirely outside the LOD. Figure U.26 Campus: Tree planting. Figure U.27 Campus: Tree preservation. Figure U.28 PROW: BMP and CDA are entirely within the LOD. Figure U.29 PROW: CDA is partially outside the LOD, but within the PROW.	U-25 U-26 U-27 U-28 U-29 U-30 U-31 U-32 U-33 U-34

List of Equations

Equation 2.1 Stormwater Retention Volume	18
Equation 2.2 Water Quality Treatment Volume	24
Equation 3.1 Storage Volume for Green Roofs	65
Equation 3.2 Reservoir Layer or Infiltration Sump Depth	128
Equation 3.3 Drawdown Time	
Equation 3.4 Permeable Pavement Storage Volume	130
Equation 3.5a Bioretention Storage Volume	166
Equation 3.5b Bioretention Infiltration Sump Depth	167
Equation 3.5c Bioretention Infiltration Rate Check	167
Equation 3.8 Minimum Filter Surface Area for Filtering Practices	195
Equation 3.9 Required Ponding Volume for Filtering Practices	196
Equation 3.10 Storage Volume for Filtering Practices	
Equation 3.11 Maximum Surface Basin Depth for Infiltration Basins	211
Equation 3.12 Maximum Underground Reservoir Depth for Infiltration Trenches	211
Equation 3.13 Surface Basin Surface Area for Infiltration Basins	212
Equation 3.14 Underground Reservoir Surface Area for Infiltration Trenches	 212
Equation 3.15 Storage Volume Calculation for Surface Basin Area for Infiltration Basins	 213
Equation 3.16 Storage Volume Calculation for Underground Reservoir Surface Area for	
Infiltration Trenches	213
Equation 3.17 Manning's Equation	232
Equation 3.18 Continuity Equation	232
Equation 3.19 Minimum Width	233
Equation 3.20 Corresponding Velocity	233
Equation 3.21 Grass Channel Length for Hydraulic Residence Time of 9 minutes (540 se	
Equation 3.22 Grass Channel Storage Volume	234
Equation 3.23 Dry Swale Storage Volume	234
Equation 3.24 Wet Swale Storage Volume.	 235
Equation 3.25 Pond Storage Volume	255
Equation 3.26 Water Balance Equation for Acceptable Water Depth in a Wet Pond	
Equation 3.27 Baseflow Conversion.	
Equation 3.28 Stormwater Wetland Storage Volume	 271
Equation 3.29 Water Balance for Acceptable Water Depth in a Stormwater Wetland	
Equation 3.30 Minimum Depth of the Permanent Pool	
Equation 2.1 Stormwater Retention Volume	18
Equation 2.2 Water Quality Treatment Volume	24
Equation 3.1 Storage Volume for Green Roofs	<u></u> 65
Equation 3.2 Reservoir Layer or Infiltration Sump Depth	128
Equation 3.3 Drawdown Time	
Equation 3.4 Permeable Pavement Storage Volume	130
Equation 3.5 Bioretention Storage Volume	
Equation 3.6 Bioretention Infiltration Sump Depth	
Equation 3.7 Bioretention Infiltration Rate Check	167
Equation 3.8 Minimum Filter Surface Area for Filtering Practices	195

Equation 3.9 Required Ponding Volume for Filtering Practices	_196
Equation 3.10 Storage Volume for Filtering Practices	196
Equation 3.11 Maximum Surface Basin Depth for Infiltration Basins	_211
Equation 3.12 Maximum Underground Reservoir Depth for Infiltration Trenches	
Equation 3.13 Surface Basin Surface Area for Infiltration Basins	_212
Equation 3.14 Underground Reservoir Surface Area for Infiltration Trenches	_212
Equation 3.15 Storage Volume Calculation for Surface Basin Area for Infiltration Basins	_213
Equation 3.16 Storage Volume Calculation for Underground Reservoir Surface Area for	
Infiltration Trenches.	_213
Equation 3.17 Manning's Equation	_232
Equation 3.18 Continuity Equation	_232
Equation 3.19 Minimum Width	233
Equation 3.20 Corresponding Velocity.	233
Equation 3.21 Grass Channel Length for Hydraulic Residence Time of 9 minutes (540 secon	ids)
	_233
Equation 3.22 Grass Channel Storage Volume.	_234
Equation 3.23 Dry Swale Storage Volume	_234
Equation 3.24 Wet Swale Storage Volume	_235
Equation 3.25 Pond Storage Volume	
Equation 3.26 Water Balance Equation for Acceptable Water Depth in a Wet Pond	_256
Equation 3.27 Baseflow Conversion.	
Equation 3.28 Stormwater Wetland Storage Volume	_271
Equation 3.29 Water Balance for Acceptable Water Depth in a Stormwater Wetland	_271
Equation 3.30 Minimum Depth of the Permanent Pool	_272
RROPOS	

Chapter 1 Introduction to the Stormwater Management Guidebook

1.1 Introduction

The District of Columbia (District), like most ultra-urban areas, experiences increased stormwater runoff that results from development. This runoff places a burden on sewer systems and degrades aquatic resources when it is not managed adequately. Unmanaged stormwater runoff overloads the capacity of streams and storm sewers and is responsible for increased combined sewer overflow events and adverse downstream impacts, such as flash flooding, channel erosion, surface and groundwater pollution, and habitat degradation.

Recognizing this issue, the District first adopted stormwater management regulations in 1988. These regulations (Chapter 5 of Title 21 of the District of Columbia Municipal Regulations) (21 DCMR), established requirements to manage both stormwater quality and quantity. Quality control focused on the removal of pollutants from up to the first 0.5 inchesinch of stormwater runoff, often referred to as the "first flush." Quantity control was mandated through detention requirements based on the 2-year, 24-hour storm event for stream bank protection (widely accepted as the channel shaping flow) and the 15-year, 24-hour storm event for flood protection (the typical design capacity of the District's sewer conveyance system).

This Stormwater Management Guidebook (SWMG) provides technical guidance on In 2013, the 2013 revisions to the 1988 District's stormwater management regulations. The detention requirements have not changed significantly, but the focus on water quality treatment has shifted to a its stormwater quality standard for volume to a retention-based standard. Major land-disturbing activities must retain the volume from a 1.2-inch storm event, and major substantial improvement activities must retain the volume from a 0.8-inch storm event. By keeping stormwater on site, retention practices effectively provide both treatment and additional volume control, significantly improving protection for District waterbodies. This The Stormwater Retention Volume (SWRv) can be managed through runoff prevention (e.g., conservation of pervious cover or reforestation), runoff reduction (e.g., infiltration or water reuse), and runoff treatment (e.g., plant/soil filter systems or permeable pavement).

The Stormwater Management Guidebook (SWMG) provides technical guidance on the 2013 and 2019 revisions to the 1988 regulations.

1.2 Purpose and Scope

The purpose of the SWMG is to provide the technical guidance required to comply with the District's stormwater management regulations, including the criteria and specifications engineers and planners use to plan, design, and construct regulated sites and stormwater best management practices (BMPs).

It is the responsibility of the design engineer to review, verify, and select the appropriate BMPs and materials for a specific project and submit to DDEEDOEE, as required, all reports, design computations, worksheets, geotechnical studies, surveys, rights-of-way determinations, etc. Each such required submittal will bear the seal and signature of the professional engineer licensed to practice in the District who is responsible for that portion of the project.

1.3 Impacts of Urban Runoff

Historically, the collective impacts of rooftops, sidewalks, roadways, and other impervious surfaces on District streams and rivers have been divided into two categories, those attributed to changes in hydrologic response or those-resulting from human activities. The hydrologic response of an urban area changes when drainage areas become increasingly impervious, causing stormwater runoff volumes, flows, and velocities to increase while base groundwater flows decrease. Small annual storm events that would ideally be captured by the plants and soils of an undeveloped landscape are instead delivered quickly and efficiently through the receiving pipe network to city streams. Human activities in the city, ranging from heavy automobile traffic to use of various chemicals, generate increased pollutant loads. During dry weather, these pollutants combine with deposits of atmospheric pollution from outside of the city to build up on impervious surfaces where rain and snow events later wash them into the District's storm sewer pipes, streams, and rivers.

1.3.1 Hydrologic Impacts

Urban development causes significant changes in the rainfall—runoff relationship within a watershed. Rainfall volumes shift from evapotranspiration and infiltration to surface and piped runoff. This shift delivers large amounts of runoff to receiving pipes and streams during even the smallest rainfall event within an urban development (see Figure 1.1).

A city represents a transformation from a natural catchment to a sewershed through an increase in impervious surfaces and the addition of an underground, piped conveyance system. Natural drainage patterns are modified and stormwater runoff is channeled through roof drains, pavement, road gutters, and storm drains. Direct connections between impervious surfaces and stormwater conveyance systems (meant to avoid flooding) deliver these larger volumes more quickly, which leads to an increase in runoff volumes and velocities. The time runoff takes to travel downstream becomes shorter, and infiltration into underlying soils and groundwater aquifers decreases or is eliminated (see Figure 1.2).

The District's 1988 stormwater management regulations responded to these volume impacts with a focus on "peak matching," where volume releases were delayed and released at a 2-year flow rate. Recent research has found that this approach has, in many cases, led to an increase in stream erosion because the full runoff volume is still forced through the receiving channel. Even at this low flow rate, the channel is subjected to an elevated flow for prolonged durations.

In addition, a 2-year flow control structure allows the large number of smaller-sized storms to wash off a site at the discharge rate allowed for the 2-year storm, when they should have a lower discharge rate. The District's new stormwater retention requirements complement and improve peak flow matching by retaining stormwater from these smaller storms on—site and reducing the

overall runoff volumes that leave the site. Retention is a better approximation of the natural drainage cycle.




Figure 1.1 Changes in the water balance resulting from urbanization (FISRWG, 1998).




Figure 1.2 Changes in streamflow resulting from urbanization (Schueler, 1987).

1.3.2 Water Quality Impacts

As land is developed, impervious surfaces replace naturally vegetated areas that once allowed water to infiltrate and become purified by the soil. Approximately 43 percent of the District's natural groundcover has been replaced with impervious surfaces, which accumulate pollutants deposited from the atmosphere, leaked from vehicles, or windblown and from adjacent areas. During storm events, these pollutants quickly wash off impervious surfaces and are delivered rapidly to downstream waters. Table 1.1 profiles common pollutants found in urban stormwater runoff and their sources.

Pollutant	Automobile/ Atmospheric Deposition	Urban Housekeeping / Landscaping Practices	Industrial Activities	Construction Activities	Connections other than Stormwater	Accidental Spills and Illegal Dumping
Sediments	X	X	X	X		
Nutrients	X	X	X	X	X	X
Bacteria and Viruses	X	X		X	X	X
Oxygen Demanding Substances		X	X	X	X	Х
Oil and Grease	X	X	X	X	X	X
Anti-Freeze	X	X		X	X	X
Hydraulic Fluid	X	X	X	X	X	X
Paint		X		X	X	X
Cleaners and Solvents	X	X	X	X	X	X
Wood Preservatives		X		X	X	X
Heavy Metals	X	X	X	X	X	X
Chromium	X	X	X			
Copper	X	X	X			
Lead	X	X	X			
Zinc	X	X	X			
Iron	X	0	X			
Cadmium	X		X			
Nickel	X		X			
Magnesium	X	7	X			
Toxic Materials						
Fuels	X		X	X	X	X
PCBs	X				X	X
Pesticides	X	X	X	X	X	X
Herbicides	X		X	X	X	X
Floatables		X	X	X		

1.4 References

- Bannerman, R., D. Owens, R. Dodds, and N. Hornewer. 1993. Sources of Pollutants in Wisconsin Stormwater. Water Science and Technology. 28(3-5):241-259.
- California Stormwater Quality Taskforce (SWQTF). 1993. California Stormwater Best Practices Handbook.
- The Federal Interagency Stream Restoration Working Group (FISRWG).1998. Stream Corridor Restoration: Principles, Processes, and Practices. GPO Item No. 0120-A; SuDocs No. A 57.6/2:EN 3/PT.653. ISBN-0-934213-59-3
- Schueler, Thomas R. 1987. Controlling Urban Runoff: A Practice Manual for Planning and Designing Urban BMPs. Department of Environmental Programs. Metropolitan Washington Council of Governments. Prepared for: Washington Metropolitan Water Resources Planning Board. Washington, DC.
- U.S. Environmental Protection Agency. 1983. Results of the Nationwide Urban Runoff Program. Volume I. Final Report. U.S. Environmental Protection Agency, Water Planning Division. Washington, DC.
- Waschbusch et al. 2000. Sources of phosphorus in stormwater and street dirt from two urban residential basins in Madison, Wisconsin, 1994-1995. In: National Conference on Tools for Urban Water Resource Management and Protection. US EPA February 2000: pp. 15-55.

Chapter 2 Minimum Control Requirements

2.1 District of Columbia Stormwater Management Performance Requirements

This chapter presents a unified approachdescribes minimum stormwater management performance requirements for sizingregulated activity and the subsequent sizing of stormwater best management practices (BMPs) in the District of Columbia (District) to retain runoff, meet pollutant removal goals, reduce peak discharges, and passcontrol discharges from extreme floods. Table 2.1 presents a summary of the sizing criteria used to achieve the stormwater management performance requirements for regulated activity. which are described in detail later in this chapter. Stormwater management performance requirements refers to these specific aspects of BMP function, while stormwater management requirements more broadly refer to all requirements under 21 DCMR, Chapter 5.

Those portions of regulated activity that involve the reconstruction of the existing public right-of-way (PROW) are governed by a "maximum extent practicable" (MER) approach, detailed in Appendix B. There, "Maximum Extent Practicable Process for Existing Public Right-of-Way." Also, there are notes throughout this chapter that identify special conditions for regulated activity located in the Anacostia Waterfront Development Zone (AWDZ) that are governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 (see D.C. Official Code §§ 2-1226.36(c)(1)). Figure 2.1 provides a map that outlines the boundaries of the AWDZ and the exact boundaries, which are provided in definitions foundalso defined in Appendix UW.

This chapter describes the seven sizing criteria in detail and provides guidance on how to properly compute and manage the required volumes. This chapter also presents an overview of acceptable BMP options that can be used to comply with the sizing criteria. Appendix A provides a line by line review of the accompanying calculator spreadsheets.

Note: 2 year post development peak discharge requirements do not apply to projects when three conditions can be established: (1) site discharges flow directly to, or through the separate sewer system, into the main stem of the tidal Potomac or Anacostia Rivers, the Washington Channel, or the Chesapeake and Ohio Canal; (2) site discharges do not flow into or through a tributary to those waterbodies that runs above ground or that the District Department of the Environment (DDOE) expects to be daylighted to run above ground; and (3) site discharges will not cause erosion of land or transport of sediment.

 Table 2.1 Sizing Criteria for Stormwater Management Performance Requirements

Sizing Criteria	Description of Stormwater Sizing Criteria				
Stormwater Retention	$SWRv = [P \times [(Rv_f \times \%I) + (Rv_C \times \%C) + (Rv_N \times \%N)] \times SA] \times 7.48/12$				
Volume	$SWR_V = \frac{P \times \left[(Rv_I \times I) + (Rv_C \times C) + (Rv_N \times N) \right] \times 7.48}{(Rv_N \times I)}$				
(SWRv) (gal)	$SWRv = \frac{12}{12}$				
	<u> </u>				
i	where:				
	SWRv = volume required to be retained on site (gal) P = variable percentile rainfall event for the District dependent on				
	regulatory trigger (see next criterion)in.)				
	$Rv_I = 0.95$ (runoff coefficient for impervious cover and BMP cover)				
	<u>I</u> = impervious cover surface area (ft ²)				
₁	Rv_C = 0.25 (runoff coefficient for compacted cover) C = compacted cover surface area (ft ²)				
	$Rv_N = 0.00$ (runoff coefficient for natural cover)				
	%I = percent of site in impervious cover (decimal)				
	%C = percent of site in compacted cover (decimal)				
	%N = percent of site in-natural cover (decimal)				
	SA = surface area (ft²) 7.48 = conversion factor, converting cubic feet to gallons				
	12 = conversion factor, converting cubic feet to ganons				
Precipitation value	Major Land Disturbing Activity and disturbing activity (AWDZ and District-wide):				
selected based on	90th percentile event (1.2 inches)in.)				
Regulatory	Major Substantial Improvement Activity substantial improvement activity (AWDZ):				
Trigger regulatory trigger	85th percentile event (1.0 inches)in.)				
(P)	Major Substantial Improvement Activity substantial improvement activity (District-				
	wide): 80th percentile event (0.8 inches)in)				
Reconstruction of public	Maximum extent practicable process for existing public right-of-way				
right-of-way	Consult Appendix B				
	Maximum Extent Practicable Process for Existing Public Right-of-Way				
Water Quality Treatment	$WQTv = (P \times \{(Rv_1 \times \%I) + (Rv_C \times \%C) + (Rv_A \times \%N) \times SA\} \times 7.48/12) - SWRv$				
Volume (WQTv) (gal)	$WQTv = \frac{P \times \left[(Rv_I \times I) + (Rv_C \times C) + (Rv_N \times N) \right] \times 7.48}{12} - SWRv$				
(applies only to regulated	$\frac{WQTV}{12}$				
activity in the AWDZ	where:				
area governed by the	WQTv = volume required to be retained or treated, above and —beyond the				
Anacostia Waterfront Environmental Standards	SWRv (gal)				
Amendment Act of 2012)	WRy = volume required to be retained on site (gal) P = 95th percentile rain event for the District (1.7 inches)in.)				
	Rv ₁ = 93th percentile rain event for the District (1.7 menes)) Rv ₁ = 0.95 (runoff coefficient for impervious cover and BMP cover)				
	$I = \text{impervious cover surface area (ft}^2)$				
·	$Rv_C = 0.25$ (runoff coefficient for compacted cover)				
	$\frac{C}{R} = \text{compacted cover surface area (ft}^2)$				
i I	$Rv_N = 0.00$ (runoff coefficient for natural cover) $\frac{\%I}{} = {}$ percent of site in impervious cover (decimal)				
	%C = percent of site in compacted cover (decimal)				
	%N = percent of site in-natural cover (decimal)				
	SA = surface area (ft ²)				
	7.48 = conversion factor, converting cubic feet to gallons SWRv = volume required to be retained (gal)				
	12 = conversion factor, converting inches to feet				
2-Year Storm Control	The peak discharge rate from the 2-year, 24-hour storm event controlled to the				

Field Code Changed

Field Code Changed

(Qp ₂)	predevelopment peak discharge rate-
15-Year Storm Control (Qp ₁₅)	The peak discharge rate from the 15-year, 24-hour storm event controlled to the preproject pre-project peak discharge rate.
Extreme Flood Requirements (Q _f)	The peak discharge rate from the 100-year storm event controlled to the preproject pre-project peak discharge rate if the site: 1. Increases the size of a Special Flood Hazard Area (SFHA) as delineated on the effective Flood Insurance Rate Maps Map (FIRM) or 2. Meets the following two conditions: (a) Does not discharge to the sewer system and (b) Has a post-development peak discharge rate for a 100-year frequency storm event that will cause flooding to a building-




Figure 2.12.1 Map of the Anacostia Waterfront Development Zone.

2.2 Stormwater Retention Volume

2.2 Regulated Site Definition and Examples

Per Appendix W. "Definitions," the following types of activities contribute to triggering stormwater management requirements:

Land-disturbing activity - Movement of earth, land, or sediment that disturbs the land surface and the related use of pervious land to support that movement. Land-disturbing activity includes stripping, grading, grubbing, trenching, excavating, transporting, and filling of land, as well as the use of pervious adjacent land for movement and storage of construction vehicles and materials. Land-disturbing activity does not include repaving or remilling that does not expose the underlying soil.

Substantial improvement - A repair, alteration, addition, or improvement of a building or structure, the cost of which equals or exceeds fifty percent (50%) of the market value of the structure before the improvement or repair is started.

When determining the pre-project assessed value of a structure, this information must come from the District's Office of Tax and Revenue (OTR). Additionally, DOEE considers excavation and other activities which expose soil within an existing building footprint to be land disturbance if at least one wall is removed from the building during construction. Otherwise, the activity is considered to be part of the improvements to the building.

If activities at a site are large or substantial enough, they may trigger stormwater management requirements if the activities fit into one or both of the following definitions:

Major land-disturbing activity - Activity that disturbs, or is part of a common plan of development that disturbs, a land area of 5,000 square feet or greater, and:

- (a) Some area of the pre-project land cover is natural, or
- (b) 2,500 square feet or greater of the post-project land cover is impervious.

Multiple distinct projects that each disturb less than 5,000 square feet of land and are in separate, non-adjacent sites do not constitute a major land-disturbing activity.

Major substantial improvement activity - Substantial improvement activity and associated land-disturbing activity, including such activities that are part of a common plan of development, for which the combined footprint of improved building and land-disturbing activity is 5,000 square feet or greater, and either of the following:

- (a) Some area of the pre-project land cover is natural; or
- (b) 2,500 square feet or greater of the post-project land cover is impervious.

A major substantial improvement activity may include a substantial improvement activity that is not associated with land disturbance.

Additionally, a project may include both major land-disturbing activity and major substantial improvement activity. See examples below.

Sites that undergo a major land-disturbing activity or a major substantial improvement activity must employ BMPs and post-development land cover necessary to achieve the stormwater retention volume (SWRv) equal to the post-development runoff from the applicable rainfall event, as measured for a 24-hour storm with a 72-hour antecedent dry period. For a major land-disturbing activity, the applicable rainfall event is the 90th percentile rainfall event (1.2 inches). For a major substantial improvement activity located in the AWDZ, governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, the applicable rainfall event is the 85th percentile rainfall event (1.0 inchesinch). For all other major substantial improvement activities throughout the District, the applicable rainfall event is the 80th percentile rainfall event (0.8 inches). The SWRv is calculated as follows for the entire site and for each drainage area:inch). For any land disturbance in the PROW, the applicable rainfall event is the 90th percentile rainfall event (1.2 inches), which should be met to the MEP. For projects that include a major land-disturbing activity and a major substantial improvement activity, calculate the SWRv for each activity using the applicable rainfall event and add them together to determine the SWRv for the entire site.

The following 16 examples help clarify how the requirements apply in a variety of situations involving building renovations or additions and accompanying land disturbances, if any. The examples assume that a project is not located in the AWDZ. While many situations are discussed in these examples, this list is not intended to be exhaustive. Site owners are strongly encouraged to reach out to DOEE to help determine whether their project triggers stormwater management requirements.

Example 1: An existing building with a footprint of 5,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. The entire project constitutes a major substantial improvement activity.

Building Renovation

Footprint = 5,000 square feet

Construction cost \geq 50% assessed value of building

Retention standard for Building Renovation (5,000 square feet) 0.8 inch

Example 2: Two existing buildings are being renovated, one of which has a footprint of 4,000 square feet and the other has a footprint of 1,000 square feet. The cost of those renovations for each building is greater than 50% of that building's assessed value. Combined, the entire project constitutes a major substantial improvement activity.

Building Renovation 1

Footprint = 4,000 square feet

Construction cost \geq 50% assessed value of

building

Building Renovation 2

Footprint = 1,000 square feet

Construction cost ≥ 50% assessed value o

Retention standard for Building Renovation 1 and 2 (5,000 square feet) 0.8 inch

Example 3: Two existing buildings are being renovated, one of which has a footprint of 4,000 square feet, and the other has a footprint of 1,000 square feet. The cost of renovations for Building 1 is less than 50% of the building's assessed value, while the cost of renovations for Building 2 is greater than 50% of the building's value. Though the combined footprint of the two buildings is 5,000 square feet or greater, since the construction cost of one of the buildings is less than 50% of its pre-project assessed value, the project is not considered a major substantial improvement activity.

Building Renovation 1

Footprint = 4,000 square feet

<u>Construction cost < 50% assessed value of building</u>

Building Renovation 2

Footprint = 1,000 square feet

Construction cost \geq 50% assessed value of building

Retention standard for Building Renovation 1 (4,000 square feet) N/A Retention standard for Building Renovation 2 (1,000 square feet) N/A

Example 4: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 1,000 square feet of adjacent land is being disturbed. Since the total project footprint is equal to 5,000 square feet and the post-project impervious area is at least 2,500 square feet, the entire project, including adjacent land disturbance, constitutes a major substantial improvement activity and is regulated at the 0.8-inch standard.

Building Renovation

Footprint = 4,000 square feet

Construction cost \geq 50% assessed value of building

<u>Land Disturbanc</u> = 1,000 square fee compacted cover

Retention standard for Building Renovation (4,000 square feet)

Retention standard for Land Disturbance (1,000 square feet)

0.8 inch

0.8 inch

Example 5: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 7,000 square feet of adjacent land is being disturbed that will include 3,000 square feet of impervious cover. The building, being part of a total project footprint that is at least 5,000 square feet with at least 2,500 square feet of post-project impervious area, is considered a major substantial improvement activity and is regulated at the 0.8-inch standard. The land disturbance is at least 5,000 square feet and includes at least 2,500 square feet of post-project impervious land cover. Therefore, it is regulated as a major land-disturbing activity, with a 1.2 inch retention standard.

Building Renovation

Footprint = 4,000 square feet

Construction cost \geq 50% assessed value of building

Land Disturbance

<u>= 4,000 square feet</u>

<u>compacted cover and 3,000</u>

Retention standard for Building Renovation (4,000 square feet) 0.8 inch

Retention standard for Land Disturbance (7,000 square feet) 1.2 inches

(Detention requirements may also apply – see sections 2.6 and 2.7.)

Example 6: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 6,000 square feet of adjacent land is being disturbed that will include 2,000 square feet of impervious cover. Since the total project footprint is at least 5,000 square feet, and the post-project impervious area is at least 2,500 square feet, the building is considered a major substantial improvement activity. While the land disturbance is greater than 5,000 square feet, it does not include at least 2,500

square feet of post-project impervious land cover. Therefore, it is not a major land-disturbing activity and is instead considered as part of the major substantial improvement activity, regulated at the 0.8-inch standard.

Building Renovation

Footprint = 4,000 square feet

Construction cost \geq 50% assessed value of building

Land Disturbance
= 4,000 square feet
compacted cover and 2,000
square feet of impervious
cover

Retention standard for Building Renovation (4,000 square feet) 0.8 inch

Retention standard for Land Disturbance (6,000 square feet) 0.8 inch

Example 7: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 5,000 square feet of adjacent land is being disturbed (including both the private property and the existing PROW) that will include a total of 3,000 square feet of impervious cover post-project. The building, being part of a total project footprint that is at least 5,000 square feet with at least 2,500 square feet of post-project impervious area, is considered a major substantial improvement activity and is regulated at the 0.8-inch standard. The land disturbance is at least 5,000 square feet and includes at least 2,500 square feet of post-project impervious land cover. Therefore, it is regulated as a major land-disturbing activity, with a 1.2-inch retention standard. Land disturbance in the existing PROW that is associated with either a major substantial improvement activity or a major land-disturbing activity is always required to meet the 1.2-inch standard to the MEP.

Building Renovation

Footprint = 4,000 square feet Construction cost $\geq 50\%$ assessed value of building Land Disturbance
= 2,000 square feet
compacted cover
and 2,000 square
feet impervious
cover

PROW Land
Disturbance
= 1,000 square feet
impervious cover

Retention standard for Building Renovation (4,000 square feet) 0.8 inch

Retention standard for Land Disturbance (4,000 square feet) 1.2 inches (Detention requirements may also apply – see sections 2.6 and 2.7.)

Retention standard for Existing PROW Land Disturbance (1,000 square feet) 1.2 inches to

the MEP

Example 8: A building with a footprint of 2,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 3,000 square feet of adjacent land is being disturbed (including both the private property and the existing PROW) that will include 500 square feet of impervious cover in the PROW. The building, being part of a total project footprint that is at least 5,000 square feet with at least 2,500 square feet of post-

project impervious area, is considered a major substantial improvement activity and is regulated at the 0.8-inch standard. The land disturbance is less than 5,000 square feet, so it is included with the major substantial improvement activity at the 0.8-inch standard. Land disturbance in the existing PROW that is associated with either a major substantial improvement activity or a major land-disturbing activity is always required to meet the 1.2-inch standard to the MEP.

Building 1

 $\frac{\text{Footprint} = 2,000 \text{ square feet}}{\text{Construction cost} \geq 50\% \text{ assessed}}$ value of building

Land Disturbance = 2,500 square feet compacted cover

PROW Land
Disturbance
= 500 square feet
impervious cover

Retention standard for Building Renovation (2,000 square feet) 0.8 inch

Retention standard for Land Disturbance (2,500 square feet) 0.8 inch

Retention standard for Existing PROW Land Disturbance (500 square feet) the MEP

1.2 inches to

Example 9: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 1,000 square feet of adjacent existing PROW is being disturbed. Since the total project footprint is at least 5,000 square feet and the post-project impervious area is at least 2,500 square feet, the building is considered a major substantial improvement activity and is regulated at the 0.8-inch standard. Land disturbance in the existing PROW that is associated with either a major substantial improvement activity or a major land-disturbing activity is always required to meet the 1.2-inch storm to the MEP.

Building Renovation

 $\underline{Footprint = 4,000 \text{ square feet}}$

Construction cost \geq 50% assessed value of building

Existing PROW Land Disturbance = 1,000 square feet impervious cover

Retention standard for Building Renovation (4,000 square feet) 0.8 inch

Retention standard for Existing PROW Land Disturbance (1,000 square feet)

1.2 inches to the MEP

Example 10: A building with a footprint of 2,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 3,000 square feet of adjacent land is being disturbed, with a portion of the pre-project land cover being natural cover. Though post-project impervious land cover is less than 2,500 square feet, the project is considered a major substantial improvement activity regulated at the 0.8-inch standard because a portion of the pre-project land cover included natural cover.

Building Renovation

Footprint = 2,000 square feet

Construction cost \geq 50% assessed value of building

Land Disturbance

= 3,000 square fee

ompacted cov

Some pre-project land cove

= natural cove

Retention standard for 2,000 square feet (Building 1)

0.8 inch

Retention standard for 3,000 square feet (Land Disturbance)

0.8 inch

Example 11: A 5,000 square foot area is being disturbed, a portion of which was natural cover prior to the project. Though post-project impervious land cover is less than 2,500 square feet, the project is considered a major land disturbing activity regulated at the 1.2-inch standard because a portion of the pre-project land cover included natural cover.

Land Disturbance

= 5,000 square feet compacted cover.

Some pre-project land cover = natural cover.

Retention standard for Land Disturbance (5,000 square feet)

1.2 inches

Example 12: A building with a footprint of 4,000 square feet is being renovated and the cost of those renovations is less than 50% of its assessed value. In addition, 7,000 square feet of adjacent land is being disturbed that will include 3,000 square feet of impervious cover. The building does not exceed the size or cost threshold to be considered a major substantial improvement activity. The land disturbance is greater than or equal to 5,000 square feet and includes at least 2,500 square feet of post-project impervious land cover. Therefore, the land disturbance is considered a major land-disturbing activity and is regulated at the 1.2-inch standard.

Building Renovation

Footprint = 4,000 square feet

Construction cost < 50% assessed value of building

Land Disturbance

=4.000 square feet

compacted cover and 3,00

square feet impervious cover

Retention standard for Building Renovation (5,000 square feet) N/A

Retention standard for Land Disturbance (5,000 square feet) 1.2 inches

(Detention requirements may also apply – see sections 2.6 and 2.7.)

Example 13: A building with a footprint of 5,000 square feet is being renovated and the cost of those renovations is less than 50% of its assessed value. In addition, 6,000 square feet of adjacent land is being disturbed that will include 2,000 square feet of impervious cover. The building has a footprint of 5,000 square feet, but it does not exceed the cost threshold to be considered a major substantial improvement activity. The land disturbance is greater than or equal to 5,000 square

feet but it does not include at least 2,500 square feet of post-project impervious land cover. Therefore, the land disturbance is not considered a major land-disturbing activity.

Building Renovation

Footprint = 5,000 square feet

Construction cost < 50% assessed value of building

Land Disturbance
= 4,000 square feet
compacted cover and 2,000
square feet impervious cover

Retention standard for Building Renovation (5,000 square feet) N/A

Retention standard for Land Disturbance (6,000 square feet) N/A

Example 14: A building with a footprint of 2,000 square feet is being renovated and the cost of those renovations is greater than 50% of its assessed value. In addition, 3,000 square feet of adjacent land is being disturbed, but it will not include any impervious cover. While the total project footprint equals 5,000 square feet and the building renovation exceeds the 50% cost threshold, the total impervious cover for the site is less than 2,500 square feet. Consequently, the project is neither a major substantial improvement nor a major land disturbing activity.

Building Renovation

Footprint = 2,000 square feet

Construction cost \geq 50% assessed value of building

<u>Land Disturbance</u> = 3,000 square feet compacted cover

Retention standard for Building Renovation (2,000 square feet) N/A

Retention standard for Land Disturbance (3,000 square feet) N/A

Example 15: An 11,000 square foot area is being disturbed, of which only 1,000 square feet will be impervious. Since the post-project impervious cover is less than 2,500 square feet, the project is not considered a major land disturbing activity.

Land Disturbance

= 10,000 square feet compacted cover and 1,000 square feet impervious cover

Retention standard for Land Disturbance (11,000 square feet) N/A

Example 16: A 5,000 square foot area is being disturbed. Once the project is complete, 2,000 square feet will be compacted cover, 1,000 square feet will be impervious cover, and 2,000 square feet will be a BMP. For the purposes of determining a project's regulatory status, BMP area is considered a part of the impervious cover. Since the disturbed area equals 5,000 square feet and the post-project impervious area (including BMP area) is greater than 2,500 square feet,

the project is considered a major land disturbing activity and is regulated at the 1.2-inch standard.

Land Disturbance

= 2,000 square feet compacted cover

1,000 square feet impervious cover,

and 2,000 square feet BMP

Retention standard for Land Disturbance (5,000 square feet) 1.2 inches

(Detention requirements may also apply – see sections 2.6 and 2.7.)

2.3 Stormwater Retention Volume

The SWRv is the volume of stormwater runoff that is required to be retained. It is calculated as shown in Equation 2.1 for the entire site and for each site drainage area (SDA).

Equation 2.1 Stormwater Retention Volume

$$SWRv = \frac{\{P \times [(Rv_I \times \%I) + (Rv_C \times \%C) + (Rv_N \times \%N)] \times SA\} \times 7.48}{12}$$

$$SWRv = \frac{P \times [(Rv_I \times I) + (Rv_C \times C) + (Rv_N \times N)] \times 7.48}{12}$$

where:

SWRv = volume required to be retained on site (gal)

P = selection of District-variable percentile rainfall event varies based for the District dependent on regulatory trigger;:

- 90th percentile (1.2 inches) for major land-disturbing activity,
- 85th percentile (1.0 <u>inchesinch</u>) for major substantial improvement activity in the AWDZ and governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, 80th percentile (0.8 inches) for other major substantial improvement activities
- 80th percentile (0.8 inch) for other major substantial improvement activities

 $Rv_I = \underline{0.95}$ (runoff coefficient for impervious cover $\underline{(0.95)}$ and BMP cover)

%I = percent of site in impervious cover surface area (ft²)

 Rv_{ϵ} = runoff coefficient for compacted cover (0.25)

 $\frac{\%C}{\text{cover}} = \frac{\text{percent of site in}Rv_C}{\text{cover}} = \frac{0.25 \text{ (runoff coefficient for compacted cover)}}{\text{cover}}$

C = compacted cover surface area (ft²)

 R_{V_A} = runoff coefficient for natural cover (0.00)

 $\frac{\%N}{N}$ = percent of site in Rv_N = 0.00 (runoff coefficient for natural cover)

SA = N = natural cover surface area (ft²)

7.48 = conversion factor, converting cubic feet to gallons 12 = conversion factor, converting inches to feet

where the <u>The</u> surface area <u>underof</u> a BMP shall be calculated as part of the impervious cover (%T); and.

A site may achieve on-site retention by directly conveying volume from the regulated site to a shared BMP with available retention capacity.

A site may achieve the SWRv on-site or through a combination of on-site retention and off-site retention under the following conditions:

- The If the site is located in the municipal separate storm sewer system (MS4), or drains to be Combined Sewer System (CSS) from a sewershed where combined sewer overflows (CSOs) will be reduced with green infrastructure, the site shall retain on site a minimum of 50 percent% of the SWRv calculated for the entire site, unless DDOEDOEE approves an application for relief from extraordinarily difficult site conditions (see Appendix E) "Relief from Extraordinarily Difficult Site Conditions"). Figure 2.2 provides a map that outlines the boundaries of the District's CSS and MS4. A more detailed map can be found in DOEE's submittal database, the Stormwater Database.
- If the site drains to the CSS from a sewershed where CSOs will be reduced with storage tunnels, there is no minimum on-site retention provided that any Stormwater Retention Credit (SRC) used to meet the Off-Site Retention Volume (Offv) is generated from a BMP or land cover change outside the CSS. These sites do not need to request relief from extraordinarily difficult site conditions.
- The site shall use off-site retention for the portion of the SWRv that is not retained on site (Seesee Chapter 6. "Use of Off-Site Retention by Regulated Sites" and Appendix C. "Off-Site Retention Forms for Regulated Sites").
- Regulated activity in the AWDZ, governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, must have all apply for relief from extraordinarily difficult site conditions (see Appendix E. "Relief from Extraordinarily Difficult Site Conditions") for any off-site retention approved by DDOE even if the minimum 50 percent% on-site requirement has been achieved. These projects may apply to achieve retention compliance with off-site retention based on considerations of technical infeasibility and environmental harm as well as the limited appropriateness of on-site compliance in terms of impact on surrounding landowners or overall benefit to District waterbodies.
- Projects requesting relief from compliance with the minimum on-site retention obligation (50% of the SWRv) and claiming "based on extraordinarily difficult site conditions" will follow are subject to the submission and evaluation process detailed in Appendix E₇, "Relief from Extraordinarily Difficult Site Conditions." Sites approved for "granted relief from extraordinarily difficult site conditions" are still responsible for the entire SWRv₂ but will be allowed to use off-site retention to achieve more than 50percent50% of the SWRv₂.

An individual Site drainage area (SDA) is defined as the area that drains to a single discharge point from the site.

A or sheet flows from a single area of the site may achieve on-site retention by retaining (see Appendix U. "Site Drainage Area and BMP Design Diagrams" for more than the SWRv in an individual drainage area information about how to identify SDAs).

Retention in excess of the regulated SWRv for one SDA may be applied to the SWRv for another SDA for the same project, subject to the following conditions:

- For each drainage area, as well as for all vehicular access areas within each drainage areaSDA that does not drain to the CSS, at least 50-percent% of the SWRv must be retained or treated with an accepted practice to remove 80-percent% of total suspended solids (TSS), unless it drains into the combined sewer system.). Figure 2.2 provides a map that outlines the boundaries of the District's CSS and MS4.
- For each SDA that does not drain to the CSS, at least 50% of the SWRv from the entire vehicular access area must be treated with an accepted practice to remove 80% of TSS. For vehicular access areas in the PROW that are part of a submission following the maximum extent practicable (that follows the MEP) process, the MEP narrative must addressidentify the opportunities for placement and sizing opportunities and of accepted practices and, if the minimum treatment volume is not achieved, the restrictions of a retention practice where these minimums are not achieved. Figure 2.2 provides a map that outlines the boundaries of the District's Combined Sewer System (CSS) and Municipal Separate Storm Sewer System (MS4)-making such treatment impracticable.
- Retention in excess of the SWRv for one drainage area may be applied to the retention volume required for another drainage area;
- Retention of <u>a volume of stormwater</u> greater than that from a 1.7-inch rainfall event, calculated using the SWRv equation with a P equal to 1.7 inches, shall not be counted toward on-site retention.




Figure 2.22.2 Map of District of Columbia MS4 and CSS areas.

The following are "Accepted Practices" by DDOE for DOEE-accepted treatment practices to remove 80-percent% of TSS:

- Permeable Pavement Systems
- Bioretention
- Stormwater-Filtering Systems
- Stormwater-Ponds
- Stormwater Wetlands
- Dry Swales
- Wet Swales
- Proprietary practices that have been demonstrated to achieve an 80-percent% reduction in TSS in accordance with the requirements of Appendix S. "Proprietary Practices Approval Process."

Major land-disturbing activities in the existing <u>public right of wayPROW</u>, including activities associated with a major land-disturbing activity on private property, must achieve the SWRv to the MEP. The MEP design and review process is detailed in Appendix B-, "Maximum Extent Practicable Process for Existing Public Right-of-Way."




Figure 2.2 Map of District of Columbia MS4 and CSS areas.

2.32.4 Water Quality Treatment Volume

In addition to the SWRv requirements above, sites located in the AWDZ that are publicly owned or publicly financed and governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 shall employ BMPs and post-development land cover necessary to achieve a water quality treatment volume (WQTv) equal to the difference between the post-development runoff from the 95th percentile rainfall event (1.7 inches), measured for a 24-hour rainfall event with a 72-hour antecedent dry period, and the SWRv. The WQTv is calculated as follows; shown in Equation 2.2 for the entire site; and each individual drainage area: SDA.

Equation 2.2 Water Quality Treatment Volume

$$WQTv = \{P \times [(Rv_I \times \%I) + (Rv_C \times \%C) + (Rv_N \times \%N)] \times SA\} \times 7.48 - SWRv$$

$$WQTv = \frac{P \times \left[(Rv_I \times I) + (Rv_C \times C) + (Rv_N \times N) \right] \times 7.48}{12} - SWRv$$

where:

WQTv = volume, in gallons, required to be retained or treated, above and beyond the Stormwater Retention Volume (SWRv). (gal)

SWRv = volume, in gallons, required to be retained, as described in Section 2.2

P = 95th percentile rainfall event for the District (1.7 inches)

 $Rv_I = 0.95$ (runoff coefficient for impervious cover and BMP cover)

I = impervious cover surface area (ft)

 $Rv_C = 0.25$ (runoff coefficient for compacted cover)

C = compacted cover surface area (ft²)

 $Rv_N = 0.00$ (runoff coefficient for natural cover)

%I = percent of site in impervious cover

%C = percent of site in compacted cover

 $\frac{9}{6}N = \frac{\text{percent of site in natural cover}}{\text{surface area in square feet } (t^2)}$

SA = _surface area in square feet, (ft^2)

where, the 7.48 = conversion factor, converting cubic feet to gallons

SWRv = volume required to be retained, as described in Section 2.3 (gal)

12 = conversion factor, converting inches to feet

The surface area under of a BMP shall be calculated as part of the impervious cover (%1); and.

A site in the AWDZ that is governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 may achieve on-site treatment for WQTv with the following methods:

- On-site treatment with an accepted treatment-practice designed to remove 80-percent of TSS;
- On-site retention; or

 Direct conveyance of stormwater from the site to an approved shared BMP with sufficient available treatment or retention capacity.


An AWDZ site that is governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 may achieve part of the WQTv by using off-site retention if site conditions make compliance technically infeasible or environmentally harmful and DDOE. DOEE approves an application for "relief from extraordinarily difficult site conditions:"," and the off-site retention is from outside the CSS.

An AWDZ site governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 that achieves 1 gallon of off-<u>Sitesite</u> retention volume (Offv) by using Stormwater Retention Credits (SRCs) certified for retention capacity located outside of the Anacostia watershed shall use 1.25 SRCs for that gallon of Offv.

2.5 Requirements and Compliance Flow Charts

Figures 2.3–2.7 describe are flow charts that can be used to determine the relationship between following for a variety site:

The type of project types, regulated activity and the rainfall event needed to determine the SWRv, and the WQTv.



Whether a site is an AWDZ site,

- Whether compliance for SDAs outside of the CSS are met, and
- Whether the site has achieved compliance with the stormwater management requirements.

Note: The 2,500 square foot post-project impervious and/or BMP land cover threshold includes both the renovated building footprint and any accompanying areas of land disturbance.

PROPOSED PREVISION





Figure 2.32.3 Determining the regulatory event used to calculate the SWRv.






Figure 2.42.4 Determining if overall retention the site is an AWDZ site.







Figure 2.5 Determining if the minimum SDA requirements have been met, outside the AWDZ.








Figure 2:52.5 Determining if overall retention and water quality treatment requirements have been met, inside the AWDZ for regulated activity governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012.



* Existing Public right-of-way (PROW) sites follow these guidelines to the maximum extent practicable (MEP). The MEP design and review process is detailed in Appendix B.

Figure 2.62.6 Determining if minimum retention and water quality treatment requirements have been met.




2.6 Control of 2-Year Storm

For most sites, detention must be provided on site to ensure the peak discharge rate from the 2-year, 24-hour storm event is reduced to the predevelopment peak discharge rate for the site as a whole. Predevelopment conditions are defined hydrologically as "meadow in good condition." Detention can be provided by the use of underground or surface storage practices or by increasing the size of BMPs used to meet SWRv requirements. Appendix A, "Compliance Calculations and Design Examples," includes more information about using the General Retention Compliance Calculator and Stormwater Database to account for retention BMPs when calculating detention requirements, and Appendix H, "Acceptable Hydrologic Methods and Models," includes further details and guidance for hydrologic computations.

Detention for the 2-year storm is not required for the following scenarios:

- 1. Major substantial improvement projects;
- 2. Projects that consist of reconstruction of the existing PROW; or
- 3. Projects for which stormwater runoff from the site:
 - a. Flows directly or through the MS4 to:
 - i. The main stem of the tidal Potomac or Anacostia Rivers;
 - ii. The Washington Channel; or
 - iii. The Chesapeake and Ohio Canal (C&O);
 - b. Does not flow through an above ground tributary (or through tributaries that DOEE expects to be daylighted in the future); and
 - c. Will not cause erosion of land or transport of sediment

Figure 2.7 illustrates the MS4 areas that may be exempt from the 2-year detention requirement. An interactive map of these areas is provided in the Stor nwater Database. If DOEE is aware of a tributary that is expected to be daylighted in the future, the applicant will be notified.



 $\underline{\textbf{Figure 2.7}} \ \ \textbf{Map of drainage types in the District. The Tidal MS4 areas in blue may be exempt from} \\ \underline{\textbf{2-vear detention requirements.}}$

2.7 Control of 15-Year Storm

Detention must be provided on site to ensure the peak discharge rate from the 15-year, 24-hour storm event is reduced to the pre-project peak discharge rate from the site as a whole (excluding the PROW areas). Pre-project conditions are defined as the conditions and land covers that existed on the site prior to construction. Detention can be provided using underground or surface storage practices, or by increasing the size of BMPs used to meet SWRv requirements. Appendix A, "Compliance Calculations and Design Examples," includes more information about using the General Retention Compliance Calculator and Stormwater Database to account for retention BMPs in calculating detention requirements. Appendix H, "Acceptable Hydrologic Methods and Models," includes further details and guidance for hydrologic computations.

Detention for the 15-year storm is not required for major substantial improvement projects of project areas in the existing PROW.

2.42.8 Extreme Flood Requirements

To meet the extreme flood (Q_f) requirements $(Q_f)_{r_a}$ a site shall maintain the peak discharge rate from the 100-year storm event controlled to the <u>preproject pre-project</u> peak discharge rate if the site meets one of the following:

- 1. Increases the size of a Special Flood Hazard Area (SFHA) as delineated on the effective Flood Insurance Rate MapsMap (FIRM) or
- **2.** Meets the following two conditions:
 - (a) Does not discharge to the sewer system and
 - (b) Has a post-development peak discharge rate for a 100-year-frequency storm event that will cause flooding to a building.

The intent of the extreme flood <u>criteria requirements</u> is to (a) prevent flood damage from large storm events, and (b) maintain the boundaries of the 100-year Federal Emergency Management Agency (FEMA) floodplain.

In general, stormwater runoff leaving a development site shall be discharged directly into an adequate natural or man-made receiving channel, pipe, or storm sewer system, or the applicant shall provide a drainage system satisfactory to DDEEDOEE to preclude an adverse impact (e.g., soil erosion, sedimentation, flooding, excessive duration of pondingponded water, inadequate overland relief) on downstream properties and receiving systems. If the applicant chooses to install a drainage system, the system shall be designed in accordance with established, applicable criteria for such systems.

Stormwater runoff leaving a development site where it does not discharge directly to the sewer system shall not aggravate or create a condition where an existing building is flooded from the 100-year storm event. If such a condition exists, on-site detention for the 100-year storm event shall be provided.

In situations where the size of the Special Flood Hazard Area (SFHA), as delineated on the effective Flood Insurance Rate Map (FIRM) by the Federal Emergency Management Agency (FEMA), will be increased based on the increased post-development 100-year discharge, the post-development 100-year peak discharge shall be maintained at a level that is equal to or less than the preproject project 100-year peak discharge.

2.52.9 Minimum Criteria for Determining Extreme Flood Requirements

It is recommended that an applicantapplicants use the District's online Flood Zone Determination Tool (available at

http://ddoe.dc.gov/floodplainmap)https://doee.dc.gov/floodplainmap) as an initial screening for this section.

An applicant Applicants shall use the following minimum criteria to determine whether extreme flood requirements are applicable:

Downstream Analysis:

- 1. Consult <u>DDOEDOEE</u> to <u>initially</u> determine whether <u>or not</u> the downstream analysis is needed. A site visit <u>is may be</u> necessary for the determination. This analysis is used to determine the impact of the 100-year post-development discharge on a building.
- 2. If the analysis is needed, the analysis shall contain supporting computations as justification for the conclusions contained in the analysis. For consistency, the following items are to be included, at a minimum:
 - (a) Site-specific narrative with a description of the elements of the storm drainage system, overland relief paths, and adjoining properties;
 - (b) A drainage plan showing outfall location(s) with the contributing drainage areas (CDAs) for each outfall. Digital pictures, accompanied by digital photos of the outfall-shall be included;
 - (c) A profile for each outfall channel and overland relief path;
 - (d) Two cross sections, at a minimum, at each critical location to verify the outfall and overland relief adequacy. Cross sections shall be based on a 2-foot contour interval and additional spot elevations in the vicinity. The cross sections shall have the same vertical and horizontal scales and shall identify the top of banks for the channel;
 - (e) Description of the outfall channel and permissible velocity. The Manning's roughness coefficient shall be supported by soil classification, cover material, and channel's or flow path's lining. The description of physical characteristics may include the amount of flow meandering, material classification of the flow path and its banks, vegetation, obstruction to flow, variations in cross sections, and surface irregularity;

- (f) Detailed hydrologic and hydraulic (H&&H) calculations to obtain the 100-year water surface elevation (WSE). The acceptable methodologies and models are specified in Appendix H; "Acceptable Hydrologic Methods and Models";
- (g) Delineation of the 100-year WSE on the project drainage plan to show the location and approximate extent of the overland relief path and areas that may be affected by the surface storage for the 100-year storm event. Overlaying arrows, shading or other suitable see throughtransparent graphics are suggested for this purpose; and
- (h) Certification by thea District professional engineer that no buildings will be subject to increased flooding by the 100-year post-development discharge from the development site.
- 3. If buildings will be flooded based on the analysis, then the design engineer must perform more precise hydraulieH&H computations. In addition to the on-site 100-year detention, the applicant shall design the outfall drainage system, overland relief swales, and/or surface storage in such a way that no building will be damaged by flooding.
- **4.** If the protection measures for the outfall drainage system or overland relief path are provided, necessary design details shall be shown and supported by calculations and submitted to DDOEDOEE for review.

Hydrologic and Hydraulic Analysis:

- 1. Consult <u>DDOEDOEE</u> to <u>initially</u> determine whether <u>or not the an</u> H&H analysis is needed. <u>If</u> an H&H analysis is needed, the best available information, including topographic and <u>structure data and modeling shall be used.</u> This analysis is used to determine the impact on SFHA by considering the entire watershed <u>or stream.</u>
- 2. The acceptable methodologies and models for H&H analysis are specified in Section 2.710, "Hydrology Methods" and further described in Appendix H-, "Acceptable Hydrologic Methods and Models."
- **3.** H&H investigations may be required to demonstrate that <u>upstream or</u> downstream roads, bridges, and public utilities are adequately protected from the Q_f storm. These investigations typically extend to the first downstream tributary of equal or greater drainage area or to any downstream dam, highway, or natural point of restricted stream flow.

2.61.1 Additional Stormwater Management Requirements

Any BMP that may receive stormwater runoff from areas that are potential sources of oil and grease contamination (concentrations exceeding 10 milligrams per liter) shall include a baffle, skimmer, oil separator, grease trap, or other mechanism that prevents oil and grease from escaping the BMP in concentrations exceeding 10 milligrams per liter.

Any BMP that receives stormwater runoff from areas used to confine animals may be required connect to a sanitary or combined sewer and to meet DC Water's pretreatment requirements.

2.72.10 Hydrology Methods

The following are the acceptable methodologies and computer models for estimating runoff hydrographs before and after development:

- Urban Hydrology for Small Watersheds TR-55
- Storage-Indication Routing
- HEC-HMS, WinTR-55, TR-20, and SWMM Computer Models
- Rational Method (limited to sites under 5 acres)

These methods are used to predict the runoff response from given rainfall information and site surface characteristic conditions. The design storm frequencies used in all of the hydrologic engineering calculations will be based on design storms required in this guidebook unless circumstances make consideration of another storm intensity eriteriacriterion appropriate.

- Urban Hydrology for Small Watersheds TR 55
- Storage-Indication Routing
- HEC-HMS, WinTR-55, TR-20, and SWMM Computer Models
- Rational Method (limited to sites under 5 acres)

These methods are given as valid in principle, and are applicable to most stormwater management design situations in the District. Other methods may be used when the District reviewing authority approves their application as approved by DOEE.

Note: Of the above methods, TR-55 and SWMM allow for the easiest correlation of the benefits of retention BMPs used to meet the SWRv with peak flow detention requirements and are therefore strongly recommended. The Rational Method is not recommended because it cannot account for the detention benefits of smaller retention BMPs applied on a site. However, the Rational Method is useful for quickly and easily calculating peak flows and detention requirements.

2.11 Additional Stormwater Management Requirements

Any BMP that may receive stormwater runoff from areas that are potential sources of oil and grease contamination (concentrations exceeding 10 milligrams per liter) shall include a baffle, skimmer, oil separator, grease trap, or other mechanism that prevents oil and grease from escaping the BMP in concentrations exceeding 10 milligrams per liter.

Any BMP that receives stormwater runoff from areas used to confine animals may be required connect to a sanitary or combined sewer and to meet DC Water's pretreatment requirements.

In an area along a water body, a 25-foot buffer must be established in which the land immediately adjacent to the waterbody is not disturbed, except to restore native vegetation, and/or by planting vegetation or installing other measures required by DOEE to ensure that the buffer acts as a filter to trap sediment. DOEE may approve an exception to or modification of this requirement if the land disturbance in the buffer is required to construct, install, or repair a public trail, public access point, stormwater outfall, or utility line, or if the disturbance is

required to enable development of the rest of the site and is done in a manner that is similar to the rest of the proposed project. In addition, the exception can only be approved if one of the following conditions is met:

- 1. Retention is provided for a 1.7-inch rainfall event for the disturbed area within the buffer;
- 2. The project receives relief from extraordinarily difficult site conditions for a portion of the

 1.7-inch retention requirement and achieves the required retention volume in another location on site or off site; or
- 3. DOEE grants relief for a portion of the 1.7-inch retention requirement because on-site treatment is not feasible, and DOEE approves alternatives to on-site treatment that will help to protect or restore the waterbody.

2.12 Exemptions

2.12.1 Detention for Major Substantial Improvement

A major substantial improvement activity is exempt from the 2-year and 15-year storm-control requirements.

2.12.2 Disturbance for BMP Installation

DOEE may determine that a land-disturbing activity is exempt from stormwater management performance requirements for major regulated projects, as well as requirements for covenants and easements, if the land-disturbing activity is conducted solely to install a BMP for the following reasons:

- 1. To generate a SRC as described in Chapter 7, 'Generation, Certification, Trading, and Retirement of Stormwater Retention Credits,' of this guidebook;
- 2. To earn a stormwater fee discount through RiverSmart Rewards;
- 3. To voluntarily reduce stormwater runoff in a manner that would be eligible to either generate SRCs or a stormwater fee discount, even if the person conducting the activity does not intend to apply to either program;
- 4. To provide for off-site retention through in-lieu fee payments;
- 5. To comply with a Watershed Implementation Plan established under a Total Maximum Daily Load for the Chesapeake Bay; or
- 6. To reduce CSOs in compliance with a court-approved consent decree, including court-approved modifications, or in compliance with a National Pollutant Discharge Elimination System permit.

Note: While SWMP approval of these projects does not require a declaration of covenants or easements, the applicant must provide an executed maintenance contract or a signed promise to follow the DOEE-approved maintenance plan for the period of time for which the certification of SRCs is requested. If the site fails to maintain these retention practices, DOEE has recourse that is spelled out in Chapter 5, "Administration of Stormwater Management Rules," and Chapter 7,

"Generation, Certification, Trading, and Retirement of Stormwater Retention Credits," of this guidebook.

2.12.3 Affordable Housing

For single-family or two-family affordable homes, DOEE may approve a SWMP that does not achieve the stormwater management performance requirements, provided that each of the following conditions are satisfied:

- The land-disturbing activity is less than 5,000 square feet on any single record lot or tax lot. This includes common plan of development projects for which the total disturbance is greater than 5,000 square feet, but disturbance on each single lot is less than 5,000 square feet.
- The applicant submits a request to DOEE following the procedure for a request for relief from extraordinarily difficult site conditions to DOEE see Appendix E, "Relief from Extraordinarily Difficult Site Conditions"). DOEE will evaluate whether the project has taken all practicable steps to comply with the stormwater management performance requirements.
- <u>Within</u> 30 days of sale of the house, the purchaser provides proof to DOEE that the purchaser's household income is no greater than 80% of the area median income. If the owner fails to provide proof, DOEE may require full compliance with the stormwater management performance requirements.

For previously approved projects with an Offv that fall under this exemption, DOEE may approve the elimination of the Offv obligation. Any on-site BMP that was previously constructed must continue to be maintained.

2.12.4 Trails

DOEE may exempt a land-disturbing activity, or a portion of a land-disturbing activity, from the stormwater management requirements if the pre-project land disturbance is not natural cover and the land disturbance consists solely of constructing trails for pedestrians or non-motorized vehicles. This exemption does not apply to reconstruction of a roadway and its adjacent sidewalks or if the project is part of a common plan of development that constitutes a major land disturbing activity or major substantial improvement activity independent of the trails.

2.12.5 Athletic Playing Fields, Permeable Athletic Tracks, and Permeable Playground Surfaces

A portion of the land-disturbing activity that consists of installation or replacement of athletic playing fields, permeable athletic tracks, or permeable playground surfaces is exempt from the stormwater management requirements, provided that the pre-project land disturbance for this portion of land disturbance is compacted cover or impervious cover. These surfaces must be in a publicly accessible area.

If these surfaces include an underdrain in the design, the project must be designed so that the storage volume captured below the surface is detained in the reservoir between 36 to 48 hours

before completely discharging through the underdrain. A minimum orifice size of 1 inch must be used regardless of the calculated drawdown time.

For previously approved projects with an Offv that fall under this exemption, DOEE may approve the elimination of the Offv obligation. Any on-site BMP that was previously constructed must continue to be maintained.

2.12.6 Small Structures at Parks

DOEE may exempt a land-disturbing activity or substantial improvement activity from the stormwater management requirements if the pre-project land disturbance is not natural cover and the land disturbance solely consists of construction of a pavilion, shed, dugout, or similar structure that does not include typical building infrastructure to support year-round use at a publicly accessible park. This exemption does not apply to projects that are part of a common plan of development that constitutes a major land disturbing activity or major substantial improvement activity independent of the pavilion, shed, dugout, or similar structure.

2.12.7 Utility Work

Land-disturbing activities that consist solely of cutting a trench for utility work and related replacement of sidewalks and ramps are exempt from stormwater management requirements if the activity does not involve the reconstruction of a roadway from curb to curb or curb to centerline of roadway. This exemption applies equally to public and private space. However, the area of a utility trench that is located within the footprint of other land-disturbing activity is considered part of the limits of disturbance that must meet stormwater management requirements and is not exempt.

The following are some examples of utility trench areas that are part of the limits of disturbance that must meet stormwater management requirements.

Figure 2.8 shows the portion of a utility trench under a building or other disturbed area that is being constructed or replaced.




Figure 2.8 Utility trench exemption example with building in LOD.

Figure 2.9 shows the portion of a utility trench under a sidewalk or driveway that is being constructed or replaced for purposes other than utility work.




Figure 2.9 Utility trench exemption example with building and sidewalk in LOD.

Figure 2.10 shows utility trenches for utility work that requires road reconstruction from curb to curb or from the curb to the centerline of the roadway.




Figure 2.10 Utility trench exemption example solely for utility work.

Note: Most land disturbance over 50 square feet for a utility trench is required to comply with soil erosion and sediment control requirements. See 21 DCMR, Chapter 5 for more details.

Land-disturbing activities conducted solely to respond to an emergency need to protect life, limb, or property or to conduct emergency repairs are exempt from most stormwater management requirements. These activities are not required to submit an SWMP, but they are subject to inspections to ensure the proper use of soil erosion and sediment control measures.

PROPOSED PENISION PROPOSED PRO

Chapter 3 Stormwater Best Management Practices (BMPs)

The use of the Natural Resource Conservation Service's (NRCS's) Storage Indication Routing method or an equivalent acceptable method may be required to route the design storms through stormwater facilities. A modified version of the NRCS Curve Number method is provided for computing the peak discharge for the SWRv 1.2-inch rain event. See Appendix H for further admitted and windows on the hydrogenical procedures.

2.8 Acceptable Urban BMP Options

This section sets forth 13 acceptable groups of BMPs that can be used to meet the SWRv and/or peak flow (Qp₂, Qp₁₅, Q_t) criteria.

The dozens of different BMP designs currently used in the District are assigned to 13 general categories for stormwater quality control:

BMP Group 1 Green Roofs

BMP Group 2 Rainwater Harvesting

BMP Group 3 Impervious Surface Disconnection

BMP Group 4 Permeable Pavement Systems

BMP Group 5 Bioretention

BMP Group 6 Filtering Systems

BMP Group 7 Infiltration

BMP Group 8 Open Channel Systems

BMP Group 9 Ponds

BMP Group 10 Wetlands

BMP Group 11 Storage Practices

BMP Group 12 Proprietary Practices

BMP Group 13 Tree Planting and Preservation

Within-each BMP group, detailed performance criteria are presented that govern feasibility, conveyance, pretreatment, treatment, landscaping, construction sequence, maintenance, and stormwater retention calculations (see Chapter 3).

Guidance on selecting the most appropriate combination of BMPs is provided in Chapter 4.

BMP Group 1 Green Roofs

Green roofs are BMPs that capture and store rainfall, which would otherwise land on an impervious rooftop, in an engineered growing media that is designed to support plant growth. A

Chapter 2 Minimum Control Requirements

portion of the captured rainfall evaporates or is taken up by plants, which helps reduce runoff volumes, peak runoff rates, and pollutant loads. Design variants include:

- G 1 Extensive green roofs have a much shallower growing media layer that typically ranges from 3 to 6 inches thick.
- G 2 Intensive green roofs have a growing media layer that ranges from 6 inches to 4 feet thick.

BMP Group 2 Rainwater Harvesting

Rain water harvesting systems intercept, divert, store, and release rainfall for future use.

Rainwater that falls on a rooftop is collected and conveyed into an above- or below-ground storage tank (also referred to as a cistern or rain tank), where it can be used for non-potable water uses and on site stormwater disposal/infiltration. The design includes:

R 1 Rainwater harvesting for non-potable uses

BMP Group 3 Impervious Surface Disconnection

This strategy involves managing runoff close to its source by intercepting, infiltrating, filtering, treating, or reusing it as it moves from the impervious surface to the drainage system. Simple disconnection variants include:

- D 1 Simple disconnection to a pervious compacted cover area
- D-2 Simple disconnection to a conserved natural cover area
- D 3 Simple disconnection to a soil compost amended filter path

Disconnection can also be employed as part of infiltration, bioretention, and rainwater harvesting systems.

BMP Group 4 Permeable Pavement Systems

Permeable pavement is an alternative paving surface that captures and temporarily stores the design volume by filtering runoff through voids in the pavement surface into an underlying stone reservoir. Filtered runoff may be collected and returned to the conveyance system, or allowed to partially infiltrate into the soil. Design variants include:

- P 1 Porous asphalt (PA)
- P-2 Pervious concrete (PC)
- P-3 Permeable pavers (PP)

BMP Group 5 Bioretention

Bioretention facilities are BMPs that capture and store stormwater runoff and pass it through a filter bed of engineered soil media comosed of sand, soil, and organic matter. Filtered runoff may be collected and returned to the conveyance system, or allowed to infiltrate into the soil. Design variants include:

- B-1 Traditional bioretention
- B-2 Streetscape bioretention
- B 3 Engineered tree pits
- **B** 4 Stormwater planters
- B-5 Residential rain gardens

BMP Group 6 Filtering Systems

Filtering systems are BMPs that capture and temporarily store the design volume and pass it through a filter bed of sand, organic matter, soil or other filtering media. Filtered runoff may be collected and returned to the conveyance system. Design variants include:

- F 1 Non structural sand filter
- F 2 Surface sand filter
- F 3 Three chamber underground sand filter
- F 4 Perimeter sand filter

BMP Group 7 Infiltration BMPs

Infiltration BMPs capture and store the design volume before allowing it to infiltrate into the soil over a 48 hour period. Design variants include:

- I 1 Infiltration trench
- I-2 Infiltration basin

BMP Group 8 Open Channel BMPs

Open channel BMPs are vegetated open channels that are designed to capture and treat or convey the design storm volume. Design variants include:

- O 1 Grass channels
- O 2 Dry swale
- O 3 Wet swale

BMP Group 9 Ponds

Chapter 2 Minimum Control Requirements

Stormwater ponds are stormwater storage BMPs that consist of a combination of a permanent pool, micropool, or shallow marsh that promote a good environment for gravitational settling, biological uptake, and microbial activity. Design variants include:

C 1 Micropool extended detention pond

C 2 Wet pond

C 3 Wet extended detention (ED) pond

BMP Group 10 Wetlands

Stormwater wetlands are BMPs that create shallow marsh areas to treat urban stormwater which often incorporate small permanent pools and/or extended detention storage. Stormwater wetlands are explicitly designed to provide stormwater detention for larger storms (2 year, 15 year or flood control events) above the SWRv. Design variants include:

W 1 Shallow wetland

W 2 Extended detention (ED) shallow wetland

BMP Group 11 Storage Practices

Storage practices are explicitly designed to provide stormwater detention (2 year, 15 year, and/or flood control). Storage practices alone are not considered acceptable practices to meet the SWRv or TSS removal requirements. Design variants include:

S 1 Underground vault

S 2 Dry pond

S 3 Rooftop storage

S 4 Stone storage under permeable pavement or other BMPs

Design guidance and criteria for the practice of rooftop storage is provided in Appendix I.

BMP Group 12 Proprietary Practices

Proprietary practices are manufactured stormwater BMPs that utilize settling, filtration, absorptive/adsorptive materials, vortex separation, vegetative components, and/or other appropriate technology to manage the impacts of stormwater runoff.

Proprietary practices may meet the SWRv value as well as the TSS removal value, provided they have been approved by DDOE through the process detailed in Appendix S. The design includes:

M 1 Proprietary practices

BMP Group 13 Tree Planting and Preservation

Trees can significantly reduce stormwater runoff by canopy interception and uptake of water from the soil. Trees are well documented in their ability to reduce stormwater runoff, particularly

when the tree canopy covers impervious surface, such as in the case of street trees. Design variants include:

- T 1 Tree planting
- T 2 Tree preservation

PROPOSED REVISION PROPOSED REVISION

Chapter 3<u>Chapter 1</u><u>Stormwater Best Management</u> <u>Practices (BMPs)</u>

3.1 Standard Stormwater Best Management Practice Design Guidance Format

This chapter outlines performance criteria for 13 stormwater best management practice (BMP) categories that include green roofs, rainwater harvesting, <u>impermeable impervious</u> surface disconnection, permeable pavement, bioretention, filtering systems, infiltration-<u>practices</u>, <u>open channels</u>, <u>ponds</u>, <u>stormwater wetlands</u>, <u>storage practices</u>, <u>ponds</u>, <u>wetlands</u>, <u>open channels</u>, <u>proprietary practices</u>, and tree planting <u>and preservation</u>.

BMP performance criteria are based on several critical design factors to ensure effective and long-lived BMPs. Design components that differ from these specifications but meet their intent may be included at the BMP performance criteria are based on several critical design factors to ensure effective and long lived BMPs. Design components that differ from these specifications but meet their intent may be included at the District Department of the Energy and Environment's (DDOE's DOEE's) discretion. In this chapter, and throughout the guidebook, the terms "must" or "shall" denote required aspects of BMPs or their design and implementation, while the term "should" denotes a recommendation. However, justification may be necessary for design or implementation that does not correspond to certain recommendations.

For each BMP, the following factors are discussed:

- General Feasibility
- Conveyance
- Pretreatment
- Design and Sizing
- Landscaping
- Construction Sequencing
- Maintenance
- Stormwater Compliance Calculations

3.2 Green Roofs

Definition. Practices that capture and store rainfall in an engineered growing media <u>installed</u> over a waterproof membrane that is designed to support plant growth on the roof of a building or other structure. A portion of the captured rainfall evaporates or is taken up by plants, which helps reduce runoff volumes, peak runoff rates, and pollutant loads on development sites. Green roofs typically contain a layered system of roofing, which is designed to support plant growth and retain water for plant uptake while preventing ponding on the roof surface. The roofs are designed so that water drains vertically through the media and then horizontally along a waterproofing layer towards the outlet. Extensive green roofs are designed to have minimal maintenance requirements. Plant species are selected so that the roof does not need supplemental irrigation and requires minimal, infrequent fertilization after vegetation is initially established.

Design variants include extensive and intensive green roofs.

- G-1 Extensive green roofs have a much shallower growing media layer that typically ranges from 3 to 68 inches thick and are designed to have minimal maintenance requirements.
- G-2 Intensive green roofs have a growing media layer that <u>typically</u> ranges from 68 to 48 inches thick.

Green roofs are typically not designed to provide stormwater detention of larger storms (e.g., 2-year, 15-year) although some intensive green roof systems may be designed to meet these criteria. Most green roof designs shall generally be combined with a separate facility to provide large storm controls.

This specification is intended for situations where the primary design objective of the green roof is stormwater management and, unless specified otherwise, addresses the design of extensive roof systems. While rooftop practices such as urban agriculture may provide some retention, their primary design objective is not stormwater management and is not addressed in this specification.

3.2.1 Green Roof Feasibility Criteria

Green roofs are ideal for use on commercial, institutional, municipal, and multi-family residential buildings. They are particularly well-suited for use on ultra-urban development and redevelopment sites. Key constraints with green roofs include the following:

Structural Capacity of the Roof. When designing a green roof, designers must not only consider the stormwater storage capacity of the green roof but also its structural capacity to support the weight of the additional water. A conventional rooftop should typically be designed to support an additional 15 to 30 pounds per square foot (psf) for an extensive green roof. As a result, a structural engineer, architect, or other qualified professional should be involved with all green roof designs to ensure that the building has enough structural capacity to support a green roof. See Section 3.2.4-, "Green Roof Design Criteria," for more information on structural design considerations.

Roof Pitch. Green roof storage volume is maximized on relatively flat roofs (a pitch of 1½ to 2 percent).%). Some pitch is needed to promote positive drainage and prevent ponding and/or saturation of the growing media. Green roofs can be installed on rooftops with slopes up to 30 percent% if baffles, grids, or strips are used to prevent slippage of the media. These baffles must be designed to ensure the roof provides adequate storage for the design storm. Slopes greater than 30 percent% would be considered a green wall, which is not specifically identified as a stormwater best management practice (BMP). Green walls can be used to receive cistern discharge (calculations are necessary to determine demand) and can be used to comply with Green Area Ratio Requirements.

Roof Access. Adequate, permanent access to the roof must be available to deliver construction materials and perform routine maintenance. A temporary ladder is not sufficient for access to the roof. Roof access can be achieved either by an interior stairway through a penthouse or by an alternating tread device with a roof hatch or trap door not less than 16 square feet in area and with a minimum dimension of 24 inches (NVRC, 2007). Designers should also consider how they will get construction materials up to the roof (e.g., by elevator or crane) and how the roof structure can accommodate material stockpiles and equipment loads. If material and equipment storage is required, rooftop storage areas must be identified and clearly marked based on structural load capacity of the roof.

Roof Type. Green roofs can be applied to most roof surfaces. Certain roof materials, such as exposed treated wood and uncoated galvanized metal, may not be appropriate for green rooftops due to pollutant leaching through the media (Clark et al., 2008).

Setbacks. Green roofs should not be located near rooftop electrical and <u>heating</u>, <u>ventilation and air conditioning (HVAC)</u> systems. A 2-foot_wide vegetation-free zone is recommended along the perimeter of the roof with a 1-foot vegetation-free zone around all roof penetrations, to act as a firebreak. The 2-foot setback may be relaxed for small or low green roof applications where parapets have been properly designed.

Contributing Drainage Area. It is recommended that the contributing drainage area (CDA) to a green roof be limited to the green roof itself. In cases where there will be additional contributing drainage area CDA, the designer must provide sufficient design detail showing distribution of this additional runoff throughout the green roof area to prevent erosion or overloading of the roof growing media with the use of level spreaders, splash pads, perforated piping, or other flow dissipation techniques. The absolute maximum contributing drainage area CDA to a green roof shall be no more than 100% larger than the area of the green roof (e.g., a 1,000-square-foot green roof can have no more than 1,000 square feet of additional impervious cover draining to it).

District Building Codes. The green roof design must comply with the District's building codes with respect to roof drains and emergency overflow devices. Regarding wind design and fire codes, the District has adopted the following building code standards:

- ANSI/SPRI VF-1 External Fire Design Standard for Vegetative Roofs (2017)
- ANSI/SPRI RP-14 Wind Design Standard for Vegetative Roofing Systems (2016)

Additionally, a District of Columbia registered structural engineer must certify that the design complies with District <u>Building building</u> structural codes. This is true for new construction as well as retrofit projects.

3.2.2 Green Roof Conveyance Criteria

The green roof drainage layer (refer to Section 3.2.4), "Green Roof Design Criteria") must convey flow from under the growing media directly to an outlet or overflow system such as a traditional rooftop downspout drainage system. The green roof drainage layer must be adequate to convey the volume of stormwater equal to the flow capacity of the overflow or downspout system without backing water up onto the rooftop or into the green roof media. Roof drains immediately adjacent to the growing media should be boxed and protected by flashing extending at least 3 inches above the growing media to prevent clogging. However, an adequate number of roof drains that are not immediately adjacent to the growing media must be provided so as to allow the roof to drain without 3 inches of ponding above the growing media.

3.2.3 Green Roof Pretreatment Criteria

Pretreatment is not necessary for green roofs.

3.2.4 Green Roof Design Criteria

Structural Capacity of the Roof. Green roofs can be limited by the additional weight of the fully saturated soil and plants, in terms of the physical capacity of the roof to bear structural loads. The designer shall consult with a licensed structural engineer to ensure that the building will be able to support the additional live and dead structural load and to determine the maximum depth of the green roof system and any needed structural reinforcement. Typically, the green roof manufacturer can provide specific background specifications and information on their product for planning and design.

In most cases, fully saturated extensive green roofs have loads of about 15 to 30 pounds per square foot, which is fairly similar to traditional new rooftops (12 to 15 pounds per square foot) that have a waterproofing layer anchored with stone ballast. For a discussion of green roof structural design issues, consult Chapter 9 in Weiler and Scholz-Barth, "Green Roof Systems" (2009), and ASTM E-2397 International Standard ASTM E2397/E2397M-15, "Standard Practice for Determination of Dead Loads and Live Loads Associated with Vegetative (Green) Roof Systems-" (2015).

Functional Elements of a Green Roof System. A green roof is composed of up to nine different systems or layers that combine to protect the roof and maintain a vigorous cover (see Figure 3.1).




Figure 3.23.23.1.1 Typical layers for a green roof. Note: the relative placement of various layers may vary depending on the type and design of the green roof system.

The design layers include the following:

- 1. **Deck Layer.** The roof deck layer is the foundation of a green roof. It may be composed of concrete, wood, metal, plastic, gypsum, or a composite material. The type of deck material determines the strength, load bearing capacity, longevity, and potential need for insulation in the green roof system.
- 2. Leak Detection System (optional). Leak detection systems are often installed above the deck layer to identify leaks, minimize leak damage through timely detection, and locate leak locations. Electric Field Vector Mapping (EFVM®) or other leak detection techniques are strongly recommended as part of the green roof installation process. In the case of EFVM®, the deck material must be conductive. If it is not, an additional conductive medium may need to be added on top of the deck. Other leak detection systems may require additional materials between the deck layer and the waterproofing layer.
- 3. Waterproofing Layer. All green roof systems must include an effective and reliable waterproofing layer to prevent water damage through the deck layer. A wide range of waterproofing materials can be used, including hot applied rubberized asphalt, built up bitumen, modified bitumen, thermoplastic membranes, polyvinyl chloride (PVC), thermoplastic olefin membrane (TPO), and elastomeric membranes (EPDM) (see Weiler and Scholz-Barth, 2009, and Snodgrass and Snodgrass, 2006). (see section 3.2.9, "References.")). The waterproofing layer must be 100 percent waterproof and have an expected life span as long as any other element of the green roof system. The waterproofing material may be loose laid or bonded (recommended). If loose laid, overlapping and additional construction techniques should be used to avoid water migration.

- 4. Insulation Layer. Many green rooftops contain an insulation layer, usually located above, but sometimes below, the waterproofing layer. The insulation increases the energy efficiency of the building and/or protects the roof deck (particularly for metal roofs). According to Snodgrass and Snodgrass (2006), the trend is to install insulation on the outside of the building, in part to avoid mildew problems. The designer should consider the use of open or closed cell insulation depending on whether the insulation layer is above or below the waterproofing layer (and thus exposed to wetness), with closed cell insulation recommended for use above the waterproofing layer.
- 5. Root Barrier. Another layer of a green roof system, which can be either above or below the insulation layer depending on the system, is a root barrier that protects the waterproofing membrane from root penetration. A wide range of root barrier options are described in Weiler and Scholz-Barth (2009). Chemical root barriers or physical root barriers which that have been impregnated with pesticides, metals, or other chemicals that could leach into stormwater runoff, must be avoided in systems where the root barrier layer will come in contact with water or allow water to pass through the barrier.
- 6. Drainage Layer and Drainage System. A drainage layer is—then placed between the root barrier and the growing media to quickly remove excess water from the vegetation root zone. The selection and thickness of the drainage layer type is an important design decision that is governed by the desired stormwater storage capacity, the required conveyance capacity, and the structural capacity of the rooftop. The effective depth of the drainage layer is generally 0.25—to—1.5 inches thick for extensive green roof system and increases for intensive designs. The drainage layer should consist of synthetic or inorganic materials (e.g., 1—2—inch layer of clean, washed granular material (ASTM D448 size No. 8 stone or lightweight granular mix), high density polyethylene (HDPE)) that are capable of retaining water and providing efficient drainage—(ASTM, 2017). A wide range of prefabricated water cups or plastic modules can be used, as well as a traditional system of protected roof drains, conductors, and roof leaders. ASTM E2396 and E2398 can be used to evaluate alternative material specifications—(ASTM, 2015).
- 7. Root-Permeable Filter Fabric. A semi-permeable needled polypropylene filter fabric is normally placed between the drainage layer and the growing media to prevent the media from migrating into the drainage layer and clogging it. The filter fabric must not impede the downward migration of water into the drainage layer.
- 8. Growing Media. The next layer in an extensive green roof is the growing media, which is typically 3-to 6_8 inches deep-(minimum 3 inches). The recommended growing media for extensive green roofs is typically composed of approximately 70-to-%_80-percent% lightweight inorganic materials, such as expanded slates, shales or clays; pumice; scoria; or other similar materials. The remaining-media must contain no more than 30-percent% organic matter, normally well-aged compost (see Appendix J)-, "Soil Compost Amendment Requirements"). The percentage of organic matter should be limited, since it can leach nutrients into the runoff from the roof and clog the permeable filter fabric. The growing media typically has a maximum water retention of approximately 30 percent. Proof of growing media maximum water retention must be provided by the manufacturer. It is advisable to mix the media in a batch facility prior to delivery to the roof. As there are many different types of proprietary growing medias and roof systems, the values provided here are recommendations only. Manufacturer's specifications should be followed for all proprietary

roof systems. More information on growing media can be found in Weiler and Scholz-Barth (2009), and Snodgrass and Snodgrass (2006), see section 3.2.9, "References.").

The composition of growing media for intensive green roofs may be different, (although the organic material limit still applies), and it is often much greater in depth (e.g., 6-to-8-48 inches). If trees are included in the green roof planting plan, the growing media must be sufficient to provide enough soil volume for the root structure of mature trees.

9. Plant Cover. The top layer of an extensive green roof typically consists of plants that are non-native, slow-growing, shallow-rooted, perennial, and succulent. These plants are chosen for their ability to withstand harsh conditions at the roof surface. Guidance on selecting the appropriate green roof plants can often be provided by green roof manufacturers and can also be found in Snodgrass and Snodgrass (2006)-see section 3.2.9, "References."). A mix of base ground covers (usually Sedum species) and accent plants can be used to enhance the visual amenity value of a green roof. See Section 3.2.4-, "Green Roof Design Criteria," for additional plant information. The design must provide for temporary, manual, and/or permanent irrigation or watering systems, depending on the green roof system and types of plants. For most application applications, some type of watering system should be accessible for initial establishment or drought periods. The use of water efficient designs and/or use of non-potable sources are strongly encouraged.

Material Specifications. Standard specifications for North American green roofs continue to evolve, and no universal material specifications exist that cover the wide range of roof types and system components currently available. The ASTM has recently issued several overarching green roof standards, which are described and referenced in Table 3.1 below.

Designers and reviewers should also fully understand manufacturer specifications for each system component, particularly if they choose to install proprietary "complete" green roof systems or modules.

Table 3.1 Extensive Green Roof Material Specifications

Material	Specification
Roof	Structural capacity must conform to ASTM E 2397-05, Practice for Determination of Live Loads and Dead Loads Associated with Vegetative (Green) Roof Systems. E2397. In addition, use standard test methods ASTM E2398-05 for Water Capture and Media Retention of Geocomposite Drain Layers for Green (Vegetated) Roof Systems and ASTME 2399-05 for Maximum Media Density for Dead Load Analysis and ASTM E2399.
Leak Detection System	Optional system to detect and locate leaks in the waterproof membrane.
Waterproof Membrane	See Chapter 6 of Weiler and Scholz-Barth (2009) for waterproofing options that are designed to convey water horizontally across the roof surface to drains or gutter. This layer may sometimes act as a root barrier.
Root Barrier	Impermeable liner that impedes root penetration of the membrane.
Drainage Layer	Depth of the drainage layer is generally 0.25+6_1.5 inches thick for extensive designs. The drainage layer should consist of synthetic or inorganic materials (e.g., gravel, high density polyethylene (HDPE), etc.)HDPE) that are capable of retaining water and providing efficient drainage. A wide range of prefabricated water cups or plastic modules can be used, as well as a traditional system of protected roof drains, conductors, and roof leaders. Designers should consult the material specifications as outlined in ASTM E2396 and E2398. Roof drains and emergency overflow must be designed in accordance with the District's construction code (DCMR, Title 12 of the District of Columbia Municipal Regulations).
Filter Fabric	Generally, needle-punched, non-woven, polypropylene geotextile, with the following qualities: Strong enough and adequate puncture resistance to withstand stresses of installing other layers of the green roof. Density as per ASTM D3776 ≥ 8 oz/yd². Puncture resistance as per ASTM D4833 ≥ 130 lb. These values can be reduced with submission of a Product Data Sheet and other documentation that demonstrates applicability for the intended use. Adequate tensile strength and tear resistance for long_term performance. Allows a good flow of water to the drainage layer. Apparent Opening Size, as per ASTM D4751, of ≥ 0.06mm ≤ 0.2mm, with other values based on Product Data Sheet and other documentation as noted above. Allows at least fine roots to penetrate. Adequate resistance to soil borne chemicals or microbial growth both during construction and after completion since the fabric will be in contact with moisture and possibly fertilizer compounds.
Growth Media	70% to %_80% lightweight inorganic materials and a maximum of 30% organic matter (e.g., well-aged compost). Material makeup of the growing media must be provided. Media must provide sufficient nutrients and water holding capacity to support the proposed plant materials. Determine acceptable saturated water permeability using ASTM E2396. An acceptable emerging industry practice combines the drainage layer with the growing media layer.
Plant Materials	Sedum, herbaceous plants, and perennial grasses that are shallow-rooted, low maintenance, and tolerant of <u>full and</u> direct sunlight, drought, wind, and frost. See ASTM E2400-06, Standard Guide for Selection, Installation and Maintenance of Plants for Green (Vegetated)-Roof Systems.

Rock Wool and Contributing Drainage Area. As stated in Section 3.2.1 above, in cases where the green roof CDA extends beyond the green roof itself, the design must include sufficient distribution or dissipation of this additional runoff throughout the green roof. Typically, in order to provide sufficient distribution, the additional roof area must have a higher elevation than the green roof, so that gravity flow will allow the runoff to reach the green roof. If rock wool is used as the drainage layer for the green roof, however, the additional CDA may be located at the same elevation as the base of the green roof.

Rock wool, also referred to as mineral wool, is a product that has begun to be incorporated as the drainage layer for green roofs, as it absorbs water, but still allows excess water to drain. The unique absorptive properties of rock wool allow it to absorb runoff from an adjacent roof surface so the additional CDA to the green roof does not need to be at a higher elevation than the green roof. The following caveats and requirements apply to this approach:

- No roof drains can be present in the additional contributing roof area, as they will provide a preferential flow path that bypasses the green roof.
- The drainage layer cannot include an air layer. The rock wool drainage layer must be in direct contact with the roof. Designs that include an air layer and rely on "wicking tongues" to capture the additional CDA are not acceptable.
- Channels to facilitate overflow and eliminate rooftop flooding may be incorporated into the rock wool:
 - The maximum channel width is 0.5 inch. Water contact with the sides of the channel is essential to ensure complete capture of smaller storm events. Wider channels may allow too much bypass.
 - Perforated pipe and other designs that limit water contact with the rock wool on the sides of the channels are not acceptable.
 - Channels must be evenly distributed throughout the green roof and be spaced no closer than one channel every 2.5 feet.

The runoff flow path from the contributing roof area must be less than or equal to the length of the channels.

Solar Panels and Other Structures. Occasionally, structures such as solar panels or HVAC systems must be installed above a green roof. These structures can be incorporated into a green roof design with no adverse effects to the retention value assigned to the green roof if specific design requirements for runoff disbursement, maintenance access, and sun-<u>and</u> wind exposure are incorporated, including the following:

- Structures above the green roof must be no more than 3.256.5 feet wide-;
- Structures must have a minimum 3-foot separation between them-; and
- The lower edge of the structure must be at least 1 foot above the top of the green roof, and the upper edge must be at least 2.5 feet above the top of the green roof. This allows for a tilt of at least a 15-degrees. For flatter installations, the lower edge would need to be raised to ensure that the 2.5-foot minimum elevation for the upper edge is met.

These design requirements are illustrated in Figure 3.2.




Figure 3.1.2 Design Requirements requirements for structures constructed above green roofs.

Green Roof Sizing. Green roof areas can be designed to capture the entire Stormwater Retention Volume (SWRv). In some cases, they could be designed to capture larger design storm volumes as well. The required size of a green roof will depend on several factors, including maximum water retention of the growing media and the underlying drainage and storage layer materials, if present (e.g., prefabricated water cups or plastic modules). As maximum water retention can vary significantly between green roof products, verification of this value must be included with the Stormwater Management Plan (SWMP). MastM tests E2396, E2397, E2398, or E2399, as appropriate, and. The test performed <a href="mailto:by an ASTM certified lab are considered acceptable verification-must be representative of the actual thickness and depth of each component of the

green roof (i.e., a test performed on a 4-inch thick green roof media cannot be used to represent the maximum water retention value for an 8-inch thick green roof media). In the absence of ASTMlaboratory test results, the baseline default values must be used. Site designers and planners should consult with green roof manufacturers and material suppliers as they can often provide specific sizing information and hydrology design tools for their products.provided in Equation 3.1 below, which shall be used to determine the storage volume retained by a green roof.



Equation 3.1 Storage Volume for Green Roofs

$$Sv = \frac{SA \times \left[\left(d \times \eta_1 \right) + \left(DL \times \eta_2 \right) \right]}{12}$$

$$Sv = \frac{SA \times [(d \times \eta_1) + (DL \times \eta_2)]}{12}$$

where:

 $Sv = \underline{\text{green roof storage volume (ft}^3)}$

SA = green roof area (ft²)

d = media depth (in.) (minimum 3 in.)

 η_1 = verified media maximum water retention (use 0.1510 as a baseline default in

the absence of verification data)

DL = drainage layer depth (in.) (if the drainage layer is combined with the media

layer, then this value is 0)

 η_2 = verified drainage layer maximum water retention (use 0.450 as a baseline

default in the absence of verification data)

The appropriate Sv can then be compared to the required SWRv for the entire rooftop area (including all conventional roof areas) to determine the portion of the design storm captured.

Green roofs can have dramatic rate attenuation effects on larger storm events and may be used, in part, to manage a portion of the 2-year and 15-year events. Designers can model various approaches by factoring in storage within the drainage layer. Routing calculations can also be used to provide a more accurate solution of the peak discharge and required storage volume.

3.2.5 Green Roof Landscaping Criteria

Plant selection, landscaping, and maintenance are critical to the performance and function of green roofs. Therefore, a landscaping plan shall be provided for green roofs.

A planting plan must be prepared for a green roof by a landscape architect, botanist, or other professional experienced with green roofs and submitted with the SWMP.

Plant selection for green roofs is an integral design consideration, which is governed by local climate and design objectives. The primary ground cover for most green roof installations is a hardy, low-growing succulent, such as *Sedum*, *Delosperma*, *Talinum*, *Semperivum*, or *Hieracium* that is matched to the local climate conditions and can tolerate the difficult growing conditions found on building rooftops (Snodgrass and Snodgrass, 2006). (see section 3.2.9, "References.")).

A list of some common green roof plant species that work well in the Chesapeake Bay watershed can be found in Table 3.2 below.

Table 3.2 Ground Covers Appropriate for Green Roofs in the District of Columbia

Plant	Light	Moisture Requirement	Notes
Delosperma cooperii	Full Sun	Dry	Pink flowers; grows rapidly
Delosperma 'Kelaidis'	Full Sun	Dry	Salmon flowers; grows rapidly
Delosperma nubigenum 'Basutoland'	Full Sun	Moist-Dry	Yellow flowers; very hardy
Sedum album	Full Sun	Dry	White flowers; hardy
Sedum lanceolatum	Full Sun	Dry	Yellow flowers; native to U.S.
Sedum oreganum	Part Shade	Moist	Yellow flowers; native to U.S.
Sedum stoloniferum	Sun	Moist	Pink flowers; drought tolerant
Sedum telephiodes	Sun	Dry	Blue green foliage; native to region
Sedum ternatum	Part Shade	Dry-Moist	White flowers; grows in shade
Talinum calycinum	Sun	Dry	Pink flowers; self-sows

Note: Designers should choose species based on shade tolerance, ability to sow or not, foliage height, and spreading rate. See Snodgrass and Snodgrass (2006)see section 3.2.9, "References.") for a definitive list of green roof plants, including accent plants.

- Plant choices can be much more diverse for deeper intensive green roof systems. Herbs, forbs, grasses, shrubs, and even trees can be used, but designers should understand they may have higher watering, weeding, and landscape maintenance requirements.
- The species and layout of the planting plan must reflect the location of the building, in terms of its height, exposure to wind, snow loading, heat stress, orientation to the sun, and impacts from surrounding buildings. (Wind scour and solar burning have been observed on green roof installations that failed to adequately account for neighboring building heights and surrounding window reflectivity.) In addition, plants must be selected that are fire resistant and able to withstand heat, cold, and high winds.
- Designers should also match species to the expected rooting depth of the growing media, which can also provide enough lateral growth to stabilize the growing media surface. The planting plan should usually include several accent plants to provide diversity and seasonal color. For a comprehensive resource on green roof plant selection, consult Snodgrass and Snodgrass (2006).see section 3.2.9, "References.").
- It is also important to note that most green roof plant species will not be native to the Chesapeake Bay watershed (which contrasts with native plant recommendations for other stormwater practices, such as bioretention and constructed wetlands).
- Given the limited number of green roof plant nurseries in the region, it may be necessary for designers to order plants 6 to 12 months prior to the expected planting date. It is also advisable to have plant materials contract grown.

- ThePlants can be established using cuttings, plugs, mats, and, more rarely, containers.

 Several vendors also sell mats, rolls, or proprietary green roof planting modules. For the pros and cons of each method, see Snodgrass and Snodgrass (see section 3.2.9, "References."). To achieve 50% coverage after one (1) year and 80% coverage after two (2) years, the recommended minimum spacing for succulent plantings is 2 plugs per square foot and 3 pounds of cuttings per 100 square feet.
- When planting cuttings, plugs, and mats, the planting window extends from the spring to early fall; although, it is important to allow plants to root thoroughly before the first killing frost. Green roof manufacturers and plant suppliers may provide guidance on planting windows as well as winter care. Proper planting and care may also be required for plant warranty eligibility.
- When appropriate species are selected, most green roofs will not require supplemental irrigation, except for temporary irrigation during drought or initial establishment. The use of water—efficient designs and/or use of non-potable sources is strongly encouraged. Permanent irrigation of extensive roof designs is prohibited. For intensive roofs, permanent irrigation may be included. However, permanent irrigation can adversely impact the rainfall retention capacity of the green roof. For this reason, soil moisture monitors are a required part of the irrigation system for all irrigated green roofs, and the calculated retention value for green roofs with permanent irrigation must be reduced by 50%.
- The goal for green roof systems designed for stormwater management is to establish a full
 and vigorous cover of low-maintenance vegetation that is self-sustaining (not requiring
 fertilizer inputs) and requires minimal mowing, trimming, and weeding.

The green roof design should include non-vegetated walkways (e.g., paver blocks) to allow for easy access to the roof for weeding and making spot repairs (see Section 3.2.4-, "Green Roof Design Criteria).").

3.2.6 Green Roof Construction Sequence

Green Roof Installation. Given the diversity of extensive vegetated roof designs, there is no typical step-by-step construction sequence for proper installation. The following general construction considerations are noted:

- Construct the roof deck with the appropriate slope and material.
- Install the waterproofing method, according to manufacturer's specifications.
- Conduct aEVFM® or flood testtesting to ensure the system is watertight by placing at least 2 inches of water. Where possible, EVFM® is strongly recommended over the membrane for 48 hours to confirm the integrity of the waterproofing system. Alternately, electric field vector mapping (EFVM) can be done to test for the presence of leaks; however, flood test, but not all impermeable membranes and deck systems are testable compatible with this method. Problems have been noted with the use of EFVM on black ethylene propylene diene terpolymer (EPDM) and with aluminized protective coatings commonly used in conjunction with modified bituminous membranes. If EVFM® or other leak detection systems are not possible, a flood test should be performed instead. The flood test is done by placing at least

two (2) inches of water over the membrane for 48 hours to confirm the integrity of the waterproofing system.

- Add additional system components (e.g., insulation, root barrier, drainage layer and interior drainage system, and filter fabric) per the manufacturer's specifications, taking care not to damage the waterproofing. Any damage occurring must be reported immediately. Drain collars and protective flashing should be installed to ensure free flow of excess stormwater.
- The growing media should be mixed prior to delivery to the site. Media must be spread evenly over the filter fabric surface as required by the manufacturer. If a delay between the installation of the growing media and the plants is required, adequate efforts must be taken to secure the growing media from erosion and the seeding of weeds. The growing media must be covered and anchored in place until planting. Sheets of exterior grade plywood can also be laid over the growing media to accommodate foot or wheelbarrow traffic. Foot traffic and equipment traffic should be limited over the growing media to reduce compaction beyond manufacturer's recommendations.
- The growing media should be moistened prior to planting, and then planted with the ground cover and other plant materials, per the planting plan or in accordance with ASTM E2400-(2015). Plants should be watered immediately after installation and routinely during establishment.
- It generally takes 2 to 3 growing seasons to fully establish the vegetated roof. The growing medium should contain enough organic matter to support plants for the first growing season, so initial fertilization is not required. Extensive green roofs may require supplemental irrigation during the first few months of establishment. Hand weeding is also critical in the first two2 years (see Table 10.1 of Weiler and Scholz-Barth (2009) for a photo guide of common rooftop weeds).
- Most construction contracts should contain a Careca e and Replacement Warrantyreplacement warranty that specifies at least 50 percent% coverage after one1 year and 80 percent% coverage after two2 years for plugs and cuttings, and 90 percent% coverage after one1 year for Sedum carpet or tile.

Construction Supervision. Supervision during construction is recommended to ensure that the vegetated roof is built in accordance with these specifications. Inspection checklists should be used that include sign-offs by qualified individuals at critical stages of construction and confirm that the contractor's interpretation of the plan is consistent with the intent of the designer and/or manufacturer.

An experienced installer should be retained to construct the vegetated roof system. The vegetated roof should be constructed in sections for easier inspection and maintenance access to the membrane and roof drains. Careful construction supervision/inspection is needed throughout the installation of a vegetated roof, as follows:

- During placement of the waterproofing layer, to ensure that it is properly installed and watertight.
- During placement of the drainage layer and drainage system.

- During placement of the growing media, to confirm that it meets the specifications and is applied to the correct depth (certification for vendor or source should be provided).
- Upon installation of plants, to ensure they conform to the planting plan (certification from vendor or source should be provided).
- Before issuing use and occupancy approvals.
- At the end of the first or second growing season to ensure <u>that the</u> desired surface cover specified in the Care and Replacement Warranty has been achieved.

 $\overline{\text{DOE's}}$ $\overline{\text{DOEE's}}$ construction phase inspection checklist for green roof practices can be found in Appendix K₇, "Construction Inspection Checklists."

3.2.7 Green Roof Maintenance Criteria

Maintenance Inspections. A green roof should be inspected by a qualified professional twice a year during the growing season to assess vegetative cover and to look for leaks, drainage problems, and any rooftop structural concerns (see Table 3.3). In addition, the green roof should be hand weeded to remove invasive or volunteer plants, and plants and/or media should be added to repair bare areas (refer to ASTM E2400 (ASTM, 20062015)).

If a roof leak is suspected, it is advisable to perform an electric leak survey (e.g., EVFM), if applicable, to pinpoint the exact location, make localized repairs, and then reestablish system components and ground cover.

The use of herbicides, insecticides, and fungicides should be avoided, since their presence could hasten degradation of some waterproofing membranes. Check with the membrane manufacturer for approval and warranty information. Also, power washing and other exterior maintenance operations should be avoided so that cleaning agents and other chemicals do not harm the green roof plant communities.

Fertilization is generally not recommended due to the potential for leaching of nutrients from the green roof. Supplemental fertilization may be required following the first growing season, but only if plants show signs of nutrient deficiencies and a media test indicates a specific deficiency. Addressing this issue with the holder of the vegetation warranty is recommended. If fertilizer is to be applied, it must be a slow-release type, rather than liquid or gaseous form.

DDOE's DOEE's maintenance inspection checklist for green roofs and the Maintenance Service Completion Inspection form can be found in Appendix L₇, "Maintenance Inspection Checklists."

Table 3.3 Typical Maintenance Activities Associated with Green Roofs

Schedule (following construction)	Activity
As needed	 Water to promote plant growth and survival.
or as required by manufacturer	 Inspect the green roof and replace any dead or dying vegetation.
Semi-annually	 Inspect the waterproof membrane for leaks and cracks. Weed to remove invasive plants and tree seedlings (do not dig or use pointed tools where there is potential to harm the root barrier or waterproof membrane). Inspect roof drains, scuppers, and gutters to ensure they are not overgrown
	and have not accumulated organic matter deposits. Remove any accumulated organic matter or debris. Inspect the green roof for dead, dying, or invasive vegetation. Plant replacement vegetation as needed.

Declaration of Covenants. A declaration of covenants is required that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP-is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5, "Administration of Stormwater Management Rules" (see Figure 5.411), although variations will exist for scenarios where situations in which stormwater crosses property lines. The covenant is between the property owner and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed be issued. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C ofto be included as an exhibit to the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined througheither signed by the Responsible Person for Maintenance on a partnership agreement or be identified in a memorandum of understanding that is incorporated into the plan submission.

Waste Materials. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.2.8 Green Roof Stormwater Compliance Calculations

Unirrigated Green Roofs. These green roofs receive 100% retention value for the amount of storage volume (Sv) provided by the practice. Permanently irrigated green roofs receive 50% retention value for the amount of Sv provided by the practice (see Table 3.4). (see Table 3.4). Since the practice gets 100% retention value, it is not considered an accepted total suspended solids (TSS) treatment practice.

Table 3.4 Unirrigated Green Roof Design Performance

Retention Value-(unirrigated)	= Sv
Retention Value (irrigated)	$=0.5 \times Sv$
Accepted TSS Treatment Practice	N/A

Irrigated Green Roofs. Permanently irrigated green roofs receive 50% retention value for the amount of Sv provided by the practice and are an accepted TSS removal practice for the amount of storage volume (Sv) provided by the practice (see Table 3.5).

Table 3.5 Irrigated Green Roof Design Performance

Retention Value	$= 0.5 \times Sv$
Accepted TSS Treatment Practice	Yes

The practice must be designed using the guidance detailed in Section 3.2.4. "Green Roof Design Criteria."

Green roofs also contribute to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the storage volume (Sv) from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced-reduced Natural Resource Conservation Service Curve Number(NRCS) curve number(CN) for the site or drainage area.SDA. The Reduced-Curve Numberreduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.2.9 References

- ASTM D448-12 (2017), Standard Classification for Sizes of Aggregate for Road and Bridge Construction, ASTM International-2006., West Conshohocken, PA, 2017, www.astm.org
- ASTM E2396 / E2396M-15, Standard Test Method for Saturated Water Permeability of Granular Drainage Media [Falling-Head Method] for Vegetative (Green) Roof Systems, ASTM International, West Conshohocken, PA, 2015, www.astm.org
- ASTM E2397 / E2397M-15, Standard Practice for Determination of Dead Loads and Live Loads

 Associated with Vegetative (Green) Roof Systems, ASTM International, West

 Conshohocken, PA, 2015, www.astm.org
- ASTM E2398 / E2398M-15a, Standard Test Method for Water Capture and Media Retention of Geocomposite Drain Layers for Vegetative (Green) Roof Systems, ASTM International, West Conshohocken, PA, 2015, www.astm.org

- ASTM E2399 / E2399M-15, Standard Test Method for Maximum Media Density for Dead Load Analysis of Vegetative (Green) Roof Systems, ASTM International, West Conshohocken, PA, 2015, www.astm.org
- ASTM E2400 / E2400M-06(2015)e1, Standard Guide for Selection, Installation, and Maintenance of Plants for Green (Vegetated) Roof Systems. Standard E2400 06., ASTM, International., West Conshohocken, PA. available online: http://www.astm.org/Standards/E2400.htm., 2015, www.astm.org
- ASTM D3776 / D3776M-09a (2017), Standard Test Methods for Mass Per Unit Area (Weight) of Fabric, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- ASTM D4751-16, Standard Test Methods for Determining Apparent Opening Size of a Geotextile, ASTM International, West Conshohocken, PA, 2016, www.astm.org
- Clark, S., B. Long, C. Siu, J. Spicher and K. Steele. 2008. "Early-life runoff quality: green versus traditional roofs." Low Impact Development 2008. Seattle, WA. American Society of Civil Engineers.
- Dunnett, N. and N. Kingsbury. 2004. Planting Green Roofs and Living Walls. Timber Press. Portland, Oregon.
- Green Roof Infrastructure: Plants and Growing Medium 401. Participant <u>Manual.</u> <u>www.greenroofs.org/</u> Manual. https://greenroofs.org/
- Luckett, K. 2009. Green Roof Construction and Maintenance. McGraw-Hill Companies, Inc.
- Northern Virginia Regional Commission (NVRC). 2007. Low Impact Development Manual. "Vegetated Roofs." Fairfax, VA.
- Snodgrass, E. and L. Snodgrass. 2006. Green Roof Plants: a resource and planting guide. Timber Press. Portland, OR.
- Weiler, S. and K. Scholz-Barth. 2009. Green Roof Systems: A Guide to the Planning, Design, and Construction of Landscapes over Structure. Wiley Press. New York, NY.
- Virginia DCR Stormwater Design Specification No. 5: Vegetated Roof Version 2.2. 2010.

3.3 Rainwater Harvesting

Definition. Rainwater harvesting systems store rainfall and release it for future use. Rainwater that falls on a rooftop or other impervious surface is collected and conveyed into an above- or below-ground tank (also referred to as a cistern), where it is stored for non-potable uses or for on-site disposal or infiltration as stormwater. Cisterns can be sized for commercial as well as residential purposes. Residential cisterns are commonly called rain barrels. The design includes the following:

R-1 Rainwater harvesting for non-potable uses

Non-potable uses of harvested rainwater may include the following:

- Landscape irrigation,
- Exterior washing (e.g., car washes, building facades, sidewalks, street sweepers, and fire trucks).
- Flushing of toilets and urinals,
- Fire suppression (e.g., sprinkler systems),
- Supply for cooling towers, evaporative coolers, fluid coolers, and chillers,
- Supplemental water for closed loop systems and steam boilers.
- Replenishment of water features and water fountains,
- Distribution to a green wall or living wall system, and
- Laundry.


In many instances, rainwater harvesting can be combined with a secondary (down-gradient) stormwater practice to enhance stormwater retention and/or provide treatment of overflow from the rainwater harvesting system. Some candidate secondary practices include the following:

- Disconnection to a pervious area (compacted cover) or conservation area (natural cover) or soil amended filter path (see Section 3.4 Impervious Surface Disconnection)
- Overflow to bioretention practices (see Section 3.6 Bioretention)
- Overflow to infiltration practices (see Section 3.8 Stormwater Infiltration)
- Overflow to grass channels or dry swales (see Section 3.12 Storage Practices)

By providing a reliable and renewable source of water to end users, rainwater harvesting systems can also have environmental and economic benefits beyond stormwater management (e.g., increased water conservation, water supply during drought and mandatory municipal water supply restrictions, decreased demand on municipal water supply, decreased water costs for the end user, and potential for increased groundwater recharge).

The seven primary components of a rainwater harvesting system are discussed in detail in Section 3.3.4-, "Rainwater Harvesting Design Criteria." Some are depicted in Figure 3.23. The components include the following:

- Contributing drainage area (CDA) surface,
- Collection and conveyance system (e.g., gutter and downspouts) (number 1 in Figure 3.23)
- Pretreatment, including prescreening and first flush diverters (number 2 in Figure 3.23)
- Cistern (no number, but depicted in Figure 3.23)
- Water quality treatment (as required by Tiered Risk Assessment Appendix M, "Rainwater Harvesting Treatment and Management (TRAM)) Requirements")
- Distribution system
- Overflow, filter path, or secondary stormwater retention practice (number 8 in Figure 3.23)






Figure 3.23.33.2.3 Example of a rainwater harvesting system detail.

3.3.1 Rainwater Harvesting Feasibility Criteria

A number of site-specific features influence how rainwater harvesting systems are designed and/or utilized. The following are key considerations for rainwater harvesting feasibility. They are not comprehensive or conclusive; rather, they are recommendations to consider during the planning process to incorporate rainwater harvesting systems into the site design.

Plumbing Code. This specification does not address indoor plumbing or disinfection issues. Designers and plan reviewers should consult Appendix M, "Rainwater Harvesting Treatment and Management Requirements," and the District's construction codes (DCMR, Title 12 of the District of Columbia Municipal Regulations) to determine the allowable indoor uses and required treatment for harvested rainwater. In cases where a municipal backup supply is used, rainwater harvesting systems must have backflow preventers or air gaps to keep harvested water separate from the main water supply. Distribution and waste pipes, internal to the building, must be

stamped non-potable and colored purple consistent with the District's building codes. Pipes and spigots using rainwater must be clearly labeled as non-potable with an accompanying pictograph sign.

Mechanical, Electrical, Plumbing (MEP). For systems that call for indoor use of harvested rainwater, the seal of an MEPa mechanical, electrical, and plumbing engineer is required.

Water Use. When rainwater harvesting will be used, a TRAM (seethe requirements in Appendix M), "Rainwater Harvesting Treatment and Management Requirements," must be completed and the appropriate form submitted to DDOE. followed. This will outline the design assumptions, outline water quality risks and provide water quality end use standards.

Available Space. Adequate space is needed to house the cistern and any overflow. Space limitations are rarely a concern with rainwater harvesting systems if they are considered during the initial building design and site layout of a residential or commercial development. Cisterns can be placed underground, indoors, adjacent to buildings, and on rooftops that are structurally designed to support the added weight. Designers can work with architects and landscape architects to creatively site the cisterns. Underground utilities or other obstructions should always be identified prior to final determination of the cistern location.

Site Topography. Site topography and cistern location should be considered as they relate to all of the inlet and outlet invert elevations in the rainwater harvesting system.

The final invert of the cistern outlet pipe at the discharge point must match the invert of the receiving mechanism (e.g., natural channel, storm drain system) and be sufficiently sloped to adequately convey this overflow. The elevation drops associated with the various components of a rainwater harvesting system and the resulting invert elevations should be considered early in the design, in order to ensure that the rainwater harvesting system is feasible for the particular site.

Site topography and cistern location will also affect pumping requirements. Locating cisterns in low areas will make it easier to get water into the cisterns; however, it will increase the amount of pumping needed to distribute the harvested rainwater back into the building or to irrigated areas situated on higher ground. Conversely, placing cisterns at higher elevations may require larger diameter pipes with smaller slopes but will generally reduce the amount of pumping needed for distribution. It is often best to locate a cistern close to the building or drainage areaSDA, to limit the amount of pipe needed.

Available Hydraulic Head. The required hydraulic head depends on the intended use of the water. For residential landscaping uses, the cistern may be sited up-gradient of the landscaping areas or on a raised stand. Pumps are commonly used to convey stored rainwater to the end use in order to provide the required head. When the water is being routed from the cistern to the inside of a building for non-potable use, often a pump is used to feed a much smaller pressure tank inside the building, which then serves the internal water demands. Cisterns can also use gravity to accomplish indoor residential uses (e.g., laundry) that do not require high water pressure.

Water Table. Underground storage tanks are most appropriate in areas where the tank can be buried above the water table. The tank should be located in a manner that isdoes not subject it to flooding. In areas where the tank is to be buried partially below the water table, special design features must be employed, such as sufficiently securing the tank (to keep it from floating), and conducting buoyancy calculations when the tank is empty. The tank may need to be secured appropriately with fasteners or weighted to avoid uplift buoyancy. The combined weight of the tank and hold-down ballast must meet or exceed the buoyancy force of the cistern. The cistern must also be installed according to the cistern manufacturer's specifications.

Soils. Cisterns should only be placed on native soils or on fill in accordance with the manufacturer's guidelines. The bearing capacity of the soil upon which the cistern will be placed must be considered, as full cisterns can be very heavy. This is particularly important for aboveground cisterns, as significant settling could cause the cistern to lean or in some cases to potentially topple. A sufficient aggregate, or concrete foundation, may be appropriate depending on the soils and cistern characteristics. Where the installation requires a foundation, the foundation must be designed to support the cistern's weight when the cistern is full, consistent with the bearing capacity of the soil and good engineering practice. The pH of the soil should also be considered in relation to its interaction with the cistern material.

Proximity of Underground Utilities. All underground utilities must be taken into consideration during the design of underground rainwater harvesting systems, treating all of the rainwater harvesting system components and storm drains as typical stormwater facilities and pipes. The underground utilities must be marked and avoided during the installation of underground cisterns and piping associated with the system.

Contributing Drainage Area. The contributing drainage area (CDA) to the cistern is the impervious area draining to the cistern. Rooftop surfaces are what typically make up the CDA, but paved areas can be used with appropriate treatment (oil/water separators and/or debris excluders). Areas of any size, including portions of roofs, can be used based on the sizing guidelines in this design specification. Runoff should be routed directly from the drainage area to rainwater harvesting systems in closed roof drain systems or storm drain pipes, avoiding surface drainage, which could allow for increased contamination of the water.

Contributing Drainage Area Material. The quality of the harvested rainwater will vary according to the roof material or drainage-areaCDA over which it flows. Water harvested from certain types of rooftops and CDAs, such as asphalt sealcoats, tar and gravel, painted roofs, galvanized metal roofs, sheet metal, or any material that may contain asbestos may leach trace metals and other toxic compounds. In general, harvesting rainwater from such surfaces should be avoided. If harvesting from a sealed or painted roof surface is desired, it is recommended that the sealant or paint be certified for such purposes by the National Sanitation Foundation (ANSI/NSF standard). to NSF Protocol P151 (see Section 3.3.9, "References").

Water Quality of Rainwater. Designers should also note that the pH of rainfall in the District tends to be acidic (ranging from 4.5 to 5.0), which may result in leaching of metals from roof surfaces, cistern lining, or water laterals, to interior connections. Once rainfall leaves rooftop surfaces, pH levels tend to be slightly higher, ranging from 5.5 to 6.0. Limestone or other materials may be added in the cistern to buffer acidity, if desired.

Hotspot Land Uses. Harvesting rainwater can be an effective method to prevent contamination of rooftop runoff that would result from mixing it with ground-level runoff from a stormwater hotspot operation.

Setbacks from Buildings. Cistern overflow devices must be designed to avoid causing ponding or soil saturation within 10 feet of building foundations. While most systems are generally sited underground and more than ten10 feet laterally from the building foundation wall, some cisterns are incorporated into the basement of a building or underground parking areas. In any case, cisterns must be designed to be watertight to prevent water damage when placed near building foundations.

Vehicle Loading. Whenever possible, underground rainwater harvesting systems should be placed in areas without vehicle traffic or other heavy loading, such as deep earth fill. If site constraints dictate otherwise, systems must be designed to support the loads to which they will be subjected.

3.3.2 Rainwater Harvesting Conveyance Criteria

Collection and Conveyance. The collection and conveyance system consists of the gutters, downspouts, and pipes that channel rainfall into cisterns. Gutters and downspouts should be designed as they would for a building without a rainwater harvesting system. Aluminum, round-bottom gutters and round downspouts are generally recommended for rainwater harvesting. Typically, gutters should be hung at a minimum of 0.5 percent for 2/3 of the length and at 1 percent for the remaining 1/3 of the length in order to adequately convey the design storm (i.e., Stormwater Retention Volume (SWRv)). If the system will be used for management of the 2-year and 15-year storms, the gutters must be designed to convey the appropriate 2-year and 15-year storm intensities.

Pipes, which connect downspouts to the cistern, should be at a minimum slope of 1.5—percent sackground-sized/designed to convey the intended design storm, as specified above. In some cases, a steeper slope and larger sizes may be recommended and/or necessary to convey the required runoff, depending on the design objective and design storm intensity. Gutters and downspouts should be kept clean and free of debris and rust.

Overflow. An overflow mechanism must be included in the rainwater harvesting system design in order to handle an individual storm event or multiple storms in succession that exceed the capacity of the cistern. Over low The overflow pipe(s) must have a capacity equal to or greater than or equal to the inflow pipe(s) and have a diameter and slope sufficient to drain the cistern while maintaining an adequate freeboard height. The overflow pipe(s) must be screened to prevent access to the cistern by small mammals and birds- and must include a backflow preventer if it connects directly to the combined sewer or storm sewer. All overflow from the system must be directed to an acceptable flow path that will not cause erosion during a 2-year storm event.

3.3.3 Rainwater Harvesting Pretreatment Criteria

Prefiltration is required to keep sediment, leaves, contaminants, and other debris from the system. Leaf screens and gutter guards meet the minimal requirement for prefiltration of small systems, although direct water filtration is preferred. The purpose of prefiltration is to

significantly cut down on maintenance by preventing organic buildup in the cistern, thereby decreasing microbial food sources.

Diverted flows (i.e., first flush diversion and/or overflow from the filter, if applicable) must be directed to an appropriate BMP or to a settling tank to remove sediment and pollutants prior to discharge from the site.

Various pretreatment devices are described below. In addition to the initial first flush diversion, filters have an associated efficiency curve that estimates the percentage of rooftop runoff that will be conveyed through the filter to the cistern. If filters are not sized properly, a large portion of the rooftop runoff may be diverted and not conveyed to the cistern at all. A design intensity of 1 inch/per_hour (for design storm = SWRv) must be used for the purposes of sizing pre-cistern conveyance and filter components. This design intensity captures a significant portion of the total rainfall during a large majority of rainfall events (NOAA, 2004). If the system will be used for channel and flood protection, the 2-year and 15-year storm intensities must be used for the design of the conveyance and pretreatment portion of the system. The Rainwater Harvesting RetentionStorage Volume Calculator, discussed more in Section 3.3.4, "Rainwater Harvesting Design Criteria," allows for input of variable filter efficiency rates for the SWRv-design storm. To meet the requirements to manage the 2-year and 15-year storms, a minimum filter efficiency of 90-percent% must be met.

- **First Flush Diverters.** First flush diverters (see Figure 3.34) direct the initial pulse of rainfall away from the cistern. While leaf screens effectively remove larger debris such as leaves, twigs, and blooms from harvested rainwater, first flush diverters can be used to remove smaller contaminants such as dust, pollen, and bird and rodent feces.
- Leaf Screens. Leaf screens are mesh screens installed over either the gutter or downspout to separate leaves and other large debris from rooftop runoff. Leaf screens must be regularly cleaned to be effective; if not maintained, they can become clogged and prevent rainwater from flowing into the cisterns. Built-up debris can also harbor bacterial growth within gutters or downspouts (Texas Water Development Board, 2005).
- Roof Washers. Roof washers are placed just ahead of cisterns and are used to filter small debris from harvested rainwater (see Figure 3.45). Roof washers consist of a cistern, usually between 25 and 50 gallons in size, with leaf strainers and a filter with openings as small as 30 microns. The filter functions to remove very small particulate matter from harvested rainwater. All roof washers must be cleaned on a regular basis.
- Hydrodynamic Separator. For large-scale applications, hydrodynamic separators and other devices can be used to filter rainwater from larger CDAs.




Figure 3.33.43.3.4 Diagram of a first flush diverter. (Texas Water Development Board, 2005)




Figure 3.43.53.4.5 Diagram of a roof washer. (Texas Water -Development Board, 2005)

3.3.4 Rainwater Harvesting Design Criteria

System Components: Seven primary components of a rainwater harvesting system require special considerations (some of these are depicted in Figure 3.23):

- CDA or CDA surface
- Collection and conveyance system (i.e., gutter and downspouts)
- Cisterns
- Pretreatment, including prescreening and first flush diverters
- Water quality treatment (as required by TRAM)described in Appendix M, "Rainwater Harvesting Treatment and Management Requirements")
- Distribution systems
- Overflow, filter path, or secondary stormwater retention practice

The system components are discussed below:

CDA Surface. When considering CDA surfaces, note-smooth, non-porous materials will drain more efficiently. Slow drainage of the CDA leads to poor rinsing and a prolonged first flush, which can decrease water quality. If the harvested rainwater will be directed towards uses with significant human exposure (e.g., pool filling, public sprinkler fountain), care should be taken in the choice of CDA materials. Some materials may leach toxic chemicals making the water unsafe for humans. In all cases, follow the advice of the TRAM found in Appendix M.

Rainwater can also be harvested from other impervious surfaces, such as parking lots and driveways; however, this practice requires more extensive pretreatment and treatment prior to reuseuse.

- Collection and Conveyance System. See Section 3.3.2-, "Rainwater Harvesting Conveyance Criteriar."
- **Pretreatment.** See Section 3.3.3-, "Rainwater Harvesting Pretreatment Criteria-."
- Cisterns. The cistern is the most important and typically the most expensive component of a rainwater harvesting system. Cistern capacities generally range from 250 to 30,000 gallons, but they can be as large as 100,000 gallons or more for larger projects. Multiple cisterns can be placed adjacent to each other and connected with pipes to balance water levels and to tailor the storage volume needed. Typical rainwater harvesting system capacities for residential use range from 1,500 to 5,000 gallons. Cistern volumes are calculated to meet the water demand and stormwater storage volume retention objectives, as described further below in this specification.

While many of the graphics and photos in this specification depict cisterns with a cylindrical shape, the cisterns can be made of many materials and configured in various shapes, depending on the type used and the site conditions where the cisterns will be installed. For example, configurations can be rectangular, L-shaped, or step vertically to match the

topography of a site. The following factors should be considered when designing a rainwater harvesting system and selecting a cistern:

- Aboveground cisterns should be ultraviolet and impact resistant.
- Underground cisterns must be designed to support the overlying sediment and any other anticipated loads (e.g., vehicles, pedestrian traffic).
- Underground rainwater harvesting systems must have a standard size manhole or equivalent opening to allow access for cleaning, inspection, and maintenance purposes. The access opening must be installed in such a way as to prevent surface- or groundwater from entering through the top of any fittings, and it must be secured/locked to prevent unwanted entry. Confined space safety precautions/requirements should be observed during cleaning, inspection, and maintenance.
- All rainwater harvesting systems must be sealed using a water-safe, non-toxic substance.
- Rainwater harvesting systems may be ordered from a manufacturer or can be constructed on—site from a variety of materials. Table 3.56 below compares the advantages and disadvantages of different cistern materials.
- Cisterns must be opaque or otherwise protected from direct sunlight to inhibit growth of algae, and they must be screened to discourage mosquito breeding.
- Dead storage below the outlet to the distribution system and an air gap at the top of the cistern must be included in the total cistern volume. For gravity-fed systems, a minimum of 6 inches of dead storage must be provided. For systems using a pump, the dead storage depth will be based on the pump specifications.
- Any hookup to a municipal backup water supply must have a backflow prevention device to keep municipal water separate from stored rainwater; this may include incorporating an air gap to separate the two supplies.

Table 3-5.6 Advantages and Disadvantages of Typical Cistern Materials (Source: Cabell Brand Center, 2007; Cabell Brand Center, 2009)

Cistern Material	Advantages	Disadvantages
Fiberglass	Commercially available, alterable and moveable; durable with little maintenance; light weight; integral fittings (no leaks); broad application	Must be installed on smooth, solid, level footing; pressure proof for below-ground installation; expensive in smaller sizes
Polyethylene	Commercially available, alterable, moveable, affordable; available in wide range of sizes; can install above or below ground; little maintenance; broad application	Can be UV-degradable; must be painted or tinted for above-ground installations; pressure-proof for below-ground installation
Modular Storage	Can modify to topography; can alter footprint and create various shapes to fit site; relatively inexpensive	Longevity may be less than other materials; higher risk of puncturing of watertight membrane during construction
Plastic Barrels	Commercially available; inexpensive	Low storage capacity (20 - 50 gallons); limited application
Galvanized Steel	Commercially available, alterable, and moveable; available in a range of sizes; film develops inside to prevent corrosion	Possible external corrosion and rust; must be lined for potable use; can only install above ground; soil pH may limit underground applications
Steel Drums	Commercially available, alterable, and moveable	Small storage capacity; prone to corrosion, and rust can lead to leaching of metals; verify prior to reuse for toxics; water pH and soil pH may also limit applications
FerroConcrete Ferroconcrete	Durable and immoveable; suitable for above or below ground installations; neutralizes acid rain	Potential to crack and leak; expensive
Cast-in-Place Concrete	Durable, immoveable, and versatile; suitable for above or below ground installations; neutralizes acid rain	Potential to crack and leak; permanent; will need to provide adequate platform and design for placement in clay soils
Stone or Concrete Block	Durable and immoveable; keeps water cool in summer months	Difficult to maintain; expensive to build

- Water Quality Treatment. Depending upon the collection surface, method of dispersal, and proposed use for the harvested rainwater, a water quality treatment device may be required by the TRAM (see Appendix M). Treatment requirements are described in Appendix M, "Rainwater Harvesting Treatment and Management Requirements.".
- **Distribution Systems.** Most distribution systems require a pump to convey harvested rainwater from the cistern to its final destination, whether inside the building, an automated irrigation system, or gradually discharged to a secondary stormwater treatment practice. The rainwater harvesting system should be equipped with an appropriately sized pump that produces sufficient pressure for all end-uses.

The typical pump and pressure tank arrangement consists of a multi-stage, centrifugal pump, which draws water out of the cistern and sends it into the pressure tank, where it is stored for distribution. Some systems will not require this two-tank arrangement (e.g., low-pressure and gravel systems). When water is drawn out of the pressure tank, the pump activates to supply

additional water to the distribution system. The backflow preventer is required to separate harvested rainwater from the main potable water distribution lines.

Distribution lines from the rainwater harvesting system should be buried beneath the frost line. Lines from the rainwater harvesting system to the building should have shut-off valves that are accessible when snow cover is present. A drain plug or cleanout sump must be installed to allow the system to be completely emptied, if needed. Above-ground outdoor pipes must be insulated or heat-wrapped to prevent freezing and ensure uninterrupted operation during winter if winter use is planned.

Overflow. See Section 3.3.2, "Rainwater Harvesting Conveyance Criteria...".

Rainwater Harvesting Material Specifications. The basic material specifications for rainwater harvesting systems are presented in Table 3.67. Designers should consult with experienced rainwater harvesting system and irrigation installers on the choice of recommended manufacturers of prefabricated cisterns and other system components.

Table 3.6.7 Design Specifications for Rainwater Harvesting Systems

١.				
	Item	Specification		
	Gutters and Downspouts	Materials commonly used for gutters and downspouts include polyvinylchloride (PVC) pipe, vinyl, aluminum, and galvanized steel. Lead must not be used as gutter and downspout solder, since rainwater can dissolve the lead and contaminate the water supply. The length of gutters and downspouts is determined by the size and layout of the catchment and the location of the cisterns. Be sure to include Include needed bends and tees.		
	Pretreatment	At least one of the following (all rainwater to pass through pretreatment): First flush diverter Hydrodynamic separator Roof washer Leaf and mosquito screen (1 mm mesh size)		
Cisterns Cisterns Cisterns Cisterns must be watertight and so Cisterns must be opaque or otherw		 Cisterns should be constructed in areas of the site where soils can support the load associated with stored water. Cisterns must be watertight and sealed using a water-safe, non-toxic substance. Cisterns must be opaque or otherwise shielded to prevent the growth of algae. 		

Note: This table does not address indoor systems or pumps.

Design Objectives and System Configuration. Rainwater harvesting systems can have many design variations that meet user demand and stormwater objectives. This specification provides a design framework to achieve the SWRv objectives that are required to comply with the regulations, and it adheres to the following concepts:

 Give preference to use of rainwater as a resource to meet on-site demand or in conjunction with other stormwater retention practices. Reduce peak flow by achieving volume reduction and temporary storage of runoff.

Based on these concepts, this specification focuses on system design configurations that harvest rainwater for internal building uses, seasonal irrigation, and other activities, such as cooling tower use and vehicle washing. While harvested rainwater will be in year-round demand for many internal building uses, some other uses will have varied demand depending on the time of year (e.g., cooling towers and seasonal irrigation). Thus, a lower retention value is assigned to a type of use that has reduced demand.

Design Objectives and Cistern Design Set-Ups. Prefabricated rainwater harvesting cisterns typically range in size from 250 to over 30,000 gallons. Three basic cistern designs meet the various rainwater harvesting system configurations in this section.

Cistern Design 1. The first cistern set-up (Figure 3.56) maximizes the available storage volume associated with the SWRv to meet the desired level of stormwater retention. This layout also maximizes the storage that can be used to meet a demand. An emergency overflow exists near the top of the cistern as the only gravity release outlet device (not including the pump, manway, or inlets). It should be noted that it is possible to address 2-

year and 15-year storm volumes with this cistern configuration, but the primary purpose is to address the smaller SWRv design storm.




Figure 3.53.63.5.6 Cistern Design 1: Storage associated with the design storm volume only.

• Cistern Design 2. The second cistern set-up (Figure 3.67) uses cistern storage to meet the SWRv storageretention objectives and also uses additional detention volume to meet some or all of the 2-year and 15-year storm volume requirements. An orifice outlet is provided at the top of the design storage for the SWRv level, and an emergency overflow is located at the top of the detention volume level.




Figure 3.63.73.6.7 Cistern Design 2: Storage associated with design storm, channel protection, and flood volume.

• Cistern Design 3. The third cistern set-up (Figure 3.78) creates a constant drawdown within the system. The small orifice at the bottom of the cistern needs to be routed to an appropriately designed secondary practice (i.e., bioretention, stormwater infiltration) that will allow the rainwater to be treated and allow for groundwater recharge over time. The release must not be discharged to a receiving channel or storm drain without treatment, and

maximum specified drawdown rates from this constant drawdown should be adhered to, since the primary function of the system is not intended to be detention.

While a small orifice is shown at the bottom of the cistern in Figure 3.8, the orifice could be replaced with a pump that would serve the same purpose by conveying a limited amount of water to a secondary practice on a routine basis.

For this design, the secondary practice is considered a component of the rainwater harvesting system with regard to the storage volume calculated in the General Retention Compliance Calculator or Stormwater Database (discussed in Chapter 5, "Administration of Stormwater Management Rules," and Appendix A, "Compliance Calculations and Design Examples"). In other words, the storage volume associated with the secondary practice must not be included as a separate BMP because the secondary practice is an integral part of a rainwater harvesting system with a constant drawdown.




Figure 3.73.83.7.8 Cistern Design 3: Constant drawdown version where storage is associated with design storm, channel protection, and flood volume.

Design Storm, Channel Protection, and Flood Volume. For the purposes of the third cistern design, the secondary practice must be considered a component of the rainwater harvesting system with regard to the storage volume percentage calculated in the General Retention Compliance Calculator (discussed in Chapter 5 and Appendix A). In other words, the storage volume associated with the secondary practice must not be added (or double counted) to the rainwater harvesting percentage because the secondary practice is an integral part of a rainwater harvesting system with a constant drawdown. The exception to this requirement would be if the secondary practice were also sized to capture and treat impervious and/or turf area beyond the area treated by rainwater harvesting (for example from the adjacent yard or a driveway). In this

ease, only these additional areas should be added into the General Retention Compliance Calculator to receive retention volume achieved for the secondary practice.

While a small orifice is shown at the bottom of the cistern in Figure 3.7, the orifice could be replaced with a pump that would serve the same purpose, conveying a limited amount of water to a secondary practice on a routine basis.

Sizing of Rainwater Harvesting Systems. The rainwater harvesting cistern sizing criteria presented in this section were developed using a spreadsheet model that used best estimates of indoor and outdoor water demand, long-term rainfall data, and CDA capture area data (Forasté2011Forasté 2011). The Rainwater Harvesting Retention Storage Volume Calculator is for cistern sizing guidance and to quantify the retention value for storage volume achieved. This retentionstorage volume value is required for input into the General Retention Compliance Calculator or Stormwater Database and is part of the submission of a Stormwater Management (SWMP) using rainwater harvesting systems for compliance. A secondary objective of the spreadsheet is to increase the beneficial uses of the stored stormwater, treating it as a valuable natural resource. More information on the Rainwater Harvesting RetentionStorage Volume Calculator can be found later in this section.follows. The spreadsheet can be found on DDOE'sDOEE's website at http://ddoe.de.gov/swregs.https://doee.dc.gov/swgudebook.

Rainwater Harvesting Retention Storage Volume Calculator. The design specification provided in this section (Rainwater Harvesting) is linked with the Rainwater Harvesting Retention Storage Volume Calculator. The spreadsheet uses daily rainfall data from September 1, 1977, to September 30, 2007, to model performance parameters of the cistern under varying CDAs, demands on the system, and cistern size.

The runoff that reaches the cistern each day is added to the water level that existed in the cistern the previous day, with all of the total demands subtracted on a daily basis. If any overflow is realized, the volume is quantified and recorded. If the cistern runs dry (reaches the cut-off volume level), then the volume in the cistern is fixed at the low level, and a dry frequency day is recorded. The full or partial demand met in both cases is quantified and recorded. A summary of the water balance for the system is provided below.

Incremental Design Volumes within Cistern. Rainwater cistern sizing is determined by accounting for varying precipitation levels, captured CDA runoff, first flush diversion (through filters) and filter efficiency, low water cut-off volume, dynamic water levels at the beginning of various storms, storage needed for the design storm (permanent storage), storage needed for 2-year or 15-year volume (temporary detention storage), seasonal and year-round demand use and objectives, overflow volume, and freeboard volumes above high water levels during very large storms. See Figure 3.89 for a graphical representation of these various incremental design volumes.

The design specification described in this section (Rainwater Harvesting) does not provide guidance for sizing larger storms (e.g., Qp_2 , Qp_{15} , and Q_f), but rather provides guidance on sizing for the $\overline{SWRv1.7-inch}$ design $\overline{stormsstorm}$.




Figure 3.83.93.8.9 Incremental design volumes associated with cistern sizing.

The "Storage Associated with the Retention Value" is the <u>average</u> storage within the cistern that is modeled and available <u>for reuseto retain rainfall</u>. While the SWRv will remain the same for a specific CDA, the "Storage Associated with the Retention Value" <u>may vary depending is dependent</u> on demand and storage volume retention objectives. It <u>includes is</u> the <u>variable</u> <u>water available space in the cistern between the average</u> level at the beginning of a storm and the low water cut off volume that is necessary to satisfy pumping requirements orifice outflow.

Water Contribution


- **Precipitation.** The volume of water contributing to the rainwater harvesting system is a function of the rainfall and CDA, as defined by the designer.
- Municipal Backup (optional). In some cases, the designer may choose to install a municipal backup water supply to supplement cistern levels. Note that municipal backups may also be connected post-cistern (i.e., a connection is made to the non-potable water line that is used for pumping water from the cistern for reuse), thereby not contributing any additional volume to the cistern. Municipal backup designs that supply water directly to the cistern are not accounted for in the Rainwater Harvesting RetentionStorage Volume Calculator.

Water Losses

- Contributing Drainage Area Runoff Coefficient. The CDA is assumed to convey 95 $\frac{1}{1000}$ percent% of the rainfall that lands on its surface (i.e., Rv = 0.95).
- **First Flush Diversion.** The first 0.02 to 0.06 <u>inchesinch</u> of rainfall that is directed to filters is diverted from the system in order to prevent clogging it with debris. This value is assumed to be contained within the filter efficiency rate.
- Filter Efficiency. It is assumed that, after the first flush diversion and loss of water due to filter inefficiencies, the remainder of the SWRvdesign storm will be captured successfully captured. For the 1.2-inch storm, a minimum of 95-percent of the runoff should be conveyed into the cistern. For the 3.2-inch storm, a minimum of 90-percent of the runoff should be conveyed. These minimum values are included as the filter efficiencies in the Rainwater Harvesting RetentionStorage Volume Calculator, although they can be altered (increased) if appropriate. The Rainwater Harvesting RetentionStorage Volume Calculator applies these filter efficiencies, or interpolated values, to the daily rainfall record to determine the volume of runoff that reaches the cistern. For the purposes of selecting an appropriately sized filter, a rainfall intensity of 1 inch per hour shall be used for when the design storm is the SWRv. The appropriate rainfall intensity values for the 2-year (3.2-inch) and 15-year storms shall be used when designing for larger storm events.
- Drawdown (Storage Volume). This is the stored water within the cistern that is reused or directed to a secondary stormwater practice. It is the volume of runoff that is reduced from the CDA. This is the water loss that translates into the achievable storage volume retention.

Overflow. For the purposes of addressing the SWRv (not for addressing larger storm volumes), orifice outlets for both detention and emergency overflows are treated the same. This is the volume of water that may be lost during large storm events or successive precipitation events.

- Storage Volume Results for all Precipitation Events. The performance results of Rainwater Harvesting Storage Volume Calculator determines the rainwater harvesting system for all days during the entire period modeled, including the full spectrum of precipitation events, is included average daily volume of water in the "Results" tab. This tab is not associated with determining the storage volume achieved, but instead may be a useful tool in assisting the user to realize the performance of the various rainwater harvesting system sizes with the design parameters and demands specified.
- Percentage of Demand Met. This is where the percentage of demand met for various size cisterns and CDA/demand scenarios is reported. A graph displaying the percentage of demand met versus the percentage of overflow frequency for various cistern sizes is provided in this tab. Normally, this graph assists the user in understanding the relationship between for a range of cistern sizes and optimal/diminishing returns. An example is provided below in Figure 3.9.
- * At some point, larger eisterns no longer provide significant increases in percentages of demand met. Conversely, the curve informs the user when a small increase in cistern size can yield a significant increase in the percentage of time that demand is met.



Example of percent demand met versus cistern storage.

Dry Frequency. Another useful measure is the dry frequency. If the cistern is dry a substantial portion of the time, this measure can inform the user that he/she may want to decrease the size of the cistern, decrease the demand on the system, or explore capturing more CDA to provide a larger supply, if feasible. It can also provide useful insight for the designer to determine whether he/she should incorporate a municipal backup supply to ensure sufficient water supply through the system at all times.


Overflow Frequency. This is a metric of both overflow frequency and average volume per year for the full spectrum of rainfall events. This metric will inform the user regarding the design parameters, magnitude of demand, and associated performance of the system. If the system overflows at a high frequency, then the designer may want to increase the size of the cistern, decrease the CDA captured, or consider other mechanisms that could increase drawdown (e.g., increase the area to be irrigated, incorporate or increase on site infiltration, etc.).

Inter-relationships and Curves of Diminishing Returns. Plotting various performance metrics against one another can be very informative and reveal relationships that are not evident otherwise. An example of this usefulness is demonstrated when the plot of "percentage of demand met versus cistern size" is compared against the plot of "the percentage of overflow-frequency versus cistern size." By depicting these plots on the same graph, a range of optimum cistern sizes emerges. This informs the designer where a small increase or decrease in cistern size will have a significant impact on dry frequency and overflow frequency. Looking outside this range will indicate where changes in cistern sizes will not have significant influence over dry

frequency and overflow frequency, but may offer a large trade-off compared to the cost of the rainwater harvesting system.

Results for Retention Value. The retention . From this value percentage of CDA runoff, the available storage volume that the cistern can capture for athe 1.7-inch storm on an can be calculated; it is simply the difference between the cistern size and the average daily basis given the water demands by the user is presented on the "Results-Retention Value" tab. This information is used to calculate the retention value percentage, which is volume. The available storage volume for the selected cistern size should be used as an input to the General Retention Compliance Calculator or Stormwater Database.

- Retention Value Percentage Achieved. Available Storage Volume (Sv). The percentage of retention value achieved volume available for storage of the 1.7-inch storm is calculated for multiple sizes of cisterns. A trade-off curve plots these results, which allows for a comparison of the retention achieved versus cistern size. While larger cisterns yield more retention, they are more costly. The curve helps the user to choose the appropriate cistern size, based on the design objectives and site needs, and to understand the rate of diminishing returns.
- Overflow Volume. The volume of the overflows resulting from a 1.7-inch precipitation event is also reported in this tab. A chart of the retention value and overflow frequency versus the storage volume is provided. An example is shown in Figure 3.10sheet. The overflow volume is also plotted to illustrate the effects of cistern size on overflow volume. An example chart is shown in Figure 3.10. The effect of diminishing returns is clear. Beyond a cistern size of 3,000 gallons, the overflow volume drops to zero. So, while the available storage continues to increase, the 1.7-inch storm is entirely retained, and no additional retention value will be possible.
- These plotted results establish a trade off relationship between these two performance metrics. In the example in Figure 3.10, a 13,000 gallon eistern optimizes the storage volume achieved and the overflow frequency (near the inflection point of both curves).






Figure $3.93.103.9\underline{10}$ Example of retention value percentage achieved versus storage for non-potable uses.

Results from the Rainwater Harvesting Retention Storage Volume Calculator to be Transferred to the General Retention Compliance Calculator, or Stormwater Database. There are two results from the Rainwater Harvesting Retention Storage Volume Calculator that are to be transferred to the General Retention Compliance Calculator or Stormwater Database, as follows:

- Contributing Drainage Area (CDA). Enter the CDA that was used in the Rainwater
 Harvesting RetentionStorage Volume Calculator in the same row into the Drainage Area
 columns in the blue-Impervious Cover Draining to BMP column (cell (cell B26-D31D25).
- Retention Value. Available Storage Volume. Once thea cistern storage volume associated with the retention value has been selected, transfer enter the Available Storage Volume (ft³) associated with that achieved percentage cistern into the General Retention Compliance Calculator column called "% Retention Value "Storage Volume Provided by BMP" in the "Rainwater Harvesting" row (cell 133).025). The storage volume is also needed for the Stormwater Database, BMPs forms, and BMP Retention and Treatment Achieved section.

Completing the Sizing Design of the Cistern. The total size of the cistern is the sum of the following four volume components:

- Low Water Cutoff Volume (Included). A dead storage area must be included so the pump will not run the cistern dry. This volume is included in the Rainwater Harvesting RetentionStorage Volume Calculator's modeled volume.
- Cistern Storage Associated with Design Volume (Included). This is the <u>cistern</u> design volume from the Rainwater Harvesting <u>RetentionStorage Volume</u> Calculator.
- Adding Channel Protection and Flood Volumes (Optional). Additional detention volume may be added above and beyond the cistern storage associated with the design storm volumes for the 2-year or 15-year events. Typical routing software programs may be used to design for this additional volume.
- Adding Overflow and Freeboard Volumes (Required). An additional volume above the emergency overflow must be provided in order for the cistern to allow very large storms to pass. Above this overflow water level, there will be an associated freeboard volume that should account for at least 5-percent% of the overall cistern size. Sufficient freeboard must be verified for large storms, and these volumes must be included in the overall size of the cistern.

3.3.5 Rainwater Harvesting Landscaping Criteria

If the harvested water is to be used for irrigation, the design plan elements must include the proposed delineation of planting areas to be irrigated, the planting plan, and quantification of the expected water demand. The default water demand for irrigation is 1.0 inchesinch per week over the area to be irrigated during the months of May through October only. Justification must be provided if larger volumes are to be used.

3.3.6 Rainwater Harvesting Construction Sequence

Installation. It is advisable to have a single contractor to install the rainwater harvesting system, outdoor irrigation system, and secondary retention practices. The contractor should be familiar with rainwater harvesting system sizing, installation, and placement. A licensed plumber is required to install the rainwater harvesting system components to the plumbing system.

A standard construction sequence for proper rainwater harvesting system installation is provided below. This can be modified to reflect different rainwater harvesting system applications or expected site conditions.

- 1. Choose the cistern location on the site.
- 2. Route all downspouts or pipes to prescreening devices and first flush diverters.
- **3.** Properly install the cistern.
- **4.** Install the pump (if needed) and piping to end uses (indoor, outdoor irrigation, or cistern dewatering release).
- **5.** Route all pipes to the cistern.

6. Stormwater must not be diverted to the rainwater harvesting system until the overflow filter path has been stabilized with vegetation.

Construction Supervision. The following items should be inspected by a qualified professional in the mechanical, electrical, or plumbing fields prior to final sign-off and acceptance of a rainwater harvesting system:

- Rooftop area matches plans
- Diversion system is properly sized and installed
- Pretreatment system is installed
- Mosquito screens are installed on all openings
- Overflow device is directed as shown on plans
- Rainwater harvesting system foundation is constructed as shown on plans
- Catchment area and overflow area are stabilized
- Secondary stormwater treatment practice(s) is installed as shown on plans
- System commissioning

DDOE's DOEE's construction phase inspection checklist for rainwater harvesting practices and the Stormwater Facility Leak Test form can be found in Appendix K-, "Construction Inspection Checklists."

3.3.7 Rainwater Harvesting Maintenance Criteria

Maintenance Inspections. Periodic inspections and maintenance shall be conducted for each system by a qualified professional.

DDOE's DOEE's maintenance inspection checklists for rainwater harvesting systems and the Maintenance Service Completion Inspection form can be found in Appendix L., "Maintenance Inspection Checklists."

Maintenance Schedule. Maintenance requirements for rainwater harvesting systems vary according to use. Systems that are used to provide supplemental irrigation water have relatively low maintenance requirements, while systems designed for indoor uses have much higher maintenance requirements. Table 3.78 describes routine maintenance tasks necessary to keep rainwater harvesting systems in working condition. Maintenance it is recommended that maintenance tasks must be performed by an "Inspector Specialist," who is certified by the American Rainwater Catchment Association. Maintenance tasks must be documented and substantially comply with the maintenance responsibilities outlined in the declaration of covenants.

Table 3.7.8 Typical Maintenance Tasks for Rainwater Harvesting Systems

Responsible Person	Frequency	Activity
Owner	Four times a year	Inspect and clean prescreening devices and first flush diverters

Responsible Person	Frequency	Activity
	Twice a year	Keep gutters and downspouts free of leaves and other debris
	Once a year	 Inspect and clean storage cistern lids, paying special attention to vents and screens on inflow and outflow spigots. Check mosquito screens and patch holes or gaps immediately Inspect condition of overflow pipes, overflow filter path, and/or secondary stormwater treatment practices
	Every third year	Clear overhanging vegetation and trees over roof surface
	According to Manufacturer	Inspect water quality devices
Qualified ThirdParty	As indicated in TRAMAppendix M, "Rainwater Harvesting Treatment and Management Requirements"	Provide water quality analysis to DDOEField verification and data logs must be available at all times and semiannual reports must be uploaded to the SW database annually.
Inspector	Every third year	 Inspect cistern for sediment buildup Check integrity of backflow preventer Inspect structural integrity of cistern, pump, pipe and electrical system Replace damaged or defective system components

Mosquitoes. In some situations, poorly designed rainwater harvesting systems can create habitat suitable for mosquito breeding. Designers must provide screens on above- and below-ground cisterns to prevent mosquitoes and other insects from entering the cisterns. If screening is not sufficient in deterring mosquitoes, dunks or pellets containing larvicide can be added to cisterns when water is intended for landscaping use.

Cold Climate Considerations. Rainwater harvesting systems have a number of components that can be impacted by freezing temperatures. Designers should give careful consideration to these conditions to prevent system damage and costly repairs.

For above-ground systems, wintertime operation may be more challenging, depending on cistern size and whether heat tape is used on piping. If not protected from freezing, these rainwater harvesting systems must be taken offline for the winter and stormwater treatment values may not be granted for the practice during that off-line period. At the start of the winter season, vulnerable above-ground systems that have not been designed to incorporate special precautions should be disconnected and drained. It may be possible to reconnect former roof leader systems for the winter.

For underground and indoor systems, downspouts and overflow components should be checked for ice blockages during snowmelt events.

Declaration of Covenants. A declaration of covenants <u>is required</u> that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP-<u>is required</u>. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes <u>DDOEDOEE</u> staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is <u>attached</u>

torecorded in the deedDistrict of the property. Columbia land records. A template form is provided at the end of Chapter 5, "Administration of Stormwater Management Rules" (see Figure 5.411), although variations will exist for scenarios where situations in which stormwater crosses property lines. The covenant is between the property owner and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed be issued. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C of to be included as an exhibit to the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined througheither signed by the Responsible Person for Maintenance on a partnership agreement or be identified in a memorandum of understanding that is incorporated into the plan submission.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.3.8 Rainwater Harvesting: Stormwater Compliance Calculations

Rainwater harvesting practices receive a partial retention value for the SWRv-that is equivalent to the percent retention achieved, which is determined by using the Rainwater Harvesting Retention-Storage Volume Calculator, as described in Section 3.3.4-, "Rainwater Harvesting Design Criteria." Rainwater harvesting is not an accepted total suspended solids treatment practice.

Rainwater harvesting practices also contribute to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the Retention Value from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a reduced NRCS CN for the site or SDA. The reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.3.9 References

- Cabell Brand Center. 2007. Virginia Rainwater Harvesting Manual. Salem, VA. http://www.cabellbrandcenter.org
- Cabell Brand Center. 2009. Virginia Rainwater Harvesting Manual, Version 2.0. Salem, VA. http://www.cabellbrandcenter.org/Downloads/RWH_Manual2009.pdf http://www.cabellbrandcenter.org/Downloads/RWH_Manual2009.pdf http://www.cabellbrandcenter.org/Downloads/RWH_Manual2009.pdf http://www.cabellbrandcenter.org/publications
- <u>Forasté, J. Alex. 2011. District of Columbia Cistern Design Spreadsheet. Center for Watershed Protection, Inc.</u>
- NSF International. NSF P151: Certification of Rainwater Catchment System Components. 2014. https://www.nsf.org/newsroom_pdf/water_rainwater_catchment.pdf

National Oceanic and Atmospheric Administration (NOAA). 2004. NOAA Atlas 14

Precipitation-Frequency Atlas of the United States, Volume 2, Version 3.0. Revised 2006.

Silver Spring, MD.

Sharvelle, S.; Ashbolt, N.; Clerico, E.; Hultquist, R.; Leverenz, H.; and Olivieri, A. (2017). Risk-Based Framework for the Development of Public Health Guidance for Decentralized Non-Potable Water Systems. Prepared by the National Water Research Institute for the Water Environment & Reuse Foundation. Alexandria, VA WE&RF Project NoSIWM10C15.

aer Harvestin

Alexandria de la companya della companya de la companya della comp Texas Water Development Board (TWDB). 2005. The Texas Manual on Rainwater Harvesting. Third Ed. Austin, TX.

Impervious Surface Disconnection

Definition, Forasté, J. Alex. 2011. District of Columbia Cistern Design Spreadsheet. Center for Watershed Protection, Inc.

National Oceanic and Atmospheric Administration (NOAA). 2004. NOAA Atlas 14 med 26

mwater Harvesting

Recorded to the second of the s Precipitation-Frequency Atlas of the United States, Volume 2, Version 3.0. Revised 2006. Silver Spring, MD.

Texas Water Development Board (TWDB). 2005. The Texas Manual on Rainwater Harvesting. Third Ed. Austin, TX.


PROPOSED PENISION PROPOSED PRO

3.41.1Impervious Surface Disconnection

Definition. This strategy involves managing runoff close to its source by intercepting, infiltrating, filtering, treating or reusing directing it as it moves from an impervious surface to the drainage system. Disconnection practices can be used to reduce the volume of runoff that enters the combined or separate sewer systems. Two kinds of disconnection are allowed: (1) simple disconnection, whereby from rooftops and/or on lot residential other impervious surfaces are directed to pervious areas. Disconnection practices can be used to reduce the volume of runoff that enters the combined or separate sewer systems. (compacted cover) or conservation areas (natural cover) or soil amended filter paths, and (2) disconnection leading to an alternative retention practice(s) adjacent to the roof (see Figure 3.11). Alternative practices can use less space than simple disconnection and can enhance retention. Applicable practices include the following:

- D-1 Simple disconnection to pervious areas with the compacted cover designation
- D-2 Simple disconnection to conservation areas with the natural cover designation
- D-3 Simple disconnection to a soil compost amended filter path
- D 4 Infiltration by small infiltration practices (dry wells or French drains) (see Section 3.8 Stormwater Infiltration)
- D 5 Filtration by rain gardens or stormwater planters (see Section 3.6 Bioretention)
- D-6 Storage and reuse with a cistern or other vessel (rainwater harvesting) (see Section 3.3 Rainwater Harvesting)

Disconnection practices reduce a portion of the Stormwater Retention Volume (SWRv). In order to meet requirements for larger storm events, disconnection practices must be combined with additional practices.



Figure

3.11 Roof disconnection with alternative retention practices

3.4.1 Impervious Surface Disconnection Feasibility Criteria

Impervious surface disconnections are ideal for use on commercial, institutional, municipal, multi-family residential, and single-family residential buildings. Key constraints with impervious surface disconnections include available space, soil permeability, and soil compaction. <u>Figure 3.11</u> illustrates some of these constraints. These and other feasibility criteria are described below and summarized in Table 3.9.

For disconnection to alternative practices (D 4, D 5, and D 6) consult Sections 3.8, 3.6, and 3.3, respectively. For simple disconnection to compacted cover (D 1) or natural cover (D 2) or soils compost amended filter paths (D-3) the following feasibility criteria exist (also see Table 3.8):

- Contributing Drainage Area. For rooftop impervious areas, the maximum impervious area
 treated cannot exceed 1,000 square feet per disconnection. For impervious areas other than
 rooftop, the longest contributing impervious area flow path cannot exceed 75 feet.
- Required Space. Minimum 150 square feet of disconnection area.
- **Sizing.** The available disconnection area must be at least 10 feet wide and 15 feet long. The disconnection width is limited to 25 feet unless the contributing runoff is conveyed via sheetflow or a level spreader. The disconnection length can be extended up to 100 feet to increase the retention value.
- **Site Topography.** Simple disconnection is best applied when the grade of the receiving pervious area is less than 2-percent, or less than 5 percent with turf reinforcement. The slope of the receiving areas must be graded away from any building foundations. Turf reinforcement may include erosion control matting or other appropriate reinforcing materials that are confirmed by the designer to be erosion resistant for the specific characteristics and flow rates anticipated at each individual application, and acceptable to the plan—approving authority.
- Soils. Impervious surface disconnection can be used on any post-construction Hydrologic Soil Group.hydrologic soil group (HSG). The disconnection area must be kept well-vegetated with minimal bare spots—at least 95 percent% soil cover (see DOEE's Erosion and Sediment Control Manual, Section 1—2.10 Vegetative Stabilization of DDOE's Soil Erosion and Sediment Control Handbook).

 https://doee.dc.gov/sites/default/files/dc/sites/ddoe/release_content/attachments/2017%20DC %20ESC%20Manual FINAL.pdf).
- Building Setbacks. If the grade of the receiving area is less than 1-percent, %, downspouts must be extended 5 feet away from building. Note that the downspout extension of 5 feet is intended for simple foundations. The use of a dry well or French drain adjacent to an inground basement or finished floor area requires an effective water proofing system (e.g., foundation drains).

Table 3-8.9 Feasibility Criteria for Simple Disconnection

Design Factor	Disconnection Design
Contributing Drainage Area	1,000 square feet per rooftop disconnection. For impervious areas other than rooftop, the longest contributing impervious area flow path cannot exceed 75 feet.
Required Space	Minimum 150 square feet of disconnection area.
Sizing	The available disconnection area must be at least 10 feet wide and 15 feet long. Maximum disconnection width is 25 feet unless the contributing runoff is conveyed via sheetflow or a level spreader. Maximum disconnection length is 100 feet.
Site Topography	Grade of the receiving pervious area is less than 2%, or less than 5% with turf reinforcement. The slope of the receiving areas must be graded away from any building foundations.
Soils	Impervious surface disconnection can be used on any post-construction Hydrologic Soil Group-HSG. The disconnection area must be kept well-vegetated with minimal bare spots.
Building Setbacks	5 feet away from building if the grade of the receiving area is less than 1%%.




Figure 3.103.113.10.11 Design requirements for rooftop and impervious surfaces.

3.4.2 Impervious Surface Disconnection Conveyance Criteria

Receiving areas in simple disconnection practices (D-1, D-2, and D-3) require a design that safely conveys the 2-year and 15-year storm events over the receiving area without causing erosion. In some applications, erosion control matting or other appropriate reinforcing materials may be needed to control flow rates anticipated for these larger design storms.

For disconnection to alternative practices, consult the appropriate specifications for information on ensuring proper conveyance of the 2 year and 15 year storm events through the practices.

3.4.3 Impervious Surface Disconnection Pretreatment Criteria

Pretreatment is not needed for simple impervious surface disconnection. For disconnection to alternative practices, external downspout pretreatment is recommended (e.g., leaf screens).

3.4.4 Impervious Surface Disconnection Design Criteria

The following design criteria apply to each disconnection practice:

(D-1) Simple Disconnection to a Pervious Area with the Compacted Cover Designation. Disconnection to pervious areas with the compacted cover designation is required to meet the feasibility criteria presented above in Section 3.4.1-, "Impervious Surface Disconnection Feasibility Criteria."

During site construction, care must be taken not to compact the receiving pervious area. To prevent soil compaction, heavy vehicular and foot traffic must be kept out of the receiving pervious area both during and after construction. This can be accomplished by clearly delineating the receiving pervious areas on all development plans and protecting them with temporary fencing prior to the start of land-disturbing activities (see Appendix N, "Land Cover Designations," for guidance on protecting natural and compacted cover designations during construction). If compaction occurs, soil amendments or post-construction aeration will be required (see Appendix J-on-soil amendments). "Soil Compost Amendment Requirements").

(D-2) Simple Disconnection to a Conservation Area with Natural Cover Designation. Disconnection to conservation areas is required to meet the feasibility criteria presented in Section 3.4.1, "Impervious Surface Disconnection Feasibility Criteria," with the following additional additions/exceptions:

- Minimum disconnection length is 40 feet.
- Maximum slope of the receiving area is 6 percent. (2 percent for the first 10 feet).
- Disconnection area cannot include regulated wetlands and buffer areas.
- Inflow must be conveyed via sheet flow or via a level spreader.

- If inflow is conveyed via sheet flow, the maximum flow path is 75 feet when the runoff is conveyed from an impervious area and 150 feet when the runoff is conveyed from a pervious area.
- If inflow is conveyed via a level spreader, the maximum flow path is 150 feet, and the level spreader must be designed with an appropriate width as specified below.
- Retention value applies only to areas directly receiving sheet flow or directly perpendicular
 to the level spreader.

A level spreader can be used to disperse or "spread" concentrated flow thinly over a vegetated or forested area to promote greater runoff infiltration in the receiving area. A level spreader consists of a permanent linear structure constructed at a 0-percent% grade that transects the slope. The influent concentrated runoff must be spread over an area wide enough area so that erosion of the receiving area does not result. Detailed information on the design and function of level spreaders can be found in Hathaway and Hunt $_{-}$ (2006) and NCDWQ $_{-}$ (2010 $_{-}$).

The minimum required width of the level spreader is

- 13 linear feet per each 1 cubic foot/second of inflow if the receiving conservation area (natural cover designation) has a minimum 90-percent% ground cover
- 40 linear feet per 1 cubic foot/second of inflow if the receiving conservation area (natural cover designation) is forested

(D-3) Simple Disconnection to a Soil Compost-Amended Filter Path. Consult Appendix J Soil Compost Amendment Requirements for detailed information on the design and function of soil compost amendments. The incorporation of compost amendments must meet the design criteria in the specification and include the following design elements:

- Flow from the downspout must spread over a 10-foot—wide strip extending down-gradient along the flow path from the building to the street or conveyance system.
- The filter path must be a minimum 15 feet in length.
- Installation of a pea gravel or river stone diaphragm, or other accepted flow—spreading device is required at the downspout outlet to distribute flows evenly across the filter path.
- The strip requires adequate freeboard so that flow remains within the strip and is not diverted away from the strip. In general, this means that the strip should be lower than the surrounding land area in order to keep flow in the filter path. Similarly, the flow area of the filter strip must be level to discourage concentrating the flow down the middle of the filter path.
- Use 2 to 4 inches of compost and till to a depth of 6 to 10 inches within the filter path.

(D-4) Infiltration by Small Infiltration Practices. Depending on soil properties, roof runoff may be infiltrated into a shallow dry well or French drain. The design for this alternative must meet the requirements of infiltration practices, as described in Section 3.8 and summarized in Table 3.9 below. Note that the building setback of 5 feet is intended for simple foundations. The use of a dry well or French drain adjacent to an in ground basement or finished floor area should

be earefully designed and coordinated with the design of the structure's water-proofing system (e.g., foundation drains), or avoided altogether.

Table 3.9 Design Criteria for Disconnection to Small-Scale Infiltration

Design Factor	Infiltration Design
Roof Area Treated	250 to 2,500 square feet
Typical Practices	Dry well and French drain
Recommended Maximum Depth	3 feet
Sizing	See Section 3.8 Stormwater Infiltration
Observation Well	No
Type of Pretreatment	External (leaf screens, grass strip, etc.)
UIC Permit Needed	Not typically ¹
Head Required	Nominal, 1 to 3 feet
Required Soil Test	One per practice
Building Setbacks	10 feet from structure ² , unless an impermeable liner is used

¹ Infiltration practice must be wider than it is deep. See Section 3.8 Stormwater Infiltration for more information.
² Note that the building setback is intended for simple foundations. The use of a dry well or French drain adjacent to an in-ground basement or finished floor area should be carefully designed and coordinated with the design of the structure's water proofing system (e.g., foundation drains), or avoided altogether.

In general, micro infiltration areas will require a surface area up to 3 percent of the contributing roof area. An on site soil test is needed to determine if soils are suitable for infiltration.

(D-5) Filtration by Rain Gardens or Stormwater Planters. For some residential applications, front, side, and/or rear yard bioretention may be an attractive option used to filter roof runoff (see Figure 3.12). Stormwater planters are also a useful option to disconnect and treat rooftop runoff, particularly in ultra urban areas. The designs for these options must meet the requirements of stormwater planters (B-4) or rain gardens (B-5), as described in Section 3.6 and summarized in Table 3.10 below.



Figure 3.12 Demonstration sites exist throughout the District to promote downspout disconnection, removing impervious pavement, and promoting native plants.

Table 3.10 Design Criteria for Disconnection to Small-scale Bioretention (D.5)

Design Factor	Bioretention Design
Impervious Area Treated	1,000 square feet (see Section 3.6 Bioretention)
Type of Inflow	Sheetflow or roof leader
Observation Well/Cleanout Pipes	No
Type of Pretreatment	External (e.g., leaf screens)
Underdrain	Optional per soils (see Section 3.6 Bioretention)
Gravel Layer	12 inches
Minimum Filter Media Depth	18 inches
Media Source	Can be mixed on site
Head Required	Nominal, 1 to 3 feet
Sizing	(See Section 3.6 Bioretention)
Required Soil Test	One per practice
Building Setbacks	10 feet from structure unless an impermeable liner is used

(D-6) Storage and Reuse with a Cistern. This form of disconnection must conform to the design requirements outlined in Section 3.3. Cisterns can be sized for commercial as well as residential purposes. Residential cisterns are commonly called rain barrels.

3.4.5 Impervious Surface Disconnection Landscaping Criteria

All receiving disconnection areas must be stabilized to prevent erosion or transport of sediment to receiving practices or drainage systems. Several appropriate types of grasses for disconnection practices area are listed in Table 3.440. Designers must ensure that the maximum flow

velocities do not exceed the values listed in the table for the selected grass species and the specific site slope. If using vegetation outside of this table, the designer must provide documentation to ensure excessive erosion will not occur. Additionally, see the DDOE Soil DOEE Erosion and Sediment Control Handbook (Manual Section J—2.10 Vegetative Stabilization) for vegetation suggestions.

(https://doee.dc.gov/sites/default/files/dc/sites/ddoe/release_content/attachments/2017%20DC%20ESC%20Manual_FINAL.pdf).

Table 3.9.10 Recommended Vegetation for Pervious Disconnection Areas

Vocatation Type	Clone (0/)	Maximum Velocity (ft/s)	
Vegetation Type	Slope (%)	Erosion resistant soil	Easily Eroded Soil
	< 5	8	6
Bermuda Grass	5–10	7	5
	> 10	6	4
Kentucky Bluegrass	< 5	7	5
	5–10	6	4
	> 10	5	3
Tall Fescue Grass Mixture	< 5	6	4
Tall Fescue Grass Mixture	5–10	4	3
Annual and Perennial Rye	0–5	4	3
Sod	0–5	4	3

Source: USDA, TP-61, 1954; City of Roanoke Virginia Stormwater Design Manual, 2008.

3.4.6 Impervious Surface Disconnection Construction Sequence

Construction Sequence for Disconnection to Pervious Areas. For simple disconnection to a pervious area, the pervious area can be within the limits of disturbance (LOD) during construction. The following procedures should be followed during construction:

- Before site work begins, the receiving pervious disconnection area boundaries should be clearly marked.
- Construction traffic in the disconnection area should be limited to avoid compaction. The material stockpile area shall not be located in the disconnection area.
- Construction runoff should be directed away from the proposed disconnection area, using perimeter silt fence, or, preferably, a diversion dike.

- If existing topsoil is stripped during grading, it shall be stockpiled for later use.
- The disconnection area may require light grading to achieve desired elevations and slopes.
 This should be done with tracked vehicles to prevent compaction.
- Topsoil and or compost amendments should be incorporated evenly across the disconnection area, stabilized with seed, and protected by biodegradable erosion control matting or blankets.
- Stormwater must not be diverted into any compost amended areas until the area is stabilized, which is defined as having groundcover of 95-percent% or greater by the DDOE SoilDOEE Erosion and Sediment Control Handbook (Manual Section J—2.10 Vegetative Stabilization). (https://doee.dc.gov/sites/default/files/dc/sites/ddoe/release_content/attachments/2017%20D C%20ESC%20Manual FINAL.pdf).

Construction Sequence for Disconnection to Conservation Areas with Natural Cover Designation. For simple disconnection to a conservation area, the conservation area must be fully protected during the construction stage of development and kept outside the LOD on the soil erosion and sediment control plan-(SESCP).

- No staging, parking, clearing, grading, or heavy equipment access is allowed in the conservation area except temporary disturbances associated with incidental utility construction, restoration operations, or management of nuisance vegetation. Incidental utility construction includes protecting existing utilities, removing abandoned utilities, rearranging service lines, temporarily rearranging utilities, and adjusting utility appurtenances.
- Any conservation areas shall be protected by super silt fence, chain link fence, orange safety
 fence, or other measures to prevent sediment discharge-consistent with the DOEE Erosion
 and Sediment Control standards and specifications as posted on DOEE's website at
 https://doee.dc.gov/esc.
- The LOD must be clearly shown on all construction drawings and identified and protected in the field by acceptable signage, silt fence, snow fence, or other protective barrier.
- If a level spreader is to be used in the design, construction of the level spreader shall not commence until the contributing drainage area CDA has been stabilized and perimeter soil erosion and sediment control measures have been removed and cleaned out. Further, stormwater Stormwater must not be diverted into the disconnection area until the level spreader is installed and stabilized.

Construction Supervision. Construction supervision is recommended to ensure compliance with design standards. A qualified professional should evaluate the performance of the disconnection after the first big stormsignificant rainfall event to look for evidence of gullies, outflanking, undercutting or sparse vegetative cover. Spot repairs should be made, as needed.

 $\overline{\text{DDOE's}}\overline{\text{DOEE's}}$ construction phase inspection checklist for impervious cover disconnection can be found in Appendix K_7 , "Construction Inspection Checklists."

3.4.7 Impervious Surface Disconnection Maintenance Criteria

Maintenance of disconnected downspouts usually involves the regular lawn or landscaping maintenance in the filter path from the roof to the street. In some cases, runoff from a simple disconnection may be directed to a more natural, undisturbed setting (i.e., where lot grading and clearing is "fingerprinted" and the proposed filter path is protected). Typical maintenance activities include erosion control of the receiving area and ensuring the receiving area remains uncompacted and pervious.

 $\overline{DDOE'sDOEE's}$ maintenance inspection checklists for disconnection can be found in Appendix L_{τ}, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants is required that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5, "Administration of Stormwater Management Rules" (see Figure 5.411), although variations will exist for seenarios wheresituations in which stormwater crosses property lines. The covenant is between the property owner and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed be issued. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C ofto be included as an exhibit to the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined througheither signed by the Responsible Person for Maintenance on a partnership agreement or be identified in a memorandum of understanding that is incorporated into the plan submission.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.4.8 Impervious Surface Disconnection Stormwater Compliance Calculations

Disconnection practices receive the following retention values:

- D-1 (A/B) Simple disconnection to a pervious compacted cover area on HSG A or B soils: retention value of 4 cubic feet (30 gallons) per 100 square feet of receiving pervious area (compacted cover).
- <u>D-1 (C/D)</u> Simple disconnection to a pervious compacted cover area on C or D Soils: retention value of 2 cubic feet (15 gallons) per 100 square footfeet of receiving pervious area (compacted cover).
- D-2 Simple disconnection to a conserved natural cover area: retention value of 6 cubic feet (45 gallons) per 100 square <u>footfeet</u> of receiving pervious conservation area (natural cover).

- D-3 Simple disconnection to a soil compost amended filter path: retention value of 4 cubic (30 gallons) feet per 100 square <u>footfeet</u> of receiving pervious conservation area (soil amended).
- D 4 Infiltration by small infiltration practices (dry wells or French drains): see compliance criteria for Section 3.8.
- D-5 Filtration by rain gardens or stormwater planters: see compliance criteria for Section
- D 6 Storage and reuse with a cistern or other vessel (rainwater harvesting): see compliance criteria for Section 3.3.

Note: The surface areas for practices D-1 and D-3 are considered compacted cover for purposes of retention calculations, and the surface area of practice D-2 is considered natural cover.

Simple disconnection practices are not accepted \underline{as} total suspended solids (TSS) treatment practices (see Table 3.12).

11).

Table 3.5 Disconnection Retention Value and Pollutant Removal

Type of Simple Disconnection	Retention Value cubic feet (gallons) per 100 ft ² of pervious receiving	Accepted TSS Treatment Practice
To a pervious compacted cover area (A/B soils)	4(30)	No
To a pervious compacted cover area_(C/D soils)	2 (15)	No
To a conserved natural cover area	6 (45)	No
To a soil compost amended filter path	4 (30)	No

Impervious surface disconnection also contributes to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the Retention Valueretention value from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced Natural Resource Conservation Service Curve Numberreduced NRCS CN for the site or drainage area. SDA. The Reduced Curve Numberreduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.4.9 References

City of Roanoke Virginia. 2007. Stormwater Design Manual. Department of Planning and Building and Development. Available online at:

 $\frac{\text{http://www.roanokeva.gov/85256A8D0062AF37/vwContentByKey/47E4E4ABDDC5DA16}}{852577AD0054958C/\$File/Table%20of%20Contents%20%26%20Chapter%201%20Design%20Manual%2008.16.10.pdf\\ \underline{\text{Available online at:}}$

http://www.roanokeva.gov/1065/Stormwater-Management-Code

District Department of Transportation (DDOT). Design and Engineering Manual. 2009.

Hathaway, J.M. and Hunt, W.F. 2006. Level Spreaders: Overview, Design, and Maintenance. Urban Waterways Design Series. North Carolina Cooperative Extension Service. Raleigh, NC. Available online:

http://www.bae.ncsu.edu/stormwater/PublicationFiles/LevelSpreaders2006.pdfAvailable online: http://chesapeakestormwater.net/wp-content/uploads/downloads/2012/01/LevelSpreaders2006.pdf

North Carolina Division of Water Quality (NCDWQ). 2010. Level Spreader-Vegetated Filter Strip System. Stormwater Best Practices Manual. Raleigh, NC.

 $\frac{http://portal.ncdenr.org/c/document\ library/get\ file?uuid=5d698f00-caaa-4f64-ac1f-d1561b4fd53d\&groupId=38364$

United States Department of Agriculture (USDA). 1954. Handbook of channel design for soil and water conservation. SCS-TP-61. Washington, DC. <u>Available online: Available online: http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1044529.pdf</u>

Virginia DCR Stormwater Design Specification No. 1: Rooftop (Impervious Surface) Disconnection Version 1.8. 2010.

3.5 Permeable Pavement Systems

Definition. This is a paving system that captures and temporarily stores the Stormwater Retention Volume (SWRv) by filtering runoff through voids in an alternative pavement surface into an underlying stone reservoir. Filtered runoff may be collected and returned to the conveyance system, or allowed to partially (or fully) infiltrate into the soil.

Design variants include the following:

- P-1 Porous asphalt (PA)
- P-2 Pervious concrete (PC)
- P-3 Permeable pavers (PP)
- P 1 Porous asphalt (PA)
- P 2 Pervious concrete (PC)
- P 3 Permeable pavers (PP)

Other <u>surface material</u> variations of permeable pavement that are <u>DDOEDOEE</u>-approved <u>and part of a permeable pavement surface materials</u> system, such as <u>porous rubber</u>, <u>plastic grid pavers</u>, and synthetic turf systems <u>with reservoir layer</u>, are also encompassed in this section.

Permeable pavement systems are not typically designed to provide stormwater detention of larger storms (e.g., 2-year, 15-year), but they may be in some circumstances. Permeable pavement practices shall generally be combined with a separate facility to provide those controls.

There are two different types of permeable pavement design configurations:

- Standard Designs. Practices Design. Practice with a standard underdrain design and no infiltration sump or water quality filter (see Figure 3.4312).
- Enhanced Designs. Practices Design. Practice with underdrains that contain a water quality filter layer and an infiltration sump beneath the underdrain sized to drain the design storm in 48 hours (see Figure 3.1413) or practices with no underdrains that can infiltrate the design storm volume in 48 hours (see Figure 3.1514).

The particular design configuration to be implemented on a site is typically dependent on specific site conditions and the characteristics of the underlying soils. These criteria are further discussed below.





Figure 3.113.12.12 Cross section of a standard permeable pavement design.



 $Figure \ 3.\underline{123.13}.\underline{13} \ Cross \ section \ of \ an \ enhanced \ permeable \ pavement \ design \ with \ an \ underdrain.$




Figure 3.133.14.14 Cross section of an enhanced standard permeable pavement design without an underdrain.

3.5.1 Permeable Pavement Feasibility Criteria

Since permeable pavement has a very high retention capability, it should always be considered as an alternative to conventional pavement. Permeable pavement is subject to the same feasibility constraints as most infiltration practices, as described below.

Required Space. A prime advantage of permeable pavement is that it does not normally require additional space at a new development or redevelopment site, which can be important for tight sites or areas where land prices are high.

Soils. Soil conditions do not typically constrain the use of permeable pavement, although they do determine whether an underdrain is needed. Underdrains may be required if the measured permeability of the underlying soils is less than 0.5 <u>inchesinch</u> per hour (although utilization of an infiltration sump may still be feasible). When designing an infiltrating permeable pavement practice, designers must verify soil permeability by using the on-site soil investigation methods provided in Appendix O₇, "Geotechnical Information Requirements for Underground BMPs." Impermeable soils will require an underdrain.

In fill soil locations, geotechnical investigations are required to determine if the use of an impermeable liner and underdrain are necessary or if the use of an infiltration sump is permissible (see Section 3.5.4-, "Permeable Pavement Design Criteria).").

Contributing Drainage Area. The portion of the contributing drainage area CDA that does not include the permeable pavement may not exceed 5 times the surface area of the permeable

pavement (2 times is recommended), and it should be as close to 100 percent 100 impervious as possible to reduce sediment loading.

Pavement Surface Slope. Steep pavement surface slopes can reduce the stormwater storage capability of permeable pavement and may cause shifting of the pavement surface and base materials. The permeable pavement slope must be less than 5-percent. Designers may consider using a terraced design for permeable pavement in areas with steeper slopes. %. In all cases, designs must ensure that the slope of the pavement does not lead to flow occurring out of the stone reservoir layer onto lower portions of the pavement surface.

Minimum Hydraulic Head. The elevation difference needed for permeable pavement to function properly is generally nominal, although 21 to 4 feet of head from the pavement surface to the underdrain outlet is typically necessary. This value may vary based on several design factors, such as required storage depth and underdrain location.

Minimum Depth to Water Table. A high groundwater table may cause runoff to pond at the bottom of the permeable pavement system. Therefore, a minimum vertical distance of 2 feet must be provided between the bottom of the permeable pavement installation (i.e., the bottom invert of the reservoir layer) and the seasonal high water table.

Setbacks. To avoid the risk of seepage, stormwater cannot flow from the permeable pavement practices must not be hydraulically connected reservoir layer to the traditional pavement base layer, existing structure foundations, or future foundations which may be built on adjacent properties. Setbacks to structures and property lines must be at least 10 feet, and adequate water-proofing waterproofing protection must be provided for foundations and basements. Where the 10-foot setback is not possible, an impermeable liner may be used along the sides of the permeable pavement practice (extending from the surface to the bottom of the practice).

Proximity to Utilities. Interference with underground utilities should be avoided, if possible. When large site development is undertaken the expectation of achieving avoidance will be high. Conflicts may be commonplace on smaller sites and in the public right-of-way. (PROW). Consult with each utility company on recommended offsets, which will allow utility maintenance work with minimal disturbance to the permeable paving BMPspavement. For permeable paving BMPspavement in the public right-of-way, (PROW), a consolidated presentation of the various utility offset recommendations can be found in Chapter 33.14.528.8.4.4 of the District of Columbia Department of Transportation (DDOT) Design and Engineering Manual, latest edition. Consult the District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines, latest edition, for water and sewer line recommendations. Where conflicts cannot be avoided, follow these guidelines:

- Consider altering the location or sizing of the permeable <u>paving BMPpavement</u> to avoid or minimize the utility conflict. Consider an alternate BMP type to avoid conflict.
- *—Use design features to mitigate the impacts of conflicts that may arise by allowing the permeable Consider an alternate BMP type to avoid conflict.
- Use design features to mitigate the impacts of conflicts that may arise by allowing the permeable paving BMPpavement and the utility to coexist. The permeable pavingpavement

design may need to incorporate impervious areas, through geotextiles or compaction, to protect utility crossings.

- Work with the utility company to evaluate the relocation of the existing utility and install the optimum placement and sizing of the permeable paving BMP pavement.
- If utility functionality, longevity, and vehicular access to manholes can be assured, accept the permeable pavingpavement design and location with the existing utility. Design sufficient soil coverage over the utility or general clearances or other features, such as an impermeable liner, to assure all entities that the conflict is limited to maintenance.
- Design sufficient soil coverage over the utility or general clearances or other features, such
 as an impermeable liner, to assure all entities that the conflict is limited to maintenance.

Note: When accepting utility conflict into the permeable <u>pavingpavement</u> location and design, it is understood the permeable <u>pavingpavement</u> will be temporarily impacted during utility work but the utility <u>owner</u> will replace the permeable <u>pavingpavement</u> or, alternatively, install a functionally comparable permeable <u>pavingpavement</u> according to the specifications in the current version of this <u>Stormwater Management Guidebook</u>. Restoration of permeable <u>pavingpavement</u> that is located in the <u>public right of wayPROW</u> will also conform with the <u>District of Columbia Department of TransportationDDOT</u> Design and Engineering Manual, with special attention to Chapter <u>33</u>, <u>Chapter 47,28</u> and the Design and Engineering Manual supplements for "Low Impact Development" and "Green Infrastructure Standards and Specifications—"

<u>Hotspot Land Uses.</u> Permeable pavements may not be used to treat hotspot runoff. For a list of potential stormwater hotspot operations, consult Appendix P. Hotspot Land Uses. Permeable pavements may not be used to treat hotspot runoff. For a list of potential stormwater hotspot operations, consult Appendix P.

, "Stormwater Hotspots."

On sites with existing contaminated soils, as indicated in Appendix P, "Stormwater Hotspots," infiltration is not allowed. Permeable pavement installations must include an impermeable liner, and the Enhanced Designenhanced design configuration cannot be used.

High Loading Situations. Permeable pavement is not intended to treat sites with high sediment or trash/debris loads, since such loads will cause the practice to clog and fail. High Loading Situations. Permeable pavement is not intended to treat sites with high sediment or trash/debris loads, since such loads will cause the practice to clog and fail. Sites with considerable pervious area (e.g., newly established turf and landscaping) can be considered high loading sites and the pervious areas should be diverted if possible from the permeable pavement area. a lot of pervious area (e.g., newly established turf and landscaping) can be considered high loading sites and the pervious areas should be diverted if possible from the permeable pavement area. If unavoidable, pretreatment measures, such as a gravel or a sod filter strip should be employed (see Section 3.5.3-, "Permeable Pavement Pretreatment Criteria).").

High Speed Roads. Permeable pavement should not be used for high speed roads, although it has been successfully applied for low speed residential streets, parking lanes, and roadway shoulders.

3.5.2 Permeable Pavement Conveyance Criteria

Permeable pavement designs must include methods to convey larger storms (e.g., 2-year, 15-year) to the storm drain system. The Conveyance methods include the following is a list of methods that can be used to accomplish this:

- Place an overdrain—a horizontal perforated pipe near the top of the reservoir layer—to pass excess flows after water has filled the base.
- Increase the thickness of the top of the reservoir layer by as much as 6 inches to increase storage (i.e., create freeboard). The design computations used to size the reservoir layer often assume that no freeboard is present.
- Create underground detention within the reservoir layer of the permeable pavement system.
 Reservoir storage may be augmented by corrugated metal pipes, plastic or concrete arch structures, etc.
- Route overflows to another detention or conveyance system.
- Set the storm drain inlets flush with the elevation of the permeable pavement surface to
 effectively convey excess stormwater runoff past the system. The design should also make
 allowances for relief of unacceptable ponding depths during larger rainfall events.

3.5.3 Permeable Pavement Pretreatment Criteria


Pretreatment for most permeable pavement applications is not necessary. Additional pretreatment is recommended if the pavement receives <u>run offrunoff</u> from adjacent pervious areas. For example, a gravel or sod filter strip can be placed adjacent to pervious (landscaped) areas to trap coarse sediment particles before they reach the pavement surface in order to <u>prevent premature reduce</u> clogging.

3.5.4 Permeable Pavement Design Criteria

Type of Surface Pavement. The type of pavement should be selected based on a review of the pavement specifications and properties and designed according to the product manufacturer's recommendations.

Pavement Bottom Slope. For unlined designs, the bottom slope of a permeable pavement installation should be as flat as possible (i.e., 0-percent longitudinal and lateral slopes) to enable even distribution and infiltration of stormwater. The maximum bottom slope is 2%. On sloped sites, internal check dams or bermsbarriers, as shown in the diagram Figure 3.46 below 15, can be incorporated into the subsurface to encourage infiltration. Barriers may be constructed of concrete, earthen berms, impermeable membranes, or low permeability geotextile (See Drawing No. 621.11 and 621.64 in the DDOT Green Infrastructure Standards for more details). In this type of design, the depth of the infiltration sump would be the depth behind the check dams. The depth and spacing of the barriers is dependent upon the underlying slope and the infiltration

ratesaturated hydraulic conductivity, as any water retained by the flow barriers must infiltrate within 48 hours. If an underdrain will be used in conjunction with the flow barriers, it can be installed over the top of the barriers, or parallel to the barriers with an underdrain in each cell.






Figure 3.143.15.15 Use of flow barriers to encourage infiltration on sloped sites.

Internal Geometry and Drawdowns.

■ **Rapid Drawdown.** Permeable pavement must be designed so that the target storage volume is detained in the reservoir for as long as possible—__36 to 48 hours—_, before completely discharging through an underdrain. A minimum orifice size of 1 inch is recommended regardless of the calculated drawdown time.

Note: A 48-hour maximum drawdown time is utilized for permeable pavement rather than the 72-hour value used for other BMPs. This shorter drawdown time, in accordance with

industry standards, is intended to ensure that the subgrade does not stay saturated for too long and cause problems with the pavement.

- **Infiltration Sump.** To promote greater retention for permeable pavement located on marginal soils, an infiltration sump can be installed to create a storage layer below the underdrain invert. This design configuration is discussed further below.
- Conservative Infiltration Rates. Designers must use 1/2 of the measured infiltration rate during design to approximate long term infiltration rates (for example, if the measured infiltration rate is 0.7 inches per hour, the design infiltration rate will be 0.35 inches per hour). This requirement is included in Equation 3.2 through Equation 3.4.

Reservoir Layer. The reservoir layer consists of the stone underneath the pavement section and above the bottom filter layer or underlying soils, including the optional infiltration sump. The total thickness of the reservoir layer is determined by runoff storage needs, the infiltration ratesaturated hydraulic conductivity of in-situ soils, structural requirements of the pavement sub-base, depth to water table and bedrock, and frost depth conditions (see Section 3.5.1-, "Permeable Pavement Feasibility Criteria,"). A geotechnical engineer should be consulted regarding the suitability of the soil subgrade.

- The reservoir below the permeable pavement surface should be composed of clean, double-washed stone aggregate and sized for both the storm event to be treated and the structural requirements of the expected traffic loading (additional chamber structures may also be used to create larger storage volumes).
- The storage layer may consist of clean, double-washed No. 57 stone, although No. 2 stone is preferred because it provides additional structural stability. Other appropriate materials may be used if accepted by DDOEDOEE.
- The bottom of the reservoir layer should be completely flat so that runoff will be able to infiltrate evenly through the entire surface. The use of terracing and check dams is permissible.

Underdrains. Most permeable pavement designs will require an underdrain (see Section 3.5.1-, "Permeable Pavement Feasibility Criteria -"). Underdrains can also be used to keep detained stormwater from flooding permeable pavement during extreme <u>rain</u> events. Multiple underdrains are <u>typically</u> necessary for permeable pavement wider than 40 feet, and each underdrain <u>mustis</u> recommended to be located 20 feet or less from the next pipe or the edge of the permeable pavement. (For long and narrow applications, a single underdrain running the length of the permeable pavement is sufficient.). The underdrain should be perforated schedule 40 PVC pipe (corrugated <u>high density propylene</u> (HDPE) may be used for smaller load-bearing applications), with <u>three or four rows of 3/8-inch perforations at 6 inches on center.</u> The underdrain must be encased in a layer of clean, double—washed No. 57 stone, with a minimum 2-inch cover over the top of the underdrain. The underdrain system must include a flow control to ensure that the reservoir layer drains slowly (within 36 to 48 hours).

The underdrain outlet can be fitted with a flow-reduction orifice within a weir or other easily
inspected and maintained configuration in the downstream manhole as a means of regulating

- the stormwater detention time. The minimum diameter of any orifice is <u>one (1)</u> inch. The designer should verify that the volume will draw down completely within 36 to 48 hours.
- On infiltration designs, an underdrain(s) can be installed and capped at the downstream structure as an option for future use if maintenance observations indicate a reduction in the soil permeability.

Observation Wells. All permeable pavement practices must include observation wells. The observation well is used to observe the rate of drawdown within the reservoir layer following a storm event and to facilitate periodic inspection and maintenance. The observation well should consist of a well-anchored, perforated 4- to 6-inch diameter PVC pipe that is tied. Perforations should only be in the reservoir layer. If the permeable pavement has an underdrain, tie the observation well into any TsT or YsY connections in the underdrain system. The observation well should extend vertically to the bottom of the reservoir layer and extend upwards to be flush with the surface (or just under pavers) with a lockable cap.

Infiltration Sump (optional, required for underdrained Enhanced Designs Design). For unlined permeable pavement systems, an optional upturned elbow or elevated underdrain configuration can be used to promote greater retention for permeable pavement located on marginal soils (see Figure 3.4413). The infiltration sump must be installed to create a storage layer below the underdrain or upturned elbow invert. The depth of this layer must be sized so that the design storm can infiltrate into the subsoils in a 48-hour period. The bottom of the infiltration sump must be at least 2 feet above the seasonally high water table. The inclusion of an infiltration sump is not permitted for designs with an impermeable liner. In fill soil locations, geotechnical investigations are required to determine if the use of an infiltration sump is permissible.

In order to improve the infiltration rate of the sump, it may be designed as a series of 1-foot—wide trenches spread 5 feet apart, which are excavated after compaction of the existing soils is performed. Excavation of these trenches may allow access to less compacted, higher permeability soils and improve the effectiveness of the infiltration sump (Brown and Hunt, 2009). Regardless of the infiltration sump design, the infiltration ratesaturated hydraulic conductivity must be field verified.

Filter Layer (optional). To protect the bottom of the reservoir layer from intrusion by underlying soils, a filter layer can be used. The underlying native soils should be separated from the stone reservoir by a 2- to 4--inch layer of choker stone (e.g., No. 8).

Geotextile (optional). Geotextile fabric is another option to protect the bottom of the reservoir layer from intrusion by underlying soils, although some practitioners recommend avoiding the use of fabric beneath permeable pavements since it may become a future plane of clogging within the system. Geotextile fabric is still recommended to protect the excavated sides of the reservoir layer, in order to prevent soil piping. An appropriate geotextile fabric that complies with AASHTO M-288 Class 2, latest edition, requirements and has a permeability of at least an order of magnitude (10 times) higher (10x) than the soil subgrade permeability must be used.

Impermeable Liner. An impermeable liner is not typically required, although it may be utilized in fill applications where deemed necessary by a geotechnical investigation, on sites with

contaminated soils, or on the sides of the practice to protect adjacent structures from seepage. Use a 30 mil (minimum) PVC geomembrane liner. (Follow or equivalent material of an appropriate thickness (follow manufacturer's instructions for installation.). Field seams must be sealed according to the liner manufacturer's specifications. A minimum 6-inch overlap of material is required at all seams.

Material Specifications. Permeable pavement material specifications vary according to the specific pavement product selected. A general comparison of different permeable pavements is provided in Table 3.43 below 12, but designers should consult manufacturer's technical specifications for specific criteria and guidance. Table 3.44 describes 13 provides general material specifications for the component structures installed beneath the permeable pavement. Note that the size of stone materials used in the reservoir and filter layers may differ depending on the type of surface material.

 $Table \ 3.44\underline{12} \ \ Permeable \ Pavement \ Specifications \ for \ a \ Variety \ of \ Typical \ Surface \ Materials$

Material	Specification	Notes
Permeable Pavers (PP)	Void content, thickness, and compressive strength vary based on type and manufacturer Open void fill media: aggregate, topsoil and grass, coarse sand, etc.	Reservoir layer required to support the structural load.
Pervious Concrete (PC)	Void content: 15% to 25%, 20% Thickness: typically 4 to Typically 4–8 inches- Compressive strength: 2.8-to_28 MPa- Open void fill media: None	May not require a reservoir layer to support the structural load, but a layer may be included to increase the storage or infiltration.
Porous Asphalt (PA)	Void content: 15% to _20%.% Thickness: typically Typically 3 to _7 in inches (depending on traffic load). Open void fill media: None.	Reservoir layer required to support the structural load.

Table 3.12.13 Material Specifications for Typical Layers Beneath the Pavement Surface

Material	Specification	Notes	
Bedding Layer	PC: 3-to_4 inches of No. 57 stone if No. 2 stone is used for Reservoir Layer PA: 3-to_4 inches of No. 57 stone PP: Follow manufacturer specifications	ASTM D448 size No. 857 stone (i.e.g., 3/8 1/2 to 3/ inch1 1/2 inches in size). Must be double-washed and clean and free of all fines.	
Reservoir Layer	PC: No. 57 stone or No. 2 stone PA: No. 2 stone PP: Follow manufacturer specifications	ASTM D448 size No. 57 stone (i_e-g., 1-1/2 to 1_1/2 inch inches in size); No. 2 Stone (i_e-g., 3 inches/4 to 3/4 inches in size). Depth is based on the pavement structural and hydraulic requirements. Must be double-washed and clean and free of all fines. Other appropriate materials may be used if accepted by DDOEDOEE.	
Underdrain	Use 4- to 6-inch diameter perforated PVC pipe (or equivalent corrugated HDPE may be used for smaller load-bearing applications), with 3 or 4 rows of 3/8-inch perforations at 6 inches on center. Perforated pipe installed for the full length of the permeable payement cell, and non-perforated pipe, as needed, is used to connect with the storm drain system. T's and Y's should be installed as needed, depending on the underdrain configuration. Extend cleanout pipes to the surface.		
Infiltration Sump (optional)	An aggregate storage layer below the underdrain invert. The material specifications are the same as Reservoir Layer.		
Filter Layer (optional)	The underlying native soils should be separated from the stone reservoir by a 2 ₋ to 4 ₋ inch layer of choker stone (e.g., No. 8).		
Geotextile (optional)	Use an appropriate geotextile fabric for both sides and/or bottom that complies with AASHTO M-288 Class 2.—(latest edition, available here: https://store.transportation.org/item/publication.detail/3791) requirements and has a permeability of at least an order of magnitude higher (10x)-than (10 times) the soil subgrade permeability. Low-permeability geotextile fabric may be used as a check dam material.		
Impermeable Liner (optional)	Where appropriate, use a thirt mill (minimum) PVC Geomembrane geomembrane liner (follow manufacturer's instructions for installation) or equivalent.		
Observation Well	Use a perforated 4- to 6-inch vertical PVC pipe (AASHTO M-252), https://www.aashtofree.com/aashto-m-252-08-pdf-free-download/) with a lockable cap, installed flush with the surface.		

Permeable Pavement Sizing. The thickness of the reservoir layer is determined by both a structural and hydraulic design analysis. The reservoir layer serves to retain stormwater and also supports the design traffic loads for the pavement. Permeable pavement structural and hydraulic sizing criteria are discussed below.

Structural Design. If permeable pavement will be used in a parking lot or other setting that involves vehicles, the pavement surface must be able to support the maximum anticipated traffic load. The structural design process will vary according to the type of pavement selected, and the manufacturer's specific recommendations should be consulted. The thickness of the permeable pavement and reservoir layer must be sized to support structural loads and to temporarily store the design storm volume (i.e.g., the water quality, channel protection, and/or flood control

volumes). On most new development and redevelopment sites, the structural support requirements will dictate the depth of the underlying stone reservoir.

The structural design of permeable pavements involves consideration of four main site elements:

- Total traffic
- In-_situ soil strength
- Environmental elements
- Bedding and reservoir layer design

The resulting structural requirements may include, but are not limited to, the thickness of the pavement, filter, and reservoir layer. Designers should note that if the underlying soils have a low California Bearing Ratio (CBR) (less than 4-percent), \(\frac{1}{2}\)), they may need to be compacted to at least 95-percent \(\frac{1}{2}\) of the Standard Proctor Density, which may limit their use for infiltration-(ASTM, 2009).

Designers should determine structural design requirements by consulting transportation design guidance sources, such as the following:

- AASHTO Guide for Design of Pavement Structures (1993)
- AASHTO Supplement to the Guide for Design of Pavement Structures (1998)

Hydraulic Design. Permeable pavement is typically sized to store the SWRv or larger design storm volumes in the reservoir layer. The storage volume in the pavements must account for the underlying infiltration ratesaturated hydraulic conductivity and outflow through any underdrains. The design storm should be routed through the pavement to accurately determine the required reservoir depth. The depth of the reservoir layer or infiltration sump needed to store the design storm can be determined by using Equation 3.2.

Equation 3.2 Reservoir Layer or Infiltration Sump Depth

$$d_{p} = \frac{\frac{P \times Rv_{t} \times CDA}{A_{p}} - (i/2 \times t_{f})}{\eta_{F}}$$

$$d_{p} = \frac{(\frac{P \times Rv \times CDA}{A_{p}}) - (K_{sat} \times t_{f})}{\eta_{r}}$$

where:

 d_p = depth of the reservoir layer (or depth of the infiltration sump for enhanced designs with underdrains) (ft)

P = rainfall depth for the SWRv or other design storm (ft)

 Rv_{I} = runoff coefficient for impervious cover (0.95)

 $DARv_I = 0.95$ (runoff coefficient of the CDA

<u>CDA</u> = total drainage area, including contributing drainage area and, including

permeable pavement surface area (ft²)

 A_p = permeable pavement surface area (ft²)

 $i\underline{K}_{sat}$ = field-verified infiltration ratesaturated hydraulic conductivity for the subgrade

soils (ft/day). If an impermeable liner is used in the design, then $\stackrel{.}{=} K_{sat} = 0$.

 t_f = time to fill the reservoir layer (day) (assume 2 hours or 0.083 day)

 t_f = time to fill the reservoir layer (day) (assume 2 hours or 0.083 day)

 $\eta_r = 0.4$ (effective porosity for the reservoir layer (0.35)

This equation makes the following design assumptions:

This equation makes the following design assumptions:

The contributing drainage area (DA) does not contain pervious areas.

- For design purposes, the field tested subgrade soil infiltration rate (i) is divided by 2 as a factor of safety to account for potential compaction during construction. If the subgrade will be compacted to meet structural design requirements of the pavement section, the design infiltration rate of the subgrade soil measured saturated hydraulic conductivity shall be based on measurement of the infiltration rate of the subgrade soil subjected to the compaction requirements.
- The porosity (η_r) for No. 57 stone is 0. The porosity $(\underline{\eta_r})$ for No. 57 stone is 0.35 $\underline{4}$.

The depth of the reservoir layer cannot be less than the depth required to meet the pavement structural requirement. The depth of the reservoir layer may need to be increased to meet structural or larger storage requirements.

Designers must ensure that the captured volume will drain from the pavement in 36 to 48 hours. For infiltration designs without underdrains or designs with infiltration sumps, Equation 3.3 can be used to determine the drawdown time in the reservoir layer or infiltration sump.

Equation 3.3 Drawdown Time

$$t_{d} = \frac{d_{p} \times \eta_{x} \times 2}{i} \frac{d_{p} \times \eta_{r}}{K_{sat}}$$

where:

 t_d = drawdown time (specify unit of measure)

 d_p = depth of the reservoir layer (or the depth of the infiltration sump, for enhanced

designs with underdrains) (ft)

 $\eta_r = 0.4$ (effective porosity for the reservoir layer-(0.35)

 $\underline{K_{sat}}$ = field-verified saturated hydraulic conductivity for the subgrade soils (ft/day). If an impermeable liner is used in the design, then $K_{sat} = 0$.

For designs with underdrains, the drawdown time should be determined using the hydrologic routing or modeling procedures used for detention systems with the depth and head adjusted for the porosity of the aggregate.

The total storage volume provided by the practice, Sv, should be determined using Equation 3.4.

Equation 3.4 Permeable Pavement Storage Volume

$$Sv = A_p[(d_p \times \eta_r) + \frac{i}{2}K_{sat} \times t_f]$$

where:

 $Sv = \text{storage volume (ft}^3)$

 d_p = depth of the reservoir layer (or depth of the infiltration sump for enhanced

designs with underdrains) (ft)

 $\eta_r = 0.4$ (effective porosity for the reservoir layer (0.35)

 A_p = permeable pavement surface area (ft²)

 $i\underline{K}_{sat}$ = field-verified infiltration ratesaturated hydraulic conductivity for the subgrade

soils (ft/day). If an impermeable liner is used in the design, then $i = K_{sat} = K_{sat}$

0.

t_f = time to fill the reservoir layer (day) (assume 2 hours or 0.083 day)

 t_f = time to fill the reservoir layer (days) (assume 2 hours or 0.083 days)

Detention Storage Design. Permeable pavement can also be designed to address, in whole or in part, the detention storage needed to comply with channel protection and/or flood control requirements. The designer can model various approaches by factoring in storage within the stone aggregate layer (including chamber structures that increase the available storage volume), expected infiltration, and any outlet structures used as part of the design. Routing calculations can also be used to provide a more accurate solution of the peak discharge and required storage volume.

Once runoff passes through the surface of the permeable pavement system, designers should calculate outflow pathways to handle subsurface flows. Subsurface flows can be regulated using underdrains, the volume of storage in the reservoir layer, the bed slope of the reservoir layer, and/or a control structure at the outlet (see Section 3.5.2-, "Permeable Pavement Conveyance Criteria).").

3.5.5 Permeable Pavement Landscaping Criteria

Permeable pavement does not have any landscaping needs associated with it. However, large-scale permeable pavement applications should be carefully planned to integrate the typical

landscaping features of a parking lot, such as trees and islands, in a manner that maximizes runoff treatment and minimizes the risk that sediment, mulch, grass clippings, leaves, nuts, and fruits other plant matter will inadvertently clog the paving surface. Bioretention areas (see Section 3.6-, "Bioretention)" may be a good design option to meet these needs landscaping goals.

3.5.6 Permeable Pavement Construction Sequence

Experience has shown that proper installation is absolutely critical to the effective operation of a permeable pavement system.

Soil Erosion and Sediment Controls. The following soil erosion and sediment control guidelines must be followed during construction:

- All permeable pavement areas must be fully protected from sediment intrusion by silt fence or construction fencing, particularly if they are intended to infiltrate runoff.
- Permeable pavement areas intended to infiltrate runoff must remain outside the <u>limidimits</u> of disturbance during construction to prevent soil compaction by heavy equipment and loss of design infiltration rate (unless the area has been determined to have a low <u>CPRCalifornia</u> <u>Bearing Ratio</u> and will require compaction during the permeable pavement construction phase) (<u>ASTM</u>, 2009). Where it is infeasible to keep the proposed permeable pavement areas outside of the limits of disturbance, there are several possible <u>or comes remedies</u> for the impacted area.
 - ◆ If excavation in the proposed permeable pavement areas can be restricted, then remediation can be achieved with deep tilling practices. This is only possible if in_situ soils are not disturbed any deeper than 2 feet above the final design elevation of the bottom of the aggregate reservoir course. In this case, when heavy equipment activity has ceased, the area is excavated to grade, and the impacted area must be tilled to a depth of 12 inches below the bottom of the reservoir layer.
 - ♦ Alternatively, if it is infeasible to keep the proposed permeable pavement areas outside of the limits of disturbance, and excavation of the area cannot be restricted—cannot be met, then infiltration tests will be required prior to installation of the permeable pavement to ensure that the design infiltration rate is still present. If tests reveal the loss of design infiltration rates, then deep tilling practices may be used in an effort to restore those rates. In this case, further testing must be done to establish design rates exist before the permeable pavement can be installed to establish that design rates have been achieved.
 - Finally, if it is infeasible to keep the proposed permeable pavement areas outside of the limits of disturbance, and excavation of the area cannot be restricted, and infiltration tests reveal design rates cannot be restored, then a resubmission of the SWMP will be required.
- Permeable pavement areas must be clearly marked on all construction documents and grading plans.
- During construction, care should be taken to avoid tracking sediments onto any permeable pavement surface to avoid post-construction clogging and long-term maintenance issues.

- Any area of the site intended ultimately to be a permeable pavement area with an infiltration component <u>mustshould</u> not be used as the site of a temporary sediment trap or basin. If locating a temporary sediment trap or basin on an area intended for permeable pavement is unavoidable, the <u>outcomes remedies</u> are <u>parallel similar</u> to those discussed for heavy equipment compaction.
 - ◆ If it is possible restrict the invert of the sediment trap or basin to at least 1 foot above the final design elevation of the bottom of the aggregate reservoir course of the proposed permeable pavement then. Then remediation can be achieved with proper removal of trapped sediments and deep tilling practices.
 - An alternate approach to deep tilling is to use an impermeable linear to protect the in-situ soils from sedimentation while the sediment trap or basin is in use.
 - In each case, all sediment deposits in the excavated area must be carefully removed prior to installing the sub-base, base, and surface materials. The plan must also show the proper procedures for converting the temporary sediment control practice to a permeable pavement BMP, including dewatering, cleanout, and stabilization.

Permeable Pavement Installation. The following is a typical construction sequence to properly install permeable pavement, which may need to be modified depending on the particular type of permeable pavement that is being installed.

- **Step 1:** Stabilize Contributing Drainage Area. Construction of the permeable pavement should only begin after the entire contributing drainage areaCDA has been stabilized. The proposed site should be checked for existing utilities prior to any excavation. Do not install the system in rain or snow and do not install frozen bedding materials.
- Step 2: Install Soil Erosion and Sediment Control Measures for the Permeable Pavement. As noted above, temporary soil erosion and sediment controls are needed during installation to divert stormwater away from the permeable pavement area until it is completed. Special protection measures, such as erosion control fabrics, may be needed to protect vulnerable side slopes from erosion during the excavation process. The proposed permeable pavement area must be kept free from sediment during the entire construction process. Construction materials contaminated by sediment must be removed and replaced with clean material.
- Step 3: Minimize Impact of Heavy Installation Equipment. Where possible, excavators or backhoes should work from the sides to excavate the reservoir layer to its appropriate design depth and dimensions. For small pavement applications, excavating equipment should have arms with adequate extension so they do not have to work inside the footprint of the permeable pavement area (to avoid compaction). Contractors can utilize a cell construction approach, whereby the proposed permeable pavement area is split into 500- to 1,000-square foot temporary cells with a 10- to 15-foot—wide earth bridge in between, so cells can be excavated from the side. Excavated material should be placed away from the open excavation so as to not jeopardize the stability of the side walls.
- **Step 4: Promote Infiltration Rate.** The native soils along the bottom of the permeable pavement system should be scarified or tilled to a depth of 3 to 4 inches prior to the placement of the filter layer or geotextile fabric. In large-scale paving applications with weak soils, the soil

subgrade may need to be compacted to 95-percent of the Standard Proctor Density to achieve the desired load-bearing capacity.

Note: This may reduce or eliminate the infiltration function of the installation, and it must be addressed during hydrologic design.

- Step 5: Order of Materials. Geotextile fabric should be installed on the sides of the reservoir layer (and the bottom if the design calls for it). Geotextile fabric strips should overlap downslope by a minimum of 2 feet and be secured a minimum of 4 feet beyond the edge of the excavation. Where the filter layer extends beyond the edge of the pavement (to convey runoff to the reservoir layer), install an additional layer of geotextile fabric 1 foot below the surface to prevent sediment from entering into the reservoir layer. Excess geotextile fabric should not be trimmed until the site is fully stabilized.
- **Step 6: Install Base Material Components.** Provide a minimum of 2 inches of aggregate above and below the underdrains. The up-gradient end of underdrains in the reservoir layer should be capped. Where an underdrain pipe is connected to a structure, there shall be no perforations within 1 foot of the structure. Ensure there are no perforations in clean-outs and observation wells within 1 foot of the surface.
- **Step 7: Stone Media**. Spread 6-inch lifts of the appropriate clean, double_washed stone aggregate (usually No. 2 or No. 57 stone). Place at least 4 inches of additional aggregate above the underdrain, and then compact it using a vibratory roller in static mode until there is no visible movement of the aggregate. Do not crush the aggregate with the roller.
- **Step 8:** Reservoir Media. Install the desired depth of the bedding layer, depending on the type of pavement, as indicated in Table 3.4413.
- **Step 9:** Paving Media. Paving materials shall be installed in accordance with manufacturer or industry specifications for the particular type of pavement.

Installation of Porous Asphalt. The following has been excerpted from various documents, most notably Jackson (2007):

- Install porous asphalt pavement similarly to regular asphalt pavement. The pavement should be laid in a single lift over the filter course. The laying temperature should be between 2300F230°F and 2600F260°F, with a minimum air temperature of 50°F, to ensure the surface does not stiffen before compaction.
- Complete compaction of the surface course when the surface is cool enough to resist a 10-ton roller. One or two passes of the roller are required for proper compaction. More rolling could cause a reduction in the porosity of the pavement.
- The mixing plant must provide certification of the aggregate mix, abrasion loss factor, and asphalt content in the mix. Test the asphalt mix for its resistance to stripping by water using ASTM <u>1664D1664</u>. If the estimated coating area is not above 95-percent,%, additional antistripping agents must be added to the mix.
- Transport the mix to the site in a clean vehicle with smooth dump beds sprayed with a nonpetroleum release agent. The mix shall be covered during transportation to control cooling.

- Test the full permeability of the pavement surface by application of clean water at a rate of at least <u>five5</u> gallons per minute over the entire surface. All water must infiltrate directly, without puddle formation or surface runoff.
- Inspect the facility 18 to 30 hours after a significant rainfall (0.5 inch or greater than 1/2 inch) or artificial flooding to determine if the facility is draining properly.

Installation of Pervious Concrete. Installation. The basic installation sequence for pervious concrete is outlined by the National Ready Mixed Concrete Association (NRMCA) (NRMCA) (NRMCA). 2004). It is strongly recommended that concrete installers successfully complete a recognized pervious concrete installers training program, such as the Pervious Concrete Contractor Certification Program offered by the NRMCA. The basic installation procedure is as follows:

- Drive the concrete truck as close to the project site as possible.
- Water the underlying aggregate (reservoir layer) before the concrete is placed, so the aggregate does not draw moisture from the freshly laid pervious concrete.
- After the concrete is placed, approximately 3/8 to 1/2 inchesinch is struck off, using a vibratory screed. This is to allow for compaction of the concrete pavement.
- Compact the pavement with a steel pipe roller. Care should be taken to ensure overcompaction does not occur.
- Cut joints for the concrete to a depth of 1/4 inch.
- The curing process is very important for pervious concrete. Concrete installers should follow manufacturer specifications to the extent allowed by on-site conditions when curing pervious concrete. This typically requires covering the pavement with plastic sheeting within 20 minutes of the strike-off, and may require keeping it covered for at least seven (7) days. Do not allow traffic on the pavement during the curing period.
- Remove the plastic sheeting only after the proper curing time. Inspect the facility 18 to 30 hours after a significant rainfall (0.5 inch or greater than 1/2 inch) or artificial flooding, to determine if the facility is draining properly.

<u>Installation of Permeable Interlocking Concrete Pavers Paver Installation</u>. The basic installation process is described in greater detail by Smith (2006):

- Place edge restraints for open-jointed pavement blocks before the bedding layer and pavement blocks are installed. Permeable interlocking concrete pavement (IP)-systems require edge restraints to prevent vehicle loads from moving the paver blocks. Edge restraints may be standard curbs or gutter pans, or precast or cast-in-place reinforced concrete borders a minimum of 6 inches wide and 18 inches deep, constructed with Class A3 concrete. Edge restraints along the traffic side of a permeable pavement block system are recommended.
- Place the double—washed No. 57 stone in a single lift. Level the filter course and compact it into the reservoir course beneath with at least four passes of a 10-ton steel drum static roller until there is no visible movement. The first 2two passes are in vibratory mode, with the final 2two passes in static mode. The filter aggregate should be moist to facilitate movement into the reservoir course.

- Place and screed the bedding course material (typically No. 8 stone).
- Fill gaps at the edge of the paved areas with cut pavers or edge units. When cut pavers are needed, cut the pavers with a paver splitter or masonry saw. Cut pavers no smaller than 1/3 of the full unit size.
- Pavers may be placed by hand or with mechanical installers. Fill the joints and openings with stone. Joint openings must be filled with ASTM D 448D448 No. 8 stone; although, No. 8P or No. 9 stone may be used where needed to fill narrower joints. Remove excess stones from the paver surface.
- Compact and seat the pavers into the bedding course with a minimum low-amplitude 5,000lbfpound-foot, 75- to 95-Hz plate compactor.
- Do not compact within 6 feet of the unrestrained edges of the pavers.
- The system must be thoroughly swept by a mechanical sweeper or vacuumed immediately after construction to remove any sediment or excess aggregate.
- Inspect the area for settlement. Any blocks that settle must be reset and re-inspected.
- Inspect the facility 18 to 30 hours after a significant rainfall (1/20.5 inch or greater) or artificial flooding to determine whether the facility is draining properly.

Construction Supervision. Supervision before, during, and after construction by a qualified professional is recommended to ensure permeable pavement is built in accordance with these specifications. ASTM test C1781 or C1701 must be performed to ensure initial pavement permeability of at least 6 inches per hour. Inspection checklists that require sign-offs by qualified individuals should be used at critical stages of construction to ensure the contractor's interpretation of the plan is consistent with the designer's intent.

 $\frac{\text{DDOE's} \underline{\text{DOEE's}}}{\text{construction phase inspection checklist for permeable pavement practices can}} be found in Appendix K_-, "Construction Inspection Checklists."}$

Some common pitfalls can be avoided by careful construction supervision that focuses on the following key aspects of permeable pavement installation:

- Store materials in a protected area to keep them free from mud, dirt, and other foreign materials.
- The <u>contributing drainage areaCDA</u> should be stabilized prior to directing water to the permeable pavement area.
- Check the aggregate material to confirm it is clean and washed, meets specifications and is installed to the correct depth. Aggregate loads that do not meet the specifications or do not appear to be sufficiently washed may be rejected.
- Check elevations (<u>i.e.-e.</u>, the invert of the underdrain, inverts for the inflow, and outflow points.) and the surface slope.
- Make sure the permeable pavement surface is even, runoff spreads evenly across it, and the storage bed drains within 48 hours.
- Ensure caps are placed on the upstream (but not the downstream) ends of the underdrains.

- Inspect the pretreatment structures (if applicable) to make sure they are properly installed and working effectively.
- Once the final construction inspection has been completed, log the GPS coordinates for each facility and submit them for entry into the BMP maintenance tracking database.

Runoff diversion structures are recommended to protect larger permeable pavement applications from early runoff-producing storms-away from, particularly when up-gradient conventional asphalt areas drain to the permeable pavement. This can help reduce the input of fine particles often produced shortly after conventional asphalt is laid.

3.5.7 Permeable Pavement Maintenance Criteria

Maintenance is a required and crucial element to ensure the long-term performance of permeable pavement. The most frequently cited maintenance problem is surface clogging caused by organic matter and sediment. Periodic street sweeping will remove accumulated sediment and help prevent clogging; however, it is also critical to ensure that surrounding land areas remain stabilized.

The following tasks must be avoided on ALLall permeable pavements:

- Sanding
- Re sealing
- Re surfacing
- Resealing
- Resurfacing
- Power washing
- Storage of snow piles containing sand
- Storage of mulch or soil materials
- Construction staging on unprotected pavement

It is difficult to prescribe the specific types or frequency of maintenance tasks that are needed to maintain the hydrologic function of permeable pavement systems over time. The frequency of maintenance will depend largely on the pavement use, traffic loads, and the surrounding land use.

One preventative maintenance task for large-scale applications (e.g., parking lots) involves vacuum sweeping on a frequency consistent with the use and loadings encountered in the site. Many experts consider an annual, dry-weather sweeping in the spring months to be important. The contract for sweeping should specify that a vacuum sweeper be used that does not use water spray, since spraying may lead to subsurface clogging. Typical maintenance tasks are outlined in Table 3.4514.

Table 3.6 Typical Maintenance Tasks for Permeable Pavement Practices

Frequency	Maintenance Tasks
After installation	 For the first 6 months following construction, the practice and CDA should be inspected at least twice after storm events that exceed <u>1/20.5</u> inch of rainfall. Conduct any needed repairs or stabilization.
Once every 1–2 months during the growing season	 Mow grass in grid paver applications (clippings should be removed from the pavement area).
As needed	 Stabilize the CDA to prevent erosion. Remove any soil or sediment deposited on pavement. Replace or repair any pavement surfaces that are degenerating or spalling.
2–4 times per year (depending on use)	Mechanically sweep -pavement with a standard street sweeper to prevent clogging.
Annually	 Conduct a maintenance inspection Spot weed for grass applications Remove weeds as needed.
Once every 2–3 years	■ Remove any accumulated sediment in pretreatment cells and inflow points.
If clogged	 Conduct maintenance using a regenerative street sweeper or a vacuum sweeper Replace any necessary joint material.

Seasonal Maintenance Considerations: Winter maintenance for permeable pavements is similar to standard pavements, with a few additional considerations:

- Large snow storage piles should be located in adjacent grassy areas so that sediment and
 pollutants in snowmelt are partially treated before they reach the permeable pavement.
- Sand or cinders should never be applied for winter traction over permeable pavement or areas
 of standard (impervious) pavement that drain toward permeable pavement, since it will
 quickly clog the system.
- When plowing plastic reinforced grid pavements, snow plow blades should be lifted \(\frac{1\sqrt{20.5}}{20.5}\) inch to 1 inch above the pavement surface to prevent damage to the paving blocks or turf. Porous asphalt \(\frac{(PA)_{52}}{2}\) pervious concrete \(\frac{(PC)_{52}}{2}\) and some permeable pavers \(\frac{(PP)}{2}\) can be plowed \(\frac{\similar similar similarly}{2}\) to traditional pavements, using similar equipment and settings.
- Chloride products should be used judiciously to deice above permeable pavement designed for infiltration, since the salt will be transmitted through the pavement. Salt can be applied but environmentally sensitive deicers are recommended. Permeable pavement applications will generally require less salt application than traditional pavements.

When permeable pavements are installed on private residential lots, homeowners will need to (1) be educated about their routine maintenance needs and (2) understand the long-term maintenance plan.

It is recommended that a qualified professional conduct a spring maintenance inspection and cleanup at each permeable pavement site, particularly at large-scale applications.

DDOE's DOEE's maintenance inspection checklists for permeable pavements and the Maintenance Service Completion Inspection form can be found in Appendix L., "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants is required that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5, "Administration of Stormwater Management Rules" (see Figure 5.411), although variations will exist for scenarios wheresituations in which stormwater crosses property lines. The covenant is between the property owner and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed_be issued. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C ofto be included as an exhibit to the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined througheither signed by the Responsible Person for Maintenance on a partnership agreement or be identified in a memorandum of understanding that is incorporated into the plan submission.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.5.8 Permeable Pavement Stormwater Compliance Calculations

Permeable pavement retention value varies depending on the design configuration of the system.

Enhanced Designs. These permeable pavement applications have an infiltration sump and water-quality filter, but no underdrain. Enhanced designs receive 100-percent retention value for the amount of storage volume (Sv) provided by the practice (Table 3.4615). Since the practice gets 100-percent retention value, it is not considered an accepted total suspended solids (TSS) treatment practice.

Table 3.7 Enhanced Permeable Pavement Retention Value and Pollutant Removal

Retention Value	=Sv
Accepted TSS Treatment Practice	N/A

Note: If using an infiltration sump design, only the volume stored in the sump can be counted as the Enhanced Design Storage Volume (Sv). Any volume stored in the practice above the sump is counted as a standard design. When using the Site Design Spreadsheet When using the Stormwater Database, enter an enhanced practice and indicate that the practice is enhanced with an underdrain. Enter the total storage volume (including the infiltration sump and reservoir layer). Then enter the portion of the storage volume that is the infiltration sump. When using the General Retention Compliance Calculator, the Sv of the infiltration sump should be entered into the cell "Storage Volume Provided by the Practice" in the Permeable Pavement – Enhanced row. Permeable Pavement – Standard should then be selected as the downstream practice. Next, in the Permeable Pavement - Standard row, the Sv provided above the infiltration sump should be entered into the cell "Storage Volume Provided by the Practice," and the surface area of the pavement should be entered in the "Area of Practice" cell.

Standard Designs. These permeable pavement applications have an underdrain, but no infiltration sump or water quality filter. Standard designs receive a retention value of 4.5.0 cubic feet per 100 square feet of practice area and are an accepted TSS removal practice for the amount of storage volume (Sv) provided by the practice (Table 3.4716).

Table 3.8 Standard Permeable Pavement Retention Value and Pollutant Removal

Retention Value	$= \frac{4.5 ft^3}{100 s^2} 5.0 \text{ cubic feet per } 100 \text{ square feet}$
Accepted TSS Treatment Practice	$=S_{\nu}\underline{Yes}$

The practice must be sized using the guidance detailed in Section 3.5.4, "Permeable Pavement Design Criteria."

Permeable pavement also contributes to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the retention valuestorage volume (Sv) achieved by the practice from the total runoff volumes for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced Natural Resource Conservation Service - Curve Number reduced NRCS CN for the site or drainage area. SDA. The Reduced Curve Number reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.5.9 References

American Association of State Highway and Transportation Officials (AASHTO). 1993. AASHTO Guide for Design of Pavement Structures, 4th Edition with 1998 Supplement. Washington, D.C.

American Association of State Highway and Transportation Officials (AASHTO). 2018. M-252, Standard Specification for Corrugated Polyethylene Drainage Pipe. Washington D.C.

American Association of State Highway and Transportation Officials (AASHTO). 2017. M-288, Standard Specification for Geosynthetic Specification for Highway Applications.

Washington D.C.

ASTM C1701 / C1701M-17a, Standard Test Method for Infiltration Rate of In Place Pervious Concrete, ASTM International, West Conshohocken, PA, 2017, www.astm.org

ASTM C1781 / C1781M-15, Standard Test Method for Surface Infiltration Rate of Permeable Unit Pavement Systems, ASTM International, West Conshohocken, PA, 2015, www.astm.org

ASTM D1664-80 (1985), Test Method for Coating and Stripping of Bitumen-Aggregate

Mixtures (Withdrawn 1992), ASTM International, West Conshohocken, PA, 1985,

www.astm.org

- ASTM D4429-09a, Standard Test Method for CBR (California Bearing Ratio) of Soils in Place (Withdrawn 2018), ASTM International, West Conshohocken, PA, 2009, www.astm.org
- ASTM D448-12 (2017), Standard Classification for Sizes of Aggregate for Road and Bridge Construction, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- Brown, R. and W. Hunt. 2009. "Improving Exfiltration from BMPs: Research and Recommendations." North Carolina Cooperative Extension Service Bulletin. Urban Waterways Series.
- District of Columbia Department of Transportation (DDOT) Design and Engineering Manual, 2017. https://ddot.dc.gov/sites/default/files/dc/sites/ddot/publication/attachments/2017-06-30 DDOT DEM.pdf
- <u>District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility</u>

 <u>Protection Guidelines, 2013.</u>

 <u>https://www.dcwater.com/sites/default/files/Green%20Infrastructure%20Utility%20Protection%20Guidelines.pdf</u>
- Hunt, W. and K. Collins. 2008. "Permeable Pavement: Research Update and Design Implications." North Carolina Cooperative Extension Service Bulletin. Urban Waterways Series.
- Jackson, N. 2007. Design, Construction and Maintenance Guide for Porous Asphalt Pavements. National Asphalt Pavement Association (NAPA), Porous Asphalt Pavements for Stormwater Management: Design, Construction, and Maintenance Guide (IS-131). Lanham, MD, 2008. http://store.asphaltpavement.org/index.php?productID=1/9
- National Ready Mixed Concrete Association (NRMCA). 2004. Concrete in Practice 38: Pervious Concrete. Silver Spring, MD. http://nrmca.org/aboutconcrete/cips/38p.pdf
- Smith, D. 2006. Permeable Interlocking Concrete Pavement-selection design, construction and maintenance. Third Edition. Interlocking Concrete Pavement Institute. Herndon, VA.
- Virginia DCR Stormwater Design Specification No. 7: Permeable Pavement Version 1.7. 2010.

3.6 Bioretention

Definition. Practices that capture and store stormwater runoff and pass it through a filter bed of engineered soilfilter media composed of sand, soil, and organic matter. Filtered runoff may be collected and returned to the conveyance system; or allowed to infiltrate into the soil. Design variants include the following:

- **B** 1 Traditional bioretention
- **B 2** Streetscape bioretention
- B 3 Engineered tree pits
- **B** 4 Stormwater planters
- B 5 Residential rain gardens
- **B-1** Traditional bioretention
- B-2 Streetscape bioretention
- B-3 Engineered tree pits
- **B-4** Stormwater planters
- B-5 Residential rain gardens (for single family homes)

Bioretention systems are typically not designed to provide stormwater detention of larger storms (e.g., 2-year, 15-year), but they may be in some circumstances. Bioretention practices shall generally be combined with a separate facility to provide those controls.

There are two different types of bioretention design configurations:

- Standard Designs. Practices with a standard underdrain design and less than 24at least 18 inches of filter media depth (see Figure 3.17). If trees are planted using this design, the filter media depth must be at least 24 inches to support the trees.16).
- Enhanced Designs. Practices with underdrains that contain at least 24 inches of filter media depth and an infiltration sump/storage layer (see Figure 3.4817) or practices that can infiltrate the design storm volume invithin 72 hours (see Figure 3.4918).

The particular design configuration to be implemented on a site is typically dependent on specific site conditions and the characteristics of the underlying soils. These criteria are further discussed in this chapter.





Figure 3.153.16.16 Example of standard bioretention design.



NOTE: If underlying soil infiltration rate <0.5'/hr, the underdrain and infiltration sump option may be used. The infiltration sump option must be designed to infiltrate the design storm volume in less than 72 hours.





Figure 3.163.17.17 Example of an enhanced bioretention design with an underdrain and infiltration sump/storage layer-






Figure 3.173.18.18 Example of enhanced bioretention design without an underdrain-

3.6.1 Bioretention Feasibility Criteria

Bioretention can be applied in most soils or topography, since runoff simply percolates through an engineered soil bed and is infiltrated or returned to the stormwater system via an underdrain. Key constraints with bioretention include the following:

Required Space. Planners and designers can assess the feasibility of using bioretention facilities based on a simple relationship between the contributing drainage area (CDA), CDA and the corresponding bioretention surface area. The surface area is recommended to be approximately 3% to 6 percent% of CDA, depending on the imperviousness of the CDA and the desired bioretention ponding depth.

Available Hydraulic Head. Bioretention is fundamentally constrained by the invert elevation of the existing conveyance system to which the practice discharges (i.e., the bottom elevation needed to tie the underdrain from the bioretention area into the storm drain system). In general, 4 to 5 feet of elevation above this invert is needed to accommodate the required ponding and filter media depths. If the practice does not include an underdrain or if an inverted or elevated underdrain design is used, less hydraulic head may be adequate.

Water Table. Bioretention must be separated from the water table to ensure that groundwater does not intersect the filter bed. Mixing can lead to possible groundwater contamination or failure of the bioretention facility. A separation distance of 2 feet is required between the bottom of the excavated bioretention area and the seasonally high ground water groundwater table.

Soils and Underdrains. Soil conditions do not typically constrain the use of bioretention, although they do determine whether an underdrain is needed. Underdrains may be required if the measured permeability of the underlying soils is less than 0.5 in./hr_inch per hour. When designing a bioretention practice, designers must verify soil permeability by using the on-site soil investigation methods provided in Appendix O₇, "Geotechnical Information Requirements for Underground BMPs." Impermeable soils will require an underdrain.

For fill soil locations, geotechnical investigations are required to determine if it is necessary to use an impermeable liner and underdrain.

Contributing Drainage Area. Bioretention cells work best with smaller CDAs, where it is easier to achieve flow distribution over the filter bed. The maximum drainage areaCDA to a traditional bioretention area (B-1) is 2.5 acres and can consist of up to 100-percent½ impervious cover. The drainage areaCDA for smaller bioretention practices (B-2, B-3, B-4, and B-5) is a maximum of 1 acre. However, if hydraulic considerations are adequately addressed to manage the potentially large peak inflow of larger drainage areasCDAs, such as off-line or low-flow diversions, or forebays, there may be case-by-case instances where the maximum drainage areasCDAs can be adjusted. Table 3.4817 summarizes typical recommendations for bioretention CDAs.

Table 3.9 Maximum Contributing Drainage Area to Bioretention

Bioretention Type	Design Variants	Maximum Contributing Drainage Area (acres of impervious cover)
Traditional	B-1	2.5
Small-scale and urban-bioretention	B-2, B-3, B-4, and B-5	1.0

Hotspot Land Uses. An impermeable bottom liner and an underdrain system must be employed when a bioretention area will receive untreated hotspot runoff, and the Enhanced Designenhanced design configuration cannot be used. However, bioretention can still be used to treat parts of the site that are outside of the hotspot area. For instance, roof runoff can go to bioretention while vehicular maintenance areas would be treated by a more appropriate hotspot practice.

For a list of potential stormwater hotspots, please consult Appendix P-, "Stormwater Hotspots."

On sites with existing contaminated soils, as indicated in Appendix P, infiltration is not allowed. Bioretention areas must include an impermeable liner, and the Enhanced Design configuration cannot be used.

No Irrigation or Baseflow. The planned bioretention area should not receive baseflow, irrigation water, chlorinated wash-water or any other flows not related to stormwater. However, irrigation is allowed during the establishment period of the bioretention area to ensure plant survival.

Setbacks. To avoid the risk of seepage, stormwater cannot flow from the bioretention areas must not be hydraulically connected reservoir layer to the traditional pavement base layer, existing structure foundations—, or an area where there may be future development adjacent to the property line. Setbacks to structures and property lines must be at least 10 feet, and adequate water proofing waterproofing protection must be provided for foundations and basements. Where the 10-foot setback is not possible, an impermeable liner may be used along the sides of the bioretention area (extending along the sides of the bioretention area from the surface to the bottom of the practice and along the bottom to the 10-foot setback point).

Proximity to Utilities. Designers should ensure that future tree canopy growth in the bioretention area will not interfere with existing overhead utility lines. Interference with underground utilities should be avoided, if possible. When large site development is undertaken the expectation of achieving avoidance will be high. Conflicts may be commonplace on smaller sites and in the public right of way. PROW. Consult with each utility company on recommended offsets, which will allow utility maintenance work with minimal disturbance to the bioretention system. For bioretention in the public right of way.PROW a consolidated presentation of the various utility offset recommendations can be found in Chapter 33.14.528.8.4.4 of the District of Columbia Department of Transportation (DDOT) Design and Engineering Manual, latest edition. Consult the District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines, latest edition, for water and sewer line recommendations. Where conflicts cannot be avoided, follow these guidelines:

- Consider altering the location or sizing of the bioretention to avoid or minimize the utility conflict. Consider an alternate BMP type to avoid conflict.
- Use design features to mitigate the impacts of conflicts that may arise by allowing the bioretention and the utility to coexist. The bioretention design may need to incorporate impervious areas, through geotextiles or compaction, to protect utility crossings. Other a key design feature may need to be moved or added or deleted

- Work with the utility to evaluate the relocation of the existing utility and install the optimum placement and sizing of the bioretention.
- If utility functionality, longevity, and vehicular access to manholes can be assured, accept the bioretention design and location with the existing utility. Incorporate into the bioretention design sufficient soil coverage over the utility or general clearances or other features such as an impermeable https://linearliner.com/linearliner to assure all entities the conflict is limited to maintenance.

Note: When accepting utility conflict into the bioretention location and design, it is understood the bioretention will be temporarily impacted during utility work but the utility owner will replace the bioretention or, alternatively, install a functionally comparable bioretention according to the specifications in the current version of this Stormwater Management Guidebook.guidebook. If the bioretention is located in the public right-of-wayPROW, the bioretention restoration will also conform with the District of Columbia Department of Transportation Design and Engineering Manual with special attention to Chapter 33, Chapter 47,28 and the Design and Engineering Manual supplements for "Low Impact Development" and "Green Infrastructure Standards and Specifications."

Minimizing External Impacts. Urban bioretention practices may be subject to higher public visibility, greater trash loads, pedestrian traffic, vandalism, and even vehicular loads. Designers should design these practices in ways that prevent, or at least minimize, such impacts. In addition, designers should clearly recognize the need to perform frequent landscaping maintenance to remove trash, check for clogging, and maintain vigorous vegetation. The urban landscape context may feature naturalized landscaping or a more formal design. When urban bioretention is used in sidewalk areas of high foot traffic, designers should not impede pedestrian movement or create a safety hazard. Designers may also install low fences, grates, or other measures to prevent damage from pedestrian short-cutting across the practices.

When bioretention will be included in public rights-of-way or spaces, design manuals and guidance developed by agencies or organizations other than <u>DDOEDOEE</u> may also apply (e.g., District Department of Transportation, <u>District</u> Office of Planning, and National Capital Planning Commission).

3.6.2 Bioretention Conveyance Criteria

There are two basic design approaches for conveying runoff into, through, and around bioretention practices:

- 1. Off-line: Flow is split or diverted so that only the design storm or design flow enters the bioretention area. Larger flows bypass the bioretention treatment.
- 2. On-line: All runoff from the drainage areaCDA flows into the practice. Flows that exceed the design capacity exit the practice via an overflow structure or weir.

If runoff is delivered by a storm drain pipe or is along the main conveyance system, the bioretention area <u>shallshould</u> be designed off-line so that flows-to do not overwhelm or damage the practice.

Off-line Bioretention. Overflows are diverted from entering the bioretention cell. Optional diversion methods include the following:

- Create an alternate flow path at the inflow point into the structure such that when the maximum ponding depth is reached, the incoming flow is diverted past the facility. In this case, the higher flows do not pass over the filter bed and through the facility, and additional flow is able to enter as the ponding water filters through the soil filter media. With this design configuration, an overflow structure in the bioretention area is not required.
- Utilize a low-flow diversion or flow splitter at the inlet to allow only the design storm volume (i.e., the Stormwater Retention Volume (SWRv))SWRv) to enter the facility (calculations must be made to determine the peak flow from the 1.2-inch, 24-hour storm). This may be achieved with a weir, curb opening, or orifice for the target flow, in combination with a bypass channel or pipe. Using a weir or curb opening helps minimize clogging and reduces the maintenance frequency. With this design configuration, an overflow structure in the bioretention area is required (see on-line bioretention below).

On-line Bioretention. An overflow structure must be incorporated into on-line designs to safely convey larger storms through the bioretention area₋ (see Figure 3.19). The following criteria apply to overflow structures:

- An overflow shall be provided within the practice to pass storms greater than the design storm storage to a stabilized water course. A portion of larger events may be managed by the bioretention area so long as the maximum depth of ponding in the bioretention cell does not exceed 18 inches.
- The overflow device must convey runoff to a storm sewer, stream, or the existing stormwater conveyance infrastructure, such as curb and gutter or an existing channel.
- Common overflow systems within bioretention practices consist of an inlet structure, where the top of the structure is placed at the maximum ponding depth of the bioretention area, which is typically 6 to 18 inches above the surface of the filter bed.
- The overflow device should be scaled to the application. This may be a landscape grate or yard inlet for small practices or a commercial-type structure for larger installations.
- At least 3—<u>to</u> 6 inches of freeboard must be provided between the top of the overflow device and the top of the bioretention area to ensure that nuisance flooding will not occur.
- The overflow associated with the 2-year and 15-year design storms must be controlled so that velocities are non-erosive (generally less than 6 feet per second) at the outlet point, to prevent downstream erosion.




Figure 3.183.19

.19 Example of an overflow structure in an on-line bioretention area

3.6.3 Bioretention Pretreatment Criteria

Pretreatment of runoff entering bioretention areas is necessary to trap coarse sediment particles before they reach and prematurely clog the filter bed. Pretreatment measures must be designed to evenly spread runoff across the entire width of the bioretention area. Several pretreatment measures are feasible, depending on the type of the bioretention practice and whether it receives sheet flow, shallow concentrated flow, or deeper concentrated flows. The following are appropriate pretreatment options:

Small-Scale Bioretention (B-2, B-3, B-4, and B-5)

- Leaf Screens. A leaf screen serves as part of the gutter system to keep the heavy loading of organic debris from accumulating in the bioretention cell.
- **Pretreatment Cells** (for channel flow). Pretreatment cells are located above ground or covered by a manhole or grate. Pretreatment cells are atypical in small-scale bioretention and are not recommended for residential rain gardens (B-5).

- Grass Filter Strips (for sheet flow). Grass filter strips are applied on residential lots, where
 the lawn area can serve as a grass filter strip adjacent to a rain garden.
- Stone Diaphragm (for either sheet flow or concentrated flow). The stone diaphragm at the end of a downspout or other concentrated inflow point should run perpendicular to the flow path to promote settling.
 - Note: stone diaphragms are not recommended for school settings.
- Trash Racks (for either sheet flow or concentrated flow). Trash racks are located between the pretreatment cell and the main filter bed or across curb cuts to allow trash to collect in specific locations and make maintenance easier.

Traditional Bioretention (B-1)

- Pretreatment Cells (for channel flow). Similar to a forebay, this cell is located at piped inlets or curb cuts leading to the bioretention area and consists of an energy dissipator sized for the expected rates of discharge. It has a storage volume equivalent to at least 15 percent% of the total storage volume (inclusive) with a recommended 2:1 length-to-width ratio. The cell may be formed by a wooden or stone check dam or an earthen or rock berm. Pretreatment cells do not need underlying engineered soil filter media, in contrast to the main bioretention cell. However, if the volume of the pretreatment cell will be included as part of the bioretention storage volume, the pretreatment cell must de-water between storm events. It cannot have a permanent ponded volume.
- Grass Filter Strips (for sheet flow). Grass filter strips that are perpendicular to incoming sheet flow extend from the edge of pavement, with a slight drop at the pavement edge, to the bottom of the bioretention basin at a 5:15H:1V slope or flatter. Alternatively, if the bioretention basin has side slopes that are 3:13H:1V or flatter, a 5-foot grass filter strip can be used at a maximum 5-percent (20:1% (20H:1V) slope.
- Stone Diaphragms (for sheet flow). A stone diaphragm located at the edge of the pavement should be oriented perpendicular to the flow path to pretreat lateral runoff, with a 2₋ to 4₋ inch drop from the pavement edge to the top of the stone. The stone must be sized according to the expected rate of discharge.
- **Gravel or Stone Flow Spreaders** (for concentrated flow). The gravel flow spreader is located at curb cuts, downspouts, or other concentrated inflow points, and should have a 2₋ to 4₋inch elevation drop from a hard-edged surface into a gravel or stone diaphragm. The gravel must extend the entire width of the opening and create a level stone weir at the bottom or treatment elevation of the basin.
- **Filter System** (see Section 3.7-, "Stormwater Filtering Systems)."). If using a filter system as a pretreatment facility, the filter will not require a separate pretreatment facility.
- Innovative or Proprietary Structure. An approved proprietary structure with demonstrated capability of reducing sediment and hydrocarbons may be used to provide pretreatment. Refer to Section 3.13-, "Proprietary Practices," for information on approved proprietary structures.

Other pretreatment options may be appropriate as long as they trap coarse sediment particles and evenly spread runoff across the entire width of the bioretention area.

3.6.4 Bioretention Design Criteria

Design Geometry. Bioretention basins must be designed with an internal flow path geometry such that the treatment mechanisms provided by the bioretention are not bypassed or short-circuited. In order for the bioretention area to have an acceptable internal geometry, the travel time from each inlet to the outlet should be maximized by locating the inlets and outlets as far apart as possible. In addition, incoming flow must be distributed as evenly as possible across the entire filter surface area.

Inlets and Energy Dissipation. Where appropriate, the inlet(s) to streetscape bioretention (B-2), engineered tree boxes (B-3), and stormwater planters (B-4) should be stabilized using No. 3 stone, splash block, river stone, or other acceptable energy dissipation measures. The following types of inlets are recommended:

- Downspouts to stone energy dissipators
- Sheet flow over a depressed curb with a 3-inch drop-
- Curb cuts allowing runoff into the bioretention area-
- Covered drains that convey flows across sidewalks from the curb or downspouts-
- Grates or trench drains that capture runoff from a sidewalk or plaza area-
- Drop structures that appropriately dissipate water energy-

<u>Inlets must be designed with sufficient width and slope to avoid unintended bypass. This is of particular concern for curb cuts on streetscape bioretention designs.</u>

Ponding Depth. The recommended surface ponding depth is $6-\underline{\text{to}}$ 12 inches. Minimum surface ponding depth is 3 inches (averaged over the surface area of the BMP). Ponding depths can be increased to a maximum of 18 inches. However, when higher ponding depths are utilized, the design must consider carefully issues such as safety, fencing requirements, aesthetics, the viability and survival of plants, and erosion and scour of side slopes. This is especially true where bioretention areas are built next to sidewalks or other areas were pedestrians or bicyclists travel. Shallower ponding depths (typically $6-\underline{\text{to}}$ 12 inches) are recommended for streetscape bioretention (B-2), engineered tree boxes (B-3), and stormwater planters (B-4).

Side Slopes. Traditional bioretention areas (B-1) and residential rain gardens (B-5) should be constructed with side slopes of 3:13H:1V or flatter. In highly urbanized or space—constrained areas, a drop curb design or a precast structure can be used to create a stable, vertical side wall. These drop curb designs should not exceed a vertical drop of more than 12 inches, unless safety precautions, such as railings, walls, grates, etc. are included.

Filter Media. The filter media of a bioretention practice consists of an engineered soil mixture that has been carefully blended to create a <u>soil_filter</u> media that maintains long-term permeability while also providing enough nutrients to support plant growth. The final filter media shall consist of a well-blended mixture of medium to coarse **sand**, **base loam soil** (soil fines), and an **organic amendment** (compost). The sand maintains the desired permeability of the media while the limited amount of <u>loam</u> soil_fines and organic amendments are considered adequate to help

support initial plant growth. It is anticipated that the gradual increase of organic material through natural processes will continue to support plant growth without the need to add fertilizer, and the root structure of maturing plants and the biological activity of the media will maintain sufficient long-term permeability.

The following is the recommended composition of the three media ingredients:

- Sand (Fine Aggregate). Sand shallshould consist of silica-based medium to coarse sand, and be angular or round in shape. The materials shall not be derived from serpentine and, shall be free of loam or clay, diabase, surface coatings, or any other deleterious materials, and shall contain less than 0.5% mica by weight when tested with ASTM C295, Standard Guide for Petrographic Examination of Aggregates for Concrete.
 - ASTM C-33, Standard Specification for Concrete Aggregates, concrete sand will typically meet the requirements for the sand to be used in filter media. However, some samples of ASTM C-33 sand may have too high a fraction of fine sand and silt- and clay-sized particles to meet the final filter media particle size distribution requirements. In general, coarser gradations of ASTM C-33 will better meet the filter media particle size distribution and hydraulic conductivity requirements.
 - Any other materials, such as <u>manufactured sand</u>, limestone-based sands or crushed glass, shall meet the required particle size distribution of the final filter media mixture and be demonstrated as adequately durable when tested by AASHTO T-103, <u>Soundness of Aggregates by Freezing and Thawing</u>, or T-104, <u>Standard Method of Test for Soundness of Aggregate by Use of Sodium Sulfate or Magnesium Sulfate</u>.
- Base Loam Soil. Base loam Loam soil is generally defined as the combination of sand-sized material, fines (silt and clay), and any associated soil organic matter. Since the objective of the specification is to carefully establish the proper blend of these ingredients in the final filter media, the designer (or contractor or materials supplier) must carefully select the topsoil source material in order to not exceed the amount of any one ingredient.
 - Generally, a natural loamy sand, sandy loam, or loam (per the USDA Textural Triangle) United States Department of Agriculture (USDA) Textural Triangle, https://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/survey/?cid=nrcs142p2 054167) A-horizon topsoil free of subsoil, large stones, earth clods, sticks, stumps, clay lumps, roots, viable noxious weed seed, plant propagules, brush, or other objectionable, extraneous matter or debris is suitable for the base-loam (soil-fines) source material.
- Organic Amendments. Organic amendments shall consist of stable, well-decomposed omposted, natural, carbon-containing organic materials such as leaf mulch, peat moss, humus, or yard waste (consistent with the material specifications found in Appendix J₇. "Soil Compost Amendment Requirements"). The material shall be free of debris such as plastics, metal, concrete, stones larger than ½1/2 inch, larger branches and roots, and wood chips over 1 inch in length or diameter.

Complete Filter Media. The complete filter media soil mix-shall consist of a pug milled or mechanically blended mix of the three source materials resulting in a . Mixing the filter media that meetson-site with excavation or loading equipment is not sufficient. The resulting filter

media must meet the following particle size composition, as well as the grain size distribution indicated in Table 3.17.:

- 80%–90% sand (at least 75 percent of which must be classified as coarse or very coarse sand)
- 10%–20% soil fines (silt and clay)
- Maximum 10% clay

Note: The above percentages are based on weight rather than volume. The particle size analysis must be conducted on the mineral fraction only or following appropriate treatments to remove organic matter before particle size analysis.

Note: The above percentages are based on weight rather than volume. The DDOT Green Infrastructure Standards include a bioretention soil specification based on volume, not weight, so the percentages listed there do not match those listed here, even though the two specifications are substantially equivalent.

Additionally, the final filter media mix must meet the grain size distribution indicated in Table 3.18 or have a saturated hydraulic conductivity of 2 to 6 inches per hour according to test procedure ASTM D2434 when compacted (at 60% to 80% optimum moisture content) to a minimum of 86% of the maximum density as determined by AASHTO T 99 Standard Method of Test for Moisture—Density Relations of Soils Using a 2.5-kg (5.5-lb) Rammer and a 305-mm (12-in.) Drop.

Table 3.10	Filter Media	Grain Size	Distribution

Sieve Type	Particle Size (mm)	Percent Passing (%)				
	8.0	100				
No. 5	4.0	92-100				
No. 10	2.0	72–100				
No. 18	1.0	43–95				
No. 35	0.5	20–65				
No. 60	0.25	11–37				
No. 140	0.105	10–25				
No. 270	0.053	10–20				
	0.002	0–10				

The filter media shall also meet the following criteria: (see summary in Table 3.19):

- Organic content shall be between 3.0% and 5.0% by weight;
- pH shall be between 6.0 and 7.25;
- Cation exchange capacity (CEC) shall be a minimum of 5 milliequivalents (meq/100g)/100 grams (g) or centimole of charge (cmol+/+)/kilogram (kg;);
- Phosphorus content shall meet one of the following:
 - P-Index between 10 and 30;
 - ♦ 5—15mg to 15 mg/kg Mehlich I Extraction;

- ◆ 18—40mg to 40 mg/kg Mehlich III Extraction; and
- Soluble salts shall be less than 500 parts per million (ppm-/) or less than 0.5 millimhos (mmhos-/)/centimeter (cm-/).

Notes:

- 1. P-Index is an agronomic test used in North Carolina to indicate the potential for P leaching from soil. The test method has been revised to add P concentration to facilitate local lab testing. The value of the P-Index is the correlation between the CEC and P concentrations: higher CEC indicates greater adsorption sites within the media, thus increasing the ability to fix P within the soil, thereby allowing higher P concentrations without leaching. While P-Index may be a better overall representation of P, the test method may not be readily available.
- 2. Tests for organic content, CEC, soluble salts, and pH are referenced to be in accordance with Recommended Soil Testing Procedures for the Northeastern United States, Current Edition, Northeastern Regional Publication No. 493. Use the following tests:
 - (a) Test for soil content by loss of weight on ignition
 - (b) Test for soil CEC by exchangeable acidity method
 - (c) Test for soluble salts shall be by the 1:2 (V:V) Soil: Water Extract Method
 - (d) Test for pH by the SMP method

Table 3.11 Summary of Filter Media Criteria for Bioretention

SoilFilter Media Criterion	Description	Standard(s)
General Composition	Filter media must have the proper proportions of sand, finesloam soil, and organic matteramendments to promote plant growth, drain at the proper rate, and filter pollutants.	80%–90% sand; 10%–20% soil fines; maximum of 10% clay; and 3%–5% organic content Must meet final filter media grain size distribution OR have a saturated hydraulic conductivity of 2–6 inches per hour
Sand	Based on final filter media particlegrain size distribution	
TopLoam Soil	Loamy sand-or, sandy loam, or loam	USDA Textural Triangle
Organic Matter Amendments	Well aged, clean compost Stable, well-composted, natural, carbon-containing organic materials such as leaf mulch, peat moss, humus, or yard waste.	Appendix J
P-Index or Phosphorus (P) Content	SoilFilter media with high P levels will export P through the media and potentially to downstream conveyances or receiving waters.	P-Index of 10–30 or P content = 5 to 15 mg/kg (Mehlich I) or 18–40 mg/kg (Mehlich III)
Cation Exchange Capacity (CEC)	The CEC is determined by the amount of soil fines and organic matter. Higher CEC will promote pollutant removal.	CEC > 5 milliequivalents per 100 grams
<u>pH</u>	Soil pH influences nutrient availability and microbial populations.	Between 6.0 and 7.5
Soluble Salts	Filter media with high levels of soluble salts can injure or kill plants.	Less than 500 ppm or less than 0.5 mmhos/cm.

In cases where greater removal of specific pollutants is desired, additives with documented pollutant removal benefits, such as water treatment residuals, alum, iron, or other materials, may be included in the filter media if accepted by DOEE.

Filter Media Depth. The filter media bed depth must be a minimum of 18 inches for the Standard Design. The media depth must be 24 inches or greater to qualify for the Enhanced Design, unless an infiltration-based design is used. The media depth must not exceed 6.5 feet. Turf, perennials, or shrubs should be used instead of trees to landscape shallower filter beds. See Table 3.2+22 and Table 3.2223 for a list of recommended native plants.

During high intensity storm events, it is possible for the bioretention to fill up faster than the collected stormwater is able to filter through the $\frac{\text{soil}_{\overline{\text{filter}}}}{\text{media}}$ media. This is dependent upon the surface area of the BMP (SA) relative to the CDA and the runoff coefficient (Rv) from the CDA.

To ensure that the design runoff volume is captured and filtered appropriately, a maximum filter media depth must not be exceeded (see Table $3.24\underline{20}$). The maximum filter media depth is based on the runoff coefficient of the CDA to the BMP (Rv_CDA) and the bioretention ratio of BMP surface area to the BMP CDA (SA:CDA) (in percent). The Rv_CDA is an average of runoff coefficients of land cover types in the BMP's CDA. The land cover runoff coefficient types can be selected from Table H.1 Runoff Coefficient Factors for Typical District of Columbia Land Uses, or using the three categories established for calculating the SWRv (natural, compacted, and impervious cover). The applicable filter media depth from Table $3.2\underline{+20}$ should be used as d_{media} in Equation 3.5. Note: In the gray cells, overflow is not likely to occur for the design storm, so no maximum filter media depth is specified.

Table 3.20 Determining Maximum Filter Media Depth (feet)

SA:CDA	Rv_{CDA}								
(%)	0.25	0.3	0.40	0.50	0.60	0.70	0.80	0.90	0.95
0.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5
1.0	5.0	5.5	6.0	6.5	6.5	6.5	6.5	6.5	6.5
1.5	3.5	4.0	5.0	6.0	6.0	6.5	6.5	6.5	6.50
2.0		3.0	4.0	4.5	5.5	6.0	6.0	6.5	6.5
2.5			3.5	4.0	4.5	5.0	5.5	6.0	6.0
3.0				3.5	4.0	4.5	5.0	5.5	5.5
3.5					3.5	4.0	4.5	5.0	5.0
4.0					3.0	3.5	4.0	4.5	4.5
4.5						3.5	3.5	4.0	4.0
5.0							3.5	4.0	4.0
5.5								3.5	3.5
6.0								3.0	3.5
6.5									3.0
7.0 <u>+</u>									
7.5									
8.0									
8.5									
9.0									
9.5									
10.0									

Surface Cover. Mulch is the recommended surface cover material, but other materials may be substituted, as described below:

• Mulch. A 2- to 3-inch layer of mulch on the surface of the filter bed enhances plant survival, suppresses weed growth, pretreats runoff before it reaches the filter media, and prevents rapid evaporation of rainwater. Shredded hardwood bark mulch, aged for at least 6 months,

makes a very good surface cover, as it retains a significant amount of pollutants and typically will not float away. The maximum depth of the mulch layer is 3 inches.

- Alternative to Mulch Cover. In some situations, designers may consider alternative surface covers, such as turf, native groundcover, erosion control matting (e.g., coir or jute matting), river stone, or pea gravel. The decision regarding the type of surface cover to use should be based on function, expected pedestrian traffic, cost, and maintenance. When alternative surface covers are used, methods to discourage pedestrian traffic should be considered. Stone or gravel are not recommended in parking lot applications, since they increase soil temperature and have low water-holding capacity.
- Media for Turf Cover. One adaptation suggested for use with turf cover is to design the filter media primarily as a sand filter with organic content only at the top. Compost, as specified in Appendix J, "Soil Compost Amendment Requirements," tilled into the top layers will provide organic content for the vegetative cover. If grass is the only vegetation, the ratio of organic matter in the filter media composition may be reduced.

Choking Layer. A 2₋ to 4-inch layer of choker stone (e.g., typically ASTM D448 No. 8 or No. 89 washed gravel) should be placed beneath the soilfilter media and over the underdrain stone.

Geotextile. If the available head is limited, or the depth of the practice is a concern, geotextile fabric may be used in place of the choking layer. An appropriate geotextile fabric that complies with AASHTO M-288 Class 2— (latest edition, available here:

https://store.transportation.org/item/publicationdetail/3791) requirements, and has a permeability of at least an order of magnitude (10 times) higher (10x)-than the soil subgrade permeability must be used. Geotextile fabric may be used on the sides of bioretention areas, as well.

Underdrains. Many bioretention designs will require an underdrain (see Section 3.6.1 Bioretention Feasibility Criteria). The underdrain should be a 4- or 6-inch perforated schedule 40 PVC pipe, or equivalent corrugated HDPE for small bioretention BMPs, with three or four rows of 3/8-inch perforations at 6 inches on center. The underdrain must be encased in a layer of clean, double washed ASTM D448 No.57 or smaller (No. 68, 8, or 89) stone. The maximum depth of the underdrain stone layer combined with the choking layer is 12 inches, and it cannot extend beyond the surface dimensions of the bioretention filter media. The underdrain must be sized so that the bioretention BMP fully drains within 72 hours or less. See Appendix G, "Design of Flow Control Structures." for the circular orifice equation.

Multiple underdrains are may be necessary for bioretention areas wider than 40 feet, and each underdrain must is recommended to be located no more than 20 feet from the next pipe or the edge of the bioretention. (For long and narrow applications, a single underdrain running the length of the bioretention is sufficient.). Each underdrain must include a cleanout pipe (minimum 4 inches in diameter).

Observation Wells. All-traditional bioretention practices must include at least one observation well and/or cleanout pipe (minimumconsisting of a well-anchored, 4 inches in_ to 6-inch diameter). The PVC pipe (see Figure 3.20). For standard bioretention practices, the non-perforated observation wells should be tied into any of the TsT or YsY connections in the underdrain system and must extend upward above the surface of the bioretention area.3.193.20

ponding level. These observation wells can also double as cleanouts. Enhanced bioretention practices should be perforated in the gravel layer only and also must extend upward to the top of ponding.




Figure 3.20 Observation well/cleanout device.

Underground Storage Layer (optional). For bioretention systems with an underdrain, an underground storage layer consisting of chambers, perforated pipe, stone, or other acceptable material can be incorporated below the filter media layer and underdrain to increase the infiltration sump volume or the storage for larger storm events. Unlike the underdrain stone layer, this storage layer can be extended be yound the surface dimensions of the bioretention filter media if additional storage volume is needed. To qualify for the Enhanced Designenhanced design, this underground storage layer must be designed to infiltrate inwithin 72 hours, at ½ the measured infiltration rate. The underground storage layer may also be designed to provide detention for the 2-year, 15-year, or 100-year storms, as needed. The depth and volume of the storage layer will then depend on the target storage volumes needed to meet the applicable detention criteria. Suitable conveyance must also be provided to ensure that the storage is fully utilized without overflow of the bioretention area.

Impermeable Liner. An impermeable liner is not typically required, although it may be utilized in fill applications where deemed necessary by a geotechnical investigation, on sites with contaminated soils, or on the sides of the practice to protect adjacent structures from seepage. Use a 30-mililiter (minimum) PVC geomembrane liner. (Follow or equivalent material of an appropriate thickness (follow manufacturer's instructions for installation.)). Field seams must be sealed according to the liner manufacturer's specifications. A minimum 6-inch overlap of material is required at all seams.

Material Specifications. Recommended material specifications for bioretention areas are shown in Table $3.\underline{2221}$.

Table 3.12 Bioretention Material Specifications

Material	Specification	Notes		
Filter Media	• See Table 3.2018 and Table 3.19	Minimum depth of 24 inches (18 inches for small scale practices)standard design). To account for settling/compaction, it is recommended that 110% of the plan volume be utilized.		
Mulch Layer	Use aged, shredded hardwood bark mulch	Lay a 2 ₋ to 3-inch layer on the surface of the filter bed.		
Alternative Surface Cover	Use river stone or pea gravel, coir and jute matting, or turf cover.	Lay a 2 ₋ to 3-inch layer of to suppress weed growth.		
Top Soil Forfor Turf Cover	Loamy sand or sandy loam texture, with less than 5% clay content, pH corrected to between 6 and 7, and an organic matter content of at least 2%.	3-inch tilled into surface layer.		
Geotextile -or Choking Layer	An appropriate geotextile fabric that complies with AASHTO M-288 Class 2_{\pm} (latest edition, available here: https://store.transportation.org/item/publicationdetail/3791) requirements and has a permeability of at least an order of magnitude (10 times) higher (10x) than the soil subgrade permeability must be used	Can use in place of the choking layer where the depth of the practice is limited. Geotextile fabric may be used on the sides of bioretention areas, as well.		
	Lay a 2 ₋ to 4- <u>i</u> nch layer of choker stone (e.g., typically No.8 underdrain stone.	.8 or No.89 washed gravel) over the		
Underdrain stone Stone	1-inch diameter stone must be double-washed and clean and free of all fines (e.g., ASTM D448 No. 57 or smaller stone).	At least 2 inches above and below the underdrain.		
Storage Layer (optional)	To increase storage for larger storm events, chambers, performaterial can be incorporated below the filter media layer.	rated pipe, stone, or other acceptable		
Impermeable Liner (optional)	Where appropriate, use a thirty mil (minimum) PVC Geometran appropriate thickness.	mbrane liner or equivalent material of		
Underdrains, Cleanouts, and Observation Wells	Use 4- or 6-inch rigid schedule 40 PVC pipe, or equivalent corrugated HDPE for small bioretention BMPs, with three or four rows of 3/8-inch perforations at 6 inches on center. Multiple underdrains aremay be necessary for bioretention areas wider than 40 feet, and each underdrain mustis recommended to be located no more than 20 feet from the next pipe or the edge of the bioretention.	Lay the perforated pipe under the length of the bioretention cell, and install non-perforated pipe as needed to connect with the storm drain system or to daylight in a stabilized conveyance. Install T's and Y's as needed, depending on the underdrain configuration. Extend cleanout pipes to the surface of ponding.		
Plant Materials	See Section 3.6.5 Bioretention Landscaping Criteria	Establish plant materials as specified in the landscaping plan and the recommended plant list.		

Signage. Bioretention units in highly urbanized areas should be stenciled or otherwise permanently marked to designate it as a structural BMP. The stencil or plaque should indicate (1) its water quality purpose, (2) that it may pond briefly after a storm, and (3) that it is not to be disturbed except for required maintenance.

Specific Design Issues for Streetscape Bioretention (B-2). Streetscape bioretention is installed in the road right-of-way either in the sidewalk area or in the road itself. In many cases, streetscape bioretention areas can also serve as a traffic—calming or street—parking control devices. The basic design adaptation is to move the raised concrete curb closer to the street or in the street, and then create inlets or curb cuts that divert street runoff into depressed vegetated areas within the right-of-way. Roadway stability can be a design issue where streetscape bioretention practices are installed. Designers should consult design standards pertaining to roadway drainage. It may be necessary to provide an impermeable liner on the road side of the bioretention area to keep water from saturating the road's sub-base. Streetscape bioretention in the PROW should comply with Section 33.14.5.1 of the DDOT Green Infrastructure Standards.

Specific Design Issues for Engineered Tree Boxes (B-3). Engineered tree boxes are installed in the sidewalk zone near the street where urban street trees are normally installed (see Figure 3.21). The soil volume for the tree pit is increased and used to capture and treat stormwater. Treatment is increased by using a series of connected tree planting areas together in a row. The surface of the enlarged planting area may be mulch, grates, permeable pavers, or conventional pavement. The large and shared rooting space and a reliable water supply increase the growth and survival rates in this otherwise harsh planting environment, Engineered tree boxes in the PROW should comply with Section 33.14.5.1 of the DDOT Green Infrastructure Standards.

When designing engineered tree boxes, the following criteria must be considered may apply:

The bottom of the soil layer must be a minimum of 4 inches below the root ball of plants to be installed.

- Engineered tree box designs sometimes cover portions of the filter media with pervious pavers or cantilevered sidewalks (see Figure 3.22). In these situations, it is important that the filter media is connected beneath the surface so that stormwater and tree roots can share this space. following design considerations must be incorporated:
 - ◆ The filter media must be connected beneath the surface so that stormwater and tree roots can share this space.
 - As with all bioretention areas, a minimum surface ponding depth of 3 inches, averaged over the surface area of the bioretention area, is required. For example, if the additional surface area under the pavement doubles the overall surface area, then the ponding depth will need to be at least 6 inches.
 - Sand based structural soil (SBSS) (as defined in Section 621.09 of the DDOT Green Infrastructure Standards) may be considered as bioretention filter media if it meets the same phosphorus content limits. However, if the SBSS is to be compacted beyond the DDOT Green Infrastructure Standards maximum compaction for bioretention, it shall be assigned a porosity of 0.10. The DDOT Green Infrastructure Standards call for

bioretention soil to be compacted to 84% maximum dry density while SBSS is to be compacted to 93%.

- Installing an engineered tree pit grate over filter bed media is one possible solution to prevent pedestrian traffic and trash accumulation.
- Low, wrought iron fences can help restrict pedestrian traffic across the tree pit bed and serve as a protective barrier if there is a drop-off from the pavement to the micro-bioretention cell.
- A removable grate may be used to allow the tree to grow through it.
- Each tree needs a minimum rootable soil volume as described in Section 3.14, "Tree Planting and Preservation.".
- See Section 3.14.2 Planting Trees and Figure 3.45 for further guidance and requirements on tree planting.




Figure 3.203.21 3.213.223.21.21 Example of tree box cross section.





Figure 3.22 Example of tree box cross section with compacted media extending below sidewalk.

Specific Design Issues for Stormwater Planters (B-4). Stormwater planters are a useful option to disconnect and treat rooftop runoff, particularly in ultra-urban areas. They consist of confined planters that store and/or infiltrate runoff in a soil bed to reduce runoff volumes and pollutant loads. Stormwater planters combine an aesthetic landscaping feature with a functional form of stormwater treatment. Stormwater planters generally receive runoff from adjacent rooftop downspouts and are landscaped with plants that are tolerant totolerate periods of both drought and inundation. The two basic design variations for stormwater planters are the infiltration planter and the filter planter, A filter planter is illustrated in Figure 3.22 below23.

An infiltration planter filters rooftop runoff through soil in the planter followed by infiltration into soils below the planter. The minimum filter media depth is 18 inches, with the shape and length determined by architectural considerations. Infiltration planters should be placed at least 10 feet away from a building to prevent possible flooding or basement seepage damage.

A filter planter does not allow for infiltration and is constructed with a watertight concrete shell or an impermeable liner on the bottom to prevent seepage. Since a filter planter is self-contained and does not infiltrate into the ground, it can be installed right next to a building. The minimum filter media depth is 18 inches, with the shape and length determined by architectural considerations. Runoff is captured and temporarily ponded above the planter bed. Overflow pipes are installed to discharge runoff when maximum ponding depths are exceeded, to avoid

water spilling over the side of the planter. In addition, an underdrain is used to carry runoff to the storm sewer system.






Figure 3.223.233.22.23 Example of a stormwater planter (B-4).

All planters should be placed at grade level or above ground. Plant materials must be capable of withstanding moist and seasonally dry conditions. The sand and gravel on the bottom of the planter should have a minimum infil tration rate of 5 inches per hour. The planter can be constructed of stone, concrete, brick, wood, or other durable material. If treated wood is used, care should be taken so that trace metals and creosote do not leach out of the planter.

Specific Design Issues for Residential Rain Gardens (B-5). For some residential applications, front, side, and/or rear yard bioretention may be an attractive option. This form of bioretention captures roof, lawn, and driveway runoff from low- to medium- density residential lots in a depressed area (i.e., 6 to 12 inches) between the home and the primary stormwater conveyance system (i.e., roadside ditch or pipe system). The bioretention area connects to the drainage system with an underdrain.

The bioretention filter media must be at least 18 inches deep. The underdrain is directly connected into the storm drain pipe running underneath the street or in the street right-of-way. A trench needs to be excavated during construction to connect the underdrain to the street storm drain system.

Construction of the remainder of the bioretention system is deferred until after the lot has been stabilized. Residential rain gardens require regular maintenance to perform effectively.

BMP Sizing. Bioretention is typically sized to capture the SWRv or larger design storm volumes in the surface ponding area, soilfilter media, and gravel reservoir layers of the BMP.

Total storage volume of the BMP is calculated using Equation 3.5a5.

Equation 3.5a Bioretention Storage Volume

$$\begin{split} \underline{Sv} &= \mathit{SA}_{\mathit{bottom}} \times [\left(d_{\mathit{media}} \times \eta_{\mathit{media}}\right) + \left(d_{\mathit{gravel}} \times \eta_{\mathit{gravel}}\right)] + \left(\mathit{SA}_{\mathit{average}} \times d_{\mathit{ponding}}\right) \\ S_v &= \mathit{SA}_{\mathit{bottom}} \times \left[\left(d_{\mathit{media}} \times \eta_{\mathit{media}}\right) + \left(d_{\mathit{gravel}} \times \eta_{\mathit{gravel}}\right)\right] + \left(\mathit{SA}_{\mathit{average}} \times d_{\mathit{ponding}}\right) \end{split}$$

where:

= total storage volume of bioretention (ft³) SA_{bottom} = bottom surface area of bioretention (ft²) = depth of the filter media, including mulch layer (ft) d_{media} = effective porosity of the filter media (typically 0.25) η_{media} = depth of the underdrain and underground storage gravel layer. d_{gravel} including choker stone (ft) = effective porosity of the gravel layer (typically 0.4) η_{gravel} = average surface area of bioretention (ft²) $SA_{average}$ typically, where SA_{top} is the top surface area of bioretention, $SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$ maximum ponding depth of bioretention (ft) $d_{ponding}$

Equation 3.5 can be modified if the storage depths of the filter media, gravel layer, or ponded water vary in the actual design or with the addition of any surface or subsurface storage components (e.g., additional area of surface ponding, subsurface storage chambers, etc.). The maximum depth of ponding in the bioretention must not exceed 18 inches. If storage practices will be provided off-line or in series with the bioretention area, the storage practices should be sized using the guidance in Section 3.12-, "Storage Practices."

For enhanced bioretention areas, the volume that will be infiltrated (the sump volume for underdrained designs or the entire volume for non-underdrained designs) must infiltrate within 72 hours. Measured infiltration rates The saturated hydraulic conductivity for the native soils must exceed 0.1 inches feet per hour day to qualify for the enhanced design retention value. The depth of the infiltration sump for underdrained designs can be determined using Equation 3.5b6.

Equation 3.6b Bioretention Infiltration Sump Depth

$$d_{sump} = \frac{\left(\frac{i}{2} \times t_d\right)}{n_r}$$

$$d_{sump} = \frac{(K_{sat} \times t_d)}{\eta_r}$$

where:

 d_{sump} = depth of the infiltration sump (in.)

 iK_{sat} = field-verified (actual) infiltration ratesaturated hydraulic

conductivity for the native soils (in./hrft/day) (must exceed 0.1

in./hr)_ft/day)

 t_d = drawdown time (hr) (within 72 hr3 days)

 n_r = available porosity of the stone reservoir (<u>ypicallyassume</u> 0.4)

For non-underdrained designs, a check must be performed to ensure that the entire Sv infiltrates within 72 hours, as in Equation 3.5e7.

Equation 3.7e Bioretention Infiltration Rate Check

$$Sv_{\text{inf }iltrate} = \frac{SA_{bottom} \left(\frac{i}{2} \times t_d\right)}{12}$$

$$Sv_{infiltrate} = \frac{SA_{bottom}(K_{sat} \times t_d)}{12}$$

where:

 $Sv_{infiltrate}$ = storage volume that will infiltrate within 72 hours (ft³)

 SA_{bottom} = bottom surface area of bioretention (ft²)

 $\frac{1}{K_{sat}}$ = field-verified (actual) infiltration ratesaturated hydraulic

conductivity for the native soils (in./hr) (must exceed 0.1

in./hrft/day)

 t_d = drawdown time (hr) (within 72 hr3 days)

If $Sv_{infiltrate}$ is greater than or equal to Sv, then the entire Sv will infiltrate within 72 hours. If it is not, the storage volume of the bioretention area should be reduced accordingly.

Bioretention can be designed to address, in whole or in part, the detention storage needed to comply with channel protection and/or flood control requirements. The Sv can be counted as part of the 2-year or 15-year runoff volumes to satisfy stormwater quantity control requirements. At least $3-\underline{\text{to }}6$ inches of freeboard are required between the top of the overflow device and the top of the bioretention area when bioretention is used as detention storage for 2-year and 15-year storms.

Note: In order to increase the storage volume of a bioretention area, the ponding surface area may be increased beyond the filter media surface area. However, the top surface area of the practice (i.e., at the top of the ponding elevation) may not be more than twice the size of the surface area of the filter media (*SA*_{bottom}).

3.6.5 Bioretention Landscaping Criteria

Landscaping is critical to the performance and function of bioretention areas. Therefore, a landscaping plan shall be provided for bioretention areas.

Minimum plan elements include the proposed bioretention template to be used, delineation of planting areas, and the planting plan including the following:

- Common and botanical names of the plants used
- Size of planted materials
- Mature size of the plants
- Light requirements
- Maintenance requirements
- Source of planting stock
- Any other specifications
- Planting sequence

It is recommended that the planting plan be prepared by a qualified landscape architect professional (e.g. licensed professional landscape architect, certified horticulturalist) in order to tailor the planting plan to the site-specific conditions.

Native plant species are preferred over non-native species, but some ornamental species may be used for landscaping effect if they are not aggressive or invasive. Some popular native species that work well in bioretention areas and are commercially available can be found in Table 3.2322 and Table 3.2423. Internet links to more detailed bioretention plant lists developed in the Chesapeake Bay region are provided below:

- Prince Georges County, MD http://www.aacounty.org/DPW/Highways/Resources/Raingarden/RG_Bioretention_PG%20 CO.pdf
- Prince Georges County, MD, http://www.aacounty.org/departments/publicworks/highways/forms-and-publications/RG Bioretention PG%20CO.pdf

Delaware Green Technology Standards and Specifications.
 http://www.dnrec.state.de.us/DNREC2000/Divisions/Soil/Stormwater/New/GT_Stds%20&%20Specs_06-05.pdf

The degree of landscape maintenance that can be provided will determine some of the planting choices for urban bioretention areas. Plant selection differs if the area will be frequently mowed, pruned, and weeded, in contrast to a site whichthat will receive minimum annual maintenance. In areas where less maintenance will be provided and where trash accumulation in shrubbery or herbaceous plants is a concern, consider a "turf and trees" landscaping model where the turf is mowed along with other turf areas on the site. Spaces for herbaceous flowering plants can be included.

Table 3.13 Herbaceous Plants Appropriate for Bioretention Areas in the District

	Tuble 1120 Tell Success Tables (App. Op. and 101 Distriction (Treats in the District							
Plant	Light	Wetland Indicator ¹	Plant Form	Inundation Tolerance	Notes			
Aster, New York (Aster novi-belgii)	Full Sun Part Shade	FACW+	Perennial	Yes	Attractive flowers; tolerates poor soils			
Aster, New England (Aster novae-angliae)	Full Sun Part Shade	FACW	Perennial	Yes	Attractive flowers			
Aster, Perennial Saltmarsh (Aster tenuifolius)	Full Sun— Part Shade	OBL	Perennial	Yes	Salt tolerant			
Coreopsis, Threadleaf (Coreopsis verticillata)	Full Sun Part Shade	FAC	Perennial	No	Drought tolerant			
Beardtongue (Penstemon digitalis)	Full Sun	FAC	Perennial	No	Tolerates poor drainage			
Beebalm (Monarda didyma)	Full Sun— Part Shade	FAC+	Perennial	Saturated	Herbal uses; attractive flower			
Black-Eyed Susan (Rudbeckia hirta)	Full Sun— Part Shade	FACU	Perennial	No	Common; Maryland state flower			
Bluebells, Virginia (Mertensia virginica)	Part Shade- _Full Shade	FACW	Perennial	Yes	Attractive flower; dormant in summer			
Blueflag,_Virginia (Iris virginica)	Full Sun- Part Shade	OBL	Perennial	Yes	Tolerates standing water			
Bluestem, Big (Andropogon gerardii)	Full Sun	FAC	Grass	No	Attractive in winter; forms clumps			
Bluestem, Little (Schizachyrium scoparium)	Full Sun	FACU	Grass	No	Tolerates poor soil conditions			
Broom-Sedge (Andropogon virginicus)	Full Sun	FACU	Grass	No	Drought tolerant; attractive fall color			
Cardinal Flower (Lobelia cardinalis)	Full Sun Part Shade	FACW+	Perennial	Yes	Long boombloom time			
Fern, New York (Thelypteris noveboracensis)	Part Shade- _Full Shade	FAC	Fern	Saturated	Drought tolerant; spreads			

Plant	Light	Wetland Indicator ¹	Plant Form	Inundation Tolerance	Notes
Fern, Royal (Osmunda regalis)	Full Sun Full Shade	OBL	Fern	Saturated	Tolerates short term flooding; drought tolerant
Fescue, Red (Festuca rubra)	Full Sun— Full Shade	FACU	Ground- cover	No	Moderate growth; good for erosion control
Iris, Blue Water (Iris versicolor)	Full Sun Part Shade	OBL	Perennial	0-6" <u>inches</u>	Spreads
Lobelia, Great Blue (Lobelia siphilitica)	Part Shade- _Full Shade	FACW+	Perennial	Yes	Blooms in late summer; bright blue flowers
Phlox, Meadow (Phlox maculata)	Full Sun	FACW	Perennial	Yes	Aromatic; spreads
Sea-Oats (Uniola paniculata)	Full Sun	FACU-	Grass	No	Salt tolerant; attractive seed heads
Swamp Milkweed (Asclepias incarnata)	Full Sun— Part Shade	OBL	Perennial	Saturated	Drought tolerant
Switchgrass (Panicum virgatum)	Full Sun	FAC	Grass	Seasonal	Adaptable; great erosion control
Turtlehead, White (Chelone glabra)	Full Sun— Part Shade	OBL	Perennial	Yes	Excellent growth; herbal uses
Violet, Common Blue (Viola papilionacea)	Full Sun Full Shade	FAC	Perennial	No	Stemless; spreads
Virginia Wild Rye (Elymus virginicus)	Part Shade- _Full Shade	FACW-	Grass	Yes	Adaptable

¹Notes:

No. 9: Bioretention.

FAC = Facultative, equally likely to occur in wetlands or non-wetlands (estimated probability 34%–%–66%).

FACU = Facultative Upland, usually occurs in non-wetlands (estimated probability 67%—%—99%), but occasionally found on wetlands (estimated probability 1%—%—33%).

FACW = FACW Facultative Wetland, usually occurs in wetlands (estimated probability 67%-%-99%), but occasionally found in non-wetlands.

OBL = Obligate Wetland, occurs almost always (estimated probability 99%) under natural conditions in wetlands. Sources: Prince George's County Maryland Bioretention Manual; Virginia DCR Stormwater Design Specification

Table 3.14 Woody Plants Appropriate for Bioretention Areas in the District

Plant	Light	Wetland Indicator ¹	Plant Form	Inundation Tolerance	Notes
Arrow-wood (Viburnum dentatum)	Full Sun— Part Shade	FAC	Shrub	Seasonal	Salt tolerant
River Birch (Betula nigra)	Full Sun— Part Shade	FACW	Tree	Seasonal	Attractive bark
Bayberry, Northern (Myrica pennsylvanica)	Full Sun— Part Shade	FAC	Shrub	Seasonal	Salt tolerant
Black Gum (Nyssa sylvatica)	Full Sun— Part Shade	FACW+	Tree	Seasonal	Excellent fall color

		Wetland	Plant	Inundation	
Plant	Light	Indicator ¹	Form	Tolerance	Notes
Dwarf Azalea (Rhododendron atlanticum)	Part Shade	FAC	Shrub	Yes	Long lived
Black-Haw (Viburnum prunifolium)	Part Shade- _ Full Shade	FACU+	Shrub	Yes	Edible Fruit
Choke Cherry (Prunus virginiana)	Full Sun	FACU+	Shrub	Yes	Tolerates some salt; can be maintained as hedge
Cedar, Eastern Red (Juniperus virginiana)	Full Sun	FACU	Tree	No	Pollution tolerant
Cotton-wood, Eastern (Populus deltoides)	Full Sun	FAC	Tree	Seasonal	Pollutant tolerant; salt tolerant
Silky Dogwood (Cornus amomum)	Full Sun Part Shade	FACW	Shrub	Seasonal	High wildlife value
Hackberry, Common (Celtis occidentalis)	Full Sun— Full Shade	FACU	Tree	Seasonal	Pollution Tolerant tolerant
Hazelnut, American (Corylus americana)	Part Shade	FACU	Shrub	No	Forms thickets; edible nut
Holly, Winterberry (Ilex laevigata)	Full Sun Part Shade	OBL	Shrub	Yes	Winter food source for birds
Holly, American (Ilex opaca)	Full Sun Full Shade	FACU	Shrub- Tree	Limited	Pollution Tolerant tolerant
Maple, Red (Acer rubrum)	Full Sun Part Shade	FAC	Tree	Seasonal	Very adaptable; early spring flowers
Ninebark, Eastern (Physocarpus opulifolius)	Full Sun— Part Shade	FACW-	Shrub	Yes	Drought tolerant; attractive bark
Oak, Pin (Quercus palustris)	Full Sun	FACW	Tree	Yes	Pollution Tolerant tolerant
Pepperbush, Sweet (Clethra alnifolia)	Part Shade- _ Full Shade	FAC+	Shrub	Seasonal	Salt tolerant
Winterberry, Common (Ilex verticillata)	Full Sun- Full Shade	FACW+	Shrub	Seasonal	Winter food source for birds
Witch-Hazel, American (Hamamelia virginiana)	Part Shade- _Full Shade	FAC-	Shrub	No	Pollution tolerant

¹Notes:

FAC = Facultative, equally likely to occur in wetlands or non-wetlands (estimated probability 34% - % - 66%).

 $FACU = Facultative\ Upland,\ usually\ occurs\ in\ non-wetlands\ (estimated\ probability\ 67\%-\underline{\%-99\%}),\ but\ occasionally\ found\ on\ wetlands\ (estimated\ probability\ 1\%-\underline{\%-33\%}).$

 $FACW = FACW \ Facultative \ Wetland, usually occurs in wetlands (estimated probability 67 \% - \% - 99\%), but occasionally found in non-wetlands.$

OBL = Obligate Wetland, occurs almost always (estimated probability 99%) under natural conditions in wetlands.

Sources: Prince George's County Maryland Bioretention Manual; Virginia DCR Stormwater Design Specification No. 9: Bioretention

Planting recommendations for bioretention facilities are as follows:

- The primary objective of the planting plan is to cover as much of the surface areas of the filter bed as quickly as possible. Herbaceous or ground cover layers are as or more important than more widely spaced trees and shrubs.
- Native plant species should be specified over non-native species.
- Plants should be selected based on a specified zone of hydric tolerance and must be capable
 of surviving both wet and dry conditions ("Wet footed" species should be planted near the
 center, whereas upland species do better planted near the edge).
- Woody vegetation should not be located at points of inflow; trees should not be planted directly above underdrains but should be located closer to the perimeter.
- Shrubs and herbaceous vegetation should generally be planted in clusters and at higher densities (i.e., 105 feet on-center and 1 to 1.5 feet on-center, respectively).
- If trees are part of the planting plan, a tree density of approximately one tree per 250 square feet (i.e., 15 feet on-center) is recommended.
- Designers should also remember that planting holes for trees must be at least 3 feet deep to
 provide enough soil volume for the root structure of mature trees. This applies even if the
 remaining soilfilter media layer is shallower than 3 feet.
- Tree species should be those that are known to survive well in the compacted soils and the
 polluted air and water of an urban landscape.
- If trees are used, plant shade-tolerant ground covers within the drip line.
- If the bioretention area is to be used for snow storage or is to accept snowmelt runoff, it should be planted with salt-tolerant, herbaceous perennials.

3.6.6 Bioretention Construction Sequence

Soil Erosion and Sediment Controls. The following soil erosion and sediment control guidelines must be followed during construction:

- All Bioretention bioretention areas must be fully protected by silt fence or construction fencing.
- Bioretention areas intended to infiltrate runoff must remain outside the <u>limitlimits</u> of disturbance during construction to prevent soil compaction by heavy equipment and loss of design infiltration rate.
 - ♦ Where it is infeasible keep the proposed bioretention areas outside of the limits of disturbance, there are several possible <u>outcomes_remedies</u> for the impacted area. If excavation in the proposed bioretention area can be restricted, then the remediation can be achieved with deep tilling practices. This is only possible if in_situ soils are not disturbed any deeper than 2 feet above the final design elevation of the bottom of the bioretention. In this case, when heavy equipment activity has ceased, the area is excavated to grade, and the impacted area must be tilled to a depth of 12 inches below the bottom of the bioretention.

- ◆ Alternatively, if it is infeasible to keep the proposed bioretention areas outside of the limits of disturbance, and excavation of the area cannot be restricted, then infiltration tests will be required prior to installation of the bioretention to ensure that the design infiltration rate is still present. If tests reveal the loss of design infiltration rates₁ then deep tilling practices may be used in an effort to restore those rates. In this case further testing must be done to establish design rates exist before the permeable pavementbioretention area can be installed.
- Finally, if it is infeasible to keep the proposed bioretention areas outside of the limits of disturbance, and excavation of the area cannot be restricted, and infiltration tests reveal design rates cannot be restored, then a resubmission of the SWMP will be required.
- Bioretention areas must be clearly marked on all construction documents and grading plans.
- Large bioretention applications may be used as small sediment traps or basins during construction. However, these must be accompanied by notes and graphic details on the soil erosion and sediment control plan specifying that (1) the maximum excavation depth of the trap or basin at the construction stage must be at least 1 foot higher than the post-construction (final) invert (bottom of the facility), and (2) the facility must contain an underdrain. The plan must also show the proper procedures for converting the temporary sediment control practice to a permanent bioretention BMP, including dewatering, cleanout, and stabilization.

Bioretention Installation. The following is a typical construction sequence to properly install a bioretention basin. The construction sequence for micro-bioretention is more simplified. These steps may be modified to reflect different bioretention applications or expected site conditions:

- Step 1: Stabilize Contributing Drainage Area. Construction of the bioretention area may only begin after the entire contributing drainage area CDA has been stabilized with vegetation. It may be necessary to block certain curb or other inlets while the bioretention area is being constructed. The proposed site should be checked for existing utilities prior to any excavation.
- Step 2: Preconstruction Meeting. The designer, the installer, and DDOEDOEE inspector must have a preconstruction meeting, checking the boundaries of the contributing drainage areaCDA and the actual inlet elevations to ensure they conform to original design. Since other contractors may be responsible for constructing portions of the site, it is quite common to find subtle differences in site grading, drainage and paving elevations that can produce hydraulically important differences for the proposed bioretention area. The designer should clearly communicate, in writing, any project changes determined during the preconstruction meeting to the installer and the inspector. Material certifications for aggregate, soilfilter media, and any geotextiles must be submitted for approval to the inspector at the preconstruction meeting.
- Step 3: Install Soil Erosion and Sediment Control Measures to Protect the Bioretention. Temporary soil erosion and sediment controls (e.g., diversion dikes, reinforced silt fences) are needed during construction of the bioretention area to divert stormwater away from the bioretention area until it is completed. Special protection measures, such as erosion control fabrics, may be needed to protect vulnerable side slopes from erosion during the construction process.
- *Step 4:* **Install Pretreatment Cells.** Any pretreatment cells should be excavated first and then sealed to trap sediment.

- **Step 5:** Avoid Impact of Heavy Installation Equipment. Excavators or backhoes should work from the sides to excavate the bioretention area to its appropriate design depth and dimensions. Excavating equipment should have scoops with adequate reach so they do not have to sit inside the footprint of the bioretention area. Contractors should use a cell construction approach in larger bioretention basins, whereby the basin is split into 500- to 1,000-square foot temporary cells with a 10- to 15 to 15-foot earth bridge in between, so that cells can be excavated from the side.
- **Step 6: Promote Infiltration Rate.** It may be necessary to rip the bottom soils to a depth of 6 to 12 inches to promote greater infiltration.
- Step 7: Order of Materials. If using a geotextile fabric, place the fabric on the sides of the bioretention area with a 6-inch overlap on the sides. If a stone storage layer will be used, place the appropriate depth of No. 57 stone (clean, double washed) on the bottom, install the perforated underdrain pipe, pack No. 57 stone to 3at least 2 inches above the underdrain pipe, and add the choking layer or appropriate geotextile layer as a filter between the underdrain and the soil filter media layer. If no stone storage layer is used, start with 6at least 2 inches of No. 57 stone on the bottom and proceed with the layering as described above.
- **Step 8:** Layered Installation of Media. Apply the media in 12-inch lifts until the desired top elevation of the bioretention area is achieved. Wait a few days to check for settlement and add additional media, as needed, to achieve the design elevation.

Note: The batch receipt confirming the source of the <u>soil_filter</u> media must be submitted to the <u>DDOEDOEE</u> inspector.

- *Step 9:* **Prepare Filter Media for Plants.** Prepare planting holes for any trees and shrubs, install the vegetation, and water accordingly. Install any temporary irrigation.
- Step 10: Planting. Install the plant materials as shown in the landscaping plan, and water them as needed.
- **Step 11:** Secure Surface Area. Place the surface cover (i.e., mulch, river stone, or turf) in both cells, depending on the design. If coir or jute matting will be used in lieu of mulch, the matting will need to be installed prior to planting (Step 10), and holes or slits will have to be cut in the matting to install the plants.
- Step 12: Inflows. If curb cuts or inlets are blocked during bioretention installation, unblock these after the drainage areaCDA and side slopes have good vegetative cover. It is recommended that unblocking curb cuts and inlets take place after two to three storm events if the drainage areaCDA includes newly installed asphalt, since new asphalt tends to produce a lot of fines and grit during the first several storms.
- *Step 13:* **Final Inspection.** Conduct the final construction inspection using a qualified professional, providing DDOEDOEE with an as-built, then log the GPS coordinates for each bioretention facility, and submit them for entry into the maintenance tracking database.

Construction Supervision. Supervision during construction is recommended to ensure that the bioretention area is built in accordance with the approved design and this specification. Qualified individuals should use detailed inspection checklists that include sign-offs at critical stages of construction, to ensure that the contractor's interpretation of the plan is consistent with the designer's intentions.

 $\overline{DDOE'sDOEE's}$ construction phase inspection checklist can be found in Appendix K_{τ_a} "Construction Inspection Checklists."

3.6.7 Bioretention Maintenance Criteria

When bioretention practices are installed, it is the owner's responsibility to ensure they, or those managing the practice, (1) be educated about their routine maintenance needs, (2) understand the long-term maintenance plan, and (3) be subject to a maintenance covenant or agreement, as described below.

Maintenance of bioretention areas should be integrated into routine landscape maintenance tasks. If landscaping contractors will be expected to perform maintenance, their contracts should contain specifics on unique bioretention landscaping needs, such as maintaining elevation differences needed for ponding, proper mulching, sediment and trash removal, and limited use of fertilizers and pesticides.

Maintenance tasks and frequency will vary depending on the size and location of the bioretention, the landscaping template chosen, and the type of surface cover in the practice. A generalized summary of common maintenance tasks and their frequency is provided in Table 3.2524.

Table 3.15 Typical Maintenance Tasks for Bioretention Practices

Frequency	Maintenance Tasks	
Upon establishment	 For the first 6 months following construction, the practice and CDA should be inspected at least twice after storm events that exceed 1/20.5 inch of rainfall. Conduct any needed repairs or stabilization. Inspectors should look for bare or eroding areas in the contributing drainage areaCDA or around the bioretention area, and make sure they are immediately stabilized with grass cover. One-time, spot fertilization may be needed for initial plantings. Watering is needed once a week during the first 2 months, and then as needed during first growing season (April-through October), depending on rainfall. Remove and replace dead plants. Up to 10% of the plant stock may die off in the first year, so construction contracts should include a care and replacement warranty to ensure that vegetation is properly established and survives during the first growing season following construction. 	
At least 4 times per year	 Mow grass filter strips and bioretention with turf cover Check curb cuts and inlets for accumulated grit, leaves, and debris that may block inflow 	
Twice during growing season	Spot weed, remove trash, and rake the mulch	
Annually	 Conduct a maintenance inspection Supplement mulch in devoid areas to maintain a 3-inch layer Prune trees and shrubs Remove sediment in pretreatment cells and inflow points 	
Once every 2–3 years	 Remove sediment in pretreatment cells and inflow points Remove and replace the mulch layer 	

Frequency	Maintenance Tasks
As needed	 Add reinforcement planting to maintain desired vegetation density Remove invasive plants using recommended control methods Remove any dead or diseased plants Stabilize the contributing drainage areaCDA to prevent erosion

Standing water is the most common problem outside of routine maintenance. If water remains on the surface for more than 72 hours after a storm, adjustments to the grading may be needed or underdrain repairs may be needed. The surface of the filter bed should also be checked for accumulated sediment or a fine crust that builds up after the first several storm events. There are several methods that can be used to rehabilitate the filter. These are listed below, starting with the simplest approach and ranging to more involved procedures (i.e., if the simpler actions do not solve the problem):

- Open the underdrain observation well or cleanout and pour in water to verify that the underdrains are functioning and not clogged or otherwise in need of repair. The purpose of this check is to see if there is standing water all the way down through the soil. If there is standing water on top, but not in the underdrain, then there is a clogged soil layer. If the underdrain and stand pipe indicates standing water, then the underdrain must be clogged and will need to be cleaned out.
- Remove accumulated sediment and till 2 to 3 inches of sand into the upper 6 to 12 inches of soil
- Install sand wicks from 3 inches below the surface to the underdrain layer. This reduces the average concentration of fines in the media bed and promotes quicker drawdown times. Sand wicks can be installed by excavating or auguring (i.e., using a tree auger or similar tool) down to the top of the underdrain layer to create vertical columns whichthat are then filled with a clean open-graded coarse sand material (e.g., ASTM C-33, Standard Specification for Concrete Aggregates, concrete sand or similar approved sand mix for bioretention media). A sufficient number of wick drains of sufficient dimension should be installed to meet the design dewatering time for the facility.
- Remove and replace some or all of the soilfilter media.

Maintenance Inspections. It is recommended that a qualified professional conduct a spring maintenance inspection and cleanup at each bioretention area. Maintenance inspections should include information about the inlets, the actual bioretention facility (sediment buildup, outlet conditions, etc.), and the state of vegetation (water stressed, dead, etc.) and are intended to highlight any issues that need or may need attention to maintain stormwater management functionality.

DDOE's DOEE's maintenance inspection checklists for bioretention areas and the Maintenance Service Completion Inspection form can be found in Appendix L_{\tau}, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants <u>is required</u> that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP-<u>is required</u>. The

declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property-Columbia land records. A template form is provided at the end of Chapter 5, "Administration of Stormwater Management Rules" (see Figure 5.411), although variations will exist for seenarios wheresituations in which stormwater crosses property lines. The covenant is between the property owner and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed-beissued. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit Cofto be included as an exhibit to the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined througheither signed by the Responsible Person for Maintenance on a partnership agreement or be identified in a memorandum of understanding that is incorporated into the plan submission.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.6.8 Bioretention Stormwater Compliance Calculations

Bioretention performance varies depending on the design configuration of the system.

Enhanced Designs. These designs are bioretention applications with no underdrain or at least 24 inches of filter media and an infiltration sump. Enhanced designs receive 100 percent retention value for the amount of storage volume (Sv) provided by the practice (Table 3.2625), and, therefore, are not considered an accepted total suspended solids (TSS) treatment practice.

Table 3.24.5 Enhanced Bioretention Retention Value and Pollutant Removal

Retention Value		=Sv	
Accepted TSS Treatment Practice	70.	N/A	

Standard Designs. These designs are bioretention applications with an underdrain and less than 24at least 18 inches of filter media. Standard designs receive 60 percent retention value and are an accepted TSS removal practice for the amount of storage volume (Sv) provided by the practice (Table 3.2726).

Table 3.25.6 Standard Bioretention Design Retention Value and Pollutant Removal

Retention Value	$=0.6 \times Sv$
Accepted TSS Treatment Practice	Yes

The practice must be sized using the guidance detailed in Section 3.6.4.

6.4 Bioretention Design Criteria.

Note: Additional retention value can be achieved if trees are utilized as part of a bioretention area (see Section 3.2.3 Green Roof Pretreatment Criteria).14, "Tree Planting and Preservation").

Bioretention also contributes to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the storage volume (Sv-or Rv) from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced NRCS) Curve Number CN for the site or drainage area.SDA. The Reduced Curve Number_reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.6.9 References

- ASTM C295 / C295M-12, Standard Guide for Petrographic Examination of Aggregates for Concrete, ASTM International, West Conshohocken, PA, 2012, www.astm.org
- ASTM D448-12(2017), Standard Classification for Sizes of Aggregate for Road and Bridge Construction, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- ASTM D2434-68(2006), Standard Test Method for Permeability of Granular Soils (Constant Head) (Withdrawn 2015), ASTM International, West Conshohocken, PA, 2006, www.astm.org
- Cappiella, K., T. Schueler and T. Wright. 2006. Urban Watershed Forestry Manual: Part 2: Conserving and Planting Trees at Development Sites. USDA Forest Service. Center for Watershed Protection. Ellicott City, MD.
- CWP. 2007. National Pollutant Removal Performance Database, Version 3.0. Center for Watershed Protection, Ellicott City, MD.
- <u>District of Columbia Department of Transportation (DDOT) Design and Engineering Manual,</u>
 2017. https://ddot.dc.gov/sites/default/files/dc/sites/ddot/publication/attachments/2017-06-30 DDOT DEM.pdf
- District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines, 2013.
 - $\frac{https://www.dcwater.com/sites/default/files/Green\%20Infrastructure\%20Utility\%20Protection\%20Guidelines.pdf$
- Hirschman, D., L. Woodworth and S. Drescher. 2009. Technical Report: Stormwater BMPs in Virginia's James River Basin An Assessment of Field Conditions and Programs. Center for Watershed Protection. Ellicott City, MD.

- Hunt, W.F. III and W.G. Lord. 2006. "Bioretention Performance, Design, Construction, and Maintenance." North Carolina Cooperative Extension Service Bulletin. Urban Waterways Series. AG-588-5. North Carolina State University. Raleigh, NC.
- Maryland Department of the Environment. 2001. Maryland Stormwater Design Manual. http://www.mde.state.md.us/programs/Water/StormwaterManagementProgram/MarylandStormwaterDesignManual/Pages/Programs/WaterPrograms/SedimentandStormwater/stormwater_design/index.aspxhttp://mde.maryland.gov/programs/Water/StormwaterManagementProgram/Pages/stormwater_design.aspx
- Prince George's Co., MD. 2007. Bioretention Manual. Available online at:

 http://www.princegeorgescountymd.gov/Government/AgencyIndex/DER/ESG/Bioretention/pdf/Bioretention%20Manual_2009%20Version.pdf
- Recommended Soil Testing Procedures for the Northeastern United States. 3rd ed., Northeast

 Regional Publication, Agricultural Experiment Station Bulletin 493, University of Delaware,
 Newark.
- Saxton, K.E., W.J. Rawls, J.S. Romberger, and R.I. Papendick. 1986. "Estimating generalized soil-water characteristics from texture." Soil Sci. Soc. Am. J. 50(4):1031-1036. Schueler, T. 2008. Technical Support for the Baywide Runoff Reduction Method. Chesapeake Stormwater Network. Baltimore, MD.
 - www.chesapeakestormwater.net/ttp://chesapeakestormwater.net/
- Smith, R.A. and Hunt, W.F. III. 1999. "Pollutant Removal in Bioretention Cells with Grass Cover"
- Smith, R. A., and Hunt, W.F. III. 2007. "Pollutant removal in bioretention cells with grass cover." Pp. 1-11 In: Proceedings of the World Environmental and Water Resources Congress 2007
- Sumner, M. E. and W. P. Miller. 1996. Cation Exchange Capacity and Exchange Coefficients. Methods of Soil Analysis, Part 3 Chemical Methods: 1201-1229
- Virginia DCR Stormwater Design Specification No. 9: Bioretention Version 1.8. 2010.
- Wisconsin Department of Natural Resources. *Storm Water Post-Construction Technical Standards*. http://dnr.wi.gov/topic/stormwater/standards/postconst_standards.html

PROPOSED REVISION PROPOSED REVISION REV

3.7 Filtering Systems


Definition. Practices that capture and temporarily store the design storm volume and pass it through a filter bed of sand media. Filtered runoff may be collected and returned to the conveyance system or allowed to partially infiltrate into the soil. Design variants include the following:

- F-1 Non-structural Nonstructural sand filter
- F-2 Surface sand filter
- F-3 Three-chamber underground sand filter
- F-4 Perimeter sand filter

Stormwater filters are a useful practice to treat stormwater runoff from small, highly impervious sites. Stormwater filters capture, temporarily store, and treat stormwater runoff by passing it through an engineered filter media, collecting the filtered water in an underdrain, and then returning it back to the storm drainage system. The filter consists of two chambers: the first is devoted to settling and the second serves as a filter bed consisting of a sand filter media.

Stormwater filters are a versatile option because they consume very little surface land and have few site restrictions. They provide moderate pollutant removal performance at small sites where space is limited. However, filters have no retention capability, so designers should consider using up-gradient retention practices, which have the effect of decreasing the design storm volume and size of the filtering practices. Filtering practices are also suitable to provide special treatment at designated stormwater hotspots. A list of potential stormwater hotspots operations can be found in Appendix P₋, "Stormwater Hotspots."

Filtering systems are typically not—to be designed to provide stormwater detention (Qp₂, Qp₁₅), but they may be in some circumstances. Filtering practices are generally combined with separate facilities to provide this type of control. However, the three-chamber underground sand filter can be modified by expanding the first or settling chamber, or adding an extra chamber between the filter chamber and the clear well chamber to handle the detention volume, which is subsequently discharged at a predetermined rate through an orifice and weir combination.



A surface sand filter is depicted in Figure 3.24, while Figures 3.25 through 3.30 depict three-chamber underground sand filters. Figure 3.31 depicts a perimeter sand filter.




Figure 3.233.243.23.24 Typical schematic for a surface sand filter (F-2). Note: Material specifications are indicated in Table 3.2827.




Figure 3.243.253.24.25 Part A – Example of a three-chamber underground sand filter (F-3) for separate sewer areas. Note: Material specifications are indicated in Table 3.2827.




Figure $3.253.263.25\underline{.26}$ Part B – Example of a three-chamber underground sand filter (F-3) for separate sewer areas. Note: Material specifications are indicated in Table $3.28\underline{27}$.




Figure 3.263.273.26.27 Part C – Example of a three-chamber underground sand filter (F-3) for separate sewer areas. Note: Material specifications are indicated in Table 3.2827.




Figure 3.273.283.27.28 Part A – Example of a three-chamber underground sand filter (F-3) for combined sewer areas. Note: Material specifications are indicated in Table 3.2827.




Figure 3.283.293.28.29 Part B – Example of a three-chamber underground sand filter (F-3) for combined sewer areas. Note: Material specifications are indicated in Table $3.28\underline{27}$.




Figure 3.293.303.29.30 Part C – Example of a three-chamber underground sand filter (F-3) for combined sewer areas. Note: Material specifications are indicated in Table 3.2827.




Figure 3.303.313.30.31 Example of a perimeter sand filter (F-4). Note: Material specifications are indicated in Table $3.28\underline{27}$.

3.7.1 Filtering Feasibility Criteria

Stormwater filters can be applied to most types of urban land. They are not always cost-effective, given their high unit cost and small area served, but there are situations where they may clearly be the best option for stormwater treatment (e.g., hotspot runoff treatment, small parking lots, ultra-urban areas, etc.). The following criteria apply to filtering practices:

Available Hydraulic Head. The principal design constraint for stormwater filters is available hydraulic head, which is defined as the vertical distance between the top elevation of the filter and the bottom elevation of the existing storm drain system that receives its discharge. The head required for stormwater filters ranges from 2 to 10 feet, depending on the design variant. It is difficult to employ filters in extremely flat terrain, since they require gravity flow through the filter. The only exception is the perimeter sand filter, which can be applied at sites with as little as 2 feet of head.

Depth to Water Table and Bedrock. The designer must assure a standard separation distance of at least 2 feet between the seasonally high groundwater table and/or bedrock layer and the bottom invert of the filtering practice.

Contributing Drainage Area. Filters are best applied on small sites where the contributing drainage (CDA) area is as close to 100-percent% impervious as possible in order to reduce the risk that eroded sediment will clog the filter. If the CDA is pervious, then the vegetation must be dense and stable. Turf is acceptable (see Section 3.7.5 Filtering Landscaping Criteria). A maximum CDA of 5 acres is recommended for surface sand filters, and a maximum CDA of 2 acres is recommended for perimeter or underground filters. Filters have been used on larger drainage areasCDAs in the past, but greater clogging problems have typically resulted. The one-chamber sand filter is only applicable for impervious area less than 10,000 ft² (1/4 acre).

Space Required. The amount of space required for a filter practice depends on the design variant selected. Surface sand filters typically consume about 2-to-%-3-percent% of the CDA, while perimeter sand filters typically consume less than 1-percent.%. Underground stormwater filters generally consume no surface area except their manholes.

Land Use. As noted above, filters are particularly well suited to treat runoff from stormwater hotspots and smaller parking lots. Other applications include redevelopment of commercial sites or when existing parking lots are renovated or expanded. Filters can work on most commercial, industrial, institutional, or municipal sites and can be located underground if surface area is not available.

Site Topography. Filters shall not be located on slopes greater than 6 percent. <u>%.</u>

Utilities. All utilities shall have a minimum 5-foot, horizontal clearance from the filtering practice.

Facility Access. All filtering systems shall be located in areas where they are accessible for inspection and for maintenance (by vacuum trucks).

Soils. Soil conditions do not constrain the use of filters. At least one soil boring must be taken at a low point within the footprint of the proposed filtering practice to establish the water table and bedrock elevations and evaluate soil suitability. A geotechnical investigation is required for all underground stormwater best management practices (BMPs), including underground filtering systems. Geotechnical testing requirements are outlined in Appendix O-, "Geotechnical Information Requirements for Underground BMPs."

3.7.2 Filtering Conveyance Criteria

Most filtering practices are designed as off-line systems so that all flows enter the filter storage chamber until it reaches capacity, at which point larger flows are then diverted or bypassed around the filter to an outlet chamber and are not treated. Runoff from larger storm events must be bypassed using an overflow structure or a flow splitter. Claytor and Schueler (1996) and ARC (2001) provide design guidance for flow splitters for filtering practices.

Some underground filters will be designed and constructed as on-line BMPs. In these cases, designers must indicate how the device will safely pass larger storm events (e.g., the 15-year event) to a stabilized water course without resuspending or flushing previously trapped material.

All stormwater filters must be designed to drain or dewater within 7240 hours (1.67 days) after a storm event to reduce the potential for nuisance conditions.

3.7.3 Filtering Pretreatment Criteria

Adequate pretreatment is needed to prevent premature filter clogging and ensure filter longevity. Dry or wet pretreatment shall be provided prior to filter media. Pretreatment devices are subject to the following criteria:

- Sedimentation chambers are typically used for pretreatment to capture coarse sediment particles before they reach the filter bed.
- Sedimentation chambers may be wet or dry but must be sized to accommodate at least 25 percent% of the total design storm volume (inclusive).
- Sediment chambers should be designed as level spreaders such that inflows to the filter bed have near zero velocity and spread runoff evenly across the bed.
- Non structural Nonstructural and surface sand filters may use alternative pretreatment measures, such as a grass filter strip, forebay, gravel diaphragm, check dam, level spreader, or a combination of these. The grass filter strip must be a minimum length of 15 feet and have a slope of 3-percent% or less. The check dam may be wooden or concrete and must be installed so that it extends only 2 inches above the filter strip and has lateral slots to allow runoff to be evenly distributed across the filter surface. Alternative pretreatment measures must contain a non-erosive flow path that distributes the flow evenly over the filter surface. If a forebay is used, it must be designed to accommodate at least 25-percent% of the total design storm volume (inclusive).

3.7.4 Filtering Design Criteria

Detention time. All filter systems must be designed to drain the design storm volume from the filter chamber within 7240 hours (1.67 days) after each rainfall event.

Structural Requirements. If a filter will be located underground or experience traffic loads, a licensed structural engineer must certify the structural integrity of the design.

Geometry. Filters are gravity flow systems that normally require 2 to 5 feet of driving head to push the water through the filter media through the entire maintenance cycle; therefore, sufficient vertical clearance between the inverts of the inflow and outflow pipes is required.

Type of Filter Media. The normal filter media consists of clean, washed AASHTO M-6/ASTM C-33 medium aggregate concrete sand with individual grains between 0.02 and to 0.04 inches inch in diameter.

Depth of Filter Media. The depth of the filter media plays a role in how quickly stormwater moves through the filter bed and how well it removes pollutants. The recommended filter bed depth is 18 inches. An absolute minimum filter bed depth of 12 inches above underdrains is required; although, designers should note that specifying the minimum depth of 12 inches will incur a more intensive maintenance schedule and possibly result in more condycostlier maintenance.

Underdrain and Liner. Stormwater filters are normally designed with an impermeable liner and underdrain system that meet the criteria provided in Table 3.2827 below.

Underdrain Stone. The underdrain should be covered by a minimum 6-inch gravel layer consisting of clean, double washed No. 57 stone.

Type of Filter. There are several design variations of the basic filter that enable designers to use filters at challenging sites or to improve pollutant removal rates. The choice of which filter design to apply depends on available space, hydraulic head, and the level of pollutant removal desired. In ultra-urban situations where surface space is at a premium, underground sand filters are often the only design that can be used. Surface and perimeter filters are often a more economical choice when adequate surface area is available. The most common design variants include the following:

- Non-Structural Nonstructural Sand Filter (F-1). The non-structural nonstructural sand filter is applied to sites less than 2 acres in size and is very similar to a bioretention practice (see Section 3.6 Bioretention), with the following exceptions:
 - The bottom is lined with an impermeable liner and always has an underdrain.
 - The surface cover is sand, turf, or pea gravel.
 - The filter media is 100-percent% sand.
 - The filter surface is not planted with trees, shrubs, or herbaceous materials.

 The filter has two cells, with a dry or wet sedimentation chamber preceding the sand filter bed.

The non-structural nonstructural sand filter is the least expensive filter option for treating hotspot runoff. The use of bioretention areas is generally preferred at most other sites.

- Surface Sand Filter (F-2). The surface sand filter is designed with both the filter bed and sediment chamber located at ground level. The most common filter media is sand; however, a peat/sand mixture may be used to increase the removal efficiency of the system. In most cases, the filter chambers are created using precast or cast-in-place concrete. Surface sand filters are normally designed to be off-line facilities, so that only the desired design volume is directed to the filter for treatment. However, in some cases they can be installed on the bottom of a Dry Extended Detention (ED) Ponddry pond (see Section 3.9 Open Channel Systems 12 Storage Practices).
- Underground Sand Filter. The underground sand filter is modified to install the filtering components underground and is often designed with an internal flow splitter or overflow device that bypasses runoff from larger stormwater events around the filter. Underground sand filters are expensive to construct, but they consume very little space and are well suited to ultra-urban areas.
- Three-Chamber Underground Sand Filter (F-3). The three-chamber underground sand filter is a gravity flow system. The facility may be precast or cast-in-place. The first chamber acts as a pretreatment facility removing any floating organic material such as oil, grease, and tree leaves. It should have a submerged orifice leading to a second chamber, and it should be designed to minimize the energy of incoming stormwater before the flow enters the second chamber (i.e., filtering or processing chamber).

The second chamber is the filtering or processing chamber. It should contain the filter material consisting of gravel and sand and should be situated behind a weir. Along the bottom of the structure should be a subsurface drainage system consisting of a parallel perforated PVC pipe system in a stone bed. A dewatering valve should be installed at the top of the filter layer for safety release in cases of emergency. A bypass pipe crossing the second chamber to carry overflow from the first chamber to the third chamber is required.

The third chamber is the discharge chamber. It should also receive the overflow from the first chamber through the bypass pipe when the storage volume is exceeded.

Water enters the first chamber of the system by gravity or by pumping. This chamber removes most of the heavy solid particles, floatable trash, leaves, and hydrocarbons. Then the water flows to the second chamber and enters the filter layer by overtopping a weir. The filtered stormwater is then picked up by the subsurface drainage system that empties it into the third chamber.

Whenever there is insufficient hydraulic head for a three-chamber underground sand filter, a well pump may be used to discharge the effluent from the third chamber into the receiving storm or combined sewer. For three-chamber sand filters in combined-sewer areas, a water trap shall be provided in the third chamber to prevent the back flow of odorous gas.

A design example for a three-chamber underground sand filter is provided in Appendix T, "Underground Sand Filter Design Example."

• **Perimeter Sand Filter (F-744).** The perimeter sand filter also includes the basic design elements of a sediment chamber and a filter bed. The perimeter sand filter typically consists of two parallel trenches connected by a series of overflow weir notches at the top of the partitioning wall, which allows water to enter the second trench as sheet flow. The first trench is a pretreatment chamber removing heavy sediment particles and debris. The second trench consists of the sand filter layer. A subsurface drainage pipe must be installed at the bottom of the second chamber to facilitate the filtering process and convey filter water into a receiving system.

In this design, flow enters the system through grates, usually at the edge of a parking lot. The perimeter sand filter is usually designed as an on-line practice (i.e., all flows enter the system), but larger events bypass treatment by entering an overflow chamber. One major advantage of the perimeter sand filter design is that it requires little hydraulic head and is therefore a good option for sites with low topographic relief.

Surface Cover. The surface cover for non-structural nonstructural and surface sand filters should consist of a 3-inch layer of topsoil on top of the sand layer. The surface may also have pea gravel inlets in the topsoil layer to promote filtration. The pea gravel may be located where sheet flow enters the filter, around the margins of the filter bed, or at locations in the middle of the filter bed.

Underground sand filters should have a pea gravel <u>or No. 57 stone</u> layer on top of the sand layer. <u>The peaThis</u> gravel <u>layer</u> helps to prevent bio-fouling or blinding of the sand surface.

Maintenance Reduction Features. The following maintenance issues should be addressed during filter design to reduce future maintenance problems:

- Observation Wells and Cleanouts. Non-structural Nonstructural and surface sand filters must include an observation well consisting of a 6-inch diameter non-perforated PVC pipe fitted with a lockable cap. It should be installed flush with the ground surface to facilitate periodic inspection and maintenance. In most cases, a cleanout pipe will be tied into the end of all underdrain pipe runs. The portion of the cleanout pipe/observation well in the underdrain layer should be perforated. At least one cleanout pipe must be provided for every 20002,000 square feet of filter surface area.
- Access. Good maintenance access is needed to allow crews to perform regular inspections and maintenance activities. "Sufficient access" is operationally defined as the ability to get a vacuum truck or similar equipment close enough to the sedimentation chamber and filter to enable cleanouts. Direct maintenance access shall be provided to the pretreatment area and the filter bed. For underground structures, sufficient headroom for maintenance should be provided. A minimum head space of 5 feet above the filter is recommended for maintenance of the structure. However, if 5 feet of headroom is not available, manhole access must be installed.
- Manhole Access (for underground filters). Access to the headbox and clearwell of Underground Filters must be provided by manholes at least 30 inches in diameter, along with steps to the areas where maintenance will occur.

- Visibility. Stormwater filters should be clearly visible at the site so inspectors and
 maintenance crews can easily find them. Adequate signs or markings must be provided at
 manhole access points for Underground Filters.
- Confined Space Issues. Underground filters are often classified as a confined space. Consequently, special OSHA rules apply, and training may be needed to protect the workers that access them. These procedures often involve training about confined space entry, venting, and the use of gas probes.

Filter Material Specifications. The basic material specifications for filtering practices that utilize sand as a filter media are outlined in Table 3.2827.

Table 3.16 Filtering Practice Material Specifications

Material	Specification	
Surface Cover	Non structural Nonstructural and surface sand filters: 3-inch layer of topsoil on top of the sand layer. The surface may also have pea gravel inlets in the topsoil layer to promote filtration. Underground sand filters: Clean, double—washed pea gravel or No. 57 stone on top of the sand layer.	
Sand	Clean AASHTO M-6/ASTM C-33 medium aggregate concrete sand with a particle size range of 0.02-to0.04 inch in diameter.	
Choker Stone and/or Geotextile/Filter Fabric	AnFor choker stone, a 2- to 4-inch layer of choker stone (e.g., typically ASTM D448 No. 8 or No. 89 washed gravel) should be placed between the sand layer and the underdrain stone. Alternatively, if available head is limited, an appropriate geotextile fabric that meets AASHTO M-288 Class 2, latest edition, requirements may be used. The geotextile fabric must have a flow rate of > 125 gpm/ft² (ASTM D4491) and an Apparent Opening Size (AOS) equivalent to a US No. 70 or No. 80 sieve.	
Underdrain/Perforated Pipe	4- or 6-inch perforated schedule 40 PVC pipe, with three or four rows of 3/8-inch perforations at 6 inches on center.	
Underdrain Stone	Use #No. 57 stone or the ASTM equivalent (1_inch maximum).	
Impermeable Liner	Where appropriate, use a thirty mil (minimum) PVC Geomembrane liner or equivalent.	

Filter Sizing. Filtering devices are sized to accommodate a specified design storm volume (typically Stormwater Retention Volume (SWRv)). SWRv). The volume to be treated by the device is a function of the storage depth above the filter and the surface area of the filter. The storage volume is the volume of ponding above the filter. For a given design volume, Equation 3.10 below8 is used to determine the required filter surface area.

Equation 3.8 Minimum Filter Surface Area for Filtering Practices

$$SA_{filter} = \frac{DesignVolume \times d_f}{k \times (h_{avg} + d_f) \times t_d}$$

$$SA_{filter} = \frac{DesignVolume \times d_f}{k \times (h_{avg} + d_f) \times t_d}$$

where:

 SA_{filter} = area of the filter surface (ft²)

 $DesignVolume = design storm volume, typically the SWRv (ft^2)$

 d_f = filter media depth (thickness) (ft), with a minimum of 1 ft

k = coefficient of permeability (ft/day) (3.5 ft/day for partially clogged sand)

 h_f = height of water above the filter bed (ft), with a maximum of 5 ft h_{avg} = average height of water above the filter bed (ft), one half of the

filter height (h_f)

 $t \underline{d}$ = allowable drawdown time (1.67 days)

The coefficient of permeability (ft/day) is intended to reflect the worst_case situation (i.e., the condition of the sand media at the point in its operational life where it is in need of replacement or maintenance). Filtering practices are therefore sized to function within the desired constraints at the end of the media's operational life cycle.

The entire filter treatment system, including pretreatment, shall temporarily hold at least 50 percent% of the design storm volume prior to filtration (see Equation 3.72). This reduced volume takes into account the varying filtration rate of the water through the media, as a function of a gradually declining hydraulic head.

Equation 3.9 Required Ponding Volume for Filtering Practices

$$V_{ponding} = 0.50 \times DesignVolume$$

$$V_{ponding} = 0.50 \times DesignVolume$$

where:

 $V_{ponding}$ = storage volume required prior to filtration (ft³) DesignVolume = design storm volume, typically the SWRv (ft²)

The total storage volume for the practice (Sv) can be determined using Equation 3.810 below.

Equation 3.10 Storage Volume for Filtering Practices

$$Sv = 2.0 \times V_{ponding}$$

$$Sv = 2.0 \times V_{ponding}$$

where:

Sv = total storage volume for the practice (ft³) $V_{ponding}$ = storage volume required prior to filtration (ft³)

3.7.5 Filtering Landscaping Criteria

A dense and vigorous vegetative cover shall be established over the contributing pervious drainage areas before runoff can be accepted into the facility. Filtering practices should be incorporated into site landscaping to increase their aesthetics and public appeal.

Surface filters (e.g., surface and non-structural nonstructural sand filters) can have a grass cover to aid in pollutant adsorption. The grass should be capable of withstanding frequent periods of inundation and drought.

3.7.6 Filter Construction Sequence

Soil Erosion and Sediment Control. No runoff shall be allowed to enter the filter system prior to completion of all construction activities, including revegetation and final site stabilization. Construction runoff shall be treated in separate sedimentation basins and routed to bypass the filter system. Should construction runoff enter the filter system prior to final site stabilization, all contaminated materials must be removed and replaced with new clean filter materials before a regulatory inspector approves its completion. The approved soil erosion and sediment control plan-(SESCP) shall include specific measures to provide for the protection of the filter system before the final stabilization of the site.

Filter Installation. The following is the typical construction sequence to properly install a structural sand filter. This sequence can be modified to reflect different filter designs, site conditions, and the size, complexity, and configuration of the proposed filtering application.

- Step 1: Stabilize Contributing Drainage Area. Filtering practices should only be constructed after the contributing drainage area CDA to the facility is completely stabilized, so sediment from the CDA does not flow into and clog the filter. If the proposed filtering area is used as a sediment trap or basin during the construction phase, the construction notes should clearly specify that, after site construction is complete, the sediment control facility will be dewatered, dredged, and regraded regraded to design dimensions for the post-construction filter.
- Step 2: Install Soil Erosion and Sediment Control Measures for the Filtering Practice. Stormwater should be diverted around filtering practices as they are being constructed. This is usually not difficult to accomplish for off-line filtering practices. It is extremely important to keep runoff and eroded sediment away from the filter throughout the construction process. Silt fence or other sediment controls should be installed around the perimeter of the filter, and erosion control fabric may be needed during construction on exposed side-slopes with gradients exceeding 4H:1V. Exposed soils in the vicinity of the filtering practice should be rapidly stabilized by hydro-seed, sod, mulch, or other method.
- **Step 3:** Assemble Construction Materials on On Site. Inspect construction materials to insure ensure they conform to design specifications and prepare any staging areas.

- **Step 4:** Clear and Strip. Bring the project area to the desired subgrade.
- **Step 5: Excavate and Grade.** Survey to achieve the appropriate elevation and designed contours for the bottom and side slopes of the filtering practice.
- Step 6: Install Filter Structure. Install filter structure in design location and check all design elevations (i.e., concrete vaults for surface, underground, and perimeter sand filters). Upon completion of the filter structure shell, inlets and outlets must be temporarily plugged and the structure filled with water to the brim to demonstrate water tightness. Maximum allowable leakage is 5-percent% of the water volume in a 24-hour period. See Appendix K, "Construction Inspection Checklists for the Stormwater Facility Leak Test" form. If the structure fails the test, repairs must be performed to make the structure watertight before any sand is placed into it.
- *Step 7:* Install Base Material Components. Install the gravel, underdrains, and choker layers of the filter.
- **Step 8: Install Top Sand Component.** Spread sand across filter bed in 1-foot lifts up to the design elevation. Backhoes or other equipment can deliver the sand from outside the filter structure. Sand should be manually raked. Clean water is then added until the sedimentation chamber and filter bed are completely full. The facility is then allowed to drain, hydraulically compacting the sand layers. After 48 hours of drying, refill the structure to the final top elevation of the filter bed.
- **Step 9: Install Surface Layer (Surface Sand Filters only).** Add a 3-inch topsoil layer and pea gravel inlets and immediately seed with the permanent grass species. The grass should be watered, and the facility should not be switched on-line until a vigorous grass cover has become established.
- *Step 10:* **Stabilize Surrounding Areas.** Stabilize exposed soils on the perimeter of the structure with temporary seed mixtures appropriate for a buffer. All areas above the normal pool should be permanently stabilized by hydroseed, sod, or seeding and mulch.
- **Step 11: Final Inspection**. Conduct the final construction inspection. Multiple construction inspections by a qualified professional are critical to ensure that stormwater filters are properly constructed. Inspections are recommended during the following stages of construction:
- Initial site preparation, including installation of soil erosion and sediment control measures;
- Excavation/grading to design dimensions and elevations;
- Installation of the filter structure, including the water tightness test;
- Installation of the underdrain and filter bed;
- Check that turf cover is vigorous enough to switch the facility on-line; and
- Final inspection after a rainfall event to ensure that it drains properly and all pipe connections are watertight. Develop a punch list for facility acceptance. Log the filtering practice's GPS coordinates and submit them for entry into the BMP maintenance tracking database.

 $\overline{\text{DDOE's}}$ Construction phase inspection checklist for filters and the Stormwater Facility Leak Test form can be found in Appendix K₇, "Construction Inspection Checklists."

3.7.7 Filtering Maintenance Criteria

Maintenance of filters is required and involves several routine maintenance tasks, which are outlined in Table 3.29 below28. A cleanup should be scheduled at least once a year to remove trash and floatables that accumulate in the pretreatment cells and filter bed. Frequent sediment cleanouts in the dry and wet sedimentation chambers are recommended every 1 to 3 years to maintain the function and performance of the filter. If the filter treats runoff from a stormwater hotspot, crews may need to test the filter bed media before disposing of the media and trapped pollutants. Petroleum hydrocarbon contaminated sand or filter cloth must be disposed of according to District solid waste disposal regulations. Testing is not needed if the filter does not receive runoff from a designated stormwater hotspot, in which case the media can be safely disposed of in a landfill.

Table 3.17 Typical Annual Maintenance Activities for Filtering Practices

Frequency	Maintenance Tasks	
At least 4 times per growing season	 Mow grass filter strips and perimeter turf around surface sand filters. Maximum grass heights should be less than 12 inches. 	
2 times per year (may be more or less frequently depending on land use)	Check to see if sediment accumulation in the sedimentation chamber has exceeded 6 inches. If so, schedule a cleanout.	
Annually	 Conduct inspection and cleanup. Dig a small test pit in the filter bed to determine whether the first 3 inches of sand are visibly discolored and need replacement. Check to see if inlets and flow splitters are clear of debris and are operating properly. Check concrete structures and outlets for any evidence of spalling, joint failure, leakage, corrosion, etc. Ensure that the filter bed is level and remove trash and debris from the filter bed. Sand or gravel covers should be raked to a depth of 3 inches. 	
Every 5 years	Replace top sand layer.Till or aerate surface to improve infiltration/grass cover.	
As needed	 Remove blockages and obstructions from inflows. Trash collected on the grates protecting the inlets shall be removed regularly to ensure the inflow capacity of the BMP is preserved. Stabilize contributing drainage area CDA and side-slopes to prevent erosion. Filters with a turf cover should have 95% vegetative cover. 	
Upon failure	 Corrective maintenance is required any time the sedimentation basin and sediment trap do not draw down completely after 72 hours (i.e., no standing water is allowed). 	

Maintenance Inspections. Regular inspections by a qualified professional are critical to schedule sediment removal operations, replace filter media, and relieve any surface clogging. Frequent inspections are especially needed for underground and perimeter filters, since they are out of sight and can be easily forgotten. Depending on the level of traffic or the particular land use, a filter system may either become clogged within a few months of normal rainfall or could possibly last several years with only routine maintenance. Maintenance inspections should be conducted within 24 hours following a storm that exceeds \(\frac{1}{20.5}\) inch of rainfall, to evaluate the condition and performance of the filtering practice.

Note: Without regular maintenance, reconditioning sand filters can be very expensive.

 $\frac{DDOE'sDOEE's}{DOEE's} \ maintenance \ inspection \ checklists \ for \ filters \ and \ the \ Maintenance \ Service \\ Completion \ Inspection \ form \ can \ be \ found \ in \ Appendix \ L_{\overline{\tau}}, \ "Maintenance \ Inspection \ Checklists."$

Declaration of Covenants. A maintenance covenant is required for all stormwater management practices. The covenant specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The covenant is attached to recorded in the deed <u>District</u> of the property <u>Columbia land records</u> (see standard form, variations exist for scenarios where stormwater crosses property lines). A template form is provided at the end of Chapter 5 <u>Administration of Stormwater Management Rules</u> (see Figure 5.411), although

variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. There may be a maintenance schedule on the drawings themselves or the plans may refer to the maintenance schedule (Exhibit C in the covenant).

Covenants are not required on government properties but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.7.8 Filtering Volume Compliance Calculations

Filtering practices receive 0 percent retention value. Filtering practices are an accepted total suspended solids (TSS) treatment practice for the amount of storage volume (Sv) provided by the BMP (Table 3.3029).

Table 3.18 Filter Retention Value and Pollutant Removal

Retention Value	= 0
Accepted TSS Treatment Practice	Yes

The practice must be sized using the guidance detailed in Section 3.7.4

3.7.4 Filtering Design Criteria.

3.7.9 References

- ASTM D448-12(2017), Standard Classification for Sizes of Aggregate for Road and Bridge Construction, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- ASTM D4491 / D4491M-17, Standard Test Methods for Water Permeability of Geotextiles by Permittivity, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- Atlanta Regional Commission (ARC). 2001. Georgia Stormwater Management Manual, First Edition. Available online at: http://www.georgiastormwater.com/Available online at: https://atlantaregional.org/natural-resources/water/georgia-stormwater-management-manual/
- Claytor, R. and T. Schueler. 1996. Design of Stormwater Filtering Systems. Chesapeake Research Consortium and the Center for Watershed Protection. Ellicott City, MD. http://www.cwp.org/online-watershed-library?view=docmanhttps://owl.cwp.org/
- Van Truong, Hung. 1989. The Sand Filter Water Quality Structure. D.C. Environmental Regulation Administration. Washington, DC.

Van Truong, Hung. 1993. Application of the Washington D.C. Sand Filter Water for Urban Runoff Control. Draft Report. Washington D.C. Environmental Regulations Administration. Washington, D.C. (30+ pages).

Virginia DCR Stormwater Design Specification No. 12: Filtering Practices Version 1.7. 2010.




3.8 Infiltration

Definition. Practices that capture and temporarily store the design storm volume before allowing it to infiltrate into the soil over a two-three-day period. Design variants include the following:

I-1 Infiltration trench

I-2 Infiltration basin

Infiltration practices use temporary surface or underground storage to allow incoming stormwater runoff to exfiltrate into underlying soils. Runoff first passes through multiple pretreatment mechanisms to trap sediment and organic matter before it reaches the practice. As the stormwater penetrates the underlying soil, chemical and physical adsorption processes remove pollutants. Infiltration practices are suitable for use in residential and other urban areas where field measured soil infiltration rates are verified saturated hydraulic conductivity is sufficient. To prevent possible groundwater contamination, infiltration practices must not be utilized at sites designated as stormwater hotspots. Figures 3.32 through 3.34 illustrate several infiltration design variations.






Figure 3.313.323.313.313.313.313.29 Example of an infiltration trench. .32 Example of an infiltration trench.




Figure 3.323.333.323.30.33 Infiltration section with supplemental pipe storage.




Figure 3.333.343.33.34 Example of an infiltration basin.

3.8.1 Infiltration Feasibility Criteria

Infiltration practices have very high storage and retention capabilities when sited and designed appropriately. Designers should evaluate the range of soil properties during initial site layout and seek to configure the site to conserve and protect the soils with the greatest recharge and infiltration rates. In particular, areas of Hydrologic Soil GroupHSG A or B soils, shown on the U.S. Department of Agriculture's Natural Resources Conservation Service (NRCS) soil surveys, should be considered as primary locations for infiltration practices. Additional information about soil and infiltration are described in more detail later in this section. During initial design phases, designers should carefully identify and evaluate constraints on infiltration, as follows:

Underground Injection Control for Class V Wells. In order for an infiltration practice to avoid classification as a Class V well, which is subject to regulation under the Federal Underground Injection Control (UIC) program, the practice must be wider than the practice is deep. If an infiltration practice is "deeper than its widest surface dimension" or if it includes an underground distribution system, then it will likely be considered a Class V injection well. Class V injection wells are subject to permit approval by the U.S. Environmental Protection Agency (EPA). For more information on Class V injection wells and stormwater management, designers should consult

http://water.epa.gov/type/groundwater/uic/class5/comply_minrequirements.cfmhttps://www.epa.gov/uic/federal-requirements-class-v-wells for EPA's minimum requirements.

Contributing Drainage Area. The maximum Contributing Drainage Area (CDA) to an individual infiltration practice should be less than 2 acres and as close to 100 percent impervious as possible. The design, pretreatment, and maintenance requirements will differ depending on the size of the infiltration practice.

Site Topography. Infiltration The infiltration practice shall not be located on slopes greater than 6-percent,%, although check dams or other devices may be employed to reduce the effective slope of the practice. Further, unless slope stability calculations demonstrate otherwise, infiltration practices should be located a minimum horizontal distance of 200 feet from downgradient slopes greater than 20-percent.%

Minimum Hydraulic Head. Two or more feet of head may be needed to promote flow through infiltration practices.

Minimum Depth to Water Table or Bedrock. A minimum vertical distance of 2 feet must be provided between the bottom of the infiltration practice and the seasonal high water table or bedrock layer.

Soils. Initially, soil infiltration rates can be estimated from NRCS soil data, but designers must verify soil permeability by using the on-site soil investigation methods provided in Appendix O₋₇, "Geotechnical Information Requirements for Underground BMPs."

Use on Urban Fill Soils/Redevelopment Sites. Sites that have been previously graded or disturbed do not typically retain their original soil permeability due to compaction. Therefore, such sites are often not good candidates for infiltration practices unless the geotechnical investigation shows that a sufficient infiltration ratesaturated hydraulic conductivity exists.

Dry Weather Flows. Infiltration practices should not be used on sites receiving regular dryweather flows from sump pumps, irrigation water, chlorinated wash-water, or flows other than stormwater.

Setbacks. Infiltration To avoid the risk of seepage, stormwater cannot flow from infiltration practices must not be hydraulically connected to traditional pavement base layer, existing structure foundations, or pavement, in order to avoid harmful seepage.future foundations which may be built on adjacent properties. Setbacks to structures varyand property lines must be at least 10 feet and adequate water proofing waterproofing protection must be provided for foundations and basements. Where the 10-foot setback is not possible, an impermeable liner may be used along the sides of the infiltration area (extending from the surface to the bottom of the practice).

All setbacks must be verified by a professional geotechnical engineer registered in the District of Columbia.

Proximity to Utilities. Interference with underground utilities should be avoided, if possible. When large site development is undertaken the expectation of achieving avoidance will be high. Conflicts may be commonplace on smaller sites and in the public right of way PROW. Consult with each utility company on recommended offsets, which will allow utility maintenance work with minimal disturbance to the infiltration BMP. For an infiltration BMP in the public right of way PROW, a consolidated presentation of the various utility offset recommendations can be found in Chapter 33.14.528.8.4.4 of the District of Columbia Department of Transportation Design and Engineering Manual, latest edition. Consult the District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines, latest edition, for water and sewer line recommendations. Where conflicts cannot be avoided, follow these guidelines:

- Consider altering the location or sizing of the infiltration BMP to avoid or minimize the utility conflict. Consider an alternate BMP type to avoid conflict.
- Use design features to mitigate the impacts of conflicts that may arise by allowing the infiltration BMP and the utility to coexist. The infiltration BMP design may need to incorporate impervious areas, through geotextiles or compaction, to protect utility crossings. Other a-key design features may need to be moved-or, added, or deleted.
- Work with the utility to eval ate Evaluate the relocation of the existing utility and install the optimum placement an optimally placed and sizing of the sized infiltration BMP.
- If utility functionality, longevity and vehicular access to manholes can be assured accept the infiltration BMP design and location with the existing utility. Incorporate into the infiltration BMP design sufficient soil coverage over the utility or general clearances or other features such as an impermeable linear to assure all entities the conflict is limited to maintenance.

Note: When accepting utility conflict into the infiltration BMP location and design, it is understood the infiltration BMP will be temporarily impacted during utility work—but. At the conclusion of this work, the utility owner will replace the infiltration BMP or, alternatively, install a functionally comparable infiltration BMP according to the specifications in the current version of this Stormwater Management Guidebook.guidebook. If the infiltration BMP is located in the public right of wayPROW, the infiltration BMP restoration will also conform with the

District of Columbia Department of Transportation Design and Engineering Manual with special attention to Chapter <u>33</u>, <u>Chapter 47,28</u> and the Design and Engineering Manual supplements for Low Impact Development and Green Infrastructure Standards and Specifications.

Hotspots and High Loading Situations. Infiltration practices are not intended to treat sites with high sediment or trash or debris loads, because such loads will cause the practice to clog and fail. Infiltration practices must be avoided at potential stormwater hotspots that pose a risk of groundwater contamination. For a list of potential stormwater hotspot operations, consult Appendix P Stormwater Hotspots.

On sites with existing contaminated soils, as indicated in Appendix O, "Geotechnical Information Requirements for Underground BMPs," infiltration is not allowed.

3.8.2 Infiltration Conveyance Criteria

The nature of the conveyance and overflow to an infiltration practice depends on the scale of infiltration and whether the facility is on-line or off-line. Where possible, conventional infiltration practices should be designed off-line to avoid damage from the erosive velocities of larger design storms. If runoff is delivered by a storm drain pipe or along the main conveyance system, the infiltration practice shall be designed as an off-line practice. Pretreatment shall be provided for storm drain pipes and conveyance systems discharging directly to infiltration systems.

Off-line Infiltration. Overflows can either be diverted from entering the infiltration practice or dealt with via an overflow inlet. Optional overflow methods include the following:

- Utilize a low-flow diversion or flow splitter at the inlet to allow only the design Stormwater Retention Volume (SWRv) to enter the facility. This may be achieved with a weir or curb opening sized for the target flow, in combination with a bypass channel. Using a weir or curb opening helps minimize clogging and reduces the maintenance frequency (further guidance on determining the peak flow rate will be necessary in order to ensure proper design of the diversion structure).
- Use landscaping type inlets or standpipes with trash guards as overflow devices.

On-line Infiltration. An overflow structure must be incorporated into on-line designs to safely convey larger storms through the infiltration area. Mechanisms such as elevated drop inlets and overflow weirs are examples of how to direct high flows to a non-erosive down-slope overflow channel, stabilized water course, or storm sewer system designed to convey the 15-year design storm.

3.8.3 Infiltration Pretreatment Criteria

Every infiltration system shall have pretreatment mechanisms to protect the long_term integrity of the infiltration rate. One of the following techniques must be installed to pretreat 100 percent% of the inflow in every facility:

Grass channel

- Grass filter strip (minimum 20 feet and only if sheet flow is established and must be maintained over a length of 20 feet)
- Forebay or sump pit (must accommodate a minimum 25 percent of the design storm volume; if the infiltration rate for the underlying soils is greater than 2 inches per hour, the forebay volume shall be increased to a minimum of 50 percent 15% of the design storm volume)
- Gravel diaphragm (minimum 1 foot deep and 2 feet wide and only if sheet flow is established and maintained)
- Filter system (see Section 3.7-Stormwater Filtering Systems) If using a filter system as a pretreatment facility, the sand filter will not require its own separate pretreatment facility.
- A proprietary structure with demonstrated capability of reducing sediment and hydrocarbons may be used to provide pretreatment. Refer to Section 3.13 Proprietary Practices and Appendix S <u>Proprietary Practices Approval Process</u> for information on approved proprietary structures.

If the basin serves a CDA greater than 20,000 square feet, a forebay, <u>sump pit</u>, filter system, or proprietary practice must be used for pretreatment.

Exit velocities from the pretreatment chamber shall not be erosive (above 6 fps) during the 15-year design storm and flow from the pretreatment chamber should be evenly distributed across the width of the practice (e.g., using a level spreader).

3.8.4 Infiltration Design Criteria

Geometry. Where possible, <u>an infiltration practices practice</u> should be designed to be wider than they are it is deep, to avoid classification as a <u>classClass</u> V injection well. For more information on Class V wells see <u>-https://www.epa.gov/uic/class_v-wells-injection-non-hazardous-fluids-or-above-underground-sources-drinking-water</u>

Practice Slope. The bottom of an infiltration practice should be flat (i.e., 0 percent <u>%</u> longitudinal and lateral slopes) to enable even distribution and infiltration of stormwater.

Infiltration Basin Geometry. The maximum vertical depth to which runoff may be ponded over an infiltration basin is 24 inches. The side-slopes should be no steeper than 4H:1V.

Surface Cover (optional). Designers may choose to install a layer of topsoil and grass above the infiltration practice.

Surface Stone. A 3-inch layer of clean, washed river stone or No. 8 or 89 stone should be installed over the stone layer.

Stone Layer. Stone layers must consist of clean, washed aggregate with a maximum diameter of 3.5 inches and a minimum diameter of 1.5 inches.

Observation Wells. All infiltration practices must include at least one observation well. The observation well is used to observe the rate of drawdown within the infiltration practice following a storm event and to facilitate periodic inspection and maintenance. The observation

well should consist of a well-anchored, perforated 4- to 6-inch diameter PVC pipe. There should be no perforation within 1 foot of the surface. The observation well should extend vertically to the bottom of the stone layer and extend upward to the top of ponding.

Underground Storage (optional). In the underground mode, runoff is stored in the voids of the stones and infiltrates into the underlying soil matrix. Perforated corrugated metal pipe, plastic pipe, concrete arch pipe, or comparable materials can be used in conjunction with the stone to increase the available temporary underground storage. In some instances, a combination of filtration and infiltration cells can be installed in the floor of a dry extended detention (ED) pond.

Overflow Collection Pipe (Overdrain). An optional overflow collection pipe can be installed in the stone layer to convey collected runoff from larger storm events to a downstream conveyance system.

Trench Bottom. To protect the bottom of an infiltration trench from intrusion by underlying soils, a sand layer must be used. The underlying native soils must be separated from the stone layer by a 6- to 8-inch layer of coarse sand (e.g., ASTM C_33, 0.02_0.04 inch in diameter).

Geotextile Fabric. An appropriate geotextile fabric that complies with AASHTO M-288 Class 2, latest edition, requirements and has a permeability of at least an order of magnitude (10 times) higher (10 x) than the soil subgrade permeability must be used. This layer should be applied only to the sides of the practice.

Material Specifications. Recommended material specifications for infiltration areas are shown in Table 3.3±30.

Table 3.29.30 Infiltration Material Specifications

Material	Specification	Notes	
Surface Layer (optional)	Topsoil and grass layer		
Surface Stone	Install a 3-inch layer of river stone or pea gravel.	Provides an attractive surface cover that can suppress weed growth.	
Stone Layer	Clean, aggregate with a maximum diameter of 3.5 inc inches.	thes and a minimum diameter of 1.5	
Observation Well	Install a vertical 6-inch Schedule 40 PVC perforated pipe, with a lockable cap and anchor plate.	Install one per 50 feet of length of infiltration practice.	
Overflow Collection Pipe (optional)	Use 4- or 6-inch rigid schedule 40 PVC pipe, with three or four rows of 3/8-inch perforations at 6 inches on center. Install a 6- to 8-inch sand layer (e.g., ASTM C-33, 0.02-0.04 inch in diameter) An appropriate geotextile fabric that complies with AASHTO M-288 Class 2, latest edition, requirements and has a permeability of at least an order of magnitude (10 times) higher (10x)-than the soil subgrade permeability must be used.		
Trench Bottom			
Geotextile Fabric (sides only)			

Practice Sizing. The proper approach for designing infiltration practices is to avoid forcing a large amount of infiltration into a small area. Therefore, individual infiltration practices that are limited in size due to soil permeability and available space need not be sized to achieve the full

design storm volume (SWRv) for the contributing drainage areaCDA, as long as other stormwater treatment practices are applied at the site to meet the remainder of the design storm volume.

Several equations (see following page) are needed to size infiltration practices. The first equations establish the maximum depth of the infiltration practice, depending on whether it is a surface basin (Equation $3.9\underline{11}$) or trench with an underground reservoir (Equation $3.\underline{1012}$).

Equation 3.11 Maximum Surface Basin Depth for Infiltration Basins

$$d_{max} = \frac{\frac{i}{2}K_{sat} \times t_d}{2}$$

Equation 3.12 Maximum Underground Reservoir Depth for Infiltration Trenches

$$d_{max} = \frac{i/2 \times t_{a}}{\eta_{\mp}}$$

$$\frac{(K_{sat} \times t_d)}{\eta_r}$$

where:

 d_{max} = maximum depth of the infiltration practice (ft)

 $i\underline{K}_{sat}$ = field-verified (actual) infiltration rate saturated hydraulic conductivity for the

native soils (ft/day)

 t_d = maximum drawdown time (day) (normally 3 days)

 η_r = available porosity of the stone reservoir (assume 0.354)

These equations make the following design assumptions:

- Conservative Infiltration Rates. For design purposes, the field tested subgrade soil infiltration rate (i) is divided by 2 as a factor of safety to account for potential compaction during construction and to approximate long term infiltration rates. On site infiltration investigations must be conducted to establish the actual infiltration capacity of underlying soils, using the methods presented in Appendix O.
- Stone Layer Porosity. A porosity value of 0.354 shall be used in the design of stone reservoirs, although a larger value may be used if perforated corrugated metal pipe, plastic pipe, concrete arch pipe, or comparable materials are installed within the reservoir.
- **Rapid Drawdown.** Infiltration practices must be sized so that the design volume infiltrates within 72 hours, to prevent nuisance ponding conditions.

Designers should compare these results to the maximum allowable depths in Table 3.3231 and use whichever value is less for the subsequent design.

Table 3.19 Maximum Facility Depth for Infiltration Practices

	Scale of Infiltration			
Mode of Entry	Micro Infiltration (250–2,500 ft²)	Small Scale Infiltration (2,500–20,000 ft²)	Conventional Infiltration (20,000–100,000 ft²)	
Surface Basin	1.0	1.5	2.0	
Underground Reservoir	3.0	5.0	varies	

Once the maximum depth is known, calculate the surface area needed for an infiltration practice using Equation 3.1113 or Equation 3.1214.

Equation 3.13 Surface Basin Surface Area for Infiltration Basins

$$SA = \frac{DesignStorm \times S}{d + (i \times t_f)}$$

$$SA = \frac{DesignStorm}{d + (K_{sat} \times t_f)}$$

Equation 3.14 Underground Reservoir Surface Area for Infiltration Trenches

$$SA = \frac{DesignStorm}{(\eta_{x} \times d) + (0.5 \times i/2 \times t_{f})}$$

$$SA = \frac{DesignStorm}{(\eta_{r} \times d) + (0.5 \times K_{sat} \times t_{f})}$$

where:

SA = surface area (ft²)
DesignStorm = SWRv or other design storm volume (ft³)
(e.g., portion of the SWRv)

 η_r = available porosity of the stone reservoir (assume 0.354) d = infiltration depth (ft) (maximum depends on the scale of infiltration and the results of Equation 3.911 or 3.1012)

$i\underline{K}_{sat}$	=	field-verified (actual) infiltration ratesaturated hydraulic
		<u>conductivity</u> for the native soils (ft/day)
tf	=	time to fill the infiltration facility (days)
		(typically 2 hours, or 0.083 days)

The storage volume (Sv) captured by the infiltration practice is defined as the volume of water that is fully infiltrated through the practice (<u>i.e.</u>, no overflow). Designers may choose to infiltrate less than the full design storm (SWRv). In this case, the design volume captured must be treated as the <u>storage volume</u>, Sv of the practice (see Section 3.8.8 Infiltration Stormwater Compliance Calculations). Sv can be determined by rearranging Equation 3.4413 and Equation 3.4214 to yield Equation 3.13 and Equation 3.15 and Equation 3.16.

Equation 3.15 Storage Volume Calculation for Surface Basin Area for Infiltration Basins

$$Sv = SA \times [d + (i/2 \times t_f)]Sv = SA \times [d + (K_{sat} \times t_f)]$$

Equation 3.16 Storage Volume Calculation for Underground Reservoir Surface Area for Infiltration Trenches

$$Sv = SA \times [(\eta_x \times d) + (i/2 \times t_f)]Sv = SA \times [(\eta_x \times d) + (K_{sat} \times t_f)]$$

Infiltration practices can also be designed to address, in whole or in part, the detention storage needed to comply with channel protection and/or flood control requirements. The designer can model various approaches by factoring in storage within the stone aggregate layer, any perforated corrugated metal pipe, plastic pipe, concrete arch pipe, or comparable materials installed within the reservoir, expected infiltration, and any outlet structures used as part of the design. Routing calculations can also be used to provide a more accurate solution of the peak discharge and required storage volume.

3.8.5 Infiltration Landscaping Criteria

Infiltration trenches can be effectively integrated into the site plan and aesthetically designed with adjacent native landscaping or turf cover, subject to the following additional design considerations:

Infiltration practices should not be installed until all up-gradient construction is completed
and pervious areas are stabilized with dense and healthy vegetation, unless the practice can
be kept off-line so it receives no runoff until construction and stabilization is complete.

 Vegetation associated with the infiltration practice buffers should be regularly maintained to limit organic matter in the infiltration device and maintain enough vegetation to prevent soil erosion from occurring.

3.8.6 Infiltration Construction Sequence

Infiltration practices are particularly vulnerable to failure during the construction phase for two reasons. First, if the construction sequence is not followed correctly, construction sediment can clog the practice. <u>In additionSecond</u>, loading from heavy construction equipment can result in compaction of the soil, which can then reduce the soil's infiltration rate. For this reason, a careful construction sequence needs to be followed.

During site construction, the following protective measures are absolutely critical:

- All areas proposed for infiltration practices should be fully protected from sediment intrusion by silt fence or construction fencing, particularly if they are intended to infiltrate runoff.
- Avoid excessive compaction by preventing construction equipment and vehicles from traveling over the proposed location of the infiltration practice. To accomplish this, areas intended to infiltrate runoff must remain outside the https://limits.com/limits/limits of disturbance during construction.
- When this is unavoidable, there are several possible outcomes emedies for the impacted area.
 - ◆ If excavation at the impacted area can be restricted, then remediation can be achieved with deep tilling practices. This is only possible if in-situ soils are not disturbed below 2 feet above the final design elevation of the bottom of the infiltration practice. In this case, when heavy equipment activity has ceased, the area is excavated to grade, and the impacted area must be tilled a minimum of 12 inches (30 cm) below the bottom of the infiltration practice.
 - ◆ Alternatively, if it is infeasible to keep the proposed infiltration practice outside of the limits of disturbance, and excavation of the area cannot be restricted, then infiltration tests will be required prior to installation of the permeable pavementinfiltration practice to ensure that the design infiltration rate is still present. If tests reveal the loss of design infiltration rates, then deep tilling practices may be used in an effort to restore those rates. In this case further testing must be done to establish design rates exist before the infiltration practice can be installed.
 - Finally, if it is infeasible to keep the proposed permeable pavement areas outside of the limits of disturbance, and excavation of the area cannot be restricted, and infiltration tests reveal design rates cannot be restored, then a resubmission of the SWMP will be required.
- Any area of the site intended ultimately to be an infiltration practice must_should not be used as the site of a temporary sediment trap or basin. If locating a sediment trap or basin on an area intended for infiltration is unavoidable, the outcomesremedies are parallelsimilar to those discussed for heavy equipment compaction. If it is possible to: restrict the invert of the sediment trap or basin to: at least 2 feet above the final design elevation of the bottom of the proposed infiltration practice then remediation can be achieved with proper removal of

trapped sediments and deep tilling practices. An alternate approach to deep tilling is to use an impermeable linear to protect the in-situ soils from sedimentation while the sediment trap or basin is in use. In each case, all sediment deposits must <u>be</u> carefully removed prior to installing the infiltration practice.

- Keep the infiltration practice "off-line" until construction is complete. Prevent sediment from entering the infiltration site by using super silt fence, diversion berms, or other means. In the soil erosion and sediment control plan, indicate the earliest time at which stormwater runoff may be directed to a conventional infiltration basin. The soil erosion and sediment control plan must also indicate the specific methods to be used to temporarily keep runoff from the infiltration site.
- Upland drainage areasCDAs need to be completely stabilized with a well-established layer of vegetation prior to commencing excavation for an infiltration practice.

Infiltration Installation. The actual installation of an infiltration practice is done using the following steps:

- **Step 1:** Avoid Impact of Heavy Installation Equipment. Excavate the infiltration practice to the design dimensions from the side using a backhoe or excavator. The floor of the pit should be completely level, but equipment should be kept off the floor area to prevent soil compaction.
- Step 2: Hang Geotextile Walls. Install geotextile fabric on the trench sides. Large tree roots should be trimmed flush with the sides of infiltration trenches to prevent puncturing or tearing of the geotextile fabric during subsequent installation procedures. When laying out the geotextile, the width should include sufficient material to compensate for perimeter irregularities in the trench and for a 6-inch minimum overlap at the top of the trench. The geotextile fabric itself should be tucked under the sand layer on the bottom of the infiltration trench. Stones or other anchoring objects should be placed on the fabric at the trench sides, to keep the trench open during windy periods. Voids may occur between the fabric and the excavated sides of a trench. Natural soils should be placed in all voids, to ensure the fabric conforms smoothly to the sides of excavation.
- *Step 3:* **Promote Infiltration Rate.** Scarify the bottom of the infiltration practice, and spread 6 inches of sand on the bottom as a filter layer.
- **Step 4:** Observation Wells. Anchor the observation well(s) and add stone to the practice in 1-foot lifts.
- **Step 5: Stabilize Surrounding Area.** Use sod, where applicable, to establish a dense turf cover for at least 10 feet around the sides of the infiltration practice, to reduce erosion and sloughing.

Construction Supervision. Supervision during construction is recommended to ensure that the infiltration practice is built in accordance with the approved design and this specification. Qualified individuals should use detailed inspection checklists to include sign-offs at critical stages of construction, to ensure that the contractor's interpretation of the plan is consistent with the designer's intentions.

DDOE's DOEE's construction phase inspection checklist for infiltration practices can be found in Appendix K-, "Construction Inspection Checklists."

3.8.7 Infiltration Maintenance Criteria

Maintenance is a crucial and required element that ensures the long-term performance of infiltration practices. The most frequently cited maintenance problem for infiltration practices is clogging of the stone <u>layer</u> by organic matter and sediment. The following design features can minimize the risk of clogging:

Stabilized CDA. Infiltration systems may not receive runoff until the entire contributing drainage area CDA has been completely stabilized.

Observation Well. Infiltration practices must include an observation well, consisting of to facilitate periodic inspection and maintenance. Design criteria must include an anchored 6-inch diameter perforated PVC pipe fitted with a lockable cap installed flush with the ground surface, to facilitate periodic inspection and maintenance.

No Geotextile Fabric on Bottom. Avoid installing geotextile fabric along the bottom of infiltration practices. Experience has shown that geotextile fabric is prone to clogging. However, permeable geotextile fabric should be installed on the trench sides to prevent soil piping.

Direct Maintenance Access. Access must be provided to allow personnel and heavy equipment to perform atypical maintenance tasks, such as practice reconstruction or rehabilitation. While a turf cover is permissible for small-scale infiltration practices, the surface must never be covered by an impermeable material, such as asphalt or concrete.

Maintenance Inspections. Effective long-term operation of infiltration practices requires a dedicated and routine maintenance inspection schedule with clear guidelines and schedules, as shown in Table 3.33 below32. Where possible, facility maintenance should be integrated into routine landscaping maintenance tasks.

Table 3.20 Typical Maintenance Activities for Infiltration Practices

Schedule	Maintenance Activity		
Quarterly	 Ensure that the contributing drainage area CDA, inlets, and facility surface are clear of debris. Ensure that the contributing drainage area CDA is stabilized. Perform spot-reseeding if where needed. Remove sediment and oil/grease from inlets, pretreatment devices, flow diversion structures, and overflow structures. Repair undercut and eroded areas at inflow and outflow structures. 		
Semi-annual inspection	 Check observation wells 3 days after a storm event in excess of ±/20.5 inch in depth. Standing water observed in the well after three3 days is a clear indication of clogging. Inspect pretreatment devices and diversion structures for sediment build-up and structural damage. 		
Annually	Clean out accumulated sediment from the pretreatment cell.		
As needed	 Replace pea gravel/topsoil and top surface geotextile fabric (when clogged). Mow vegetated filter strips as necessary and remove the clippings. 		

It is highly recommended that a qualified professional conduct annual site inspections for infiltration practices to ensure the practice performance and longevity of infiltration practices.

 $\frac{\text{DDOE's} \text{DOEE's}}{\text{SDOEE's}} \ \text{maintenance inspection checklist for infiltration systems and the Maintenance} \\ \text{Service Completion Inspection form can be found in Appendix L}_{\tau,} \ \text{"Maintenance Inspection} \\ \text{Checklists."}$

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C of the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District of Columbia law.

3.8.8 Infiltration Stormwater Compliance Calculations

Infiltration practices receive 100-percent <u>%</u> retention value for the amount of storage volume (Sv) provided by the practice (Table 3.3433). Since the practice gets 100-percent <u>%</u> retention value, it is not considered an accepted total suspended solids (TSS) treatment practice.

Table 3.21 Infiltration Retention Value and Pollutant Removal

Retention Value	=Sv	
Accepted TSS Treatment Practice	N/A	

The practice must be sized using the guidance detailed in Section 3.8.4—. "Infiltration Design Criteria."

Infiltration practices also contribute to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the storage volume (Sv-or Retention Value) from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced NRCS) Curve Number CN for the site or drainage area.SDA. The Reduced Curve Number-reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.8.9 References

Virginia DCR Stormwater Design Specification No. 8: Bioretention Version 1.8. 2010.

3.9 Open Channel Systems

Definition. Vegetated open channels that are designed to capture and treat or convey the design storm volume (Stormwater Retention Volume (SWRv)). Design variants include the following:

- O-1 Grass channels
- O-2 Dry swales/bioswales
- O-3 Wet swales

Open channel systems shall not be designed to provide stormwater detention except under extremely unusual conditions. Open channel systems must generally be combined with a separate facility to meet these requirements.

Grass channels (O-1) can provide a modest amount of runoff filtering and volume attenuation within the stormwater conveyance system resulting in the delivery of less runoff and pollutants than a traditional system of curb and gutter, storm drain inlets, and pipes-(see Figure 3.35). The performance of grass channels will vary depending on the underlying soil permeability. Grass channels, however, are not capable of providing the same stormwater functions as dry swales as they lack the storage volume associated with the engineered soilfilter media. Their retention performance can be boosted when compost amendments are added to the bottom of the swale (see Appendix J)-, "Soil Compost Amendment Requirements"). Grass channels are a preferable alternative to both curb and gutter and storm drains as a stormwater conveyance system, where development density, topography, and soils permit.

Dry swales (O-2), also known as bioswales, are essentially bioretention cells that are shallower, configured as linear channels, and covered with turf or other surface material (other than mulch and ornamental plants: see Figure 3.36). The dry swale is a soil filter system that temporarily stores and then filters the desired design storm volume. Dry swales rely on a premixed soil media filter media below the channel that is similaridentical to that used for bioretention. If soils are extremely permeable, runoff infiltrates into underlying soils. In most cases, however, the runoff treated by the soilfilter media flows into an underdrain, which conveys treated runoff back to the conveyance system further downstream. The underdrain system consists of a perforated pipe within a gravel layer on the bottom of the swale, beneath the filter media. However, if soils are permeable, runoff infiltrates into underlying soils and the dry swale can be designed without an underdrain as if it were an enhanced bioretention. In either case, check dams should be constructed to encourage ponding (see Site Topography). Dry swales may appear as simple grass channels with the same shape and turf cover, while others may have more elaborate landscaping. Swales can be planted with turf grass, tall meadow grasses, decorative herbaceous cover, or trees.

Wet swales (O-3) can provide a modest amount of runoff filtering within the conveyance-(see Figure 3.37). These linear wetland cells often intercept shallow groundwater to maintain a wetland plant community. The saturated soil and wetland vegetation provide an ideal environment for gravitational settling, biological uptake, and microbial activity. On-line or off-line cells are formed within the channel to create saturated soil or shallow standing water conditions (typically less than 6 inches deep).




Figure 3.343.353.34.35 Grass channel typical plan, profile, and section views (O-1).




Figure 3.353.363.35.36 Example of a dry swale (O-2).




Figure 3.363.373.36.37 Example of a wet swale (O-3).

3.9.1 Open Channel Feasibility Criteria

Open channel systems are primarily applicable for land uses, such as roads, highways, and residential development. Some key feasibility issues for open channels include the following:

Contributing Drainage Area. The maximum contributing drainage areaCDA to an open channel should be 2.5 acres, preferably less. When open channels treat and convey runoff from drainage areasCDAs greater than 2.5 acres, the velocity and flow depth through the channel often becomes too great to treat runoff or prevent erosion in the channel. The design criteria for maximum channel velocity and depth are applied along the entire length (see Section 3.9.4 Open Channel Design Criteria). Dry Swales should be approximately 3%–10% of the size of the CDA, depending on the amount of impervious cover. Wet swale footprints usually cover about 5%–15% of their CDA.

Available Space. Open channel footprints can fit into relatively narrow corridors between utilities, roads, parking areas, or other site constraints. Dry Swales should be approximately 3 to 10 percent of the size of the contributing drainage area, depending on the amount of impervious cover. Wet swale footprints usually cover about 5 to 15 percent of their contributing drainage area. Grass channels can be incorporated into linear development applications (e.g., roadways) by utilizing the footprint typically required for an open section drainage feature. The footprint required will likely be greater than that of a typical conveyance channel. However, the benefit of the retention may reduce the footprint requirements for stormwater management elsewhere on the development site.

Site Topography. Grass channels and wet swales should be used on sites with longitudinal slopes of less than 4-percent. Check dams can be used to reduce the effective slope of the channel and lengthen the contact time to enhance filtering and/or infiltration. Longitudinal slopes of less than 2-percent are ideal and may eliminate the need for check dams. However, channels designed with longitudinal slopes of less than 1-percent should be monitored carefully during construction to ensure a continuous grade, in order to avoid flat areas with pockets of standing water.

For dry swales, check dams will be necessary regardless of the longitudinal slope to create the necessary ponding volume. Check dams must be constructed of a solid material that will allow ponding.

Land Uses. Open channels can be used in residential, commercial, or institutional development settings.

When open channels are used for both conveyance and water quality treatment, they should be applied only in linear configurations parallel to the contributing impervious cover, such as roads and small parking areas. The linear nature of open channels makes them well-suited to treat highway or low- and medium-density residential road runoff, if there is adequate right-of-way width and distance between driveways. Typical applications of open channels include the following, as long as drainage areaCDA limitations and design criteria can be met:

- Within a roadway or bicycle path right-of-way;
- Along the margins of small parking lots;
- Oriented from the roof (downspout discharge) to the street.
- Disconnecting small impervious areas; and
- Used to treat the managed turf areas of <u>parkland</u> sports fields, golf courses, and other turfintensive land uses, or to treat <u>drainage areasCDAs</u> with both impervious and managed turf cover (such as residential streets and yards).

Open channels are not recommended when residential density exceeds more than 4 dwelling units per acre, due to a lack of available land and the frequency of driveway crossings along the channel.

Open channels can also provide pretreatment for other stormwater treatment practices.

Available Hydraulic Head. A minimum amount of hydraulic head is needed to implement open channels in order to ensure positive drainage and conveyance through the channel. The hydraulic head for wet swales and grass channels is measured as the elevation difference between the channel inflow and outflow point. The hydraulic head for dry swales is measured as the elevation difference between the inflow point and the storm drain invert_? (unless an infiltration-based design will be used). Dry swales typically require 3 to 5 feet of hydraulic head since they have both a filter bed and underdrain.

Hydraulic Capacity. Open channels are typically designed as on-line practices which that must be designed with enough capacity to (1) convey runoff from the 2-year and 15-year design

storms at non-erosive velocities, and (2) contain the 15-year flow within the banks of the swale. This means that the swale's surface dimensions are more often determined by the need to pass the 15-year storm events, which can be a constraint in the siting of open channels within existing rights-of-way (e.g., constrained by sidewalks).

Depth to Water Table. The bottom of dry swales and grass channels must be at least 2 feet above the seasonally high groundwater table, to ensure that groundwater does not intersect the filter bed, since this could lead to groundwater contamination or practice failure. It is permissible for wet swales to intersect the water table.

Soils. Soil conditions do not constrain the use of open channels, although they do dictate some design considerations:

- Dry swales in soils with <u>low</u> infiltration rates of <u>less than 1/2 inch per hour</u> may need an underdrain. Designers must verify site-specific soil permeability at the proposed location using the methods for on-site soil investigation presented in Appendix O <u>Geotechnical Information Requirements for Underground BMPs</u>, in order to eliminate the requirements for a dry swale underdrain.
- Grass channels situated on low-permeability soils may incorporate compost amendments in order to improve performance (see Appendix J)-, "Soil Compost Amendment Requirements").
- Wet swales work best on the more impermeable Hydrologie Soil Group (HSG) C or D soils.
- Infill At infill soil locations, geotechnical investigations are required to determine if the use of an impermeable liner and underdrain are necessary for open channel designs.

Utilities. Typically, utilities can cross linear channels if they are specially protected (e.g., double-casing). Interference with underground utilities should be avoided, if possible. When large site development is undertaken, the expectation of achieving avoidance will be high. Conflicts may be commonplace on smaller sites and in the <u>public right of way.PROW.</u> Where conflicts cannot be avoided, these guidelines shall be followed:

- Consult with each utility company on recommended offsets that will allow utility maintenance work with minimal disturbance to the BMP.
- Whenever possible, coordinate with utility companies to allow them to replace or relocate their aging infrastructure while BMPs are being implemented.
- BMP and utility conflicts will be a common occurrence in public right of wayPROW projects. However, the standard solution to utility conflict should be the acceptance of conflict provided sufficient soil coverage over the utility can be assured.
- Additionally, when accepting utility conflict into the BMP design, it is understood that the BMP will be temporarily impacted during utility maintenance but restored to its original condition.

Avoidance of Irrigation or Baseflow. Open channels should be located so as to avoid inputs of springs, irrigation systems, chlorinated wash-water, or other dry weather flows.

Setbacks. To avoid the risk of seepage, stormwater cannot flow from the open channels must not be hydraulically connected channel reservoir layer or via baseflow to the traditional pavement base layer, existing structure foundations, or an area where there may be future development adjacent to the property line. Setbacks to structures and property lines must be at least 10 feet and adequate water proofing waterproofing protection must be provided for foundations and basements.

Hotspot Land Use. Runoff from hotspot land uses must not be treated with infiltrating dry swales due to the potential interaction with the water table and the risk that hydrocarbons, trace metals, and other toxic pollutants could migrate into the groundwater. An impermeable liner must be used for filtration of hotspot runoff for dry swales. Grass channels can typically be used to convey runoff from stormwater hotspots, but they do not qualify as a hotspot treatment mechanism. Wet swales are not recommended to treat stormwater hotspots, due to the potential interaction with the water table and the risk that hydrocarbons, trace metals, and other toxic pollutants could migrate into the groundwater. For a list of designated stormwater hotspot operations, consult Appendix P Stormwater Hotspots.

On sites with existing contaminated soils, as indicated in Appendix P, "Stormwater Hotspots," infiltration is not allowed. Dry and wet swales must include an impermeable liner.

3.9.2 Open Channel Conveyance Criteria

The bottom width and slope of a grass channel must be designed such that the velocity of flow from the design storm provides a minimum hydraulic residence time (average travel time for a particle of water through a waterbody) of 9 minutes for the peak flows from the SWRv or design storm. Check dams may be used to achieve the needed retention volume, as well as to reduce the flow velocity. Check dams must be spaced based on channel slope and ponding requirements, consistent with the criteria in Section 3.9.4-_"Open Channel Design Criteria-_"

Open channels must also convey the 2- and 15-year storms at non-erosive velocities (generally less than 6 fpsfeet per second) for the soil and vegetative cover provided. The final designed channel shall provide 1 foot 6 inches minimum freeboard above the designated water surface profile of the channel. The analysis must evaluate the flow profile through the channel at normal depth, as well as the flow depth over top of the check dams.

3.9.3 Open Channel Pretreatment Criteria

Pretreatment is required for open channels to dissipate energy, trap sediments, and slow down the runoff velocity.

The selection of a pretreatment method depends on whether the channel will experience sheet flow or concentrated flow. Several options are as follows:

■ Check Dams (channel flow). These energy dissipation devices are acceptable as pretreatment on small open channels with <u>drainage areasCDAs</u> of less than 1 acre. The most common form is the use of wooden or stone check dams. The pretreatment volume stored must be 15-<u>percent%</u> of the design volume.

- Tree Check Dams (channel flow). These are street tree mounds that are placed within the bottom of grass channels up to an elevation of 9 to 12 inches above the channel invert. One side has a gravel or river stone bypass to allow runoff to percolate through (Cappiella et al, 2006). The pretreatment volume stored must be 15 percent of the design volume.
- **Grass Filter Strip** (sheet flow). Grass filter strips extend from the edge of the pavement to the bottom of the open channel at a slope of 5:15H:1V or flatter. Alternatively, provide a combined 5 feet of grass filter strip at a maximum 5 percent (20:1½ (20H:1V) cross slope and 3:13H:1V or flatter side slopes on the open channel.
- **Gravel or Stone Diaphragm (sheet flow).** The gravel diaphragm is located at the edge of the pavement or the edge of the roadway shoulder and extends the length of the channel to pretreat lateral runoff. This requires a 2₋ to 4--inch elevation drop from a hard-edged surface into a gravel or stone diaphragm. The stone must be sized according to the expected rate of discharge.
- Gravel or Stone Flow Spreaders (concentrated flow). The gravel flow spreader is located at curb cuts, downspouts, or other concentrated inflow points, and should have a 2₋ to 4₋inch elevation drop from a hard-edged surface into a gravel or stone diaphragm. The gravel should extend the entire width of the opening and create a level stone weir at the bottom or treatment elevation of the channel.
- Initial Sediment Forebay (channel flow). This grassed cell is located at the upper end of the open channel segment with a recommended 2:1 length to width ratio and a storage volume equivalent to at least 15-percent% of the total design storm volume. If the volume of the forebay will be included as part of the dry swale storage volume, the forebay must de-water between storm events. It cannot have a permanent ponded volume.

3.9.4 Open Channel Design Criteria

Channel Geometry. Design guidance regarding the geometry and layout of open channels is provided below:

- Open channels should generally be aligned adjacent to and the same length as the contributing drainage areaCDA identified for treatment.
- Open channels should be designed with a trapezoidal or parabolic cross section. A parabolic shape is preferred for aesthetic, maintenance, and hydraulic reasons.
- The bottom width of the channel should be between 4 to 8 feet wide to ensure that an adequate surface area exists along the bottom of the swale for filtering. If a channel will be wider than 8 feet, the designer must incorporate benches, check dams, level spreaders, or multi-level cross sections to prevent braiding and erosion along the channel bottom.
- Open-channel side slopes should be no steeper than 3H:1V for ease of mowing and routine
 maintenance. Flatter slopes are encouraged, where adequate space is available, to enhance
 pretreatment of sheet flows entering the channel.

Check dams. Check dams may be used for pretreatment, to break up slopes, and to increase the hydraulic residence time in the channel. Design requirements for check dams are as follows:

- Check dams should be spaced based on the channel slope, as needed to increase residence time, provide design storm storage volume, or any additional volume attenuation requirements. In typical spacing, the ponded water at a downhill check dam should not touch the toe of the upstream check dam. More frequent spacing may be desirable in dry swales to increase the ponding volume.
- The maximum desired check dam height is 12 inches, for maintenance purposes. However, for some sites, a maximum of 18 inches can be allowed, with additional design elements to ensure the stability of the check dam and the adjacent and underlying soils. The average ponding depth throughout the channel should be 12 inches.
- Armoring may be needed at the downstream toe of the check dam to prevent erosion.
- Check dams must be firmly anchored into the side-slopes to prevent outflanking; check dams must also be anchored into the channel bottom so as to prevent hydrostatic head from pushing out the underlying soils.
- Check dams must be designed with a center weir sized to pass the channel design storm peak flow (15-year storm event for man-made channels).
- For grass channels, each check dam must have a weep hole or similar drainage feature so it can dewater after storms. This is not appropriate for dry swales.
- Check dams should be composed of wood, concrete, stone, compacted soil, or other nonerodible material, or should be configured with elevated driveway culverts.
- Individual channel segments formed by check dams or driveways should generally be at least 25 to 40 feet in length.

Check dams for grass channels must be spaced to reduce the effective slope to less than 2 percent, %, as indicated below-in Table 3.3534.

Table 3.22 Typical Check Dam Spacing to Achieve Effective Channel Slope

Channel Longitudinal Slope	Check Dam ^{a, b} Spacing ^c to Achieve Effective Slope (ft)		
(%)	Effective Slope of 2%	Effective Slope of 0%–1%	
0.5	<u> </u>	200-	
1.0	-	100-	
1.5	-	67–200	
2.0	_	50–100	
2.5	200	40–67	
3.0	100	33–50	
3.5	67	30–40	
4.0	50	25–33	
4.5 ^d	40	20–30	
5.0 ^d	40	20–30	

^a All check Check dams may require a stone energy dissipater dissipator at the downstream toe.

^b Check dams require weep holes at the channel invert. Swales with slopes less than 2-percent% will require

- multiple weep holes (at least 3) in each check dam.
- ^c Maximum check dam spacing height is 12 inches. The spacing dimension is half of the above distances if a 6-inch check dam is used.
- ^d Open channels with slopes greater than 4-percent% require special design considerations, such as drop structures to accommodate greater than 12-inch high check dams (and therefore a flatter effective slope), in order to ensure non-erosive flows.

Ponding Depth. Check dams must be used in dry swales to create ponding cells along the length of the channel. The maximum ponding depth in a dry swale must not exceed 18 inches. Minimum surface ponding depth is 3 inches (averaged over the surface area of the open channel). In order to increase the ponding depth, it may be necessary or desirable to space check dams more frequently than is shown in Table 3.35.

Dry Swale Filter Media. Dry swales require replacement of native soils with a prepared filter media. The soilfilter media provides adequate drainage, supports plant growth, and facilitates pollutant removal within the dry swale. At least 18 inches of filter media must be added above the choker stone layer (and no more than 6 feet) to create an acceptable filter. The recipe for the filter media is identical to that used for bioretention and is provided in Section 3.6-, "Bioretention-," The batch receipt confirming the source of the filter media must be submitted to the DDOEDOEE inspector. One acceptable design adaptation is to use 100 percent% sand for the first 18 inches of the filter and add a combination of topsoil and compost, as specified in Appendix J, "Soil Compost Amendment Requirements," for the top 4 inches, where turf cover will be maintained.

Dry Swale Drawdown. Dry swales must be designed so that the desired design storm volume is completely filtered within 72 hours, using the equations specified in Section 3.9.6₇, "Open Channel Construction Sequence."

Dry Swale Underdrain. Some dry swale designs will not use an underdrain (where soil infiltration rates meet minimum standards). See Section 3.9.1 Open Channel Feasibility Criteria for more details. When underdrains are necessary, they should have a minimum diameter of 4 to 6 inches and be encased in a 12-inch deep gravel bed. Two layers of stone should be used. A choker stone layer, consisting of #No. 8 or #78No. 89 stone at least 3 inches deep, must be installed immediately below the filter media. Below the choker stone layer, the underdrain must be encased (a minimum of 2 inches above and below the underdrain) in a layer of clean, double—washed ASTM D448 No.57 or smaller (No. 68, 8, or 89) stone. The maximum depth of the underdrain stone layer combined with the choking layer is 12 inches, and it cannot extend beyond the surface dimensions of the dry swale filter media.

Impermeable Liner. An impermeable liner is not typically required, although it may be utilized in fill applications where deemed necessary by a geotechnical investigation, on sites with contaminated soils, or on the sides of the practice to protect adjacent structures from seepage. Use a 30 mil (minimum) PVC geomembrane liner. (Follow or an equivalent of an appropriate thickness (follow manufacturer's instructions for installation.). Field seams must be sealed according to the liner manufacturer's specifications. A minimum 6-inch overlap of material is required at all seams.

Dry Swale Observation Well. A dry swale must include well-anchored, 4- to 6-inch diameter PVC pipe observation wells with cleanout pipes along the length of the swale. The For a dry swale with an underdrain, the wells should be tied into any Ts or Ys in the underdrain system and must extend upward above the surface of the dry swale ponding. These observation wells may double as clean outs. For an infiltrating dry swale, the observation well should be perforated in the gravel layer only.

Grass Channel Material Specifications. The basic material specifications for grass channels are outlined in Table 3.36 below 35.

Table 3.23 Grass Channel Material Specifications

Component		
Component	Specification	
A dense cover of water-tolerant, erosion-resistant grass. The selection of an appr species or mixture of species is based on several factors including climate, soil topography, and sun or shade tolerance. Grass species should have the following characteristics: A deep root system to resist scouring; A high stem density with well-branched top growth; Water-tolerance; Resistance to being flattened by runoff; An ability to recover growth following inundation; and If receiving runoff from roadways, salt-tolerance.		
Check Dams	Check dams should be constructed of a non-erodible material such as wood, gabions, riprap, or concrete. Wood used for check dams should consist of pressure-treated logs or timbers or water-resistant tree species such as cedar, hemlock, swamp oak, or locust. Computation of check dam material is necessary, based on the surface area and depth used in the design computations.	
Diaphragm	Pea gravel used to construct pretreatment diaphragms must consist of washed, open-graded, course aggregate between 3 and 10 mm in diameter.	
Erosion Control Fabric	Where flow velocities dictate, biodegradable erosion control netting or mats that are durable enough to last at least two growing seasons must be used, conforming to Standard and Specification 3.36 of the Virginia Erosion and Sediment Control Handbook.	

Dry Swale Material Specifications. For additional material specifications pertaining to dry swales, designers should consult Section 3.6.4 <u>Bioretention Design Criteria</u> and Table 3.37 <u>below36</u>.

Table 3.24 Dry Swale Material Specifications

Material	Specification	Notes
Filter Media Composition	Filter Media to contain: 80-%—90% sand 10-%—20% soil fines Maximum 10% clay 3-%—5% organic matter	To account for settling/compaction, it is recommended that 110% of the plan volume be utilized.
Filter Media Testing	P content = 5 to 15 mg/kg (Mehlich I) or 18 to 40 mg/kg (Mehlich III) CEC > 5 milliequivalents per 100 grams	See Section 3.6 Bioretention, for additional soil filter media information.
Geotextile	Geotextile fabric meeting the following specifications: AASHTO M-288 Class 2, latest edition Has a permeability of at least an order of magnitude (10 times) higher (10x) than the soil subgrade permeability. Apply along sides of the filter media only and do not apply along the swale bottom.	
Choking Layer	above the underdrain stone.	ally #No. 8 or #No. 89 washed gravel) laid
Underdrain Stone Layer	Stone must be double-washed and clean ar smaller stone).	nd free of all fines (ASTM D448 No. 57 or
Underdrains, and Cleanouts, and Observation Wells	4-inch or 6-inch rigid schedule 40 PVC pipe, with 3 or 4 rows of 3/8-inch perforations at 6 inches on center. Install perforated pipe for the full letter bry Swale cell. Use non-perforated pipe, as needed connect with the storm drain system.	
Observation Wells	4-inch or 6-inch rigid schedule 40 PVC pipe	For dry swales with underdrains, tie the non-perforated observation well to the underdrain via T or Y connection. This observation well can double as a cleanout. For dry swales without an underdrain, the pipe should only be perforated in the gravel layer. The observation wells should extend to the top of ponding.
Impermeable Liner	Where appropriate, use a thirty min (minimum) PVC Geomembrane geomembrane liner or equivalent. Plant species as specified on the landscaping plan. Use non-erosive material, such as wood, gabions, riprap, or concrete. Wood used for check dams should consist of pressure-treated logs or timbers, or water-resistant tree species, such as cedar, hemlock, swamp oak, or locust. Where flow velocities dictate, use woven biodegradable erosion control fabric or mats (EC2) that are durable enough to last at least 2 growing seasons.	
Vegetation		
Check Dams		
Erosion Control Fabric		

Wet Swale Design Issues. The following criteria apply to the design of wet swales:

- The average normal pool depth (dry weather) throughout the swale must be 6 inches or less.
- The maximum temporary ponding depth in any single Wet Swale wet swale cell must not exceed 18 inches at the most downstream point (e.g., at a check dam or driveway culvert).
- Check dams should be spaced as needed to maintain the effective longitudinal slope.

- Individual Wet Swalewet swale segments formed by check dams or driveways should generally be at least 25 to 40 feet in length.
- Wet <u>Swaleswale</u> side slopes should be no steeper than 4H:1V to enable wetland plant growth. Flatter slopes are encouraged where adequate space is available, to enhance pretreatment of sheet flows entering the channel. Under no circumstances are side slopes to steeper than 3H:1V.

Grass Channel Enhancement using Compost Soil Amendments. Soil compost amendments serve to increase the retention capability of a grass channel. The following design criteria apply when compost amendments are used:

- The compost-amended strip must extend over the length and width of the channel bottom, and the compost must be incorporated to a depth as outlined in Appendix J., "Soil Compost Amendment Requirements."
- The amended area will need to be rapidly stabilized with perennial, salt—tolerant grass species— (if contributing impervious surfaces are likely to be salted).
- For grass channels on steep slopes, it may be necessary to install a protective biodegradable
 erosion control mat to protect the compost-amended soils. Care must be taken to consider the
 erosive characteristics of the amended soils when selecting an appropriate erosion control
 mat.

Grass Channel Sizing. Unlike other BMPs, grass channels are designed based on a peak rate of flow. Designers must demonstrate channel conveyance and treatment capacity in accordance with the following guidelines:

- Hydraulic capacity should be verified using Manning's Equation or an accepted equivalent method, such as erodibility factors and vegetal retardance.
- The flow depth for the peak flow generated by the SWRv must be maintained at 4 inches or less
- Manning's "n" value for grass channels is 0.2 for flow depths up to 4 inches, decreasing to 0.03 at a depth of 12 inches and above, which would apply to the 2-year and 15-year storms if an on-line application (Haan et. al., 1994).
- Peak flow rates for the 2-year and 15-year frequency storms must be non-erosive, in accordance with Table 3.3837 (see Section 3.9.5 Open Channel Landscaping Criteria), or subject to a site-specific analysis of the channel lining material and vegetation; and the 15-year peak flow rate must be contained within the channel banks (with a minimum of 6 inches of freeboard).
- Calculations for peak flow depth and velocity must reflect any increase in flow along the length of the channel, as appropriate. If a single flow is used, the flow at the outlet must be used.
- The hydraulic residence time (e.g., the average travel time for a particle of water through a waterbody) must be a minimum of 9 minutes for the peak flows from the SWRv or design storm (Mar et al., 1982; Barrett et al., 1998; Washington State Department of Ecology, 2005). If flow enters the swale at several locations, a 9-minute minimum hydraulic residence

time must be demonstrated for each entry point, using Equation $3.45\underline{17}$ through Equation 3.49 below 21.

The bottom width of the grass channel is therefore sized to maintain the appropriate flow geometry as follows:

Equation 3.17 Manning's Equation

$$V = \left(\frac{1.49}{n}\right) \times D^{2/3} \times S^{1/2}$$

$$V = (\frac{1.49}{n}) \times D^{2/3} \times S^{1/2}$$

where:

V = flow velocity (ft/s)

n = roughness coefficient (0.2, or as appropriate)

D = flow depth (ft) (Note: D approximates hydraulic radius for shallow flows)

S = channel slope (ft/ft)

Equation 3.18 Continuity Equation

$$Q = V \times (W \times D)$$

$$Q = V \times (W + 3 \times D) \times D$$

where:

Q = design storm peak flow rate (cfs)

V = design storm flow velocity (ft/s)

W = channel bottom width (ft)

D = flow depth (ft)

(Note: Channel width (W) plus 3 times the depth (D) represents the average width of a trapezoidal channel with 3H:1V side slopes. Average width multiplied by depth (D) approximates equals the cross-sectional flow area-for shallow flows.)

Combining Equation $3.45\underline{17}$ and Equation $3.46\underline{18}$, and rewriting rewriting them provides a solution for the minimum width: (Equation 3.19):

Equation 3.19 Minimum Width

$$W = \frac{n \times Q}{1.49 \times D^{5/3} \times S^{1/2}}$$

Solving
$$W = \frac{n \times Q}{1.49 \times D^{5/3} \times S^{1/2}} - (3 \times D)$$

where:

W = channel bottom width (ft)

 \underline{n} = roughness coefficient (0.2, or as appropriate)

Q = design storm peak flow rate (cfs)

D = flow depth (ft)

S = channel slope (ft/ft)

Equation 3.20 for provides the corresponding velocity-provides:

Equation 3.20 Corresponding Velocity

$$V = \frac{Q}{W \times D}$$

$$V = \frac{Q}{(W+3\times D)\times D}$$

where:

V = design storm flow velocity (ft/s)

Q = design storm peak flow rate (cfs)

W = channel bottom width (ft)

D = flow depth (ft)

The width, slope, or Manning's "n" value can be adjusted to provide an appropriate channel design for the site conditions. However, if a higher density of grass is used to increase the Manning's "n" value and decrease the resulting channel width, it is important to provide material specifications and construction oversight to ensure that the denser vegetation is actually established. Equation 3.4921 can then be used to ensure adequate hydraulic residence time.

Equation 3.21 Grass Channel Length for Hydraulic Residence Time of 9 minutes (540 seconds)

$$L = 540 \times V$$

$$L = 540 \times V$$

where:

L = minimum swale length (ft) V = flow velocity (ft/s)

The storage volume (Sv) provided by the grass channel is equal to the total runoff from the design storm (typically SWRv) used to size the channel (conveyed at a depth of 4 inches or less), as shown in Equation 3.22.

Equation 3.22 Grass Channel Storage Volume

Sv = DesignStorm

Sv = DesignStorm

where:

Dry Swale Sizing. Dry swales are typically sized to capture the SWRv or larger design storm volumes in the surface ponding area, soil <u>filter</u> media, and gravel reservoir layers of the dry swale.

Total storage volume of the BMP is calculated using Equation 3.2423.

Equation 3.23 Dry Swale Storage Volume

$$Sv = SA_{bottom} \times [(d_{media} \times \eta_{media}) + (d_{gravel} \times \eta_{gravel})] + (SA_{average} \times d_{ponding})$$

$$Sv = SA_{bottom} \times [(d_{media} \times \eta_{media}) + (d_{gravel} \times \eta_{gravel})] + (SA_{average} \times d_{ponding})$$

where:

Sv = total storage volume of dry swale (ft³) SA_{bottom} = bottom surface area of dry swale (ft²)

 d_{media} = depth of the filter media, including mulch layer (ft) η_{media} = effective porosity of the filter media (typically 0.25)

 d_{gravel} = depth of the underdrain and underground storage gravel layer.

including choker stone (ft)

 η_{gravel} = effective porosity of the gravel layer (typically 0.4) $SA_{average}$ = the average surface area of the dry swale (ft²)

typically, where
$$SA_{top}$$
 is the top surface area of bioretentiondry
$$\frac{\text{swale}}{\text{swale}}, SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$$

$$d_{ponding} = \text{the maximum ponding depth of the dry swale (ft)}$$

Equation 3.2423 can be modified if the storage depths of the soil<u>filter</u> media, gravel layer, or ponded water vary in the actual design or with the addition of any surface or subsurface storage components (e.g., additional area of surface ponding, subsurface storage chambers, etc.). The maximum depth of ponding in the dry swale must not exceed 18 inches. If storage practices will be provided off-line or in series with the dry swale, the storage practices should be sized using the guidance in Section 3.12-, "Storage Practices-."

Dry swales can be designed to address, in whole or in part, the detention storage needed to comply with channel protection and/or flood control requirements. The Sv can be counted as part of the 2-year or 15-year runoff volumes to satisfy stormwater quantity control requirements.

Note: In order to increase the storage volume of a dry swale, the ponding surface area may be increased beyond the filter media surface area. However, the top surface area of the BMP (at the top of the ponding elevation) may not be more than twice the size of surface area of the filter media (*SA*_{bottom}).

Wet Swale Sizing. Wet swales can be designed to capture and treat the SWRv remaining from any upstream stormwater retention practices. The storage volume is made up of the temporary and permanent storage created within each wet swale cell. This includes the permanent pool volume and up to 12 inches of temporary storage created by check dams or other design features that has 24 hours extended detention.

The storage volume (Sv) of the practice is equal to the volume provided by the pond permanent pool plus the 24-hour extended detention (ED) volume provided by the practice (Equation 3.2224). The total Sv cannot exceed the design SWRv.

Equation 3.24 Wet Swale Storage Volume

Sv = Pond permanent pool volume + 24 hour ED volumeSv = Pond permanent pool volume + 24 hour ED volume

3.9.5 Open Channel Landscaping Criteria

All open channels must be stabilized to prevent erosion or transport of sediment to receiving practices or drainage systems. There are several types of grasses appropriate for dry open channels (grass channels and dry swales). These are listed in Table 3.3837. Designers should choose plant species that can withstand both wet and dry periods and relatively high velocity flows for planting within the channel. Designers should ensure that the maximum flow velocities do not exceed the values listed in the table for the selected grass species and the specific site slope.

Table 3.25 Recommended Vegetation for Open Channels

Vegetation Type_	Slope (%)	Maximum Velocity (ft/s)	
	-	Erosion Resistant Soil	Easily Eroded Soil
Bermuda Grass	0- <u>-</u> 5	8	6
	510	7	5
	>10	6	4
Kentucky Bluegrass	0- <u>-</u> 5	7	5
	510	6	4
	>10	5	3
Tall Fescue Grass Mixture	0- <u>_</u> 5	6	4
	5- <u>_</u> 10	4	3
Annual and Perennial Rye	0- <u>-</u> 5	4	3
Sod		4	3.

Source: USDA, TP-61, 1954; Roanoke Virginia, Stormwater Design Manual, 2008

Wet swales should be planted with grass and wetland plant species that can withstand both wet and dry periods as well as relatively high velocity flows within the channel. For a list of wetland plant species suitable for use in wet swales, refer to the wetland panting guidance and plant lists provided in Section 3.11-. "Stormwater Wetlands-."

If roadway salt will be applied to the contributing drainage area CDA, open channels should be planted with salt-tolerant plant species.

Landscape design shall specify proper grass species based on site-specific soils and hydric conditions present along the channel.

Open channels should be seeded at such a density to achieve a 90-percent vegetated cover after the second growing season. Taller and denser grasses are preferable, although the species is less important than good stabilization and dense vegetative cover.

Grass channels should be seeded and not sodded. Seeding establishes deeper roots and sod may have muck soil that is not conducive to infiltration. Grass channels should be protected by a biodegradable erosion control fabric to provide immediate stabilization of the channel bed and banks.

3.9.6 Open Channel Construction Sequence

Design Notes. Channel invert and tops of banks are to be shown in plan and profile views. A cross sectional view of each configuration must be shown for proposed channels. Completed and completed limits of grading must be shown for proposed channels. For proposed channels, the transition at the entrance and outfall is to be clearly shown on plan and profile views.

Open Channel Installation. The following is a typical construction sequence to properly install open channels, although steps may be modified to reflect different site conditions or design variations. Grass channels should be installed at a time of year that is best to establish turf cover

without irrigation. For more specific information on the installation of wet swales, designers should consult the construction criteria outlined in Section 3.11-, "Stormwater Wetlands-."

- Step 1: Protection During Site Construction. Ideally, open channels should remain outside the <a href="https://linear.com
- Step 2: Installation. Installation may only begin after the entire contributing drainage area CDA has been stabilized with vegetation. Any accumulation of sediments that does occur within the channel must be removed during the final stages of grading to achieve the design cross section. Soil erosion and sediment controls for construction of the channel must be installed as specified in the soil erosion and sediment control plan. Stormwater flows must not be permitted into the channel until the bottom and side slopes are fully stabilized.
- Step 3: Grading. Grade the grass channel to the final dimensions shown on the plan. Excavators or backhoes should work from the sides to grade and excavate the open channels to the appropriate design dimensions. Excavating equipment should have scoops with adequate reach so they do not have to sit inside the footprint of the open channel area. If constructing a dry swale, the bottom of the swale should be ripped, rototilled or otherwise scarified to promote greater infiltration.
- Step 4: Placing Stone Layer (for dry swales). If constructing a dry swale, place an acceptable geotextile fabric on the underground (excavated) sides of the dry swale with a minimum 6-inch overlap. Place the stone needed for storage layer over the filter bed.

 Perforate Add the perforated underdrain pipe. Add the remaining stone jacket, and then pack #No. 57 stone (clean, double—washed) to 3 inches above the top of the underdrain, and then add 3 inches of pea gravel as a filter layer. Add the soil filter media in 12-inch lifts until the desired top elevation of the dry swale is achieved. Water thoroughly and add additional media as needed where settlement has occurred.
- *Step 5:* Add Amendments (optional, for grass channels). Add soil amendments as needed. Till the bottom of the grass channel to a depth of 1 foot and incorporate compost amendments according to Appendix J₋, "Soil Compost Amendment Requirements."
- **Step 6:** Install Check Dams. Install check dams, driveway culverts and internal pretreatment features as shown on the plan. Fill material used to construct check dams should be placed in 8-to 12-inch lifts and compacted to prevent settlement. The top of each check dam must be constructed level at the design elevation.
- *Step 7:* **Hydro-seed.** Hydro-seed the bottom and banks of the open channel, and peg in erosion control fabric or blanket where needed. After initial planting, a biodegradable erosion control fabric should be used, conforming to the District of Columbia Soil Erosion and Sediment Control Standards and Specifications.

Step 8: Plant. Plant landscaping materials as shown in the landscaping plan, and water them weekly during the first 2 months. The construction contract should include a care and replacement warranty to ensure that vegetation is properly established and survives during the first growing season following construction.

Step 9: **Final Inspection.** A qualified professional should conduct the final construction inspection and develop a punch list for facility acceptance.

Open Channel Construction Supervision. Supervision during construction is recommended to ensure that the open channel is built in accordance with these specifications.

DDOE's DOEE's construction phase inspection checklist is available in Appendix K"Construction Inspection Checklists."

Some common pitfalls can be avoided by careful construction supervision that focuses on the following key aspects of dry swale installation:

- Make sure the desired coverage of turf or erosion control fabric has been achieved following construction, both on the channel beds and their contributing side-slopes.
- Inspect check dams and pretreatment structures to make sure they are at correct elevations, are properly installed, and are working effectively.
- For dry swale designs:
 - Check the filter media to confirm that it meets specifications and is installed to the correct depth.
 - Check elevations, such as the invert of the underdrain, inverts for the inflow and outflow points, and the ponding depth provided between the surface of the filter bed and the overflow structure.
 - Ensure that caps are placed on the upstream (but not the downstream) ends of the underdrains.
 - Check that outfall protection/energy dissipation measures at concentrated inflow and outflow points are stable.

The real test of an open channel occurs after its first big storm. The post-storm inspection should focus on whether the desired sheetflow, shallow concentrated flows or fully concentrated flows assumed in the plan actually occur in the field. Minor adjustments are normally needed as part of this post-storm inspection (e.g., spot reseeding, gully repair, added armoring at inlets, or realignment of outfalls and check dams). Also, a qualified professional should check that dry swale practices drain completely within the 72-hour drawdown period.

3.9.7 Open Channel Maintenance Criteria

Maintenance is a crucial and required element that ensures the long-term performance of open channels. Once established, grass channels have minimal maintenance needs outside of the spring cleanup, regular mowing, repair of check dams, and other measures to maintain the hydraulic efficiency of the channel and a dense, healthy grass cover. Dry swale designs may

require regular pruning and management of trees and shrubs. The surface of dry swale filter beds can become clogged with fine sediment over time, but this can be alleviated through core aeration or deep tilling of the filter bed. Additional effort may be needed to repair check dams, stabilize inlet points, and remove deposited sediment from pretreatment cells. Table 3.3938 provides a schedule of typical maintenance activities required for open channels.



Table 3.26 Typical Maintenance Activities and Schedule for Open Channels

Schedule	Maintenance Activity
As needed	 Mow grass channels and dry swales during the growing season to maintain grass heights in the 4- to 6-inch range.
Quarterly	 Ensure that the contributing drainage areaCDA, inlets, and facility surface are clear of debris. Ensure that the contributing drainage areaCDA is stabilized. Perform spot-reseeding if where needed. Remove accumulated sediment and oil/grease from inlets, pretreatment devices, flow diversion structures, and overflow structures. Repair undercut and eroded areas at inflow and outflow structures.
Annual inspection	 Add reinforcement planting to maintain 90% turf cover. Reseed any salt-killed vegetation. Remove any accumulated sand or sediment deposits behind check dams. Inspect upstream and downstream of check dams for evidence of undercutting or erosion, and remove and trash or blockages at weep holes. Examine channel bottom for evidence of erosion, braiding, excessive ponding, or dead grass. Check inflow points for clogging and remove any sediment. Inspect side slopes and grass filter strips for evidence of any rill or gully erosion and repair. Look for any bare soil or sediment sources in the contributing drainage areaCDA and stabilize immediately.

Maintenance Inspections. Annual inspections by a qualified professional are used to trigger maintenance operations, such as sediment removal, spot revegetation, and inlet stabilization. DDOE's DOEE's maintenance inspection checklists for disconnection and the Maintenance Service Completion Inspection form can be found in Appendix L_{\tau}, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOED staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C of the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.9.8 Open Channel Stormwater Compliance Calculations

Grass Channels receive 10 percent retention value and are not an accepted total suspended solids practice for the amount of storage volume (Sv) provided by the BMP (Table 3.4039).

Table 3.27 Grass Channel Retention Value and Pollutant Removal

Retention Value	$=0.1\times Sv$
Accepted Total Suspended Solids (TSS) Treatment Practice	No

Grass channels on amended soils receive 30-percent% retention value 1 for the amount of storage volume (Sv) provided by the practice (Table 3.4140).

Table 3.39.40 Grass Channel on Amended Soils Retention Value and Pollutant Removal

Retention Value	$=0.3 \times Sv$	
Accepted TSS Treatment Practice	No	()_v

Dry swales receive 60 percent Dry swales receive 60% retention value and are an accepted TSS removal practice for the amount of storage volume (Sy) provided by the practice (Table 3.41).

Table 3.28 Dry Swale Retention Value and Pollutant Removal

Retention Value	$= 0.6 \times Sv$
Accepted TSS Treatment Practice	<u>Yes</u>

<u>Wet swales receive 10%</u> retention value and are an accepted TSS removal practice for the amount of storage volume (Sv) provided by the <u>practiceBMP</u> (Table 3.42).

Table 3.40 Dry Swale Retention Value and Pollutant Removal

Retention Value	<u> </u>
Accepted TSS Treatment Practice	Yes

Wet swales receive 10 percent retention value and are an accepted TSS removal practice for the amount of storage volume (Sv) provided by the BMP (Table 3.43).

Table 3.4129 Wet Swale Retention Value and Pollutant Removal

Retention Value	$=0.1 \times Sv$
Accepted TSS Treatment Practice	Yes

All practices must be sized using the guidance detailed in Section 3.9.4—, "Open Channel Design Criteria."

Grass channels and dry swales also contribute to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the storage volume (Sv) or Retention Value from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced Natural Resource Conservation Service (reduced NRCS) Curve Number CN for the site or <a href="drainage area SDA. The Reduced Curve Number reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.9.9 References

- ASTM D448-12(2017), Standard Classification for Sizes of Aggregate for Road and Bridge Construction, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- Barrett, Michael E., Michael V. Keblin, Patrick M. Walsh, Joseph F. Malina, Jr., and Randall J. Charbeneau. 1998. Evaluation of the Performance of Permanent Runoff Controls: Summary and Conclusions. Center for Transportation Research Bureau of Engineering Research. The University of Texas at Austin. Available online at:

 http://www.utexas.edu/research/ctr/pdf_reports/2954_3F.pdf
- Haan, C.T., B.J Barfield., and J.C. Hayes, Design Hydrology and Sedimentology for Small Catchments. Academic Press, New York, 1994.
- Mar, B.W., R.R. Horner, J.F. Ferguson, D.E. Spyridakis, E.B. Welch. 1982. Summary "C Highway Runoff Water Quality Study, 1977 "C 1982. WA RD 39.16. September, 1982.
- Roanoke Virginia, Stormwater Design Manual. 2008. Stormwater Management Design Manual. Department of Planning Building and Development. Roanoke, Virginia.
- USDA. 1954. Handbook of Channel of Design for Soil and Water Conservation. Stillwater Outdoor Hydraulic Laboratory and the Oklahoma Agricultural Experiment Station. SCS-TP-61, Washington, DC.
- Virginia DCR Stormwater Design Specification No. 3: Grass Channels Version 1.8. 2010.
- Virginia DCR Stormwater Design Specification No. 10: Dry Swales Version 1.8. 2010.

Virginia DCR Stormwater Design Specification No. 11: Wet Swales Version 1.8. 2010.

Washington State Department of Ecology. 2005. Stormwater Manual for Western Washington. State of Washington Department of Ecology. Available online at:

http://www.eey.wa.gov/programs/wq/stormwater/manual.htmlAvailable online at: https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Stormwaterpermittee-guidance-resources/Stormwater-manuals



PROPOSED REVISION PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REVISION REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REVI


3.10 Ponds

Definition. Stormwater ponds are stormwater storage practices that consist of a combination of a permanent pool, micropool, or shallow marsh that promote a good environment for gravitational settling, biological uptake, and microbial activity. Ponds are widely applicable for most land uses and are-best suited for larger drainage areas SDAs. Runoff from each new storm enters the pond and partially displaces pool water from previous storms. The pool also acts as a barrier to resuspension estimates and other pollutants deposited during prior storms. When sized properly, stormwater ponds have a residence time that ranges from many days to several weeks, which allows numerous pollutant removal mechanisms to operate. Stormwater ponds can also provide storage above the permanent pool to help meet stormwater management requirements for larger storms. Design variants include: the following (see Figures 3.38 and 3.39):

- C-1 Micropool extended detention pond
- C-2 Wet pond
- C-3 Wet extended detention pond

Stormwater ponds should be considered for use after all other upland retention opportunities have been exhausted and there is still a remaining treatment volume or runoff from larger storms (i.e., 2-year, 15-year or flood control events) to manage.

Stormwater ponds receive only 10% stormwater retention value and should be considered mainly for management of larger storm events. Stormwater ponds have both community and environmental concerns (see Section 3.10.1 Pond Feasibility Criteria) that should be considered before choosing stormwater ponds for as the appropriate stormwater practice on_ site.







Figure 3.373.383.37.38 Design schematics for a wet pond (PC-2).






Figure 3.383.393.38.39 Typical extended detention pond (PC-3) details.

3.10.1 Pond Feasibility Criteria

The following feasibility issues need to be considered when ponds are considered a final stormwater management practice of the treatment train.

Adequate Water Balance. Wet ponds must have enough water supplied from groundwater, runoff, or baseflow so that the wet pools will not draw down by more than 2 feet after a 30-day summer drought. A simple water balance calculation must be performed using the equation provided Equation 3.26 in Section 3.10.4. Wetland, "Pond Design Criteria and Section 3.11.4 Wetland Design Criteria.."

Contributing Drainage Area. A contributing drainage area CDA of 10 to 25 acres is typically recommended for ponds to maintain constant water elevations. Ponds can still function with drainage areas CDAs less than 10 acres, but designers should be aware that these "pocket" ponds will be prone to clogging, experience fluctuating water levels, and generate more nuisance conditions.

Space Requirements. The surface area of a pond will normally be at least 1-to-%_3 percent% of its contributing drainage area CDA, depending on the pond's depth.

Site Topography. Ponds are best applied when the grade of contributing slopes is less than 15 percent.%.

Available Hydraulic Head. The depth of a pond is usually determined by the hydraulic head available on the site. The bottom elevation is normally the invert of the existing downstream conveyance system to which the pond discharges. Typically, a minimum of 6 to 8 feet of head are needed to hold the wet pool and any additional large storm storage or overflow capacity for a pond to function.

Setbacks. To avoid the risk of seepage, stormwater cannot flow via baseflow from stormwater ponds must not be hydraulically connected to the traditional pavement base layer, existing structure foundations, or an area where there may be future development adjacent to the property line. Setbacks to structures and property lines must be at least 10 feet and adequate water proofing waterproofing protection must be provided for foundations and basements.

Proximity to Utilities. For an open pond system, no utility lines shall be permitted to cross any part of the embankment of a wet pool.

Depth to Water Table. The depth to the groundwater table is not a major constraint for wetpondsstormwater ponds because a high water table can help maintain wetland conditions. However, groundwater inputs can also reduce the pollutant removal rates of ponds. Further, if the water table is close to the surface, it may make excavation difficult and expensive.

Soils. Highly permeable soils will make it difficult to maintain a healthy permanent pool. Soil infiltration tests need to be conducted at proposed pond sites to determine the need for a pond liner or other method to ensure a constant water surface elevation. Underlying soils of Hydrologie Soil Group (HSG) C or D should be adequate to maintain a permanent pool. Most HSG A soils and some HSG B soils will require a liner (see Table 3.4443). Geotechnical tests

should be conducted to determine the <u>infiltration rates</u>saturated <u>hydraulic conductivity</u> and other subsurface properties of the soils beneath the proposed pond.

Use of or Discharges to Natural Wetlands. Ponds cannot be located within <u>jurisdictional District</u> waters, including wetlands, without obtaining a <u>section Section</u> 404 permit <u>or other permissions</u> from the appropriate state or federal regulatory agency. In addition, the designer should investigate the wetland status of adjacent areas to determine if the discharge from the pond will change the hydroperiod of a downstream natural wetland (see Cappiella et al., 2006, for guidance on minimizing stormwater discharges to existing wetlands).

Perennial Streams. Locating ponds on perennial streams will require both a Section 401 and Section 404 permit or other permissions from the appropriate state or federal regulatory agency.

Community and Environmental Concerns. Ponds can generate the following community and environmental concerns that need to be addressed during design:

- Aesthetic Issues. Many residents feel that ponds are an attractive landscape feature, promote
 a greater sense of community and are an attractive habitat for fish and wildlife. Designers
 should note that these benefits are often diminished where ponds are under-sized or have
 small contributing drainage areas CDAs.
- Existing Forests. Construction of a pond may involve extensive clearing of existing forest cover. Designers can expect a great deal of neighborhood opposition if they do not make a concerted effort to save mature trees during pond design and construction. In the District of Columbia, a permit is required to remove a tree with a circumference greater than 55 44 inches on private lands. A permit is required to prune or remove any street tree between the sidewalk and the curb. These permits are issued by the District Department of Transportation, Urban Forestry Administration UFADivision (DDOT UFD).
- Safety Risk. Pond safety is an important community concern, since both young children and adults have perished by drowning in ponds through a variety of accidents, including falling through thin ice cover. Gentle side slopes and safety benches should be provided to avoid potentially dangerous drop-offs, especially where ponds are located near residential areas.
- Pollutant Concerns. Ponds collect and store water and sediment to increase residence time that will increase the likelihood for contaminated water and sediments to be neutralized. However, poorly sized, maintained, and/or functioning ponds can export contaminated sediments and/or water to receiving waterbodies (Mallin, 2000; Mallin et al., 2001; Messersmith, 2007). Further, designers are cautioned that recent research on ponds has shown that some ponds can be hotspots or incubators for algae that generate harmful algal blooms (HABs).
- Mosquito Risk. Mosquitoes are not a major problem for larger ponds (Santana et al., 1994; Ladd and Frankenburg, 20037; Hunt et al7,2 2005). However, fluctuating water levels in smaller or under-sized ponds could pose some risk for mosquito breeding. Mosquito problems can be minimized through simple design features and maintenance operations described in MSSC (2005).

Geese and Waterfowl. Ponds with extensive turf and shallow shorelines can attract nuisance populations of resident geese and other waterfowl, whose droppings add to the nutrient and bacteria loads, thus reducing the removal efficiency for those pollutants. Several design and landscaping features can make ponds much less attractive to geese (see Schueler, 1992).

3.10.2 Pond Conveyance Criteria

Internal Slope. The longitudinal slope of the pond bottom should be at least 0.5 to $\frac{1}{1}$ percent $\frac{1}{2}$ to facilitate maintenance.

Primary Spillway. The spillway shall be designed with acceptable anti-flotation, anti-vortex and trash rack devices. The spillway must generally be accessible from dry land. When reinforced concrete pipe is used for the principal spillway to increase its longevity, "O-ring" gaskets (ASTM C361) shall be used to create watertight joints.

Non-Clogging Low-Flow Orifice. A low-flow orifice must be provided that is adequately protected from clogging by either an acceptable external trash rack or by internal orifice protection that may allow for smaller diameters. Orifices less than 3 inches in diameter may require extra attention during design, to minimize the potential for clogging.

- One option is a submerged reverse-slope pipe that extends downward from the riser to an inflow point 1 foot below the normal pool elevation.
- Alternative methods must employ a broad crested rectangular V-notch (or proportional) weir, protected by a half-round CMP that extends at least 12 inches below the normal pool elevation.

Emergency Spillway. Ponds must be constructed with overflow capacity to pass the 100-year design storm event through either the primary spillway or a vegetated or armored emergency spillway unless waived by **DDOEDOEE**.

Adequate Outfall Protection. The design must specify an outfall that will be stable for the 15-year design storm event. The channel immediately below the pond outfall must be modified to prevent erosion and conform to natural dimensions in the shortest possible distance. This is typically done by placing appropriately sized riprap over geotextile fabric, which can reduce flow velocities from the principal spillway to non-erosive levels (3.5 to 5.0 fpsfeet per second) depending on the channel lining material. Flared pipe sections, which discharge at or near the stream invert or into a step pool arrangement, should be used at the spillway outlet.

When the discharge is to a manmade pipe or channel system, the system must be adequate to convey the required design storm peak discharge.

If a pond daylights to a channel with dry weather flow, care should be taken to minimize tree clearing along the downstream channel, and to reestablish a forested riparian zone in the shortest possible distance. Excessive use of rip rapriprap should be avoided.

The final release rate of the facility shall be modified if any increase in flooding or stream channel erosion would result at a downstream structure, highway, or natural point of restricted streamflow (see Section 2.611 Additional Stormwater Management Requirements).

Inlet Protection. Inflow points into the pond must be stabilized to ensure that non-erosive conditions exist during storm events up to the overbank flood event (i.e., the 15-year storm event). Inlet pipe inverts should generally be located at or slightly below the permanent pool elevation. A forebay shall be provided at each inflow location, unless the inlet is submerged or inflow provides less than 10-percent% of the total design storm inflow to the pond.

Dam Safety Permits. The designer must verify whether or not Dam Safety permits or approvals are required for the embankment.

3.10.3 Pond Pretreatment Criteria

Sediment forebays are considered to be an integral design feature to maintain the longevity of all ponds. A forebay must be located at each major inlet to trap sediment and preserve the capacity of the main treatment cell. The following criteria apply to forebay design:

- A major inlet is defined as an individual storm drain inlet pipe or open channel serving at least 10-percent% of the pond's contributing drainage area CDA.
- The forebay consists of a separate cell, formed by an acceptable barrier (e.g., an earthen berm, concrete weir, gabion baskets, etc.).
- The forebay should be between 4 and 6 feet deep and must be equipped with a variable width aquatic bench for safety purposes. The aquatic bench should be 4 to 6 feet wide at a depth of 1 to 2 feet below the water surface. Small forebays may require alternate geometry to achieve the goals of pretreatment and safety within a small area.
- The forebay shall be sized to contain 0.1 <u>inches nch</u> of runoff from the contributing drainage impervious area. The relative size of individual forebays should be proportional to the percentage of the total inflow to the pond.
- The bottom of the forebay may be hardened (e.g., with concrete, asphalt, or grouted riprap) to make sediment removal easier.
- The forebay must be equipped with a metered rod in the center of the pool (as measured lengthwise along the low-flow water travel path) for long-term monitoring of sediment accumulation.
- Exit velocities from the forebay shall be non-erosive or an armored overflow shall be provided. Non-erosive velocities are 4 feet per second for the two2-year event, and 6 feet per second for the 15-year event.
- Direct maintenance access for appropriate equipment shall be provided to the each forebay.
- The bottom of the forebay may be hardened to make sediment removal easier.

3.10.4 Pond Design Criteria

Pond Storage Design. The pond permanent pool must be sized to store a volume equivalent to the SWRv. Volume storage may be provided in multiple cells. Performance is enhanced when multiple treatment pathways are provided by using multiple cells, longer flowpaths, high surface area to volume ratios, complex microtopography, and/or redundant treatment methods (combinations of pool, ED, and marsh).

Pond Geometry. Pond designs should have an irregular shape and a long flow path from inlet to outlet; to increase water residence time and pond performance. The minimum length to width ratio (i.e., length relative to width) for ponds is 1.5:1. Greater flowpaths and irregular shapes are recommended. Internal berms, baffles, or vegetated peninsulas can be used to extend flow paths and/or create multiple pond cells.

Permanent Pool Depth. The maximum depth of the permanent pool should not generally exceed eight8 feet unless the pond is designed for multiple uses.

Micropool. A micropool is a three3_ to six-6_foot_deep pool used to protect the low-flow pipe from clogging and to prevent sediment resuspension. For micropool extended detention ponds, the micropool shall be designed to hold at least 10-to-<u>%</u>-25-percent<u>%</u> of the 1.2-inch storm event.

Side Slopes. Side slopes for ponds should generally have a gradient no steeper than 3H:1V. Mild slopes promote better establishment and growth of vegetation and provide for easier maintenance and a more natural appearance.

Maximum Extended Detention Levels. The total storage, including any ponding for larger flooding events (100-year storm) should not extend more than 5 feet above the pond permanent pool unless specific design enhancements to ensure side slope stability, safety, and maintenance are identified and approved.

Stormwater Pond Benches. The perimeter of all pool areas greater than 4 feet in depth must be surrounded by two benches, as follows:

- Safety Bench. This is a flat bench located just outside of the perimeter of the permanent pool to allow for maintenance access and reduce safety risks. Except when the stormwater pond side slopes are 5H:1V or flatter, provide a safety bench that generally extends 8 to 15 feet outward from the normal water edge to the toe of the stormwater pond side slope. The maximum slope of the safety bench is 5-percent.%.
- Aquatic Bench. This is a shallow area just inside the perimeter of the normal pool that promotes growth of aquatic and wetland plants. The bench also serves as a safety feature, reduces shoreline erosion, and conceals floatable trash. Incorporate an aquatic bench that generally extends up to 10 feet inward from the normal shoreline, has an irregular configuration, and extends a maximum depth of 18 inches below the normal pool water surface elevation.

Liners. When a stormwater pond is located over highly permeable soils or fractured bedrock, a liner may be needed to sustain a permanent pool of water. If geotechnical tests confirm the need for a liner, acceptable options include the following: (1) a clay liner following the specifications outlined in Table 3.44 below43; (2) a 30-mil_ poly-liner; (3) bentonite; (4) use of chemical additives; or (5) an engineering design, as approved on a case-by-case basis by DDOEDOEE. A clay liner must have a minimum thickness of 12 inches with an additional 12-inch layer of compacted soil above it, and it must meet the specifications outlined in Table 3.4443. Other synthetic liners can be used if the designer can supply supporting documentation that the material will achieve the required performance.

Table 3.30 Clay Liner Specifications

Property	Test Method	Unit	Specification
Permeability	ASTM D-2434 D2434	cm/s	1×10^{-6}
Plasticity Index of Clay	ASTM D-	%	Not less than 15
Liquid Limit of Clay	ASTM <u>D-2216</u> <u>D2216</u>	%	Not less than 30
Clay Particles Passing	ASTM <u>D-422</u> <u>D422</u>	%	Not less than 30
Clay Compaction	ASTM D-2216D2216	%	95% of standard proctor density

Source: DCR (1999). VA

Required Geotechnical Testing. Soil borings must be taken below the proposed embankment, in the vicinity of the proposed outlet area, and in at least two locations within the proposed pond treatment area. Soil boring data is needed to (1) determine the physical characteristics of the excavated material, (2) determine its adequacy for use as structural fill or spoil, (3) provide data for structural designs of the outlet works (e.g., bearing capacity and buoyancy), (4) determine compaction/composition needs for the embankment_ (5) determine the depth to groundwater and bedrock_ and (6) evaluate potential infiltration losses (and the potential need for a liner).

Non-clogging Low-Flow (Extended Detention) Orifice. The low-flow ED orifice shall be adequately protected from clogging by an acceptable external trash rack. The preferred method is a submerged reverse-slope pipe that extends downward from the riser to an inflow point one_1 foot below the normal pool elevation. Alternative methods are to employ a broad crested rectangular, V-notch, or proportional weir, protected by a half-round CMP that extends at least 12 inches below the normal pool.

Riser in Embankment. The riser should be located within the embankment for maintenance access, safety, and aesthetics. Access to the riser is to be provided by lockable manhole covers, and manhole steps within easy reach of valves and other controls. The principal spillway opening can be "fenced" with pipe or rebar at 8-inch intervals for safety purposes.

Trash Racks. Trash racks shall be provided for low-flow pipes and for riser openings not having anti-vortex devices.

Pond Drain. Ponds should have a drainpipe that can completely or partially drain the permanent pool. In cases where a low—level drain is not feasible (such as in an excavated pond), a pump well must be provided to accommodate a temporary pump intake when needed to drain the pond.

- The drainpipe must have an upturned elbow or protected intake within the pond to help keep it clear of sediment deposition, and a diameter capable of draining the pond within 24 hours.
- The pond drain must be equipped with an adjustable valve located within the riser, where it will not be normally inundated and can be operated in a safe manner.

Care must be exercised during pond drawdowns to prevent downstream discharge of sediments or anoxic water and rapid drawdown. The approving authority shall be notified before draining a pond.

Adjustable Gate Valve. Both the outlet pipe and the pond drain must be equipped with an adjustable gate valve (typically a handwheel activated knife gate valve) or pump well and be sized one pipe size greater than the calculated design diameter. Valves must be located inside of the riser at a point where they (a)-will not normally be inundated and (b) can be operated in a safe manner. To prevent vandalism, the handwheel should be chained to a ringbolt, manhole step, or other fixed object.

Safety Features.

- The principal spillway opening must be designed and constructed to prevent access by small children.
- End walls above pipe outfalls greater than 48 inches in diameter must be fenced to prevent a falling hazard.
- Storage practices must incorporate an additional 1 foot of freeboard above the emergency spillway, or 2 feet of freeboard if design has no emergency spillway, for the maximum Qf design storm unless more stringent Dam Safety requirements apply.
- The emergency spillway must be located so that downstream structures will not be impacted by spillway discharges.
- Both the safety bench and the aquatic bench should be landscaped with vegetation that hinders or prevents access to the pool.
- Warning signs prohibiting swimming must be posted.
- Where permitted, fencing of the perimeter of ponds is discouraged. The preferred method to reduce risk is to manage the contours of the stormwater pond to eliminate drop-offs or other safety hazards. Fencing is required at or above the maximum water surface elevation in the rare situations when the pond slope is a vertical wall.
- Side slopes to the pond shall not be steeper than 3H:1V, and shall terminate on a 15-ft-foot-wide safety bench. Both the safety bench and the aquatic bench may be landscaped to prevent access to the pool. The bench requirement may be waived if slopes are 4H:1V or flatter.

Maintenance Reduction Features. Many maintenance issues can be addressed through well design access. -All ponds must be designed for annual maintenance. Good access is needed so crews can remove sediments, make repairs, and preserve pond-treatment capacity. Design for the following,

- Adequate maintenance access must extend to the forebay, safety bench, riser, and outlet structure and must have sufficient area to allow vehicles to turn around.
- The riser should be located within the embankment for maintenance access, safety, and aesthetics. Access to the riser should be provided by lockable manhole covers and manhole steps within easy reach of valves and other controls.
- ◆ Access roads must (1) be constructed of load-bearing materials or be built to withstand the expected frequency of use, (2) have a minimum width of 15 feet, and (3) have a profile grade that does not exceed 5:15H:1V.
- A maintenance right-of-way or easement must extend to the stormwater pond from a public or private road.
- Material Specifications. ED ponds are generally constructed with materials obtained onsite, except for the plant materials, inflow and outflow devices (e.g., piping and riser materials), possibly stone for inlet and outlet stabilization, and geotextile fabric for lining banks or berms.
- **Pond Sizing.** Stormwater ponds can be designed to capture and treat the remaining stormwater discharged from upstream practices from the design storm (SWRv). Additionally, stormwater ponds may be sized to control peak flow rates from the 2-year and 15-year frequency storm event or other design storms as required. Design calculations must ensure that the post-development peak discharge does not exceed the predevelopment peak discharge. See Section 2.710 Hydrology Methods for a summary of acceptable hydrologic methodologies and models.

For treatment train designs where upland practices are utilized for treatment of the SWRv, designers can use a site-adjusted Rv or \underline{NRCS} CN that reflects the volume reduction of upland practices to compute the Qp_2 and Qp_{15} that must be treated by the stormwater pond.

The pond permanent pool must be sized to store a volume equivalent to the SWRv or design volume.

The storage volume (Sv) of the practice is equal to the volume provided by the pond permanent pool (Equation 3.2325). The total Sv cannot exceed the design SWRv.

Equation 3.25 Pond Storage Volume

Sv = Pond permanent pool volume Sv = Pond permanent pool volume

■ Water Balance Testing. A water balance calculation is recommended to document that sufficient inflows to wet ponds and wet ED ponds exist to compensate for combined infiltration and evapotranspiration losses during a 30-day summer drought without creating unacceptable drawdowns (see Equation 3.2426, adapted from Hunt et al., 2007). The recommended minimum pool depth to avoid nuisance conditions may vary; however, it is generally recommended that the water balance maintain a minimum 24-inch reservoir.

Equation 3.26 Water Balance Equation for Acceptable Water Depth in a Wet Pond

$$DP > ET + INF + RES - MB$$

$$DP > ET + INF + RES - MB$$

where:

DP = average design depth of the permanent pool (in.)
ET = summer evapotranspiration rate (in.) (assume 8 in.)

INF = monthly infiltration loss (assume 7.2 <u>inches</u> at 0.01 in./hour)

RES = reservoir of water for a factor of safety (assume 24 in.)

MB = measured baseflow rate to the pond, if any convert to pond-inches (in.)

Design factors that will alter this equation are the measurements of seasonal base flow and infiltration rate. The use of a liner could eliminate or greatly reduce the influence of infiltration. Similarly, land use changes in the upstream watershed could alter the base flow conditions over time (e.g., urbanization and increased impervious cover).

Translating the baseflow to inches refers to the depth within the pond. Therefore, Equation 3.2527 can be used to convert the baseflow, measured in cubic feet per second (cfs), to pond-inches:

Equation 3.27 Baseflow Conversion

$$\underline{Pond-inches} = \frac{MB \times 2.592 \times 10^{6} \times 12}{SA}$$

$$Pond-inches = \frac{MB \times 2.592 \times 10^{6} \times 12}{SA}$$

where:

pond-pond-inches=depth within the pond (in,)MB=measured baseflow rate to the pond (cfs) 2.592×106 =conversion factor-from, converting cfs to ft³/month12=conversion from factor, converting feet to inchesSA=surface area of pond (ft²)

3.10.5 Pond Landscaping Criteria

Pond Benches. The perimeter of all deep pool areas (<u>four4</u> feet or greater in depth) must be surrounded by two benches:

• A safety bench that extends 8 to 15 feet outward from the normal water edge to the toe of the pond side slope. The maximum slope of the safety bench shall be 6 percent.%.

An aquatic bench that extends up to 10 feet inward from the normal shoreline and has a maximum depth of 18 inches below the normal pool water surface elevation.

Landscaping and Planting Plan. A landscaping plan must be provided that indicates the methods used to establish and maintain vegetative coverage in the pond and its buffer (see Section 3.6.5 Bioretention Landscaping Criteria for extended landscaping and planting details). Minimum elements of a landscaping plan include the following:

- Delineation of pondscaping zones within both the pond and buffer.
- Selection of corresponding plant species.
- The planting plan.
- The sequence for preparing the wetland benches (including soil amendments, if needed?)
- Sources of native plant material.
- The landscaping plan should provide elements that promote diverse wildlife and waterfowl
 use within the stormwater wetland and buffers.
- Woody vegetation may not be planted or allowed to grow within 15 feet of the toe of the embankment nor within 25 feet from the principal spillway structure.
- A vegetated buffer should be provided that extends at least 25 feet outward from the maximum water surface elevation of the pond. Permanent structures (e.g., buildings) should not be constructed within the buffer area. Existing trees should be preserved in the buffer area during construction.
- The soils in the stormwater buffer area are often severely compacted during the construction process, to ensure stability. The density of these compacted soils can be so great that it effectively prevents root penetration and, therefore, may lead to premature mortality or loss of vigor. As a rule of thumb, planting holes should be three times deeper and wider than the diameter of the root ball for ball-and-burlap stock, and five times deeper and wider for container-grown stock.
- Avoid species that require full shade, or are prone to wind damage. Extra mulching around
 the base of trees and shrubs is strongly recommended as a means of conserving moisture and
 suppressing weeds.

For more guidance on planting trees and shrubs in pond buffers, consult Cappiella et al. (2006).

3.10.6 Pond Construction Sequence

The following is a typical construction sequence to properly install a stormwater pond. The steps may be modified to reflect different pond designs; site conditions; and the size, complexity, and configuration of the proposed facility.

Step 1: Use of Ponds for Soil Erosion and Sediment Control. A pond may serve as a sediment basin during project construction. If this is done, the volume should be based on the more stringent sizing rule (soil erosion and sediment control requirement <u>vs.versus</u> storage volume requirement). Installation of the permanent riser should be initiated during the

construction phase, and design elevations should be set with final cleanout of the sediment basin and conversion to the post-construction pond in mind. The bottom elevation of the pond should be lower than the bottom elevation of the temporary sediment basin. Appropriate procedures must be implemented to prevent discharge of turbid waters when the basin is being converted into a pond.

Approval from DDOEDOEE must be obtained before any sediment pond can be used as for stormwater management.

- Step 2: Stabilize the Contributing Drainage Area. Ponds should only be constructed after the contributing drainage areaCDA to the pond is completely stabilized. If the proposed pond site will be used as a sediment trap or basin during the construction phase, the construction notes should clearly indicate that the facility will be de-watered, dredged, and re-graded regraded to design dimensions after the original site construction is complete.
- **Step 3:** Assemble Construction Materials On Site. Inspect construction materials to insure ensure they conform to design specifications, and prepare any staging areas.
- Step 4: Clear and Strip. Bring the project area to the desired sub-gradesubgrade.
- **Step 5:** Soil Erosion and Sediment Controls. Install soil erosion and sediment control measures prior to construction, including temporary de-watering devices and stormwater diversion practices. All areas surrounding the pond that are graded or denuded during construction must be planted with turf grass, native plantings, or other approved methods of soil stabilization.
- Step 6: Excavate the Core Trench and Install the Spillway Pipe.
- **Step 7: Install the Riser or Outflow Structure.** Once riser and outflow structures are installed ensure the top invert of the overflow weir is constructed level at the design elevation.
- **Step 8:** Construct the Embankment and any Internal Berms. These features must be installed -in 8- to 12-inch lifts; compact the lifts with appropriate equipment.
- **Step 9:** Excavate and Grade. Survey to achieve the appropriate elevation and designed contours for the bottom and side slopes of the pond.
- *Step 10:* **Construct the Emergency Spillway.** The emergency spillway must be constructed in cut or structurally stabilized soils.
- *Step 11:* **Install Outlet Pipes.** The installation of outlet pipes must include a downstream riprapriprap protection apron.
- *Step 12:* **Stabilize Exposed Soils.** Use temporary seed mixtures appropriate for the pond buffer to stabilize the exposed soils. All areas above the normal pool elevation must be permanently stabilized by hydroseeding or seeding over straw.
- *Step 13:* **Plant the Pond Buffer Area.** Establish the planting areas according to the pondscaping plan (see Section 3.10.5 Pond Landscaping Criteria).

Construction Supervision. Supervision during construction is recommended to ensure that stormwater ponds are properly constructed, especially during the following stages of construction:

- Preconstruction meeting
- Initial site preparation including the installation of soil erosion and sediment control measures
- Excavation/Grading (interim and final elevations)
- Installation of the embankment, the riser/primary spillway, and the outlet structure
- Implementation of the pondscaping plan and vegetative stabilization
- Final inspection (develop a punch list for facility acceptance)

DDOE's DOEE's construction phase inspection checklist for ponds can be found in Appendix Ka. "Construction Inspection Checklists."

To facilitate maintenance, contractors should measure the actual constructed pond depth at three areas within the permanent pool (forebay, mid-pond and at the riser), and they should mark and geo-reference them on an as-built drawing. This simple data set will enable maintenance inspectors to determine pond sediment deposition rates in order to schedule sediment cleanouts.

3.10.7 Pond Maintenance Criteria

Maintenance is needed so stormwater ponds continue to operate as designed on a long-term basis. Ponds normally have fewer routine maintenance requirements than other stormwater control measures. Stormwater pond maintenance activities vary regarding the level of effort and expertise required to perform them. Routine stormwater pond maintenance, such as mowing and removing debris and trash, is needed several times each year (see Table 3.4544). More significant maintenance (e.g., removing accumulated sediment) is needed less frequently but requires more skilled labor and special equipment. Inspection and repair of critical structural features (e.g., embankments and risers) needs to be performed by a qualified professional (e.g., a structural engineer) who has experience in the construction, inspection, and repair of these features.

Sediment removal in the pond pretreatment forebay should occur every 5 to 7 years or after 50 percent% of total forebay capacity has been lost. The designer should also check to see whether removed sediments can be spoiled on site or must be hauled away. Sediments excavated from ponds are not usually considered toxic or hazardous. They can be safely disposed of by either land application or land filling. Sediment testing may be needed prior to sediment disposal if the pond serves a hotspot land use.

Table 3.31 Pond Maintenance Tasks and Frequency

Frequency	Maintenance Items				
During establishment, as needed (first year)	 Inspect the site at least twice after storm events that exceed a 1/2-inch of rainfall. Plant the aquatic benches with emergent wetland species, following the planting recommendations contained in Section 3.11.6, "Stormwater Wetland Landscaping Criteriar." Stabilize any bare or eroding areas in the contributing drainage areaCDA or around the pond buffer. Water trees and shrubs planted in the pond buffer during the first growing season. In general, consider watering every 3 days for first month, and then weekly during the remainder of the first growing season (April -through October), depending on rainfall. 				
Quarterly or after major storms (>1 inch of rainfall)	 Mowing —(twice a year) Remove debris and blockages Repair undercut, eroded, and bare soil areas 				
Twice a year	Mowing of the buffer and pond embankment				
Annually	 Shoreline cleanup to remove trash, debris, and floatables A full maintenance inspection Open up the riser to access and test the valves Repair broken mechanical components, if needed 				
Once—during the second year following construction	Pond buffer and aquatic bench reinforcement plantings				
Every 5 to 7 years	■ Forebay Sediment Removalsediment removal				
From 5 to 25 years	• Repair pipes, the riser and spillway, as needed				

Maintenance Plans. Maintenance plans must clearly outline how vegetation in the pond and its buffer will be managed or harvested in the future. Periodic mowing of the stormwater buffer is only required along maintenance rights-of-way and the embankment. The remaining buffer can be managed as a meadow (mowing every other year) or forest. The maintenance plan should schedule a shoreline cleanup at least once a year to remove trash and floatables.

Maintenance Inspections. Maintenance of a pond is driven by annual inspections by a qualified professional that evaluate who evaluates the condition and performance of the pond. Based on inspection results, specific maintenance tasks will be triggered.

 $\overline{DDOE'sDOEE's}$ maintenance inspection checklist for stormwater ponds and the Maintenance Service Completion Inspection form can be found in Appendix $L_{\overline{\tau}}$, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C of the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.10.8 Pond Stormwater Compliance Calculations

Stormwater ponds receive 10 percent retention value and are an accepted total suspended solids (TSS) treatment practice for the amount of storage volume (Sv) provided by the BMP (Table 3.4645).

Table 3.32 Pond Retention Value and Pollutant Removal

Retention Value	$=0.1 \times Sv$
Accepted TSS Treatment Practice	Yes

The resulting reduced runoff volumes can then be used to calculate a reduced NRCS CN for the site or SDA. The reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.10.9 References

ASTM C361-16, Standard Specification for Reinforced Concrete Low-Head Pressure Pipe, ASTM International, West Conshohocken, PA, 2016, www.astm.org

- ASTM D2216-10, Standard Test Methods for Laboratory Determination of Water (Moisture)

 Content of Soil and Rock by Mass, ASTM International, West Conshohocken, PA, 2010,
 www.astm.org
- ASTM D2434-68(2006), Standard Test Method for Permeability of Granular Soils (Constant Head) (Withdrawn 2015), ASTM International, West Conshohocken, PA, 2006, www.astm.org
- ASTM D4318-17, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils, ASTM International, West Conshohocken, PA, 2017, www.astm.org
- ASTM D422-63(2007)e2, Standard Test Method for Particle-Size Analysis of Soils (Withdrawn 2016), ASTM International, West Conshohocken, PA, 2007, www.astm.org
- Cappiella, K., T. Schueler and T. Wright. 2006. Urban Watershed Forestry Manual: Part 2: Conserving and Planting Trees at Development Sites. USDA Forest Service. Center for Watershed Protection. Ellicott City, MD.
- Hunt, W., C. Apperson, and W. Lord. 2005. "Mosquito Control for Stormwater Facilities." Urban Waterways. North Carolina State University and North Carolina Cooperative Extension. Raleigh, NC.
- Hunt, W., M. Burchell, J. Wright and K. Bass. 2007. "Stormwater Wetland Design Update: Zones, Vegetation, Soil and Outlet Guidance." Urban Waterways. North Carolina State Cooperative Extension Service. Raleigh, NC.
- Ladd, B and J. Frankenburg. 2003. Management of Ponds, Wetlands and Other Water Reservoirs. Purdue Extension. WO-41-W.
- Mallin, M. 2000. Effect of human development on bacteriological water quality in coastal watersheds. Ecological Applications 10(4):1047-1056.
- Mallin, M.A., S.H. Ensign, Matthew R. McIver, G. Christopher Shank, and Patricia K. Fowler. 2001. Demographic, landscape, and meteorological factors controlling the microbial pollution of coastal waters. Hydrobiologia 460(1-3):185-193.
- Messersmith, M.J. 2007. Assessing the hydrology and pollutant removal efficiencies of wet detention ponds in South Carolina. MS. Charleston, S.C. College of Charleston, Master of Environmental Studies.
- Minnesota Stormwater Steering Committee (MSSC). 2005. Minnesota Stormwater Manual. Emmons & Oliver Resources, Inc. Minnesota Pollution Control Agency. St. Paul, MN.
- Santana, F., J. Wood, R. Parsons, and S. Chamberlain. 1994. Control of Mosquito Breeding in Permitted Stormwater Systems. Southwest Florida Water Management District. Brooksville, FL.

- Schueler, T, 1992. Design of Stormwater Wetland Systems. Metropolitan Washington Council of Governments. Washington, DC.
- Virginia Department of Conservation and Recreation (VA DCR). 1999. Virginia Stormwater Management Handbook, first edition.
- Virginia DCR Stormwater Design Specification No. 14: Wet Ponds Version 1.8. 2010.
- Virginia DCR Stormwater Design Specification No. 15: Extended Detention (ED) Pond Version 1.8. 2010.
- VA Department of Conservation and Recreation (VA DCR). 1999. Virginia Stormwater Management Handbook, first edition.

3.11 Stormwater Wetlands

Definition. Practices that create shallow marsh areas to treat urban stormwater, which often incorporate small permanent pools and/or extended detention storage. Stormwater wetlands are explicitly designed to provide stormwater detention for larger storms (2-year, 15-year, or flood control events) above the design storm (Stormwater Retention Volume (SWRv))) storage. Design variants include the following:

- W-1 Shallow wetland
- W-2 Extended detention shallow wetland

Stormwater wetlands, sometimes called constructed wetlands, are shallow depressions that receive stormwater inputs for water quality treatment. Wetlands are typically less than 1 foot deep (although they have greater depths at the forebay and in micropools) and possess variable microtopography to promote dense and diverse wetland cover. Runoff from each new storm displaces runoff from previous storms, and the long residence time allows multiple pollutant removal processes to operate. The wetland environment provides an ideal environment for gravitational settling, biological uptake, and microbial activity. Several stormwater wetland design features are illustrated in Figures 3.40 through 3.42.

Stormwater wetlands should be considered for use after all other upland retention opportunities have been exhausted and there is still a remaining treatment volume or runoff from larger storms (i.e., 2-year, 15-year or flood control events) to manage.

Stormwater wetlands receive only 10% stormwaterof the storage volume as retention valuevolume and should be considered mainly for management of larger storm events. Stormwater wetlands have both community and environmental concerns (see Section 3.11.1 Stormwater Wetland Feasibility Criteria) that should be considered before choosing stormwater ponds for the appropriate stormwater practice on site.

Note: All of the pond performance criteria presented in Section 3.10, "Ponds" also apply to the design of stormwater wetlands. Additional criteria that govern the geometry and establishment of created wetlands are presented in this section.




Figure 3.393.39.40 Example of extended detention shallow wetland.




Figure 3.403.40.41 Cross section of a typical stormwater wetland.




Figure 3.413.41_42 Interior wetland zones: (I) Deep Pool (depth -48 to -18 inches), (II) Transition Zone (depth -18 to -6 inches), (III and IV) High Marsh Zone (depth -6 to +6 inches), (IV) Temporary Inundation Area, and (V) Upper Bank (adapted from Hunt et al_{3.2} 2007).

3.11.1 Stormwater Wetland Feasibility Criteria

Constructed wetland designs are subject to the following site constraints:

Adequate Water Balance. Wetlands Stormwater wetlands must have enough water supplied from groundwater, runoff, or baseflow so that the permanent pools will not draw down by more than 2 feet after a 30-day summer drought. A simple water balance calculation must be performed using the equation provided in Section 3.11.4-, "Stormwater Wetland Design Criteria-."

Contributing Drainage Area (CDA). The contributing drainage area CDA must be large enough to sustain a permanent water level within the stormwater wetland. If the only source of wetland hydrology is stormwater runoff, then several dozen acres of drainage area CDA are typically needed to maintain constant water elevations. Smaller drainage areas CDAs are acceptable if the bottom of the stormwater wetland intercepts the groundwater table or if the designer or approving agency is willing to accept periodic wetland drawdown.

Space Requirements. Constructed wetlands normally require a footprint that takes up about 3 percent% of the contributing drainage areaCDA, depending on the average depth of the wetland and the extent of its deep pool features.

Site Topography. Wetlands Stormwater wetlands are best applied when the grade of contributing slopes is less than 8 percent. %.

Steep Slopes. A modification of the constructed wetland (and linear wetland or wet swale system) is the regenerative stormwater conveyance (RSC) or step pool storm conveyance channel. The RSC can be used to bring stormwater down steeper grades through a series of step pools. This can serve to bring stormwater down outfalls where steep drops on the edge of the tidal receiving system can create design challenges. For more information on RSC systems, designers can consult the Anne Arundel County Design Specifications, available at http://www.aacounty.org/departments/public-works/wprp/watershed-assessment-and-planning/step-pool-conveyance-systems/index.html

Available Hydraulic Head. The depth of a constructed wetland is usually constrained by the hydraulic head available on the site. The bottom elevation is fixed by the elevation of the existing downstream conveyance system to which the wetland will ultimately discharge. Because constructed wetlands are typically shallow, the amount of head needed (usually a minimum of 2 to 4 feet) is typically less than for wet ponds.

Setbacks. To avoid the risk of seepage, stormwater cannot flow via baseflow from stormwater wetlands must not be hydraulically connected to the traditional pavement base layer, existing structure foundations—, or an area where there may be future development adjacent to the property line. Setbacks to structures and property lines must be at least 10 feet and adequate water proofing waterproofing protection must be provided for foundations and basements.

Depth to Water Table. The depth to the groundwater table is not a major constraint for constructed wetlands, since a high water table can help maintain wetland conditions. However, designers should keep in mind that high groundwater inputs may increase excavation costs (refer to Section 3.10 Stormwater Ponds).

Soils. Soil tests should be conducted to determine the <u>infiltration ratessaturated hydraulic conductivity</u> and other subsurface properties of the soils underlying the proposed <u>stormwater</u> wetland. Highly permeable soils will make it difficult to maintain a healthy permanent pool. Underlying soils of <u>Hydrologic Soil Group (HSG)HSG</u> C or D should be adequate to maintain a permanent pool. Most HSG A soils and some HSG B soils will require a liner (see Table 3.4443).

Use of or Discharges to Natural Wetlands. Constructed wetlands may not be located within jurisdictional waters, including wetlands, without obtaining a Section 404 permit from the appropriate federal regulatory agency. In addition, designer should investigate the status of adjacent wetlands to determine if the discharge from the constructed wetland will change the hydroperiod of a downstream natural wetland—(see, See Cappiella et al., (2006) for guidance on minimizing stormwater discharges to existing wetlands).

Regulatory Status. Constructed wetlands built for the express purpose of stormwater treatment are generally not considered jurisdictional wetlands.

Perennial Streams. Locating a constructed wetland along or within a perennial stream will require both Section 401 and Section 404 permits from the state or federal regulatory authority.

Community and Environmental Concerns. In addition to the community and environmental concerns that exist for stormwater ponds, stormwater wetlands can generate the following tomust be addressed during design of stormwater wetlands:

- Aesthetics and Habitat. Constructed wetlands can create wildlife habitat and can also become an attractive community feature. Designers should think carefully about how the wetland plant community will evolve over time, since the future plant community seldom resembles the one initially planted.
- Existing Forests. Given the large footprint of a constructed wetland, there is a strong chance that the construction process may result in extensive tree clearing. The designer should preserve mature trees during the facility layout, and he/she may consider creating a wooded wetland (see Cappiella et al., 2006). In the District of Columbia, a permit is required to remove a tree with a circumference greater than 55 44 inches on private lands. A permit is required to prune or remove any street tree between the sidewalk and the curb. These permits are issued by the District Department of Transportation, Urban Forestry Administration (UFA). DDOT UFD.
- Safety Risk. Constructed wetlands are safer than other types of ponds, although forebays and micropools must be designed with aquatic benches to reduce safety risks.
- Mosquito Risk. Mosquito control can be a concern for stormwater wetlands if they are under-sized or have a small contributing drainage area. CDA. Deepwater zones serve to keep mosquito populations in check by providing habitat for fish and other pond life that prey on mosquito larvae. Few mosquito problems are reported for well_designed, properly sized, and frequently maintained constructed wetlands; however, no design can eliminate them completely. Simple precautions can be taken to minimize mosquito breeding habitat within constructed wetlands (e.g., constant inflows, benches that create habitat for natural predators, and constant pool elevations—MSSC, 2005).

3.11.2 Stormwater Wetland Conveyance Criteria

 The slope profile within individual <u>stormwater</u> wetland cells should generally be flat from inlet to outlet (adjusting for microtopography). The recommended maximum elevation drop between wetland cells is 1 foot or less.

- Since most constructed wetlands are on-line facilities, they need to be designed to safely pass the maximum design storm (e.g., the 15-year and 100-year design storms). While the ponding depths for the more frequent 2-year storm are limited in order to avoid adverse impacts to the planting pallet, the overflow for the less frequent 15- and 100-year storms must likewise be carefully designed to minimize the depth of ponding. A maximum depth of 4 feet over the wetland pool is recommended.
- While many-different options are available for setting the normal pool elevation, it is strongly recommended that removable flashboard risers be used, given their greater operational flexibility to adjust water levels following construction (see Hunt et al_{5.2} 2007). Also, a weir can be designed to accommodate passage of the larger storm flows at relatively low ponding depths.

3.11.3 Stormwater Wetland Pretreatment Criteria

Sediment regulation is critical to sustain stormwater wetlands. Consequently, a forebay shall be located at the inlet, and a micropool shall be located at the outlet—. A micropool is a three— to six 6—foot—deep pool used to protect the low-flow pipe from clogging and to prevent sediment resuspension—. Forebays are designed in the same manner as stormwater ponds (see Section 3.10.3 Pond Pretreatment Criteria). The design of forebays should consider the possibility of heavy trash loads from public areas.

3.11.4 Stormwater Wetland Design Criteria

Internal Design Geometry. Research and experience have shown that the internal design geometry and depth zones are critical in maintaining the pollutant removal capability and plant diversity of stormwater wetlands. WetlandStormwater wetland performance is enhanced when the wetland has multiple cells, longer flowpaths, and a high ratio of surface area to volume. Whenever possible, constructed wetlands should be irregularly shaped with long, sinuous flow paths. The following design elements are required for stormwater wetlands:

Multiple-Cell Wetlands. Wetlands Stormwater wetlands can be divided into at least four internal sub-cells of different elevations: the forebay, a micro-pool outlet, and two additional cells. Cells can be formed by sand berms (anchored by rock at each end), back-filled coir fiber logs, or forested peninsulas (extending as wedges across 95-percent% of the wetland width). The vegetative target is to ultimately achieve a 50-50 mix of emergent and forested wetland vegetation within all four cells.

The first cell (the forebay) is deeper and is used to receive runoff from the pond cell or the inflow from a pipe or open channel and distribute it as sheetflow into successive wetland cells. The surface elevation of the second cell is the normal pool elevation. It may contain a forested island or a sand wedge channel to promote flows into the third cell, which is 3 to 6 inches lower than the normal pool elevation. The purpose of the wetland cells is to create an alternating sequence of aerobic and anaerobic conditions to maximize pollutant removal. The fourth wetland cell is located at the discharge point and serves as a micro-pool with an outlet structure or weir.

Extended Detention Ponding Depth. When extended detention is provided for management of larger storm events, the total ED volume shall not comprise more than 50-percent of the total

volume stored by the <u>stormwater</u> wetland, and its maximum water surface elevation shall not extend more than <u>three3</u> feet above the normal pool.

Deep Pools. Approximately 25-percent of the wetlandstormwater surface area must be provided in at least three deeper pools—located at the inlet (forebay), center, and outlet (micropool) of the wetland—with each pool having a depth of from 18 to 48 inches. Refer to the sizing based on water balance below for additional guidance on the minimum depth of the deep pools.

High Marsh Zone. Approximately 70-percent of the stormwater wetland surface area must exist in the high marsh zone (-6 inches to +6 inches, relative to the normal pool elevation).

Transition Zone. The low marsh zone is no longer an acceptable wetland zone, and is only allowed as a short transition zone from the deeper pools to the high marsh zone_(-6 to -18 inches below the normal pool elevation). In general, this transition zone should have a maximum slope of 5H:1V (or preferably flatter) from the deep pool to the high marsh zone. It is advisable to install biodegradable erosion control fabrics or similar materials during construction to prevent erosion or slumping of this transition zone.

Flow Path. In terms of the flow path, there are two design objectives:

- The overall flow path through the <u>stormwater</u> wetland can be represented as the length-towidth ratio OR the flow path ratio. A minimum overall flow path of 2:1 must be provided across the stormwater wetland.
- The shortest flow path represents the distance from the closest inlet to the outlet. The ratio of the shortest flow path to the overall length must be at least 0.5. In some cases—_due to site geometry, storm sewer infrastructure, or other factors—some inlets may not be able to meet these ratios. However, the drainage areaCDA served by these "closer" inlets must constitute no more than 20-percent% of the total contributing drainage areaCDA.

Side Slopes. Side slopes for the <u>stormwater</u> wetland should generally have gradients of 4H:1V or flatter. These mild slopes promote better establishment and growth of the wetland vegetation. They also contribute to easier maintenance and a more natural appearance.

Micro-Topographic Features. Stormwater wetlands must have internal structures that create variable micro-topography, which is defined as a mix of above-pool vegetation, shallow pools, and deep pools that promote dense and diverse vegetative cover.

Constructed Stormwater Wetland Material Specifications. Wetlands Stormwater wetlands are generally constructed with materials obtained on-site, except for the plant materials, inflow and outflow devices (e.g., piping and riser materials), possibly stone for inlet and outlet stabilization, and geotextile fabric for lining banks or berms. Plant stock should be nursery grown, unless otherwise approved, and must be healthy and vigorous native species free from defects, decay, disfiguring roots, sun-scald, injuries, abrasions, diseases, insects, pests, and all forms of infestations or objectionable disfigurements, as determined by DOCEDOEE.

Stormwater Wetland Sizing. Constructed Stormwater wetlands can be designed to capture and treat the remaining stormwater discharged from upstream practices from the design storm (SWRv). Additionally, stormwater wetlands can be sized to control peak flow rates from the 2year and 15-year frequency storm event or other design storm. Design calculations must ensure that the post-development peak discharge does not exceed the predevelopment peak discharge. See Section 2.710 Hydrology Methods for a summary of acceptable hydrological hydrologic methodologies and models.

For treatment train designs where upland practices are utilized for treatment of the SWRv, designers can use a site-adjusted Rv or NRCS CN that reflects the volume reduction of upland practices to compute the Qp₂ and Qp₁₅ that must be treated by the <u>stormwater</u> wetland.

The wetland permanent pools (volume stored in deep pools and pool depths) must be sized to store a volume equivalent to the SWRv or design volume.

The storage volume (Sv) of the practice is equal to the volume provided by the wetland permanent pool (Equation 3.2628). The total Sv cannot exceed the SWRv.

Equation 3.28 Stormwater Wetland Storage Volume

Sv = Wetland permanent pool volume Sv = Stormwater wetland permanent pool volume

Sizing for Minimum Pool Depth. Initially, it is recommended that there be no minimum drainage areaCDA requirement for the system, although it may be necessary to calculate a water balance for the wet pond cell when its CDA is less than 10 acres (Refer to Section 3.10 Stormwater Ponds).

Similarly, if the hydrology for the constructed wetland is not supplied by groundwater or dry weather flow inputs, a simple water balance calculation must be performed, using Equation 3.2729 (Hunt et al., 2007), to assure the deep pools will not go completely dry during a 30-day summer drought.

Equation 3.29 Water Balance for Acceptable Water Depth in a Stormwater Wetland

$$DP = \left(RF_m \times EF \times \frac{WS}{WL}\right) - \left(ET - INF - RS\right)$$

$$DP = \left(RF_m \times EF \times \frac{WS}{WL}\right) - \left(ET - INF - I$$

$$DP = \left(RF_m \times EF \times \frac{WS}{WL}\right) - (ET - INF - S)$$

where:

DP= depth of pool (in.)

 RF_m = monthly rainfall during drought (in.)

EF= fraction of rainfall that enters the stormwater wetland (in.)

 $(CDA \times Rv)$

WS/WL = ratio of contributing drainage area to <u>stormwater</u> wetland surface

area

ET = summer evapotranspiration rate (in.) (assume 8 in.)

INF = monthly infiltration loss (assume 7.2 inches at 0.01 in./hr)

RES = reservoir of water for a factor of safety (assume 6 in.)

Using Equation 3.2830, setting the groundwater and (dry weather) base flow to zero and assuming a worst—case summer rainfall of 0 inches, the minimum depth of the pool <u>calculates is calculated</u> as follows (Equation 3.28):30):

Equation 3.30 Minimum Depth of the Permanent Pool

Depth of Pool (DP) = 0 in. (RFm) 8 in. (ET) 7.2 in. (INF) 6 in. (RES) = 21.2 in. DP =
$$RF_m - ET - INF - RES = -21.2$$

where:

DP =	depth of pool (in.)
RF_m =	monthly rainfall during drought (in.)
\overline{ET} =	summer evapotranspiration rate (in.) (assume 8 in.)
INF =	monthly infiltration loss (assume 7.2 inches at 0.01 in./hr)
RES =	reservoir of water for a factor of safety (assume 6 in.)

Therefore, unless there is other input, such as base flow or groundwater, the minimum depth of the pool should be at least 22 inches (rather than the 18-inch minimum depth noted in Section 3.11.4 and depicted in Figure 3.39). this section).

3.11.5 Stormwater Wetland Construction Sequence

The construction sequence for stormwater wetlands depends on—site conditions, design complexity, and the size and configuration of the proposed facility. The following two-stage construction sequence is recommended for installing an on-line stormwater wetland facility and establishing vigorous plant cover.

Stage 1 Construction Sequence: Wetland Facility Construction.

Step 1: Stabilize Contributing Drainage Area. Stormwater wetlands should only be constructed after the contributing drainage area CDA to the wetland is completely stabilized. If the proposed stormwater wetland site will be used as a sediment trap or basin during the construction phase, the construction notes must clearly indicate that the facility will be dewatered, dredged and re-graded to design dimensions after the original site construction is complete.

- **Step 2:** Assemble Construction Materials On-site <u>Site</u>. Inspect construction materials to insure ensure they conform to design specifications, and prepare any staging areas.
- Step 3: Clear and Strip. Bring the project area to the desired sub-gradesubgrade.
- Step 4: Install Soil Erosion and Sediment Control Measures prior to construction, including sediment basins and stormwater diversion practices. All areas surrounding the stormwater wetland that are graded or denuded during construction of the wetland are to be planted with turf grass, native plant materials, or other approved methods of soil stabilization. Grass sod is preferred over seed to reduce seed colonization of the stormwater wetland. During construction, the stormwater wetland must be separated from the contributing drainage area CDA so that no sediment flows into the wetland areas. In some cases, a phased or staged soil crosion and sediment control plan (SESCP)—may be necessary to divert flow around the stormwater wetland area until installation and stabilization are complete.
- Step 5: Excavate the Core Trench for the Embankment and Install the Spillway Pipe.
- **Step 6: Install the Riser or Outflow Structure** and ensure that the top invert of the overflow weir is constructed level and at the proper design elevation (flashboard risers are strongly recommended by Hunt et al. 2007).
- **Step 7:** Construct the Embankment and any Internal Berms in 8₂ to 12-inch lifts and compacted compact them with appropriate equipment.
- **Step 8:** Excavate and Grade. Survey to achieve the appropriate elevation and designed contours for the bottom and side slopes of the <u>stormwater</u> wetland. This is normally done by "roughing up" the interim elevations with a skid loader or other similar equipment to achieve the desired topography across the wetland. Spot surveys should be made to ensure that the interim elevations are 3 to 6 inches below the final elevations for the wetland.
- Step 9: Install Micro-Topographic Features and Soil Amendments within the stormwater wetland area. Since most stormwater wetlands are excavated to deep sub-soils, they often lack the nutrients and organic matter needed to support vigorous growth of wetland plants. It is therefore essential to add sand, compost, topsoil, or wetland mulch to all depth zones in the stormwater wetland. The importance of soil amendments in excavated stormwater wetlands cannot be over-emphasized; poor survival and future wetland coverage are likely if soil amendments are not added. The planting soil should be a high organic content loam or sandy loam, placed by mechanical methods, and spread by hand. Planting soil depth should be at least 4 inches for shallow wetlands. No machinery should be allowed to traverse over the planting soil during or after construction. Planting soil should be tamped as directed in the design specifications, but it should not be overly compacted. After the planting soil is placed, it should be saturated and allowed to settle for at least one week prior to installation of plant materials.
- *Step 10:* Construct the Emergency Spillway. The emergency spillway must be constructed in cut or structurally stabilized soils.
- *Step 11:* **Install Outlet Pipes.** The installation of outlet pipes must include a -the-downstream rip-rapriprap protection apron.
- *Step 12:* **Stabilize Exposed Soils** with temporary seed mixtures appropriate for a wetland environment. All wetland features above the normal pool elevation should be temporarily stabilized by hydro-seeding or seeding over straw.

Stage 2 Construction Sequence: Establishing the Wetland Vegetation.

- **Step 13:** Finalize the Stormwater Wetland Landscaping Plan. At this stage the engineer, landscape architect, and wetland expert work jointly to refine the initial wetland landscaping plan after the stormwater wetland has been constructed. Several weeks of standing time is needed so that the designer can more precisely predict the following two things:
- Where the inundation zones are located in and around the stormwater wetland; and
- Whether the final grade and wetland microtopography will persist over time.

This allows the designer to select appropriate species and additional soil amendments, based on field confirmation of soils properties and the actual depths and inundation frequencies occurring within the stormwater wetland.

- Step 14: Open Up the Stormwater Wetland Connection. Once the final grades are attained, the pond and/or contributing drainage areaCDA connection should be opened to allow the wetland cell to fill up to the normal pool elevation. Gradually inundate the stormwater wetland to avoid erosion of unplanted features. Inundation must occur in stages so that deep pool and high marsh plant materials can be placed effectively and safely. Wetland planting areas should be at least partially inundated during planting to promote plant survivability.
- **Step 15:** Measure and Stake Planting Depths at the onset of the planting season. Depths in the <u>stormwater</u> wetland should be measured to the nearest inch to confirm the original planting depths of the planting zone. At this time, it may be necessary to modify the plan to reflect altered depths or a change in the availability of wetland plant stock. Surveyed planting zones should be marked on the as-built or design plan, and their locations should also be identified in the field, using stakes or flags.
- *Step 16:* **Propagate the Stormwater Wetland.** Three Two techniques are used in combination to propagate the emergent community over the wetland bed:
- 1. Initial Planting of Container-Grown Wetland Plant Stock. The transplanting window extends from early April to mid-June. Planting after these dates is quite chancycan decrease the chance of survival, since emergent wetland plants need a full growing season to build the root reserves needed to get through the winter. It is recommended that plants be ordered at least 6 months in advance to ensure the availability and on-time delivery of desired species.
- 2. Broadcasting Wetland Seed Mixes. The higher wetland elevations should be established by broadcasting wetland seed mixes to establish diverse emergent wetlands. Seeding of switchgrass or wetland seed mixes as a ground cover is recommended for all zones above 3 inches below the normal pool elevation. Hand broadcasting or hydroseeding can be used to spread seed, depending on the size of the wetland cell.
- 3. Allowing "Volunteer Wetland Plants to Establish on Their Own. The remaining areas of the stormwater wetland will eventually (within 3 to 5 years) be colonized by volunteer species from upstream or the forest buffer.

Step 17: Install Goose Protection to Protect Newly Planted or Newly Growing Vegetation. This is particularly critical for newly established emergents and herbaceous plants, as predation by Canada geese can quickly decimate wetland vegetation. Goose protection can consist of

by Canada geese can quickly decimate wetland vegetation. Goose protection can consist of netting, webbing, or string installed in a crisscross pattern over the surface area of the <u>stormwater</u> wetland, above the level of the emergent plants.

Step 18: Plant the Stormwater Wetland Fringe and Buffer Area. This zone generally extends from 1 to 3 feet above the normal pool elevation (from the shoreline fringe to about half of the maximum water surface elevation for the 2-year storm). Consequently, plants in this zone are infrequently inundated (5 to 10 times per year), and must be able to tolerate both wet and dry periods.

Construction Supervision. Supervision during construction is recommended to ensure that stormwater wetlands are properly constructed and established. Multiple site visits and inspections by a qualified professional are recommended during the following stages of the stormwater wetland construction process:

- Preconstruction meeting
- Initial site preparation including the installation of project soil erosion and sediment control
 measures
- Excavation/Gradinggrading (e.g., interim/final elevations)
- Wetland installation (e.g., microtopography, soil amendments, and staking of planting zones)
- Planting Phasephase (with an experienced landscape architect or wetland expert)
- Final Inspection inspection (develop a punch list for facility acceptance)

 $\overline{DDOE'sDOEE's}$ construction phase inspection checklist for $\overline{ConstructedStormwater}$ Wetlands can be found in Appendix K_{τ} , "Construction Inspection Checklists."

3.11.6 Stormwater Wetland Landscaping Criteria

An initial stormwater wetland landscaping plan is required for any stormwater wetland and should be jointly developed by the engineer and a wetlands expert or experienced landscape architect. The plan should outline a detailed schedule for the care, maintenance, and possible reinforcement of vegetation in the wetland and its buffer for up to 10 years after the original planting.

The plan should outline a realistic, long-term planting strategy to establish and maintain desired wetland vegetation. The plan should indicate how wetland plants will be established within each inundation zone (e.g., wetland plants, seed-mixes, volunteer colonization, and tree and shrub stock) and whether soil amendments are needed to get plants started. At a minimum, the plan should contain the following:

Plan view(s) with topography at a contour interval of no more than 1 foot and spot elevations throughout the cell showing the <u>stormwater</u> wetland configuration, different planting zones (e.g., high marsh, deep water, upland), microtopography, grades, site preparation, and construction sequence. A plant schedule and planting plan specifying emergent, perennial, shrub and tree species, quantity of each species, stock size, type of root stock to be installed, and spacing. To the degree possible, the species list for the constructed wetland should contain plants found in similar local wetlands.

The following general guidance is provided:

- Use Native Species Where Possible. Table 3.46 provides a list of common native shrub and tree species and Table 3.47 provides a list of common native shrub and tree species and Table 3.48 provides a list of common native emergent, submergent, and perimeter plant species, all of which have proven to do well in stormwater wetlands in the mid-Atlantic region and are generally available from most commercial nurseries (consult DDOE's DOEE's webpage for information on area suppliers). Other native species can be used that appear in state-wide plant lists. The use of native species is strongly encouraged, but in some cases, non-native ornamental species may be added as long as they are not invasive. Invasive species such as cattails, Phragmites, and purple loosestrife must not be planted.
- Match Plants to Inundation Zones. The various plant species shown in Table 3.4746 and Table 3.4847 should be matched to the appropriate inundation zone. The first four inundation zones are particularly applicable to stormwater wetlands, as follows:
 - **Zone 1** -6 inches to -12 inches below the normal pool elevation
 - **Zone 2** -6 inches to the normal pool elevation
 - **Zone 3** From the normal pool elevation to +-12 inches above it
 - **Zone 4** +12 inches to +36 inches above the normal pool elevation (i.e., above ED Zone)

Note: The Low Marsh Zone (-6 inches to -18 inches below the normal pool elevation) has been dropped since experience has shown that few emergent wetland plants flourish in this deeper zone.

■ Aggressive Colonizers. To add diversity to the <u>stormwater</u> wetland, <u>5five</u> to <u>7seven</u> species of emergent wetland plants should be planted, using at least four emergent species designated as aggressive colonizers (shown in bold in Table 3.4847). No more than 25-percent% of the high marsh wetland surface area needs to be planted. If the appropriate planting depths are achieved, the entire <u>stormwater</u> wetland should be colonized within <u>three3</u> years. Individual plants should be planted 18 inches on center within each single species "cluster"."

Shrubs		Trees		
Common and Scientific Names Zone ¹		Common and Scientific Names	Zone ¹	
Button Bush	2, 3	Atlantic White Cedar	2, 3	
(Cephalanthus occidentalis)		(Charnaecyparis thyoides)		
Common Winterberry	3, 4	Bald Cypress	2, 3	
(Ilex verticillatta)		(Taxodium distichum)		
Elderberry	3	Black Willow	3, 4	
(Sambucus canadensis)		(Salix nigra)		
Indigo Bush	3	Box Elder	2, 3	
(Amorpha fruticosa)		(Acer Negundo)		

Shrubs		Trees		
Common and Scientific Names Zone ¹		Common and Scientific Names	Zone ¹	
Inkberry	2, 3	Green Ash	3, 4	
(Ilex glabra)		(Fraxinus pennsylvanica)		
Smooth Alder	2, 3	Grey Birch	3, 4	
(Alnus serrulata)		(Betula populifolia)		
Spicebush	3, 4	Red Maple	3, 4	
(Lindera benzoin)		(Acer rubrum)		
Swamp Azalea	2, 3	River Birch	3, 4	
(Azalea viscosum)		(Betula nigra)		
Swamp Rose	2, 3	Swamp Tupelo	2, 3	
(Rosa palustris)		(Nyssa biflora)		
Sweet Pepperbush	2, 3	Sweetbay Magnolia	3, 4	
(Clethra ainifolia)		(Magnolia virginiana)		
		Sweetgum	3, 4	
		(Liquidambar styraciflua)		
		Sycamore	3, 4	
		(Platanus occidentalis)		
		Water Oak	3, 4	
		(Quercus nigra)		
		Willow Oak	3,4	
		(Quercus phellos)		

¹Zone 1: -6 inches to -12 inches *OR* 18 inches below the normal pool elevation

Zone 2: -6 inches to the normal pool elevation

Zone 3: From the normal pool elevation to +12 inches

Zone 4: +12 inches to +36 inches; above ED zone Source: Virginia DCR Stormwater Design Specification No. 13: Constructed Wetlands Version 1.8. 2010.

Table 3.34 Popular, Versatile, and Available Native Emergent and Submergent Vegetation for $\underline{Constructed}\underline{Stormwater}\ Wetlands$

Plant	Zone ¹	Form	Inundation Tolerance	Wildlife Value	Notes
Arrow Arum (Peltandra virginica)	2	Emergent	Up to 1 ft	High; berries are eaten by wood ducks	Full sun to partial shade
Broad-Leaf Arrowhead (Duck Potato) (Saggitaria latifolia)	2	Emergent	Up to 1 ft	Moderate; tubers and seeds eaten by ducks	Aggressive colonizer
Blueflag Iris* (Iris versicolor)	2, 3	Emergent	Up to 6 in.	Limited	Full sun (to flower) to partial shade
Broomsedge (Andropogon virginianus)	2, 3	Perimeter	Up to 3 in.	High; songbirds and browsers; winter food and cover	Tolerant of fluctuating water levels and partial shade
Bulltongue Arrowhead (Sagittaria lancifolia)	2, 3	Emergent	0– <u>to</u> 24 in.	Waterfowl, small mammals	Full sun to partial shade
Burreed (Sparganium americanum)	2, 3	Emergent	0– <u>to</u> 6 in.	Waterfowl, small mammals	Full sun to partial shadshade
Cardinal Flower * (Lobelia cardinalis)	3	Perimeter	Periodic inundation	Attracts hummingbirds	Full sun to partial shade

Chapter 3 Stormwater Best Management Practices (BMPs)

Plant	Zone ¹	Form	Inundation Tolerance	Wildlife Value	Notes
Common Rush (Juncus spp.)	2, 3	Emergent	Up to 12 in.	Moderate; small mammals, waterfowl, songbirds	Full sun to partial shade
Common Three Square (Scipus pungens)	2	Emergent	Up to 6 in.	High; seeds, cover, waterfowl, songbirds	Fast colonizer; can tolerate periods of dryness; full sun; high metal removal
Duckweed (Lemna sp)	1, 2	Submergent / Emergent	Yes	High; food for waterfowl and fish	May biomagnify metals beyond concentrations found in the water
Joe Pye Weed (Eupatorium purpureum)	2, 3	Emergent	Drier than other Joe-Pye Weeds; dry to moist areas; periodic inundation	Butterflies, songbirds, insects	Tolerates all light conditions
Lizard's Tail (Saururus cernus)	2	Emergent	Up to 1 ft	Low; except for wood ducks	Rapid growth; shade- tolerant
Marsh Hibiscus (Hibiscus moscheutos)	2, 3	Emergent	Up to 3 in.	Low; nectar	Full sun; can tolerate periodic dryness
Pickerelweed (Pontederia cordata)	2, 3	Emergent	Up to 1 ft	Moderate; ducks, nectar for butterflies	Full sun to partial shade
Pond Weed (Potamogeton pectinatus)	1	Submergent	Yes	Extremely high; waterfowl, marsh and shore birds	Removes heavy metals from the water
Rice Cutgrass (Leersia oryzoides)	2, 3	Emergent	Up to 3 in.	High; food and cover	Prefers full sun, although tolerant of shade; shoreline stabilization
Sedges (Carex spp.)	2, 3	Emergent	Up to 3 in.	High; waterfowl, songbirds	Wetland and upland species
Softstem Bulrush (Scipus validus)	2, 3	Emergent	Up to 2 ft	Moderate; good cover and food	Full sun; aggressive colonizer; high pollutant removal
Smartweed (Polygonum spp.)	2	Emergent	Up to 1 ft	High; waterfowl, songbirds; seeds and cover	Fast colonizer; avoid weedy aliens, such as <i>P. Perfoliatum</i>
Spatterdock (Nuphar luteum)	2	Emergent	Up to 1.5 ft	Moderate for food, but High for cover	Fast colonizer; tolerant of varying water levels
Switchgrass (Panicum virgatum)	2, 3, 4	Perimeter	Up to 3 in.	High; seeds, cover; waterfowl, songbirds	Tolerates wet/dry conditions
Sweet Flag * (Acorus calamus)	2, 3	Perimeter	Up to 3 in.	Low; tolerant of dry periods	Tolerates acidic conditions; not a rapid colonizer

Plant	Zone ¹	Form	Inundation Tolerance	Wildlife Value	Notes
Waterweed (Elodea canadensis)	1	Submergent	Yes	Low	Good water oxygenator; high nutrient, copper, manganese, and chromium removal
Wild celery (Valisneria americana)	1	Submergent	Yes	High; food for waterfowl; habitat for fish and invertebrates	Tolerant of murkeymurky water and high nutrient loads
Wild Rice (Zizania aquatica)	2	Emergent	Up to 1 ft	High; food, birds	Prefers full sun
Woolgrass (Scirpus cyperinus)	3, 4	Emergent	yes Yes	High: waterfowl, small mammals	Fresh tidal and non- tidal, swamps, forested wetlands, meadows, ditches

¹Zone 1: -6 inches to -12 inches OR 18 inches below the normal pool elevation

Source: Virginia DCR Stormwater Design Specification No. 13: Constructed Wetlands Version 1.8. 2010.

- Suitable Tree Species. The major shift in stormwater wetland design is to integrate trees and shrubs into the design, in tree islands, peninsulas, and fringe buffer areas. Deeper-rooted trees and shrubs that can extend to the stormwater wetland's local water table are important for creating a mixed wetland community. Table 3.4746 above presents some recommended tree and shrub species in the mid-Atlantic region for different inundation zones. A good planting strategy includes varying the size and age of the plant stock to promote a diverse structure. Using locally grown container or bare root stock is usually the most successful approach; if planting in the spring. It is recommended that buffer planting areas be overplanted with a small stock of fast growing successional species to achieve quick canopy closure and shade out invasive plant species. Trees may be planted in clusters to share rooting space on compacted wetland side-slopes. Planting holes should be amended with compost (a 2:1 ratio of loose soil to compost) prior to planting.
- **Pre- and Post-Nursery Care.** Plants should be kept in containers of water or moist coverings to protect their root systems and keep them moist when in transporting them to the planting location. As much as six6 to nine9 months of lead time may be needed to fill orders for wetland plant stock from aquatic plant nurseries. Consult DOEE's webpage for information on area suppliers.

3.11.7 Stormwater Wetland Maintenance Criteria

Successful establishment of constructed wetland areas requires that the following tasks be undertaken in the first two2 years:

Zone 2: -6 inches to the normal pool elevation

Zone 3: From the normal pool elevation to +12 inches

Zone 4: +12 inches to +36 inches; above ED zone

^{*}Not a major colonizer, but adds color (Aggressive colonizers are shown in **bold** type).)

- Initial Inspections. During the first 6 months following construction, the site should be
 inspected by a qualified professional at least twice after storm events that exceed 1/20.5 inch
 of rainfall.
- **Spot Reseeding.** Inspections should include looking for bare or eroding areas in the contributing drainage area CDA or around the wetland buffer, and make sure they are immediately stabilized with grass cover.
- Watering. Trees planted in the buffer and on wetland islands and peninsulas need watering
 during the first growing season. In general, consider watering every three3 days for first
 month, and then weekly during the first growing season (April -through October), depending
 on rainfall.
- Reinforcement Plantings. Regardless of the care taken during the initial planting of the stormwater wetland and buffer, it is probable that some areas will remain unvegetated and some species will not survive. Poor survival can result from many unforeseen factors, such as predation, poor quality plant stock, water level changes, and drought. Thus, it is advisable to budget for an additional round of reinforcement planting after one or two growing seasons. Construction contracts should include a care and replacement warranty extending at least two growing seasons after initial planting, to selectively replant portions of the stormwater wetland that fail to fill in or survive. If a minimum coverage of 50 percent is not achieved in the planted wetland zones after the second growing season, a reinforcement planting will be required.

Managing vegetation is an important ongoing maintenance task at every constructed wetland and for each inundation zone. Following the design criteria above should result in a reduced need for regular mowing of the embankment and access roads. Vegetation within the <u>stormwater</u> wetland, however, will require some annual maintenance.

Designers should expect significant changes in wetland species composition to occur over time. Inspections should carefully track changes in wetland plant species distribution over time. Invasive plants should be dealt with as soon as they begin to colonize the stormwater wetland. As a general rule, control of undesirable invasive species (e.g., cattails and Phragmites) should commence when their coverage exceeds more than 15-percent% of a wetland cell area. Although the application of herbicides is not recommended, some types (e.g., Glyphosate) have been used to control cattails with some success. Extended periods of dewatering may also work, since early manual removal provides only short-term relief from invasive species. While it is difficult to exclude invasive species completely from stormwater wetlands, their ability to take over the entire wetland can be reduced if the designer creates a wide range of depth zones and a complex internal structure within the wetland.

Thinning or harvesting of excess forest growth may be periodically needed to guide the forested stormwater wetland into a more mature state. Vegetation may need to be harvested periodically if the constructed wetland becomes overgrown. Thinning or harvesting operations should be scheduled to occur approximately 5 and 10 years after the initial stormwater wetland construction. Removal of woody species on or near the embankment and maintenance access areas should be conducted every 2 years.

Designers should refer to Section 3.10.7 Pond Maintenance Criteria for additional maintenance responsibilities associated with stormwater wetlands. Ideally, maintenance of constructed wetlands should be driven by annual inspections by a qualified professional that evaluateevaluates the condition and performance of the stormwater wetland. Based on inspection results, specific maintenance tasks will be triggered. DDOE'sDOEE's maintenance inspection checklist for stormwater wetlands and the Maintenance Service Completion Inspection form can be found in Appendix L-, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is <a href="https://docs.py.ncbe/https://docs.py.nc

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.11.8 Stormwater Wetland Stormwater Compliance Calculations

Stormwater wetlands receive 10-percent retention value and are an accepted total suspended solids (TSS) treatment practice for the amount of storage volume (Sv) provided by the BMP (Table 3.49).48).

Table 3.35 Stormwater Wetland Retention Value and Pollutant Removal

Retention Value	$=0.1 \times Sv$
Accepted TSS Treatment Practice	Yes

The retention achieved by stormwater wetlands also contributes to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the retention value from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a reduced NRCS CN for the site or SDA. The

reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.11.9 References

- Cappiella, K., T. Schueler and T. Wright. 2006. Urban Watershed Forestry Manual: Part 2: Conserving and Planting Trees at Development Sites. USDA Forest Service. Center for Watershed Protection. Ellicott City, MD.
- Hunt, W., M. Burchell, J. Wright and K. Bass. 2007. "Stormwater Wetland Design Update: Zones, Vegetation, Soil and Outlet Guidance." Urban Waterways. North Carolina State Cooperative Extension Service. Raleigh, NC.
- Minnesota Stormwater Steering Committee (MSSC). 2005. Minnesota Stormwater Manual. Emmons & Oliver Resources, Inc. Minnesota Pollution Control Agency. St. Paul, MN.
- Virginia DCR Stormwater Design Specification No. 13: Constructed Wetlands Version 1.8. 2010.

3.12 Storage Practices

Definition. Storage practices are explicitly designed to provide stormwater detention (2-year, 15-year, and/or flood control). Design variants include the following:

- S-1 Underground detention vaults and tanks——
- S-2 Dry detention ponds
- S-3 Rooftop storage
- S-4 Stone storage under permeable pavement or other BMPs

Detention vaults are box-shaped underground stormwater storage facilities typically constructed with reinforced concrete. Detention tanks are underground storage facilities typically constructed with large diameter metal or plastic pipe. (see Figure 3.43). Both serve as an alternative to surface dry detention for stormwater quantity control, particularly for space-limited areas where there is not adequate land for a dry detention basin or multi-purpose detention area. Prefabricated concrete vaults are available from commercial vendors. In addition, several pipe manufacturers have developed packaged detention systems.

Dry detention ponds are widely applicable for most land uses and are best suited for larger drainage areas an SDAs. An outlet structure restricts stormwater flow so it backs up and is stored within the basin- (see Figure 3.44). The temporary ponding reduces the maximum peak discharge to the downstream channel, thereby reducing the effective shear stress on the bed and banks of the receiving stream.

Storage practices do not receive any stormwater retention or treatment volume and should be considered only for management of larger storm events. Storage practices are not considered an acceptable practice to meet the SWRv. Storage practices must be combined with a separate facility to meet these requirements. Upland practices can be used to satisfy some or all of the stormwater retention requirements at many sites, which can help to reduce the footprint and volume of storage practices.





Figure 3.423.433.42.43 Example of an underground detention vault and/or tank (S-1).






Figure 3.433.443.43.44 Example of a dry detention pond (S-2).

3.12.1 Storage Feasibility Criteria

The following feasibility issues need to be evaluated when storage practices are considered as the final practice in a treatment train:

Space Required. A typical storage <u>practices practice</u> requires a footprint of 1 <u>to % _ 3 percent %</u> of its <u>contributing drainage areaCDA</u>, depending on the depth of the pond or storage vault (i.e., the deeper the practice, the smaller footprint needed).

Contributing Drainage Area. A contributing drainage area CDA of at least 10 acres is preferred for dry ponds in order to keep the required orifice size from becoming a maintenance problem. Designers should be aware that small "pocket" ponds will typically (1) have very small orifices that will be prone to clogging, (2) experience fluctuating water levels such that proper

stabilization with vegetation is very difficult, and (3) generate more significant maintenance problems.

Underground detention systems can be located downstream of other structural stormwater controls providing treatment of the design storm. For treatment train designs where upland practices are utilized for treatment of the SWRv, designers can use a site-adjusted Rv or NRCS CN that reflects the volume reduction of upland practices and likely reduce the size and cost of detention (see Storage Practice Sizing in Section 3.12.4-, "Storage Design Criteria).").

The maximum contributing drainage area<u>CDA</u> to be served by a single underground detention vault or tank is 25 acres.

Available Hydraulic Head. The depth of a storage practice is usually determined by the amount of hydraulic head available at the site (dimension between the surface drainage and the bottom elevation of the site). The bottom elevation is normally the invert of the existing downstream conveyance system to which the storage practice discharges. Depending on the size of the development and the available surface area of the basin, as much as 6 to 8 feet of hydraulic head may be needed for a dry detention practice to function properly for storage. An underground storage practice will require sufficient head room to facilitate maintenance—at least 5 feet depending on the design configuration.

Setbacks. To avoid the risk of seepage, stormwater cannot flow wa baseflow from storage practices must not be hydraulically connected to the traditional pavement base layer, existing structure foundations, or an area where there may be future development adjacent to the property line. Setbacks to structures and property lines must be at least 10 feet, and adequate water proofing waterproofing protection must be provided for foundations and basements.

Depth to Water Table and Bedrock. Dry ponds are not allowed if the water table or bedrock will be within 2 feet of the floor of the pond. For underground detention vaults and tanks, an anti-flotation analysis is required to check for buoyancy problems in the high water table areas.

Soils. The permeability of soils is seldom a design constraint for storage practices. Soil infiltration tests should be conducted at proposed dry pond sites to estimate infiltration rates and patterns, which can be significant in Hydrologic Soil Group (HSG) A soils and some group B soils. Infiltration through the bottom of the pond is typically encouraged unless it may potentially migrate laterally thorough a soil layer and impair the integrity of the embankment or other structure.

Structural Stability. Underground detention vaults and tanks must meet structural requirements for overburden support and traffic loading if appropriate as verified by shop drawings signed by an appropriately licensed professional.

Geotechnical Tests. At least one soil boring must be taken at a low point within the footprint of any proposed storage practice to establish the water table and bedrock elevations and evaluate soil suitability. A geotechnical investigation is required for all underground BMPs, including underground storage systems. Geotechnical testing requirements are outlined in Appendix O₇, "Geotechnical Information Requirements for Underground BMPs."

Utilities. For a dry pond system, no utility lines shall be permitted to cross any part of the embankment where the design water depth is greater than 2 feet. Typically, utilities require a minimum 5-foot horizontal clearance from storage facilities.

Perennial Streams. Locating dry ponds on perennial streams will require both a Section 401 and Section 404 permit from the appropriate state or federal regulatory agency.

3.12.2 Storage Conveyance Criteria

Designers must use accepted hydrologic and hydraulic routing calculations to determine the required storage volume and an appropriate outlet design for storage practices. See Section 2.710 Hydrology Methods for a summary of acceptable hydrologic methodologies and models.

For management of the 2-year storm, a control structure with a trash rack designed to release the required predevelopment Qp_2 must be provided. Ideally, the channel protection orifice should have a minimum diameter of 3 inches in order to pass minor trash and debris. However, where smaller orifices are required, the orifice must be adequately protected from clogging by an acceptable external trash rack.

As an alternative, the orifice diameter may be reduced if internal orifice protection is used (i.e., a perforated vertical stand pipe with 0.5-inch orifices or slots that are protected by wirecloth and a stone filtering jacket). Adjustable gate valves, weir manholes, and other structures designed for simple maintenance can also be used to achieve this equivalent diameter.

For overbank flood protection, an additional outlet is sized for Qp_{15} control and can consist of a weir, orifice, outlet pipe, combination outlet, or other acceptable control structure.

Riprap, plunge pools or pads, or other energy (histipaters/dissipators) are to be placed at the end of the outlet to prevent scouring and erosion and to provide a non-erosive velocity of flow from the structure to a water course. The design must specify an outfall that will be stable for the 15-year design storm event. The channel immediately below the storage practice outfall must be modified to prevent erosion. This is typically done by calculating channel velocities and flow depths, then placing appropriately sized riprap, over geotextile fabric, which can reduce flow velocities from the principal spillway to non-erosive levels (3.5 to 5.0 fpsfeet per second depending on the channel lining material). The storage practice geometry and outfall design may need to be altered in order to yield adequate channel velocities and flow.

Flared pipe sections that discharge at or near the stream invert or into a step pool arrangement should be used at the spillway outlet. An outfall analysis shall be included in the stormwater management planSWMP showing discharge velocities down to the nearest downstream water course. Where indicated, the developer <u>for</u> contractor must secure an off-site drainage easement for any improvements to the downstream channel.

When the discharge is to a manmade pipe or channel system, the system must be adequate to convey the required design storm peak discharge.

If discharge daylights to a channel with dry weather flow, care should be taken to minimize tree clearing along the downstream channel, and to reestablish a forested riparian zone in the shortest possible distance. Excessive use of rip-rapriprap should be avoided.

The final release rate of the facility shall be modified if any increase in flooding or stream channel erosion would result at a downstream structure, highway, or natural point of restricted streamflow (see Section 2.611 Additional Stormwater Management Requirements).

The following additional conveyance criteria apply to underground detention or ponds:

- High Flow Bypass (underground detention). An internal or external high flow bypass or overflow must be included in the underground detention designs to safely pass the extreme flood flow.
- **Primary Spillway (dry ponds).** The primary spillway shall be designed with acceptable anti-flotation, anti-vortex, and trash rack devices. The spillway must generally be accessible from dry land. When reinforced concrete pipe is used for the principal spillway to increase its longevity, "O"-ring gaskets (ASTM C-361C361) must be used to create watertight joints, and they should be inspected during installation.
- **Avoid Outlet Clogging (dry ponds).** -The risk of clogging in outlet pipes with small orifices can be reduced by the following:
 - Providing a micropool at the outlet structure. For more information on micropool extended detention ponds see Section 3.10 Stormwater Ponds.
 - Installing a trash rack to screen the low-flow orifice.
 - Using a perforated pipe under a gravel blanket with an orifice control at the end in the riser structure.
- Emergency Spillway (dry ponds). Dry ponds must be constructed with overflow capacity to safely pass the 100-year design storm event through either the primary spillway or a vegetated or armored emergency spillway unless waived by DDOEDOEE.
- Inlet Protection (dry ponds). Inflow points into dry pond systems must be stabilized to ensure that non-erosive conditions exist during storm events up to the overbank flood event (i.e., the 15-year storm event).

3.12.3 Storage Pretreatment Criteria

Dry Pond Pretreatment Forebay. A forebay must be located at each major inlet to a dry pond to trap sediment and preserve the capacity of the main treatment cell. The following criteria apply to dry pond forebay design:

- A major inlet is defined as an individual storm drain inlet pipe or open channel serving at least 10-percent% of the storage practice's contributing drainage areaCDA.
- The forebay consists of a separate cell, formed by an acceptable barrier (e.g., an earthen berm, concrete weir, gabion baskets, etc.).

- The forebay shall be sized to contain 0.1 inchesinch per impervious acre of contributing drainage. The relative size of individual forebays should be proportional to the percentage of the total inflow to the dry pond.
- The forebay should be designed in such a manner that it acts as a level spreader to distribute runoff evenly across the entire bottom surface area of the main storage cell.
- Exit velocities from the forebay shall be non-erosive or an armored overflow shall be provided. Non-erosive velocities are 4 feet per second for the two2-year event, and 6 feet per second for the 15-year event.
- The bottom of the forebay may be hardened (e.g., concrete, asphalt, or grouted riprap) in order to make sediment removal easier.
- Direct maintenance access for appropriate equipment shall be provided to the each forebay.

Underground Detention Pretreatment. A pretreatment structure to capture sediment, coarse trash, and debris must be placed upstream of any inflow points to underground detention. A separate sediment sump or vault chamber sized to capture 0.1 inchesinch per impervious acre of contributing drainage, or a proprietary structure with demonstrated capability of removing sediment and trash, should be provided at the inlet for underground detention systems that are in a treatment train with off-line water quality treatment structural controls. Refer to Section 3.13 Proprietary Practices for information on approved proprietary practices.

3.12.4 Storage Design Criteria

Dry Pond Internal Design Features. The following apply to dry pond design:

- No Pilot Channels. Dry ponds shall not have a low-flow pilot channel, but instead must be constructed in a manner whereby flows are evenly distributed across the pond bottom, to avoid scour, promote attenuation and, where possible, infiltration.
- **Internal Slope.** The maximum longitudinal slope through the pond should be approximately 0.5-to-%-1-percent.%.
- **Side Slopes.** Side slopes within the dry pond should generally have a gradient of 3H:1V to 4H:1V. The mild slopes promote better establishment and growth of vegetation and provide for easier maintenance and a more natural appearance. Ponds with side slopes steeper than 5H:1V must be fenced and include a lockable gate.
- Long Flow Path. Dry pond designs should have an irregular shape and a long flow path distance from inlet to outlet to increase water residence time, treatment pathways, pond performance, and to eliminate short-cutting. In terms of flow path geometry, there are two design considerations: (1) the overall flow path through the pond, and (2) the length of the shortest flow path (Hirschman et al., 2009):
 - ◆ The overall flow path can be represented as the length-to-width ratio OR the flow path ratio. These ratios must be at least 2L:1W (3L:1W preferred). Internal berms, baffles, or topography can be used to extend flow paths and/or create multiple pond cells.
 - The shortest flow path represents the distance from the closest inlet to the outlet. The ratio of the shortest flow to the overall length must be at least 0.4. In some cases——due

to site geometry, storm sewer infrastructure, or other factors—some inlets may not be able to meet these ratios. However, the <u>drainage areaCDA</u> served by these "closer" inlets must constitute no more than 20-percent% of the total <u>contributing drainage areaCDA</u>.

Safety Features. The following safety features must be considered for storage practices:

- The principal spillway opening must be designed and constructed to prevent access by small children.
- End walls above pipe outfalls greater than 48 inches in diameter must be fenced at the top of the wall to prevent a falling hazard.
- Storage practices must incorporate an additional 1 foot of freeboard above the emergency spillway, or 2 feet of freeboard if design has no emergency spillway, for the maximum Qf design storm unless more stringent Dam Safety requirements apply.
- The emergency spillway must be located so that downstream structures will not be impacted by spillway discharges
- Underground maintenance access should be locked at all times.

Maintenance Access. All storage practices shall be designed so as to be accessible to annual maintenance. Unless waived by the DOEDOEE, a 5:15H:1 v slope and 15-foot-wide entrance ramp is required for maintenance access to dry ponds. Adequate maintenance access must also be provided for all underground detention systems. Access must be provided over the inlet pipe and outflow structure with access steps. Access openings can consist of a standard 30-inch diameter frame, grate and solid cover, or a hinged door, or removable panel. Removable panels must be designed with sufficient support so they cannot fall through the opening into the vault when removed.

Outlets. Trash racks shall be provided for low-flow pipes and for risers not having anti-vortex devices.

In order to reduce maintenance problems for small orifices, a standpipe design can be used that includes a smaller inner standpipe with the required orifice size, surrounded by a larger standpipe with multiple openings, and a gravel jacket surrounding the larger standpipe. This design will reduce the likelihood of the orifice being clogged by sediment.

Detention Vault and Tank Materials. Underground stormwater detention structures shall be composed of materials as approved by the DDOEDOEE. All construction joints and pipe joints shall be water tight. Cast-in-place wall sections must be designed as retaining walls. The maximum depth from finished grade to the vault invert is 20 feet. The minimum pipe diameter for underground detention tanks is 24 inches unless otherwise approved by DDOEDOEE. Manufacturer's specifications should be consulted for underground detention structures.

Anti-floatation Analysis for Underground Detention. Anti-floatation analysis is required to check for buoyancy problems in the high water table areas. Anchors shall be designed to counter the pipe and structure buoyancy by at least a 1.2 factor of safety.

Storage Practice Sizing. Storage facilities should be sized to control peak flow rates from the 2-year and 15-year frequency storm event or other design storm. Design calculations must ensure that the post-development peak discharge does not exceed the predevelopment peak discharge. See Section 2.710 Hydrology Methods for a summary of acceptable hydrologicalhydrologic methodologies and models.

For treatment train designs where upland practices are utilized for treatment of the SWRv, designers can use a site-adjusted Rv or NRCS CN that reflects the volume reduction of upland practices to compute the Qp_2 and Qp_{15} that must be treated by the storage practice.

3.12.5 Storage Landscaping Criteria

No landscaping criteria apply to underground storage practices.

For dry ponds, a landscaping plan must be provided that indicates the methods used to establish and maintain vegetative coverage within the dry pond. Minimum elements of a plan include the following:

- Delineation of pondscaping zones within the pond.
- Selection of corresponding plant species.
- The planting plan.
- The sequence for preparing the wetland bed, if one is incorporated with the <u>Drydry</u> pond (including soil amendments, if needed).
- Sources of native plant material.
- The planting plan should allow the pond to mature into a native forest in the right places, but yet keep mowable turf along the embankment and all access areas. The wooded wetland concept proposed by Cappiella et al., (2005) may be a good option for many dry ponds.
- Woody vegetation may not be planted or allowed to grow within 15 feet of the toe of the embankment nor within 25 feet from the principal spillway structure.
- Avoid species that require full shade, or are prone to wind damage.

3.12.6 Storage Construction Sequence

Construction of underground storage systems must be in accordance with manufacturer's specifications. All runoff into the system should be blocked until the site is stabilized. The system must be inspected and cleaned of sediment after the site is stabilized.

The following is a typical construction sequence to properly install a dry pond. The steps may be modified to reflect different dry pond designs, site conditions, and the size, complexity, and configuration of the proposed facility.

- Step 1: Use of Dry Pond for Soil Erosion and Sediment Control. A dry pond may serve as a sediment basin during project construction. If this is done, the volume should be based on the more stringent sizing rule (soil erosion and sediment control requirement vs. water quality treatment requirement). Installation of the permanent riser should be initiated during the construction phase, and design elevations should be set with final cleanout of the sediment basin and conversion to the post-construction dry pond in mind. The bottom elevation of the dry pond should be lower than the bottom elevation of the temporary sediment basin. Appropriate procedures must be implemented to prevent discharge of turbid waters when the basin is being converted into a dry pond.
- **Step 2:** Stabilize the Contributing Drainage Area. Dry ponds should only be constructed after the contributing drainage areaCDA to the pond is completely stabilized. If the propose dry pond site will be used as a sediment trap or basin during the construction phase, the construction notes must clearly indicate that the facility will be dewatered, dredged, and re-graded to design dimensions after the original site construction is complete.
- **Step 3:** Assemble Construction Materials On-site <u>Site</u>. Inspect construction materials to <u>insureensure</u> they conform to design specifications, and prepare any staging areas.
- Step 4: Clear and StripGrade. Bring the project area to the desired sub-gradesubgrade.
- *Step 5:* **Soil Erosion and Sediment Controls.** Install soil erosion and sediment control measures prior to construction, including temporary stormwater diversion practices. All areas surrounding the pond that are graded or denuded during construction must be planted with turf grass, native plantings, or other approved methods of soil stabilization.
- **Step 6: Install the Spillway Pipe.** Ensure the top invert of the spillway pipe is set to design elevation.
- **Step 7: Install the Riser or Outflow Structure.** Once riser and outflow structures are installed, ensure the top invert of the overflow weir is constructed level and at the design elevation.
- Step 8: Construct the Embankment and any Internal Berms. These features must be installed Construct the embankment and berms in 8- to 12-inch lifts and compact the lifts with appropriate equipment.
- **Step 9:** Excavate and Grade. Survey to achieve the appropriate elevation and designed contours for the bottom and side slopes of the dry pond.
- *Step 10:* Construct the Emergency Spillway. The emergency spillway must be constructed in cut or structurally stabilized soils.
- *Step 11:* **Install Outlet Pipes.** The installation of outlet pipes must include a downstream riprapriprap protection apron.
- *Step 12:* **Stabilize Exposed Soils.** All areas above the normal pool elevation should be permanently stabilized by hydroseeding or seeding over straw.

Dry Pond Construction Supervision. Ongoing construction supervision is recommended to ensure that stormwater ponds are properly constructed. Supervision/inspection is recommended during the following stages of construction:

- Preconstruction meeting
- Initial site preparation including the installation of soil erosion and sediment control measures
- Excavation/Grading grading (interim and final elevations)
- Installation of the embankment, the riser/primary spillway, and the outlet structure
- Implementation of the pondscaping plan and vegetative stabilization
- Final inspection (develop a punch list for facility acceptance)

DDOE's DOEE's construction phase inspection checklist for storage practices and the Stormwater Facility Leak Test form can be found in Appendix K-, "Construction Inspection Checklists."

If the dry pond has a permanent pool, then to facilitate maintenance the contractor should measure the actual constructed dry pond depth at three areas within the permanent pool (forebay, mid-pond, and at the riser), and they should mark and geo-reference them on an as-built drawing. This simple data set will enable maintenance inspectors to determine pond sediment deposition rates in order to schedule sediment cleanouts.

3.12.7 Storage Maintenance Criteria

Typical maintenance activities for storage practices are outlined in Table 3.5049. Maintenance requirements for underground storage facilities will generally require quarterly visual inspections from the manhole access points by a qualified professional to verify that there is no standing water or excessive sediment buildup. Entry into the system for a full inspection of the system components (pipe or vault joints, general structural soundness, etc.) should be conducted annually. Confined space entry credentials are typically required for this inspection.

Table 3.36 Typical Maintenance Activities for Storage Practices

Schedule	Maintenance Activity	
As needed	 Water dry pond side slopes to promote vegetation growth and survival. 	
Quarterly	 Remove sediment and oil/grease from inlets, pretreatment devices, flow diversion structures, storage practices, and overflow structures. Ensure that the contributing drainage area CDA, inlets, and facility surface are clear of debris. Ensure that the contributing drainage area CDA is stabilized. Perform spot-reseeding where needed. Repair undercut and eroded areas at inflow and outflow structures. 	

Schedule	Maintenance Activity
	 Measure sediment accumulation levels in forebay. Remove sediment when 50% of the forebay capacity has been lost. Inspect the condition of stormwater inlets for material damage, erosion, or undercutting. Repair as necessary. Inspect the banks of upstream and downstream channels for evidence of sloughing, animal
	 burrows, boggy areas, woody growth, or gully erosion that may undermine pond embankment integrity. Inspect outfall channels for erosion, undercutting, rip rapriprap displacement, woody growth, etc.
Annual inspection	 Inspect condition of principal spillway and riser for evidence of spalling, joint failure, leakage, corrosion, etc.
	 Inspect condition of all trash racks, reverse sloped pipes, or flashboard risers for evidence of clogging, leakage, debris accumulation, etc.
	■ Inspect maintenance access to ensure it is free of debris or woody vegetation, and check to see whether valves, manholes, and locks can be opened and operated.
	 Inspect internal and external side slopes of dry ponds for evidence of sparse vegetative cover, erosion, or slumping, and make needed repairs immediately. Monitor the growth of wetlands, trees, and shrubs planted in dry ponds. Remove invasive species and replant vegetation where necessary to ensure dense coverage.

Maintenance of storage practices is driven by annual inspections that evaluate the condition and performance of the storage practice. Based on inspection results, specific maintenance tasks will be triggered.

 $\frac{DDOE'sDOEE's}{DOEE's} \ maintenance \ inspection \ checklists \ for extended \ detention \ ponds \ and \ the \ Maintenance \ Service \ Completion \ Inspection \ form \ can be found in \ Appendix \ L_{\tau}, \ "Maintenance \ Inspection \ Checklists."$

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. A maintenance schedule must appear on the SWMP. Additionally, a maintenance schedule is required in Exhibit C of the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.12.8 Storage Volume Compliance Calculations

Storage practices receive no retention value and <u>are not</u> an accepted total suspended solids (TSS) treatment practice for the amount of storage volume (Sv) provided by the practice (Table 3.5149). These practices should be used only for control of larger storm events.

Table 3.37 Storage Retention Value and Pollutant Removal

Retention Value	= 0
Accepted TSS Treatment Practice	No

3.12.9 References

- ASTM C361-16, Standard Specification for Reinforced Concrete Low-Head Pressure Pipe, ASTM International, West Conshohocken, PA, 2016, www.astm.org
- Cappiella, K., Schueler, T., and T. Wright. 2005. Urban Watershed Forestry Manual. Part 1: Methods for Increasing Forest Cover in a Watershed. NA-TP-04-05. USDA Forest Service, Northeastern Area State and Private Forestry. Newtown Square, PA.
- City of Austin. 1988. Design Guidelines for Water Quality Control Basins. City of Austin Environmental and Conservation Services Department, Environmental Resources Management Division. Austin, TX.
- Hirschman, D., L. Woodworth and S. Drescher. 2009. Technical Report: Stormwater BMPs in Virginia's James River Basin: An Assessment of Field Conditions & Programs. Center for Watershed Protection. Ellicott City, MD.
- Virginia DCR Stormwater Design Specification No. 15: Extended Detention (ED) Pond Version 1.8. 2010.

PROPOSED PENISION PROPOSED PRO

3.13 Proprietary Practices

Definition. Proprietary practices are manufactured stormwater treatment practices that utilize settling, filtration, absorptive/adsorptive materials, vortex separation, vegetative components, and/or other appropriate technology to manage the impacts stormwater runoff. The design includes the following:

M-1 Proprietary practices

Proprietary practices may be used to achieve treatment compliance, provided they have been approved by the District and meet the performance criteria outlined in this specification. Historically, proprietary practices do not provide retention volume. Proprietary practices A proprietary practice will not be valued for retention volume unless the practice can demonstrate the occurrence of retention processes.

3.13.1 Proprietary Practice Feasibility Criteria

Individual proprietary practices will have different site constraints and limitations. Manufacturer's specifications should be consulted to ensure that proprietary practices are feasible for application on a site-by-site basis.

3.13.2 Proprietary Practice Conveyance Criteria

All proprietary practices must be designed to safely overflow or bypass flows from larger storm events to downstream drainage systems. The overflow associated with the 2-year and 15-year design storms must be controlled so that velocities are non-erosive at the outlet point (i.e., to prevent downstream erosion).

Manufactured treatment devices may be constructed on-line or off-line. On-line systems receive upstream runoff from all storms, providing runoff treatment for the stormwater quality design storm and conveying the runoff from larger storms through an overflow. In off-line devices, most or all of the runoff from storms larger than the stormwater quality design storm bypass the device through an upstream diversion or other mechanism.

3.13.3 Proprietary Practice Pretreatment Criteria

Individual proprietary practices may require pretreatment, or may be appropriate for use as pretreatment devices. Manufacturer's specifications should be consulted to determine the device-specific pretreatment requirements.

3.13.4 Proprietary Practice Design Criteria

The basic design parameters for a proprietary practice will depend on the techniques it employs to control stormwater runoff and remove particulate and dissolved pollutants from runoff. In general, the design of devices that treat runoff with no significant storage and flow rate attenuation must be based upon the peak design flow rate. However, devices that do provide storage and flow rate attenuation must be based, at a minimum, on the design storm runoff

volume and, in some instances, on a routing of the design runoff hydrograph. Hydrologic design is discussed further in Appendix H_τ, "Acceptable Hydrologic Methods and Models."

Appendix S_Proprietary Practices Approval Process includes details of the verification process and the required data submittals for determination of proprietary practice performance.

Adequate maintenance access must be provided for all proprietary practice systems. Access, with access steps, as applicable, must be provided for the inlet pipe, outflow structure, and over any other functional components.

3.13.5 Proprietary Practice Landscaping Criteria

Proprietary devices may or may not require landscaping considerations. Manufacturer's specifications should be consulted to determine any landscaping requirements for the device

3.13.6 Proprietary Practice Construction Sequence

The construction and installation of individual proprietary practices will vary based on the specific proprietary practice. Manufacturer's specifications should be consulted to determine the device specific construction sequencing requirements. DDOE's DOEE's construction inspection checklist for generic structural BMPs can be found in Appendix K-, "Construction Inspection Checklists."

3.13.7 Proprietary Practice Maintenance Criteria

In order to ensure effective and long-term performance of a proprietary practice, regular maintenance tasks and inspections are required.

All proprietary practices should be inspected by a qualified professional and maintained in accordance with the manufacturer's instructions and/or recommendations and any maintenance requirements associated with the device's verification by DDOEDOEE.

DDOE's DOEE's maintenance inspection checklist for generic structural BMPs and the Maintenance Service Completion Inspection form can be found in Appendix L₇, "Maintenance Inspection Checklists."

Declaration of Covenants. A declaration of covenants that includes all maintenance responsibilities to ensure the continued stormwater performance for the BMP is required. The declaration of covenants specifies the property owner's primary maintenance responsibilities, and authorizes DDOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The declaration of covenants is attached torecorded in the deedDistrict of the property.Columbia land records. A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. A maintenance schedule must appear on the

SWMP. Additionally, a maintenance schedule is required in Exhibit C of the declaration of covenants.

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.13.8 Proprietary Practice Stormwater Compliance Calculations

Proprietary practices receive retention value when explicitly approved by the District. Pollutant removal (TSS EMC reduction) may be awarded for specific practices provided that they meet the performance criteria outlined in Section 3.13.4—"Proprietary Practice Design Criteria."

PROPOSED PENISION PROPOSED PRO

3.14 Tree Planting and Preservation

Definition. Existing trees can be preserved or new trees can be planted to reduce stormwater runoff. The design includes the following:

- T-1 Tree planting
- T-2 Tree preservation

Tree canopy can intercept a significant amount of rainfall before it becomes runoff, particularly if the tree canopy covers impervious <u>surface</u>, <u>suchsurfaces</u>, as in the case of street trees. Through the processes of evapotranspiration and nutrient uptake, trees<u>even when</u> located on a development site<u>have</u> the capacity to reduce stormwater runoff volumes and improve water quality. Further, through root growth, trees can improve the infiltration capacity of the soils in which they grow.

Both tree planting and tree preservation can contribute to stormwater management on a site. Note that retention value is available for preserved trees only when they are within the limits of disturbance of a project. Preserved trees outside of the limits of disturbance may offer an opportunity for additional retention when they constitute an area of natural cover and stormwater is conveyed to that area.

3.14.1 Preserving Existing Trees During Construction

The preferred method for increasing tree cover at a development site is to preserve existing trees during construction, particularly where mature trees are present. Existing trees are preserved during construction through a four-step process:

- **Step 1:** Inventory existing trees.
- **Step 2:** Identify trees to preserve.
- **Step 3:** Protect trees and soil during construction.
- **Step 4:** Protect trees after construction.

Inventory Existing Trees. A licensed forester or arborist must conduct an An inventory of existing trees and forested areas at the development site must be conducted before any site design, clearing, or construction takes place, as specified by the Urban Forestry Administration (UFA). DDOT UFD. The inventory must be conducted by one of the following landscape professionals:

- Maryland Licensed Forester
- Maryland Licensed Tree Expert
- Virginia Experienced Forester
- Maryland or Virginia Licensed Landscape Architect
- International Society of Arboriculture (ISA) Certified Arborist

The inventory must include a survey of existing trees and determine their size, species, condition, and ecological value. Locations of trees and forest stands must be recorded. Special Trees and Heritage Trees, defined by Tree Canopy Protection Amendment Act of 2016 as having a minimum circumference of 44 or 100 inches, respectively, will require special permitting and qualify for a higher retention credit.

Identify Trees to Preserve. From the tree inventory, individual trees can be identified for preservation and protection during site development. In order to receive Preserved trees fall into three categories of retention value, preserved trees must be a: tree species with an average mature spread of at least 35less than or equal to 40 feet. ("small" trees) receive 10 cubic feet of retention value; trees species with an average mature spread greater than or equal to 40 feet ("large" trees) receive 20 cubic feet of retention value; and Special Trees/Heritage Trees receive 40 cubic feet of retention value, regardless of mature spread size. Additional selection criteria may include tree species, size, condition, and location (see Table 3.5251).

2EV151

Table 3.38 Selecting Priority Trees and Forests for Preservation

Selection Criteria for Tree Preservation	Examples of Priority Tree and Forests to Conserve		
Species	 Rare, threatened, or endangered species Specimen trees High quality tree species (e.g., white oaks and sycamores because they are structurally strong and live longer than trees such as silver maple and cottonwood) Species that are tolerant of specific site conditions and soils 		
Size	 Trees over a specified diameter at breast height (d.b.h.)DBH) or other size measurement Trees designated as national, state, or local champions Contiguous forest stands of a specified minimum area 		
Condition	 Healthy trees that are structurally sound in "fair" or better condition High quality forest stands with high forest structural diversity 		
Location	 Trees located where they will provide direct benefits at the site (e.g., shading, privacy, windbreak, buffer from adjacent land use) Forest stands that are connected to off-site forests that create wildlife habitat and corridors Trees located in protected natural areas such as floodplains, stream buffers, wetlands, erodible soils, critical habitat areas, and steep slopes. Forest stands that are connected to off-site non-forested natural areas or protected land (e.g., has potential to provide wildlife habitat) 		

Trees selected for preservation and protection must be clearly marked both on construction drawings and at the actual site. Flagging or fencing is typically used to protect trees at the construction site. Areas of trees to preserve should be marked on the site map and walked during preconstruction meetings.

Protect Trees and Soil During Construction. Physical barriers must be properly installed around the Critical Root Zone (CRZ) of trees to be preserved. The CRZ shall be determined by a licensed forester or ISA certified arboristlandscape professional from the above list, and in general includes a circular area with a radius (in feet) general includes a circular area with a radius (in feet) general to 1.5 times the feet of tree protection (radius of circle) for every 1 inch in tree diameter—of—For example, a 10-inch diameter tree would have a CRZ radius extending 15 feet from the trunk (in inches). Tree. The barriers must be maintained and enforced throughout the construction process. Tree protection barriers include highly visible, well-anchored temporary protection devices, such as 6-foot-tall chain link or 4-foot fencing, blaze orange plastic mesh fencing, or wooden snow fencing (Greenfeld and others, 1991).

All protection devices must remain in place throughout construction

When excavation is proposed immediately adjacent to the CRZ, roots must first be pruned at the edge of the excavation with a trenching machine, vibratory knife or rock saw to a depth of 18 inches.

Protect Trees After Construction. Maintenance covenants, as described below, are required to ensure that preserved trees are protected.

3.14.2 Planting Trees

Considerations at Development Sites. New development sites provide many opportunities to plant new trees. Planting trees at development sites is done in three steps:

- **Step 1:** Select tree species.
- **Step 2:** Evaluate and improve planting sites.
- **Step 3:** Plant and maintain trees.

Tree Species. In order to receive Planted trees fall into two categories of retention value, the: tree species planted must have with an average mature spread of at least 35 less than or equal to 40 feet. ("small" trees) receive 5 cubic feet of retention value and trees species with an average mature spread greater than or equal to 40 feet ("large" trees) receive 10 cubic feet of retention value. Trees to be planted must be container grown, or ball and burlap, and have a minimum caliper size of 1.5 inches. Bare root trees or seedlings do not qualify for retention value.

Refer to the planting guides provided by DOEE's Green Area Ratio Guidebook, DDOT Green Infrastructure Standards, and Casey Trees Urban Tree Selection Guide to determine plant species' average mature spread.

Planting Sites. Ideal planting sites within a development are those that create interception opportunities around impervious surfaces. These include areas along pathways, roads, islands and median strips, and parking lot interiors and perimeters. Other areas of a development site may benefit from planting trees (including stream valleys and floodplains, areas adjacent to existing forest, steep slopes, and portions of the site where trees would provide buffers, screening, noise reduction, or shading).

It is important to evaluate and record the conditions, such as soil type, soil pH, soil compaction, and the hydrology of proposed planting sites to ensure they are suitable for planting. These evaluations provide a basis for species selection and determination of the need for any special site preparation techniques.

A minimum of 1,500 cubic feet of rootable soil volume must be provided per <u>large</u> tree. In planting arrangements that allow for shared rooting space amongst multiple trees, a minimum of 1,000 cubic feet of rootable soil volume must be provided for each <u>tree.large tree</u>. Rootable soil volume must be within 3 feet of the surface.

Smaller trees with an average mature spread of less than or equal to 40 feet must have a minimum of 600 cubic feet of rootable soil volume. In planting arrangements that permit shared rooting space amongst multiple trees, a minimum of 400 cubic feet of rootable soil volume must be provided for each tree. Rootable soil volume must be within 3 feet of the surface.

Site characteristics determine what tree species will flourish there and whether any of the conditions, such as soils, can be improved through the addition of compost or other amendments. Table 3.5352 presents methods for addressing common constraints to urban tree planting.

Table 3.39 Methods for Addressing Urban Planting Constraints

Potential Impact	Potential Resolution		
Limited Soil Volume	 Provide 1,500 cubic feet of rootable soil volume per treelarge tree (greater than or equal to 40-foot spread) and 600 cubic feet of rootable soil volume per small tree (less than or equal to 40-foot spread). This soil must be within 3 feet of the surface. Use planting arrangements that allow shared rooting space. A minimum of 1-,000 cubic feet of rootable soil volume must be provided for each large tree in shared rooting space arrangements. Provide 1500 A minimum of 400 cubic feet of rootable soil volume per tree 		

Potential Impact	Potential Resolution	
	(this soil must be within 3 feet of the surface) provided for each small tree in shared rooting arrangements.	
Poor Soil Quality	 Test soil and perform appropriate restoration. Select species tolerant of soil pH, compaction, drainage, etc. Replace very poor soils if necessary. 	
Air Pollution	■ Select species tolerant of air pollutants.	
Damage from Lawnmowers	■ Use mulch to protect trees.	
Damage from Vandalism	 Use tree cages or benches to protect trees_ Select species with inconspicuous bark or thorns_ Install lighting nearby to discourage vandalism_ 	
Damage from Vehicles	Provide adequate setbacks between vehicle parking stalls and trees.	
Damage from animals such as deer, rodents, rabbits, and other herbivores	■ Use protective fencing or chemical retardants.	
Exposure to pollutants in stormwater and snowmelt runoff	Select species that are tolerant of specific pollutants, such as salt and metals.	
Soil moisture extremes	Select species that are tolerant of inundation or drought. Install underdrains if necessary Select appropriate backfill soil and mix thoroughly with site soil. Improve soil drainage with amendments and tillage if needed.	
Increased temperature	Select drought tolerant species.	
Increased wind	Select drought tolerant species_	
Abundant populations of invasive species	 Control invasive species prior to planting. Continually monitor for and remove invasive species. 	
Conflict with infrastructure	 Design the site to keep trees and infrastructure separate. Provide appropriate setbacks from infrastructure. Select appropriate species for planting near infrastructure. Use alternative materials to reduce conflict. 	
Disease or insect infestation	Select resistant species	

Planting trees at development sites requires prudent species selection, a maintenance plan, and careful planning to avoid impacts from nearby infrastructure, runoff, vehicles or other urban elements.

Trees Along Streets and in Parking Lots. When considering a location for planting, clear lines of sight must be provided, as well as safe travel surfaces, and overhead clearance for pedestrians and vehicles. Also, ensure enough future-soil volume for healthy tree growth. At least two cubic feet of useable soil per square foot of average mature tree canopy is required. (Useable Usable soil must be uncompacted, and may not be covered by impervious material), unless structural

<u>soils or other tree soil systems are utilized.</u> Having at least a 6-foot-wide planting strip or locating sidewalks between the trees and street allows more rooting space for trees in adjacent property.

Select tree species that are drought tolerant, can grow in poor or compacted soils, and are tolerant to typical urban pollutants (oil and grease, metals, and chlorides). Additionally, select species that do not produce excessive fruits, nuts, or leaf litter, that have fall color, spring flowers or some other aesthetic benefit, and can be limbed up to 6 feet to provide pedestrian and vehicle traffic underneath. The District Department of Transportation, Urban Forestry Administration (DDOT UFA) The DDOT UFD provides guidance on preferred street tree species based on neighborhoods.

Planting Techniques. Prepare a hole no deeper than the root ball or mass but two to three times wider than the spread of the root ball or mass. The majority of the roots on a newly planted tree will develop in the top 12 inches of soil and spread out laterally. There are some additional considerations depending on the type of plant material being used (Table 3.5453).

Table 3.40 Tree Planting Techniques

Plant Material	Planting Technique	Planting Season
Bare root	Hand plant	Spring or fall when tree is dormant
Container grown	Hand plant or use mechanical planting tools (e.g., auger)	Spring or fall, summer if irrigated
Balled and burlapped	Use backhoe (or other specialized equipment) or hand plant	Spring or fall

Sources: Palone and Todd (1998), WSAHGP (2002)

One of the most important planting guidelines is too make sure the tree is not planted too deeply. The root collar, the lowest few inches of trunk just above its junction with the roots (often indicated by a flare), should be exposed (Flott, 2004). Trees planted too deeply have buried root collars, and are weakened, stressed, and predisposed to pests and disease (Flott, 2004). Trees planted too deeply can also form adventitious roots near the soil surface in an attempt to compensate for the lack of oxygen available to buried roots. Adventitious roots are not usually large enough to provide support for a large tree and may eventually lead to collapse (Flott, 2004). ISA (2005) provides additional guidance on how to avoid planting too deeply. It is generally better to plant the tree a little high, that is, with the base of the trunk flare 2 to 3 inches above the soil, rather than at or below the original growing level (ISA, 2003b).

Proper handling during planting is essential to avoid prolonged transplant shock and ensure a healthy future for new trees and shrubs. Trees should always be handled by the root ball or container, never by the trunk. Specifications for planting a tree are illustrated in Figure 3.4245. Trees must be watered well after planting.




Figure 3.443.44.45 Tree planting guidelines. (Adapted from Flott, 2004 and ISA, 2003b).

Steep slopes require additional measures to ensure planting success and reduce erosion, especially if the slope receives stormwater runoff from upland land uses. Depending on the steepness of the slope and the runoff volume, rill or gully erosion may occur on these slopes, requiring a twofold approach: controlling the stormwater and stabilizing the slope.

Erosion control blankets are recommended to temporarily stabilize soil on slopes until vegetation is established (Caraco, 2000; Morrow and others, 2002). Erosion control fabrics come in a variety of weights and types, and should be combined with vegetation establishment such as seeding. Other options for stabilizing slopes include applying compost or bark mulch, plastic sheeting, or sodding (Caraco, 2000).

Trees will add stability to slopes because of their deep roots, provided they are not planted by digging rows of pits across a slope (Morrow and others, 2002). Required maintenance will include mowing (if slopes are not too steep), and establishing cover on bare or eroded areas.

Planting methods for slopes steeper than 3:1 (1 foot vertical change for every 3 horizontal feet)3H:1V involve creating a level planting space on the slope (see Figure 3.4346). A terrace can be dug into the slope in the shape of a step. The existing slope can be cut and the excavated soil can be used as fill. A low soil berm (or rock berm) can be formed at the front edge of each step or terrace to slow the flow of water. Trees can also be planted in clusters on slopes (using the above method) to limit potential for desiccation. Staggering tree placement and mulching will prevent water from running straight downhill.




Figure 3.453.463.45.46 The specifications for planting on a steep slope, require creating a level planting surface.

Post-Planting Tree Protection. Once the tree has been properly planted, 2 to 4 inches of organic mulch must be spread over the soil surface out to the drip line (the outermost circumference of the tree canopy) of the tree. If planting a cluster of trees, mulch the entire planting area. Slow-decomposing organic mulches, such as shredded bark, compost, leaf mulch, or wood chips provide many added benefits for trees. Mulch that contains a combination of chips, leaves, bark, and twigs is ideal for reforestation sites. (ACB, 2000; ISA, 2003a). Grass clippings and sawdust are not recommended as mulches because they decompose rapidly and require frequent application, resulting in reduced benefits.

For well-drained sites, up to 4 inches of mulch may be applied, and for. For poorly drained sites, a thinner layer of mulch should be applied. Mulch should never be more than 4 inches deep or applied right next to the tree trunk; however, a common sight in many landscaped areas is the "mulch volcano". This over-mulching technique can cause oxygen and moisture-level problems, and decay of the living bark at the base of the tree. A mulch-free area, 2- to 3-inches wide at the base of the tree, must be provided to avoid moist bark conditions and prevent decay (ISA, 2003a).

Studies have shown that trees will establish more quickly and develop stronger trunk and root systems if they are not staked at the time of planting-(ISA, 2003b). Staking for support may be necessary only for top-heavy trees or at sites where vandalism or windy exposure are a concern (Buckstrup and Bassuk, 2003; Doherty and others, 2003; ISA, 2003b).

If staking is necessary for support, two stakes used in conjunction with a wide flexible tie material will hold the tree upright, provide flexibility, and minimize injury to the trunk. To prevent damage to the root ball, stakes should be placed in undisturbed soil beyond the outer edges of the root ball. Perhaps the most important part of staking is its removal. Over time, guy wires (or other tie material) can cut into the growing trunk bark and interfere with the movement of water and nutrients within the tree. Staking material should be removed within 1 year of planting (Doherty and others, 2003).

3.14.3 Tree Inspection Criteria

An initial inspection by a qualified professional must be done to ensure the tree has been planted, watered, and protected correctly with locations flagged if appropriate. For newly planted trees, transplant shock is common and causes stress on a newthe tree. For this reason, newly planted trees must be inspected more frequently than established trees. The time it takes for a tree to become established varies with the size at planting, species, stock, and site conditions, but generally, trees should be inspected every few months during the first 3 years after planting, to identify problems and implement repairs or modify maintenance strategies (WSAHGP, 2002).

After the first 3 years, annual inspections are sufficient to check for problems. Trees must also be inspected after major storm events for any damage that may have occurred. The inspection should take only a few minutes per tree, but prompt action on any problems encountered results in healthier, stronger trees. Inspections should include an assessment of overall tree health, an assessment of survival rate of the species planted, cause of mortality, if maintenance is required, insect or disease problems, tree protection adjustment, and weed control condition.

 $\frac{\text{DDOE's} \underline{\text{DOEE's}}}{\text{construction phase inspection checklist for tree planting and preservation can}} be found in Appendix K_-, "Construction Inspection Checklists."}$

3.14.4 Tree Maintenance Criteria

Water newly planted trees regularly (at least once a week) during the first growing season. Water trees less frequently (about once a month) during the next two growing seasons. After three growing seasons, water trees only during drought. The exact watering frequency will vary for each tree and site.

A general horticultural rule of thumb is that trees need 1 inch of rainfall per week during the growing season (Petit and others, 1995). This means new trees need a minimum of 25 gallons of water a week to stay alive ().(http://caseytrees.org/get-involved/water/). Water trees deeply and slowly near the roots. Light, frequent watering of the entire plant can actually encourage roots to grow at the surface. Soaker hoses and drip irrigation work best for deep watering of trees. It is recommended that slow leak watering bags or tree buckets are installed to make watering easier and more effective. Continue watering until mid-fall, tapering off during lower temperatures.

Pruning is usually not needed for newly planted trees but may be beneficial for tree structure. If necessary, prune only dead, diseased, broken or crossing branches at planting (Doherty and others, 2003; Trowbridge and Bassuk, 2004). As the tree grows, lower branches may be pruned to provide clearance above the ground, or to remove dead or damaged limbs.

 $\frac{DDOE'sDOEE's}{DOEE's} \ maintenance \ inspection \ checklist \ for \ tree \ planting \ and \ preservation \ and \ the \ Maintenance \ Service \ Completion \ Inspection \ form \ can \ be \ found \ in \ Appendix \ L_{\overline{r},} \ "Maintenance \ Inspection \ Checklists."$

Declaration of Covenants. A maintenance covenant is required for all stormwater management practices. The covenant specifies the property owner's primary maintenance responsibilities, and authorizes DOEDOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The covenant is attached torecorded in the deedDistrict of the propertyColumbia land records (see standard form, variations exist for scenarios where stormwater crosses property lines). A template form is provided at the end of Chapter 5 Administration of Stormwater Management Rules (see Figure 5.411), although variations will exist for scenarios where stormwater crosses property lines. The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. There may be a maintenance schedule on the drawings themselves or the plans may refer to the maintenance schedule (Exhibit C in the covenant).

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

Waste Material. Waste material from the repair, maintenance, or removal of a BMP or land cover shall be removed and disposed of in compliance with applicable federal and District law.

3.14.5 Tree Stormwater Compliance Calculations

Trees receive retention value but they are not accepted total suspended solids (TSS) treatment practices.

To ensure appropriate stormwater benefits associated with proposed tree preservation or planting, all trees receiving retention value must be properly maintained until redevelopment of the area occurs. If trees die they must be replaced with a <u>tree of similar treemature spread</u> no longer than 6 months from time of death in an appropriate location.

Preserved trees that meet the requirements described above receive located within a retention value site's limits of disturbance (LOD) that meet the requirements described above receive a retention value of 10, 20, or 40 cubic feet each, depending upon the size of the mature spread of the tree and whether the tree is designated as Special or Heritage. Planted trees that meet the requirements described above receive a retention value of 5 or 10 cubic feet each, depending upon the size of the mature spread of the tree.

In order to receive the preserved tree retention value, trees must be left undisturbed in their original location. Trees that are removed and replanted are not considered preserved trees.

Note: Trees planted as part of another BMP, such as a bioretention area, also receive the <u>5 or 10</u> cubic foot retention value. Retention values are shown in <u>Tables Table 3.54 and Table 3.55 and 3.56 below.</u>

Table 3.41 Preserved Tree Retention Value and Pollutant Removal

	Small Trees (average spread ≤ 40 feet)	<u>Large Trees</u> (average spread > 40 feet)	Special Trees and Heritage Trees (> 44-inch circumference)
Retention Value	= 10 ft ³ (75 gallons)	$= \frac{20cf}{20 \text{ ft}^3} (150 \text{ gallons})$	<u>= 40 ft³ (300 gallons)</u>
Accepted TSS Treatment Practice	No	No	<u>No</u>

Table 3.42 Planted Tree Retention Value and Pollutant Removal

	Small Trees (average spread ≤ 40 feet)	Large Trees (average spread > 40 feet)
Retention Value	= 5 ft ³ (37.5 gallons)	$= \frac{10cf}{10 \text{ ft}^3} (75 \text{ gallons})$
Accepted TSS Treatment Practice	<u>No</u>	No

Trees also contribute to peak flow reduction. This contribution can be determined in several ways. One method is to subtract the retention value from the total runoff volume for the 2-year, 15-year, and 100-year storms. The resulting reduced runoff volumes can then be used to calculate a Reduced Natural Resource Conservation Service (reduced NRCS) Curve Number CN for the site or drainage area. SDA. The Reduced Curve Number reduced NRCS CN can then be used to calculate peak flow rates for the various storm events. Other hydrologic modeling tools that employ different procedures may be used as well.

3.14.6 References

- Alliance for the Chesapeake Bay (ACB). 2000. Pennsylvania Stream ReLeaf forest buffer toolkit. Harrisburg, PA: Pennsylvania Department of Environmental Protection.
- Arendt, R. G. 1996. Conservation design for subdivisions. A practical guide to creating open space networks. Washington, DC: Island Press. 184 p.
- Bassuk, N.; Curtis, D. F.; Marranca, B. Z.; Neal, B. 2003. Recommended urban trees: site assessment and tree selection for stress tolerance. Ithaca, NY: Cornell University, Urban Horticulture Institute. 127 p. www.hort.cornell.edu/uhi/ (Accessed December 28, 2005).
- Buckstrup, M.; Bassuk, N. 2000. Transplanting success of balled-and-burlapped versus bare-root trees in the urban landscape. Journal of Arboriculture 26(6): 298-308.

- Cappiella, K.; Schueler, T.; Wright, T. 2006. Urban Watershed Forestry Manual. United States Department of Agriculture Forest Service. Newtown Square, PA.
- Caraco, D. 2000. Keeping soil in its place. In: Schueler, T.; Holland, H., eds. The practice of watershed protection. Ellicott City, MD; 323-328.
- Casey Trees. 2015. Urban Tree Selection Guide. Washington, DC. https://issuu.com/caseytrees
- Center for Watershed Protection. 1998. Better site design: a handbook for changing development rules in your community. Ellicott City, MD. 174 p.
- Cornell University. 2004. Conducting a street tree inventory. Ithaca, NY: Cornell University, Department of Horticulture.
 - www.hort.cornell.edu/commfor/inventory/index.html (Accessed December 28, 2005).
- <u>District of Columbia Department of Transportation.</u> 2014. Green Infrastructure Standards. Washington DC.
 - https://ddot.dc.gov/sites/default/files/dc/sites/ddot/publication/attachments/2014-Final%20DDOT%20Green%20Infrastructure%20Standards.pdf
- District of Columbia Department of Energy and Environment Natural Resources Administration.

 2017. Green Area Ratio Guidebook. Washington, DC.

 https://doee.dc.gov/sites/default/files/dc/sites/ddoe/service-content/attachments/GARGuidebook FINAL November2017 0.pdf
- Doherty, K.; Bloniarz, D.; Ryan, H. 2003. Positively the pits: successful strategies for sustainable streetscapes. Tree Care Industry 14(11): 34-42.

 www.umass.edu/urbantree/publications/pits.pd http://www.umass.edu/urbantree/publications
 - www.umass.edu/urbantree/publications/pus.pdf http://www.umass.edu/urbantree/publications/pits.pdf (Accessed 2006).
- Flott, J. 2004. Proper planting begins below ground. TreeLink 19: 1-4.
- Georgia Forestry Commission (GFC). 2002. Community tree planting and establishment guidelines. Dry Branch, GA.
- Gilman, E. F. 1997. Trees for urban and suburban landscapes. Albany, NY: Delmar Publishers.
- Greenfeld, J.; Herson, L.; Karouna, N.; Bernstein, G. 1991. Forest conservation manual: guidance for the conservation of Maryland's forests during land use changes, under the 1991 Forest Conservation Act. Washington, DC: Metropolitan Washington Council of Governments. 122 p.
- Hairston-Strang, A. 2005. Riparian forest buffer design and maintenance. Annapolis: Maryland Department of Natural Resources.
 - $\frac{http://www.dnr.state.md.us/forests/download/rfb_design\&maintenance.pdf \underline{http://dnr.marylan}}{d.gov/forests/Pages/publications.aspx}$

- Head, C.; Robinson, F.; O'Brien, M. 2001. Best management practices for community trees: a guide to tree conservation in Athens-Clarke County, Georgia. Athens, GA: Athens-Clarke County Unified Government.
- International Society of Arboriculture (ISA). 2005. Avoiding excessive soil over the root systems of trees. Arborist News, April.
- International Society of Arboriculture (ISA). 2003a. Proper mulching techniques. Champaign, IL: International Society of Arboriculture.
 - www.treesaregood.com/treecare/mulching.aspxhttp://treesaregood.org/portals/0/docs/treecare/ProperMulching.pdf (Accessed 2006).
- International Society of Arboriculture (ISA). 2003b. New tree planting. Champaign, IL:
 International Society of Arboriculture. www.treesaregood.com/treecare/tree_planting.aspx
 (Accessed 2006).
- Johnson, G. R. 2005. Protecting trees from construction damage: a homeowner's guide. St. Paul, MN: Regents of the University of Minnesota.
 - www.extension.umn.edu/distribution/housingandelothing/DK6135.htmlhttp://www.extension.umn.edu/garden/yard-garden/trees-shrubs/protecting-trees-from-construction-damage/(Accessed December 28, 2005).
- Kochanoff, S., 2002. Trees vs. power lines: priorities and implications in Nova Scotia. Presented at the 5th Annual Canadian Urban Forest Conference. Markham, ON.
- Maryland National Capital Parks and Planning Commission. 1992. Trees. Approved Technical Manual. Maryland National Capital Parks and Planning Commission, Montgomery County, MD. 144 p. http://www.montgomeryplanning.org/en/vironment/forest/trees/toc_trees.shtm
- Meyer, D. 1993. Tree shelters for seedling protection and increased growth. Forestry Facts 59. Madison, WI: University of Wisconsin Extension.
- Minnesota Department of Natural Resources. 2000. Conserving wooded areas in developing communities. BMPs in Minnesota. Minnesota Department of Natural Resources, St. Paul, MN. 113 p.
 - $\frac{www.dnr.state.mn.us/forestry/urban/bmps.html}{(Accessed December 28, 2005)}.$
- Morrow, S.; Smolen, M.; Stiegler, J.; Cole, J. 2002. Using vegetation for erosion control. Landscape Architect 18(11): 54-57.
- Nebraska Forest Service. 2004. Tree selection and placement. Storm Damage Bulletin No. 7. http://digitalcommons.unl.edu/cgi/viewcontent.cgi?article=1068&context=nebforestpubs
- Palone, R. S.; Todd, A. H., eds. 1998. Chesapeake Bay riparian handbook: a guide for establishing and maintaining riparian forest buffers. NA-TP-02-97. Radnor, PA: USDA Forest Service, Northeastern Area State and Private Forestry.

- Pennsylvania State University. 1999. A guide to preserving trees in development projects.
 University Park, PA: Penn State College of Agricultural Sciences, Cooperative Extension. 27 p.
- Pennsylvania State University (PSU). 1997. Questions about trees and utilities. Forestry Fact Sheet #7. University Park: Pennsylvania State University, College of Agricultural Sciences.
- Petit, J.; Bassert, D. L.; Kollin, C. 1995. Building greener neighborhoods. Trees as part of the plan. Washington, DC: American Forests and the National Association of Homebuilders.
- Schueler, T. R. 1995. Site planning for urban stream protection. Ellicott City, MD: Center for Watershed Protection. 232 p.
- Schueler, T.; Brown, K. 2004. Urban stream repair practices. Version 1.0. Manual 4 of the Urban Subwatershed Restoration Manual Series. Ellicott City, MD: Center for Watershed Protection.
- Sweeney, B. W. 1993. Effects of streamside vegetation on macroinvertebrate communities of White Clay Creek in Eastern North America. In: Proceedings of the Academy of Natural Sciences of Philadelphia. Philadelphia, PA; 291-340.
- Tree Care Industry Association (TCIA). 2004. ANSI A300 Standards for tree care operations.

 Manchester, NH; www.natlarb.com/content/laws/a 300.htmManchester, NH;

 https://www.tcia.org/TCIA/BUSINESS/ANSI A300 Standards /TCIA/BUSINESS/A300 Standards/A300 Standards.aspx?hkey=202ff566-4364-4686-b7c1-2a365af59669 (Accessed 2005).
- Trowbridge, P.; Bassuk, N. 2004. Trees in the urban landscape: site assessment, design, and installation. Hoboken, NJ: John Wiley & Sons, Inc.
- USDA Forest Service. 1998. Volunteer training manual. Amherst, MA: Northeast Center for Urban and Community Forestry. 86 p. www.umass.edu/urbantree/volmanual.pdf (Accessed December 28, 2005).
- Washington State Aquatic Habitat Guidelines Program (WSAHGP). 2002. Integrated streambank protection guidelines. Olympia, WA. Unpaginated.

Chapter 4 Selecting and Locating the Most Effective Stormwater Best Management Practice System

4.1 Choosing Stormwater Management Best Practices (BMPs)

This chapter outlines a general process for selecting appropriate <u>best management practices</u> (BMPs) at a development site. Guidelines are presented for choosing which BMPs can meet the retention and treatment volume targets for design storms and which BMPs are most feasible when various site constraints are present.

This chapter represents guidelines, not rules, to determine the most appropriate BMP for a site. It is important to note that certain BMP design modifications or specific site characteristics may allow for a particular BMP to become better suited at a particular location. Several of these design modifications are noted in the following tables and are described in more detail in the individual BMP specifications (see Chapter 3):, "Stormwater Best Management Practices (BMPs)").

The following questions organize a framework for decision making:

Regulatory Criteria

Can the BMP meet all stormwater sizing criteria at the site or are a combination of BMPs needed?

Land Use Factors

Which practices are best suited for the proposed land use at this site?

Physical Feasibility Factors

Are there any physical constraints at the project site that may restrict or preclude the use of a particular BMP?

Community and Environmental Factors

Do the remaining BMPs have any important community or environmental benefits or drawbacks that might influence the selection process?

Location and Permitting Considerations

What environmental features must be avoided or considered when locating the BMP system at a site to fully comply with District and federal regulations?

4.2 Regulatory Compliance

Table 4.1 summarizes the capability of each BMP to meet the stormwater management sizing criteria outlined in Chapter 2_{τ_a} "Minimum Control Requirements." Designers can use Table 4.1 to screen BMP options to determine whether a particular BMP can meet the SWRv storage, peak discharge (Qp₂, Qp₁₅, and Q_f), and pollutant removal requirements. Finding that a particular BMP cannot meet a requirement does not necessarily mean that it should be eliminated from consideration. This screening process can reduce BMP options to a manageable number and determine whether a single BMP or a group of BMPs will be needed to meet stormwater sizing criteria at the site.

The following are key considerations for compliance:

- Stormwater Retention Volume (SWRv) Storage. A single BMP may not be capable of meeting the SWRv requirement. This column can assist in identifying supplemental practices.
- Quantity Control (Qp₂, Qp₁₅, or Q_f). These columns show whether a BMP can typically meet the peak discharge requirements.
- Pollutant Removal. This column examines the capability of each BMP option to remove total suspended solids (TSS) from stormwater runoff.

Note: Table 4.1 should be used as a guide for how practices typically perform. Individual designs may be sized or designed with greater or lesser capabilities than are indicated in the table.

Table 4.1 BMP Selection Based on Regulatory Criteria

Code	ВМР	SWRv Storage	Qp ₂ /Qp ₁₅ Control	Q _f Control	TSS Removal
G-1	Extensive Green Roof		•	×	N/A
G-2	Intensive Green Roof	•	•	LXI	N/A
R-1	Rainwater Harvesting	•	•	X	N/A
D-1	Simple Disconnection to a Pervious Area				
D-2	Simple Disconnection to a Conservation Area	•	X	×	NO
D-3	Simple Disconnection to a Soil Compost Amended Filter Path				NO
P-1	Porous Asphalt				NT/A
P-2	Pervious Concrete	•	•	X	N/A or
P-3	Permeable Pavers				Yes*
B-1	Traditional Bioretention		•		
B-2	Streetscape Bioretention		•		7.4
B-3	ExpandedEngineered Tree Pits	•	•	X	N/A or
B-4	Stormwater Planters		•	1/-	Yes*
B-5	Residential Rain Gardens		•		
F-1	SurfaceNonstructural Sand Filter				
F-2	1 Chamber UndergroundSurface Sand Filter	1 _			
F-3	3Three-Chamber Underground Sand Filter	\boxtimes	X	X	Yes
F-4	Perimeter Sand Filter	1			
I-1	Infiltration Trench		_		27/4
I-2	Infiltration Basin		•	X	N/A
O-1	Grass Channels	0			No
O-2	Dry <u>SwaleSwales/Bioswales</u>		X	X	Yes
O-3	Wet SwaleSwales	X			Yes
P <u>C</u> -1	Micropool Extended Detention Pond				
<u>₽</u> C-2	Wet Pond	\boxtimes	•	•	Yes
<u>₽</u> <u>C</u> -3	Wet Extended Detention Pond	1			
W-1	Shallow Wetland				37
W-2	Extended Detention Shallow Wetland		•	•	Yes
S-1	Underground Detention Vaults and Tanks				
S-2	Dry Extended Detention Pond Ponds				
<u>S-3</u>	Rooftop Storage	\boxtimes	•	•	No
<u>S-4</u>	Stone Storage Under Permeable Pavement or	1			
	Other BMPs	<u> </u>	<u> </u>		
<u>PPM</u> -1	Proprietary Practices Practices	X	X	X	Yes
TPT-1	Tree Preservation	•	X	X	No
TP <u>T</u> -2	Tree Planting S. • Partial: X - Minor or No Renefit			_	

 $[\]bullet$ = Yes; \bullet = Partial; \boxtimes = Minor or No Benefit

4.3 Land Use Factors

^{*} Depends upon design type.

Designers can use Table 4.2 to evaluate BMPs that are best suited to a particular land use, including highly urbanized areas.

The following are key considerations for land use factors:

- Residential. This column identifies the best treatment options in medium to high density residential developments.
- Commercial Development. This column identifies practices that are suitable for new commercial development.
- Roads and Highways. This column identifies the best practices to treat runoff from major roadway and highway systems.
- Hotspot Land Uses. This column examines the capability of BMPs to treat runoff from designated hotspots. BMPs that receive hotspot runoff may have design restrictions, as noted.

Table 4.2 BMP Selection Based on Land Use Screening Factors

Code	ВМР	Residential	Commercial	Roads and	Hotspots
G-1	Extensive Green Roof			Highways	-
G-1	Intensive Green Roof	•	•	X	X
R-1	Rainwater Harvesting		. •	X	X
D-1	Simple Disconnection to a Pervious Area				
D-2	Simple Disconnection to a Conservation Area			•	X
D-3	Simple Disconnection to a Soil Compost Amended Filter Path			•	L)
P-1	Porous Asphalt				
P-2	Pervious Concrete	•	•	①	X
P-3	Permeable Pavers				
B-1	Traditional Bioretention		•	•	
B-2	Streetscape Bioretention		•	•	
B-3	Expanded Engineered Tree Pits	•	•	•	2
B-4	Stormwater Planters		•	X	
B-5	Residential Rain Gardens		X	X	
F-1	SurfaceNonstructural Sand Filter			•	
F-2	1 Chamber UndergroundSurface Sand Filter	-		•	
F-3	3 <u>Three</u> -Chamber Underground Sand Filter	X	•	•	•
F-4	Perimeter Sand Filter			•	
I-1	Infiltration Trench			0	[V]
I-2	Infiltration Basin	•	•	•	\boxtimes
O-1	Grass Channel			•	(2)
O-2	Dry Swale	_	•	•	· ·

Code	ВМР	Residential	Commercial	Roads and Highways	Hotspots
O-3	Wet Swale				
PC-1	Micropool Extended Detention Pond				
<u>₽C</u> -2	Wet Pond	•	•	◉	3
₽ <u>C</u> -3	Wet Extended Detention Pond				
W-1	Shallow Wetland			•	3)
W-2	Extended Detention Shallow Wetland			•	(3)
S-1	Underground Detention Vaults and Tanks	X	•	•	
S-2	Dry Pond Detention Ponds	•	•	•	
<u>S-3</u>	Rooftop Storage	X	•	X	\boxtimes
<u>S-4</u>	Stone Storage Under Permeable Pavement or Other BMPs	•	•	•	
<u>PPM</u> -	Proprietary Practice Practices	•	•	•	
TP <u>T</u> -	Tree Preservation) (
TP <u>T</u> - 2	Tree Planting				

- \bullet = Yes; \odot = Maybe; \boxtimes = No
- ①- Recommended for low volume roads or parking lanes
- ②-Yes, only if designed with an impermeable liner
- 3-May require pond liner to reduce the risk of GWgroundwater contamination

4.4 Physical Feasibility Factors

Typically, the designer narrows the BMP selection list based on regulatory goals and land use constraints before considering physical feasibility factors. Table 4.3 identifies the typical physical conditions needed for each type of BMP. Designers can use Table 4.3 to screen BMP options to determine whether the soils, water table, site drainage area, (SDA), slope, or head conditions present at a particular development site might limit the use of a BMP. These factors are intended as guidelines rather than requirements.

The following are key considerations for physical feasibility:

- Underlying Soils. The designer should use NRCS hydrologic soils maps to generally identify expected soils and their locations at the site. More detailed geotechnical tests are required during BMP design to evaluate infiltration feasibility and related design parameters. Once the infiltration rate at a site has been measured, use this column and Table 4.4 to identify recommended design criteria for proposed BMPs that have an infiltration option.
- **Distance to Water Table.** Measure the depth of the groundwater and estimate the depth of the seasonally high water table (see Appendix O)—, "Geotechnical Information Requirements for Underground BMPs"). Use this column as an aid to determine recommended BMP sizing.
- Contributing Drainage Area. Delineate the contributing drainage area (CDA) to the proposed BMP, and use this column as an aid to determine the appropriate sizing factor. If

the <u>drainage areaCDA</u> present at a site is slightly greater than the maximum allowable <u>drainage areaCDA</u> for a practice, some leeway is permitted. Likewise, the minimum <u>drainage areasCDAs</u> indicated for ponds and <u>stormwater</u> wetlands should not be considered inflexible limits, and may be increased or decreased depending on water availability (baseflow or groundwater) or the mechanisms employed to prevent clogging or ensure an impermeable pond bottom.

- Practice Surface Slope. Evaluate the site topography. Determine the potential for cut and fill
 operations. Use this column as an aid to evaluate BMP surface slope restrictions.
 Specifically, the slope restrictions refer to how flat the area where the practice is installed
 must be.
- Head. To evaluate BMP options, determine the elevation of the discharge point, and use this
 column as an aid to estimate the elevation difference needed from the inflow to the outflow
 to allow for gravity operation.

Table 4.3 BMP Selection Based on Physical Feasibility Screening Factors

Code	BMP List	Underlying Soils	Distance to Water Table (ft)	Contributing Drainage Area (ac)	Practice Surface Slope (%)	Head (ft)	
G-1	Extensive Green Roof	27/4	NT/ 4	green roof	1 08	27/4	
G-2	Intensive Green Roof	N/A	N/A	surface area+	1–2 ^a	N/A	
R-1	Rainwater Harvesting	N/A	N/A	no limit	N/A	N/A	
D-1	Simple Disconnection to a Pervious Area				< 5		
D-2	Simple disconnection to a conservation area Conservation Area	all soils	all soils N/A	< 1,000 ft ² per rooftop downspout ^b	< 6	N/A	
D-3	Simple Disconnection to a Soil Compost Amended Filter Path				< 5		
P-1	Porous Asphalt	all soils					
P-2	Pervious Concrete	$\frac{4K_{sat}}{10.5}$ in./hr may	2	$2-5 \times practice$	< 5	2–4	
P-3	Permeable Pavers	require underdrains)	2	surface area	<i>\</i>	2-4	
B-1	Traditional Bioretention	all soils	2	< 2.5	< 1	4–5	

Code	BMP List	Underlying Soils	Distance to Water Table (ft)	Contributing Drainage Area (ac)	Practice Surface Slope (%)	Head (ft)
B-2	Streetscape Bioretention	$(i\underline{K}_{\underline{sat}} < 0.5$		< 1		
B-3	Expanded Engineered Tree Pits	in./hr may require		< 1		
B-4	Stormwater Planters	underdrains)		< 1		
B-5	Residential Rain Gardens	·		< 1		
F-1	Surface Nonstructural Sand Filter			< <u>52</u>		5
F-2	1 Chamber UndergroundSurface Sand Filter	all soils	2	$< \frac{10,000 \text{ ft}^2}{5}$	N/A	5—10
F-3	3 <u>Three</u> -Chamber Underground Sand Filter			< 2	. (5–10
F-4	Perimeter Sand Filter			< 2		2–3
I-1	Infiltration Trench	$\pm \underline{K}_{\underline{\text{sat}}} > 0.5 \text{ in/hr}$	2	< 2	<1	2
I-2	Infiltration Basin	is preferred	2	< 5		2
O-1	Grass Channel	all soils	2			1
O-2	Dry Swale	all soils $(\frac{1}{2} \underline{K}_{sat} < 0.5)$ in./hr may require underdrains)	2	< 2.5	<4	3–5
O-3	Wet Swale	$\frac{1}{4} \underline{K_{sat}} < 0.5$ in./hr	intersect WT			1
<u>PC</u> -1	Micropool Extended Detention Pond	soils $\frac{1}{2} \frac{K_{sat}}{M_{sat}} > 0.5$ in./hr may	N/A	10–25		6–8
<u>₽C</u> -2	Wet Pond	require pond	N/A	10–25	< 1	6–8
<u>₽C</u> -3	Wet Extended Detention Pond	liner	N/A	10–25		6–8
W-1 W-2	Shallow Wetland Extended Detention Shallow Wetland	soils <u>iKsat</u> > 0.5 in./hr may require pond liner	N/A N/A	> 25°	< 1	2–4
S-1	Underground Detention Vaults and Tanks	0	no restrictions	no restrictions	< 1	> 5
S-2	Dry Extended Detention Pond		2	> 10 ^d	< 1	6–8
<u>S-3</u>	Rooftop Storage	all soils	no restrictions	no limit	<u>N/A</u>	<u>N/A</u>
<u>S-4</u>	Stone Storage Under Permeable Pavement or Other BMPs		<u>2</u>	<u>< 2.5</u>	<u><1</u>	<u>> 5</u>
PP-1	Proprietary Practice	All soils	2	design dependent	N/A	2–5
TP-1	Tree Preservation		N/A	N/A	27/4	27/4
TP-2	Tree Planting	All soils	N/A	N/A	N/A	N/A

Notes: $\stackrel{:}{:}=$ infiltration rate or permeability $\underline{K}_{sat}=$ saturated hydraulic conductivity, WT_= water table, N/A_= not applicable

a Green roof slope can be up to 25% if baffles are used to ensure detention of the design storm.

b For impervious areas other than rooftop, the longest contributing impervious area flow path cannot exceed 75 feet.

Code	BMP List	Underlying Soils	Distance to Water Table (ft)	Contributing Drainage Area (ac)	Practice Surface Slope (%)	Head (ft)
------	----------	---------------------	---------------------------------------	--	-------------------------------------	--------------

c The required head for bioretention areas can be reduced in small applications or when an upturned or elevated underdrain design is used.

Table 4.4 Selection of Infiltration BMPs Based on Measured Infiltration Rate*Saturated Hydraulic Conductivity

		Measured Infiltration Ra	teSaturated Hydraulic Conductivity (in./hi	r)
		Less than ≤ 0.25	0.25-to0.5	More than≥ 0.5
De	ecommended esign olution	Use Bioretention, Dry Swale, or Permeable Pavement (likely with an underdrain). Do not use Infiltration Trench/Basin.	Use Bioretention, Dry Swale, or Permeable Pavement (likely with an underdrain). It may be beneficial to include an infiltration sump below the underdrain invert. Infiltration Trench/Basin may not be appropriate.	Use Infiltration Trench/Basin, Bioretention, Dry Swale, or Permeable Pavement without an underdrain.

^{*}Designers must use ½ of the measured infiltration rate for design purposes, as indicated in the design equations given in Chapter 3.

4.5 Community and Environmental Factors

Designers can use Table 4.5 to compare the BMP options with regard to maintenance, habitat, community acceptance, cost, safety, space consumption, and other environmental factors. Table 4.5 employs a comparative index approach to rank the benefits of community and environmental factors as high, medium, or low.

The following are key considerations for community and environmental factors:

- **Maintenance Burden.** This column identifies the relative maintenance effort needed for each BMP option, in terms of the frequency of scheduled maintenance, chronic maintenance problems (such as clogging), and reported failure rates. All BMPs require routine inspection and maintenance (see Appendix L-, "Maintenance Inspection Checklists).").
- Cost. This column ranks BMPs according to their relative construction cost per cubic foot of stormwater retained, as determined from cost surveys and local experience.
- Safety Risk. This column provides a comparative index of the potential safety risks of each BMP option, when designed according to the performance criteria outlined in Chapter 3_{7,2} "Stormwater Best Management Practices (BMPs)". The index is included to highlight the need for considerations of liability and public safety in locations, such as residential, public

d No limit but practical drainage area CDA limitations may exist due to minimum orifice size (e.g., 1-inch diameter with internal orifice).

e CDA can be smaller if the practice intersects the water table.

space, schools, and others. A comparatively higher risk BMP may require signage, fencing, or other measures needed to alert the general public or maintenance provider of a potentially harmful situation.

- **Space Required.** This column provides a comparative index of the amount of space each BMP option typically consumes at a site. It may be helpful to consider this factor at an early stage of design because many urban BMPs are constrained by availability of open land.
- Environmental Factors. This column assesses the range of environmental factors considered under the Green Area Ratio (GAR) process to identify the broader human and environmental beneficial intersections some BMPs provide. For instance, some BMPs contribute to air quality improvements and reduce the urban heat island effect.
- Habitat Value. This column evaluates the ability of BMPs to provide wildlife or wetland
 habitat, assuming that an effort is made to landscape them appropriately. Objective criteria
 include size, water features, wetland features, and vegetative cover of the BMP and its buffer.
- Other Factors. This column indicates other considerations in BMP selection.

Table 4.5 BMP Selection Based on Community and Environmental Factors

G-1 E G-2 I R-1 E	25101 112.51	221101122111		17711111	33000				Ī
G-1 E G-2 I R-1 E		Domlar	Cost*	Dill	D	Donofile	T/cl-s	Other Factors	T
	G-1 Extensive Green Roof	Г	Н				Г	Increases structural	
	Intensive Green Roof	M	Н	L	L	Н	M	loading on building	
	Rainwater Harvesting	T	M	L	Т	Н	L		
D-1	Simple Disconnection to a Pervious Area								
D-2 S	Simple Disconnection to a Conservation Area	ı	ı	L	Σ	M	J		
D-3	Simple Disconnection to a Soil Compost Amended Filter Path								
P-1 F	P-1 Porous Asphalt								
P-2 II	Pervious Concrete	н	н	2	7	M	ı		
P-3 F	Permeable Pavers				1				
B-1	Traditional Bioretention	M	T	T	M	Н	M	Can be used as landscaping features	
		Н	Н		M		M		
B-3	ExpandedEngineered Tree Pits	M	Н		J		W		
	Stormwater Planters	Г	M		Г		Г		_
_	Residential Rain Gardens	Г	Γ		Γ		M		7
	SurfaceNonstructural Sand Filter	M	l,	Г	M			Minimize concrete	$\overline{\mathbf{A}}$
	1 Chamber UndergroundSurface Sand Filter	Н	Z:	∑ ;	긔,	J	J		Del
F-7 F-4	♣ I hree-Chamber Underground Sand Filter Perimeter Sand Filter	ΗW	ΞZ	Z L	JÆ			Out of sight Traffic bearing	etec
	Infiltration Trench	Т	M	Г	M	Г	Т		l Cel
1-2 I	Infiltration Basin reases on a per cuerc root of stormware recard							Frequent pooling	lls

Other Factors	Out of sight		Trash/debris	High pond premium			Limit ED depth			Possible mosquitoes					Mottes, H. High; M Medium; LLow * Cost based on \$ per eubic foot of stormwater treated
Habitat Value	4	Ţ	Ħ		#	Π	: 4	ı	4		*				
Environmental Benefits	7	₩		⇉		Ħ		¥					5		
Space Required	7	Ħ		茸		#		*			1/5)			
Safety Risk	*		*		4		≉		4						
Cost*	Ħ	4		4		*	1	*							
Maintenance Burden	*	*	耳		茸	M			♯		#			 	
BMPList	Underground Detention	.Dry. Pond	Micropool Extended Detention Pond	Wet Pond	Wet Extended Detention Pond	Challout Matland	Extended Detention Shallow Wetland	Grass Channel		Amarc (17)	Wet Swale			1	
Code	\$ 1	2 S	1	<u>5 d</u>	P 3	W 1		1			7				

Code	BMP List	Maintenance Burden	Cost*	Safety Risk	Space Required	Environmental Benefits	Habitat Value	Other Factors
0-1	Grass Channel	$\overline{\mathbb{W}}$	ī				ī	
0-2	Dry Swale	Ħ	$\overline{\mathbb{M}}$	I	\boxtimes	M	コ	
0-3	Wet Swale	Ħ	$\overline{\mathbb{M}}$				$\overline{\mathbb{M}}$	Possible mosquitoes
C-1	Micropool Extended Detention Pond	M					긔	Trash/debris
C-2	Wet Pond	Ħ	T	\boxtimes	H	M	Ħ	High pond premium
C-3	Wet Extended Detention Pond	Ħ					H	
W-1	Shallow Wetland		7.4	Ī	-	11	;	
W-2	Extended Detention Shallow Wedand	M	M	M	피	Π	피	Limit ED depth
S-1	Underground Detention Vaults and Tanks		H		Ī	Ī		Out of sight
<u>S-2</u>	Dry Detention Pond	Č	Ī		H	$\overline{\mathbb{W}}$		
S-3	Rooftop Storage		Ī	M	T	ī	Ţ	
S-4	Stone Storage Under Permeable Pavement or Other BMPs		寸		Ī	$\overline{\mathbb{W}}$		
Notes:	Notes: H = High; M = Medium: L=Low * Cost based on \$ per cubic foot of stormwater treated)	X					
]			,		11/51	,05		

4.6 Location and Permitting Considerations

In this step, the designer follows an environmental features checklist that asks whether any of the following are present at the site: wetlands, <u>surface</u> waters-of the <u>United States</u>, floodplains, and development infrastructure. Brief guidance is then provided on how to locate BMPs to avoid impacts to sensitive resources. <u>If a BMP must be located within a sensitive environmental area, a brief summary of applicable permit requirements is provided.</u>

In the last step, a designer assesses the physical and environmental features at the site to determine the optimal location for the selected BMP or group of BMPs (Table 4.5). The checklist below (Table 4.6) provides a condensed summary on current BMP restrictions as they relate to common site features that may be regulated under District or federal law. These restrictions fall into one of three general categories:

- 1. Locating a BMP within an area that is expressly *prohibited* by law.
- **2.** Locating a BMP within an area that is *strongly discouraged*, and is only allowed on a case by case basis. District and/or federal permits shall be obtained, and the applicant will need to supply additional documentation to justify locating the BMP within the regulated area.
- **3.** BMPs must be *set back* a fixed distance from the site feature.

This checklist is only intended as a general guide to location and permitting requirements as they relate to siting of stormwater BMPs. Consultation with the appropriate regulatory agency is the best strategy.

Table 4.6 Location and Permitting Considerations

Site Features and Relevant Agencies	Location and Permitting Guidance
Jurisdictional-Wetland U.S. Army Corps of Engineers Section 404 Permit Section 401 Water Quality Certification	 Delineate wetlands prior to locating BMPs. Use of natural wetlands for stormwater management is <i>strongly discouraged</i>. BMPs are also <i>restricted</i> in the 25₋ to 100–foot required wetland buffer. Buffers may be utilized as a non-structural filter strip (i.e., accept sheetflow). Must justify that no practical upland treatment alternatives exist. Stormwater must be treated to meet the District's water quality standards prior to discharge into a wetland. Where practical, excess stormwater flows should be conveyed away from jurisdictional and isolated wetlands.
Stream Channel (Waters of the U.S.) U.S. Army Corps of Engineers Section 404 Permit	 Delineate stream channels prior to design. In-stream ponds (should be located near the origin of first order streams) are strongly discouraged and require review and permit. Must justify that no practical upland treatment alternatives exist. Temporary runoff storage (peak flow management) is preferred over permanent pools. Implement measures that reduce downstream warming.

Chapter 4 Selecting and Locating the Most Effective Stormwater Best Management Practice System

Site Features and Relevant Agencies	Location and Permitting Guidance
100 Year Floodplain District of Columbia Homeland Security and Emergency Management Agency Department of Energy and Environment	■ When other on-site locations are available, DOEE discourages construction of BMPs in the floodplain because they may require more intensive maintenance. ■ SignficantSignificant grading and fill for BMP construction within the 100-year floodplain, as delineated by FEMA Flood Insurance Rate Maps (FIRM) may be restricted with respect to impacts on surface elevation (DCMRTitle 20 of the District of Columbia Municipal Regulations, Chapter 31 Flood Hazard Rules →).
Utilities	 Locate existing utilities prior to design. Note the location of proposed utilities to serve new construction. Consult with each Utility on their recommended offsets Consider altering the location or sizing of the BMP to avoid or minimize the utility conflict. Consider an alternate BMP type to avoid conflict. Use design features to mitigate the impacts of conflicts that may arise by allowing the BMP and the utility to coexist. The BMP design may need to incorporate impervious areas, through geotextiles or compaction, to protect utility crossings. Other On a key design feature may need to be moved or added or deleted. Coordinate with Utilities to allow them to replace or relocate their aging infrastructure during construction. If utility functionality, longevity, and vehicular access to manholes can be assured, accept the BMP design and location with the existing utility. Incorporate into the BMP design sufficient soil coverage over the utility or general clearances or other features such as an impermeable linear to assure all entities the conflict is limited to maintenance. When accepting utility conflict into BMP design, it is understood that the BMP will be temporarily impacted during utility work but the utility will replace the BMP or, alternatively, install a functionally comparable BMP according to the specifications in the current version of this Stormwater Management Guidebook, guidebook. If the BMP is located in the public right-of-way the BMP restoration will also conform with the District of Columbia Department of Transportation Design and Engineering Manual with special attention to Chapter 33, Chapter 47,28 and the Design and Engineering Manual supplements for Low Impact Development and Green Infrastructure Standards and Specifications.
Public Right-of-Way (PROW) District Department of Transportation	 BMP installation in PROW will require a DDOT Public Space Permit. Consult DDOT for guidance on placement and any setback requirement from local roads.

Site Features and Relevant Agencies	Location and Permitting Guidance
Structures	 Consult review authority for BMP setbacks from structures. Recommended setbacks for each BMP group are provided in the
District Department of Transportation	performance criteria in Chapter 3-, "Stormwater Best Management Practices (BMPs)."
District of Columbia Water and Sewer Authority	
Department of Consumer and Regulatory Affairs	

4.7 References

Galli, John. 1992. Analysis of Urban BMP Performance and Longevity in Prince George's County, Maryland. Prepared for Prince George's County Department of Environmental Resources Watershed Protection Branch. Prepared by Metropolitan Washington Council of Governments, Department of Environmental Programs. Washington DC.

Chapter 5 Administration of Stormwater Management Rules

5.11.1Stormwater Management Plans

5.1 Administration

5.1.1 Approval Requirements

Before the District of Columbia Department of Consumer and Regulatory Affairs (DCRA) may issue a building permit for any project requiring stormwater management, as described in Chapter 2, "Minimum Control Requirements" of this guidebook, the Department of Energy and Environment (DOEE) must approve a Stormwater Management Plan (SWMP) meeting the requirements of the Stormwater Management and Soil Erosion and Sediment Control Regulations (District of Columbia Municipal Regulations (DCMR) Title 21, Chapter 5).

For all major regulated projects, and projects for the generation of Stormwater Retention Credit (SRC), and submissions for the Stormwater Fee Discount, Credits (SRCs), the applicant is responsible for submitting a Stormwater Management Plan (SWMP) which SWMP that meets the requirements defined within the Stormwater Management and Soil Erosion and Sediment Control Regulation (District of Columbia Municipal Regulations (DCMR) Title 21, Chapter 5), and the details outlined within this guidebook. of this guidebook and of 21 DCMR, Chapter 5. Each SWMP submitted must be signed and sealed by a registered professional engineer, licensed in the District. All SWMP applications are reviewed by DDOEDOEE to determine compliance with the requirements of 21 DCMR, Chapter 5.


Some projects may also require an Environmental Intake Screening Form (EISF). This can be determined using DCRA's Environmental Intake Form (EIF). The EISF review process occurs concurrently with DOEE's SWMP review process. Both the EISF and EIF are available at https://dcra.dc.gov/service/permits-environmental-review. If the EISF is required, SWMP approval will not be granted until after EISF approval.

5.1.2 Fees

An applicant is responsible for paying fees that provide for the cost of review, administration, and management of the stormwater permitting process and inspection of all projects subject to the requirements of 21 DCMR, Chapter 5, Sections 516 through 539. These fees are posted on DOEE's website at https://doee.dc.gov/swregs within several tables and can be found in 21 DCMR, Chapter 5, Section 501. The fees are adjusted for inflation annually, using the Urban Consumer Price Index published by the United States Bureau of Labor Statistics.

DOEE charges review fees for all projects including major regulated projects, projects for the generation of SRCs, and projects requiring review for soil erosion and sediment control or Green Area Ratio. Refer to Figure 5.1 to determine when DOEE will charge review fees.

Note: A supplemental plan review fee is required for each DOEE review after first resubmission of a plan or for revisions to a plan after plan approval. Phased review requirements that follow the maximum extent practicable (MEP) process (see Appendix B, "Maximum Extent Practicable Process for Existing Public Right-of-Way") for a project, or portion of a project, entirely in the existing public right-of-way (PROW) are not required to pay a supplemental review fee.






Figure 5.1 Fees.

5.2 Stormwater Management Plans

5.2.1 Submittal and Review Process of Stormwater Management Plans

-A series of flow charts at the end of this chapter illustrate the SWMP review and approval process, within the overall context of the permitting process (see Figures 5.2 and 5.3). This process includes use of DOEE's Stormwater Database for submittal and review.

5.1.11.1.1 Submittal and Review Process of Stormwater Management Plans

AAn SWMP contains supporting computations, drawings, and sufficient information to evaluate the environmental characteristics of the affected areas, the potential impacts of the proposed development on water resources, the effectiveness and acceptability of stormwater best management practices (BMPs), and land covers for managing stormwater runoff; and maintenance and construction schedules. If the applicant proposes to use off site retention the SWMP must indicate the number of gallons the applicant is required to retain off site, termed

All SWMPs must include the Required Plan Compliance Sheet from DOEE's Stormwater Database. This includes the calculated Stormwater Retention Volume (SWRv) as well as any SRC eligibility or Off-Site Retention Volume (Offv)-) obligation. When submitting the SWMP for review, the applicant must submit compliance information online through the Stormwater Database. Additional information on this process is available in Appendix A, "Compliance Calculations and Design Examples" and online at https://doee.dc.gow/swdb.

The applicant submits—must upload one complete electronic set of the SWMP, including two sets carrying the stamp of certified by a registered-professional engineer licensed in the District of Columbia with all—to the Stormwater Database. The applicant must also upload each supporting documentation, to the District of Columbia Regulatory and Consumer Affairs (DCRA). Projects may be submitted in person-document listed in this chapter. If requested by DOEE's reviewer, the applicant must also provide one paper set of the SWMP, certified by a professional engineer licensed in the District of Columbia. Submit paper copies at the DCRA headquarters at 1100 4th Street SW, Second Floor, or through the DCRA online intake form available at http://epms.dcra.dc.gov/OCPI/Perm tMena.aspx.

Some projects, for example, when the application is Some submittals, including applications that are limited to Soil Erosion and Sediment Control Plans or Green Area Ratio, may be handled only require review by DDOEDOEE staff located at the DCRA intake counter. All other projects will be forwarded for review to DDOEDOEE Headquarters at 1200 First Street NWNE, Fifth Floor. Other District agencies with review authority will also evaluate a project's SWMP. For each project the applicant has the choice of submitting the SWMP electronically or in paper form. If the SWMP is submitted in paper form, then two plan sets of the project are required.

Upon receiving an application, <u>DDOEDOEE</u> will determine if the <u>application it</u> is complete and acceptable for review, accept it for review with conditions, or reject the <u>application it</u>. <u>DOEE will</u> not begin to review an SWMP until the applicant has paid filing fees.

Within 10 to 30 working days of the submission date of accepting an accepted complete application DDOE as complete (which includes payment of filing fees), DOEE will review the SWMP, and make a determination to approve, approve with conditions, or disapprove the SWMP. Relatively large and/or complicated projects tend to require longer review time than smaller and less complicated projects.

If it is determined that more information is needed or that a significant number of changes must be made before the SWMP can be approved, the applicant may withdraw the SWMP, make the necessary changes, and Relatively large and/or complicated projects tend to require longer review time than smaller and less complicated projects.

If it is determined that more information is needed or that a significant number of changes musbe made before the SWMP can be approved, the applicant may withdraw the SWMP, make the necessary changes, and re submit the SWMP. DDOE resubmit the SWMP. The applicant must update any information in the Stormwater Database that has been changed and include a new Required Plan Compliance Sheet as part of the SWMP. DOEE requires that all resubmissions contain a list of the changes made. A new 10—to 30-day review period begins on the date of the resubmission.

<u>If SWMP approval is denied, the reasons for the denial will be communicated to the applicant in writing.</u>

-day review period begins on the date of the resubmission.

If SWMP approval is denied, the reasons for the denial will be communicated to the applicant in writing.

When ean SWMP approval is granted, a final submission package is required, including

- One MylarPDF copy of the SWMP, certified by a registered professional engineer licensed in the District of Columbia, uploaded to the Stormwater Database per DOEE requirements.
- Seven paper copies of the SWMP, certified by a registered professional engineer licensed in the District of Columbia.
- A declaration of covenants that has been approved for legal sufficiency by the Office of the Attorney General (OAG). Government properties are exempt from this requirement but evidence of a maintenance partnership agreement or a maintenance memorandum of understanding is required prior to SWMP approval. Five additional types of SWMP submissions are not required to file a declaration of covenants, nor are they required to file easements. These are detailed in Section 2.12, "Exemptions."
- All supporting documents specified within this <u>SWMGguidebook</u> or as requested during the review process <u>by DDOE</u>must be uploaded to the <u>Stormwater Database</u>, <u>per DOEE</u> requirements.

Note: The District of Columbia is in the process of creating a single electronic submission, review, and approval process for all DCRA building permit applicants. When DCRA migrates to


the electronic submission process, this will become an alternate option for item 2 above in the final SWMP submission.

Note: DOEE may adopt an alternate format for these documents.

After the applicant submits a final package that, DOEE will review the declaration of covenants for technical sufficiency. If the final package meets the requirements for DDOE's DOEE's approval, DDOE provides the applicant with one approved copy of the SWMP for the applicant to file at the Recorder of Deeds with DOEE will approve the declaration of covenants and, if applicable, an easement.

Note: provide it to the applicant for recording. The applicant must submit the SWMP declaration of covenants to the Office of Attorney General (OAG) for legal sufficiency review. OAG approval is required before the SWMP can be filed with the Recorder of Deeds. Government Properties are exempt from this requirement but evidence of a maintenance partnership agreement or a maintenance memorandum of understanding is required prior to SWMP approval. There are six additional types of SWMP submissions that are not required to file a declaration of covenants, nor are they required to file easements. These are detailed in the exemptions Section 5.5 Exemptions.

The remaining approved paper copies of the approved SWMP are issued to the applicant after the submission of proof of filing the declaration of covenants, (or evidence of a maintenance partnership agreement or a maintenance memorandum of understanding in the case of a government owned project, and each applicable easement with the Recorder of Deeds, and proof of payment of applicable fee(s) for DDOE services DOEE services. After submission of proof of filing and payment, the approved SWMP is available to the applicant via the Stormwater Database.



DOEE approval of an SWMP will expire if the building permit or building permit application expires, with the exception of approvals for federal projects that are not required to obtain a building permit, in which case the SWMP will not expire unless the performance requirements of 21 DCMR, Chapter 5 change.






Figure 5.2 Plan review process.

PROPOSED REVISION PROPOSED REVISION




Figure 5.3

Upon job completion, the applicant must certify on the approved SWMP that all activities including clearing, grading, site stabilization, the preservation or creation of pervious land cover, the construction of drainage conveyance systems, the construction of BMPs, and all other stormwater related components of the project were accomplished in strict accordance with the approved SWMP.

Within 21 days of the final Construction inspection, the applicant must submit an as-built package, including one 1 Mylar copy of the as-built SWMP certified by a registered professional engineer licensed in the District of Columbia and one as-built form from Section 5.6 For a project consisting entirely of work in the public right of way, the submission of a Record Drawing certified by an officer of the project contracting company is acceptable if it details the as-built construction of the BMPs, related stormwater infrastructure and land covers and maintenance process.

5.2.2 SWMP Submittal Documents

The submission of aan SWMP is supported by these documents, as applicable:

- DC Water/DOEE Storm Sewer Verification Form
- As-Built Certification by Professional Engineer Form
- Statement By Professional Engineer Registered In the District of Columbia Form
- Statement By Person Responsible For Maintenance Form
- Statement By Person Responsible For Achieving Off-Site Retention Form
- Anacostia Waterfront Development Submittal InformationZone Site Form
- DC Water Storm Sewer Verification Form
- DCRA Application for Construction Permit on Private Property Vesting Status
- Declaration of Covenants Template
- Environmental Intake Form (EIF)
- Environmental Intake Screening Form (EISF)
- Environmental Questionnaire
- Reasonable Accommodations and Modifications for Persons with Disabilities Form
- DCRA Flood Hazard Development Form
- Environmental Intake Screening Form (EISF)
- Environmental Questionnaire
- DC Green Building Act Permit Application Intact Form
- 4. Contract Agreement
- Lead Permit Screening Form

- Zoning Data Summary Form
- Reasonable Accommodations and Modifications for Persons with Disabilities Form
- DCRA Flood Hazard Development Form

The forms 1 and 2 are foundForms not available in Section 5.6-, "Supporting-Forms-Forms-3 through 10" are available at the DCRA intake counter, or they can may be downloaded at http://dcra.dc.gov/sites/default/files/dc/sites/dcra/publication/attachments/permitpackage_0.pdf.

https://dcra.dc.gov/node/1245331. Note: In general, filing a Notice of Intent Form-with the US Environmental Protection Agency (EPA) is required if the project will disturb 4one or more acres of land, or is part of a common plan of development or sale that will ultimately disturb 4one or more acres of land-must file. Consult US-EPA's web site for details, https://www.epa.gov/npdes/2017-construction-general-permit-cgp

5.2.3 A Stormwater Management Plan (SWMP Components

A SWMP) includes the following:

Site Plan

The following information must be submitted on a standard drawing size of 24 inches by 36 inches. The site drawing will provide details of existing and proposed conditions:

- A cover page that contains a blank space measuring 7 inches wide by 9.5 inches high. The blank space must be located 1 inch below the top edge and 1 inch from the left edge of the page;
- 4-2. A plan showing property boundaries and the complete address of the property-;
- 2-3.Lot number, square number, or parcel number designation (if applicable)-);
- 3.4. North arrow, scale, and date-:
- 4.5. Property lines (include longitude and latitude).):
- 5.6.Location of easements (if applicable).);
- 6-7. Existing and proposed structures, utilities, roads, and other paved areas-;
- 7-8. Existing and proposed topographic contours-:
- 8.9. Soil information for design purposes:
- 9-10. Area(s) of soil disturbance-;
- 10.11. Volume(s) of excavation-;
- 11.12._Volume(s) of fill-:
- 12.13. Volume(s) of backfill-:
- 13.14. rainage Site drainage area(s) (SDAs) within the limits of disturbance (LOD) and contributing to the LOD.

- 15. Contributing drainage area (CDA) to each BMP;
- 16. Location(s) of BMPs, marked with the BMP ID Numbers assigned by the Stormwater Database;
- 14.17. Delineation of existing and proposed land covers including natural cover, compacted cover, and impervious surfaces. Consult Appendix N <u>Land Cover Designations</u> for details—on land cover designations.;
- 45.18. Location of existing stream(s), wetlands, or other natural features within the project area-;
- All plans and profiles must be drawn at a scale of 1 in. = 10 ft, 1 in. = 20 ft, 1 in. = 30 ft, 1 in. = 40 ft, 1 in. = 50 ft, or 1 in. = 80 ft. Although, 1 in. = 10 ft, 1 in = 20 ft, and 1 in. = 30 ft, are the most commonly used scales. Vertical scale for profiles must be 1 in. = 2 ft, 1 in. = 4 ft, 1 in. = 5 ft, or 1 in. = All plans and profiles must be drawn at a scale of 1 in. = 10 ft, 1 in. = 20 ft, 1 in. = 30 ft, 1 in. = 40 ft, 1 in. = 50 ft, or 1 in. = 80 ft. Although, 1 in. = 10 ft, 1 in. = 20 ft, and 1 in. = 30 ft, are the most commonly used scales. Vertical scale for profiles must be 1 in. = 2 ft, 1 in. = 4 ft, 1 in. = 5 ft, or 1 in. = 10 ft.

19. 10 ft;

- 16.20. Drafting media that yield first- or second-generation, reproducible drawings with a minimum letter size of No. 4 (1/8 inch)-);
- <u>17.21.</u> Location and size of existing utility lines including gas lines, sanitary lines, telephone lines or poles, and water mains-:
- 18.22. A legend identifying all symbols used on the plan-
- 19.23. Applicable flood boundaries for sites lying wholly or partially within the 100-year floodplain-;
- 20.24. Information regarding the mitigation of any off-site impacts anticipated as a result of the proposed development.
- 21.25. Stormwater Pollution Prevention Plan (SWPPP_{CGP}SWPPP) (for projects disturbing over an acre) or Good House Keeping House keeping Stamp (SWPPP_{min}), details provided in Appendix Q, "Pollution Prevention Through Good Housekeeping (for sites under an acre).);"
- 22.26. Stormwater Hotspot Cover Sheet and Checklists, details provided in Appendix P_{7.} "Stormwater Hotspots;"
- 23.27. Integrated Pest Management Plan (IPM) for sites in the AWDZ governed by the by the Anacostia Waterfront Environmental Standards Amendment Act of 2012. Consult Appendix R Integrated Pest Management for details on the IPM plan submission formata;
- 24.28. Construction specifications-:
- 25.29. Design and "As-Built" Certification, including the following:
 - a. Certification by a registered professional engineer licensed in the District that the site design, land covers, and design of the BMPs conforms to engineering principles applicable to the treatment and disposal of stormwater pollutants.; and

- b. Certification and submission of the As-Built Certification by Professional Engineer form (provided in at the end of this chapter) and one set of the "As Built" as-built plans within 21 days after completion of construction of the site, all BMPs, land covers, covers and stormwater conveyances. For a project consisting entirely of work in the public right of wayPROW, the submission of a Record Drawing certified by an officer of the project contracting company is acceptable if it details the as-built construction of the BMP and related stormwater infrastructure;
- 26.30. Maintenance of best management practices stormwater BMPs, including the following:
 - a. A maintenance plan that identifies routine and long-term maintenance needs and a maintenance schedule must be submitted as part of the SWMP.;
 - b. AFor major regulated projects, a declaration of covenants stating the owner's specific maintenance responsibilities identified in the maintenance plan and maintenance schedule. These must be exhibits recorded with the property deed, at the Recorder of Deeds. An example of a Declaration declaration of Covenants is provided at the end of this chapter. Government Though government-owned properties are exempt from the declaration of covenants requirement but evidence of a maintenance partnership agreement or a, long-term maintenance memorandum of understanding is required that identifies who will implement the maintenance plan and maintenance schedule.obligations are the same as for any other regulated site; and
 - c. For applicants using BMP Group 2, Rainwater Harvesting, submission of third-party testing of end-use water quality may be required at equipment commissioning as determined by the Tiered Risk Assessment requirements in Appendix M, "Rainwater Harvesting Treatment and Management (TRAM) analysis. Requirements." Additional regular water quality reports certifying compliance for the life of the BMP may also be required in Appendix M, "Rainwater Harvesting Treatment and Management Requirements."

Stormwater Retention Volume Computations

based The following calculations must be included on the plan set. Many of these calculations are included on the TRAM analysis Required Plan Compliance Sheet from the Stormwater Database, which must be incorporated in the plan set.

Stormwater Retention Volume Computations

- 1. Calculation(s) of the required Stormwater Retention Volume (SWRv) for the entire site within the limits of disturbance (LOD) and each individual drainage area contained SDA within the LOD;
- 4.2.Calculation(s) of the required Water Quality Treatment Volume (WQTv) for AWDZ sites for the entire site within the LOD; and each SDA within the LOD;

- 2-3. Calculation(s) for each proposed BMP demonstrating retention value towards SWRv in accordance with Chapter 3. Stormwater Best Management Practices (BMPs);
- 3.4. For BMP Group 2, Rainwater Harvesting, calculations demonstrating the annual water balance between collection, storage, and demand-, as determined using the Rainwater Harvesting Retention Calculator;
- 4.5_For proprietary and non-proprietary BMPs outside the Stormwater Management Guidebook, complete documentation defined in Appendix S, "Proprietary Practices Approval Process" for BMP Group 12, Proprietary Practices, in Section 3.13-, "Proprietary Practices" to identify/receive approval or denial to use these practice(s)-);
- Deficit SWRv gallons requiring off site mitigation.
- Statement of participation in off site mitigation program(s), in lieu fee or retention credit trading to manage SWRv deficit.
- 6. Offv requirement and/or SRC eligibility;
- 5-7. For PROW projects (Type 1), complete <u>Maximum Extent Practicable (the MEP)</u> stormwater report as defined in Appendix B-, "<u>Maximum Extent Practicable Process for Existing Public Right-of-Way</u>;' and
- 6-8.-For PROW portions of projects (Type 2), complete the MEP memo with supporting documentation as defined in Appendix B.

Pre- and Post-Development Hydrologic Computations

The pre-- and post-development runoff analysis must include the following:

- 1. A summary of soil conditions and field data-;
- 2. Pre--- and post-project curve number computation-
- 3. Time of concentration calculation-;
- 4. Travel time calculation-; and
- 5. Peak discharge computation for each <u>trainage areaSDA</u> within the project's <u>limits of disturbanceLOD</u> for the 24-hour storms of 2-year and 15-year frequencies. All hydrologic computations must be included on the plan.

Hydraulic Computations

Hydraulic computations for the final design of water quality and quantity control structures may be accomplished by hand or through the use of software using equations/formulae generally accepted in the water resources industry. The summary of collection or management systems will include the following:

1. Existing and proposed drainage area SDA must be delineated on separate plans with the flow paths used for calculation of the times of concentration.

- 2. Hydraulic capacity and flow velocity for drainage <u>conveyances</u>, including <u>ditchditches</u>, swales, pipes, inlets, and <u>guttergutters</u>. Plan profiles for all open <u>conveyances</u> and pipelines, with energy and hydraulic gradients shown thereon;
- 3. The proposed development layout including the following:
- 4. Location and design of BMP(s) on site-, marked with the BMP ID Numbers assigned by the Stormwater Database;
- 5. Stormwater lines and inlets-;
 - c. Location and design of BMP(s) on site.
- 6. A list of design assumptions (e.g., design basis, 15-year return period)-);
- 7. The boundary of the contributing drainage areaCDA to the BMP.;
- 8. Schedule of structures (a listing of the structures, details, or elevations including inverts); and
- 9. Manhole to manhole listing of pipe size, pipe type, slope, computed velocity, and computed flow rate (i.e., a storm drain pipe schedule).

5.1.25.2.4 Resubmission of Stormwater Management Plans

If a SWMP is accepted but If changes occur in the design or construction of an accepted SWMP, the applicant may be required to resubmit the SWMP for approval. Examples of changes during design and construction that maywill require re-submission SWMP resubmission for review include the following:

- A document in the original submission requires significant correction
- A document in the original submission is missing
- A document in the original submission has changed sufficiently to require replacement
- 1. Relocation of an on-site storm sewer or conveyance
- 2.1.Revision to the methodology used for design of BMP(s)property boundary, property size, or LOD boundaries that may require redesigning BMPs
- 2. Modification to an approved BMP design, such as Any change to SWRv through land cover designation change
- 3. Change in compaction or infiltration rates and contributing drainage areasdue to construction activities
- 4. Encountering contaminated soil or other underground source of contamination
- 4.5. Changes to the proposed land coverfloodplain designation or requirements
- 6. Changes to their any component of the BMP that may adversely affect the intended capacity of the approved BMP, such as the following:
 - a. <u>Modification to approved BMP</u> selection, <u>dimensions, or location, or sizing of BMP(s)</u>
 - b. Modification to approved material specification

- b.c.Changes to the size, invert, elevation, and <u>slopeslopes</u> of pipes and conveyances e.d. Installation of new drains and conveyance structures
- Installation or relocation of the sediment trap or basin
 - e. Need for a new storm sewer outlet connection to the sanitary/storm sewer main
 - f. Changes to the amount of off-site requirements
 - g. Changes to the CDA to a BMP
- 5-7. Revision to the approved grading and drainage divides and that may require redesigning BMPs
- 8. Relocation of an on-site storm sewer or conveyance
- Removal of contaminated soil from the site
- Revision to the boundaries of the floodplain
- Revision to the property boundary
- New storm sewer outlet connection to the main storm or sanitary sewer
- 6.9 Abandonment, removal, or demolition of a BMP

If the applicant resubmits an SWMP after making changes, the resubmission resubmission must contain a list of the changes made. The applicant must update any information in the Stormwater Database that has been changed and place a new Required Plan Compliance Sheet on the plan set. The applicant may also need to update and resubmit the declaration of covenants. After DDOE's DOEE's initial review and its review of the first resubmission, an applicant will pay the supplemental review fee for each subsequent review. This includes review for revisions to plans after plan approval. Supplemental fees will not be assessed when a submission is for a project, or portion of a project, that is entirely in the existing PROW and is following the MEP process (see Appendix B)-, "Maximum Extent Practicable Process for Existing Public Right-of-Way").

5.2 Administration

5.2.1 Approval Requirements

A DDOE approved SWMP meeting the requirements of 21 DCMR, Chapter 5 is required before a building permit for any District project requiring stormwater management, as defined in Chapter 2 of this guidance manual is issued by the District of Columbia Department of Consumer and Regulatory Affairs (DCRA)

5.2.2 Fees

An applicant is responsible for paying fees that provide for the cost of review, administration, and management of the stormwater permitting process and inspection of all projects subject to the requirements of Chapter 5 of Title 21 of the District of Columbia Municipal Regulations Sections 516 through 539. These fees are posted on DDOE's website at http://ddoe.dc.gov/swregs and will be adjusted for inflation annually, using the Urban Consumer Price Index published by the United States Bureau of Labor Statistics.

Note: A supplemental plan review fee is required for each DDOE review after first resubmission of a plan. Phased review requirements that follow the Maximum Extent Practicable (MEP) process (see Appendix B) for a project, or portion of a project, entirely in the existing public right of way are not required to pay a supplemental review fee.

Note: There is no fee charged for the plan review of a SWMP submitted solely to obtain the Stormwater Fee Discount.

If any of the following minor changes are made to the SWMP, resubmission is not required. A DOEE inspector may approve these minor changes at anytime during inspection or at the as-built submittal by a DOEE inspector.

- 1. Changes to SWM components that do not adversely affect BMP capacity while in consultation with the review engineer. The inspector should review the appropriate manufacturer's documentation to his/her satisfaction before approving such a change and should ensure that such changes are recorded as red line changes or deviations in the as-built plans. These changes include the following:
 - a. Changes to part manufacturer of similar function (e.g. dewatering valve from one manufacturer to another)
 - b. Change in hole pattern or size of underdrain pipe perforations
- 2. Change in project address, ownership, permit status, or zoning

For resubmissions of the Erosion and Sediment Control Plan, refer to the DOEE website https://doee.dc.gov/esc for further information.

5.3 Construction Inspection Requirements

5.3.1 Inspection Schedule and Reports

Prior to the approval of an SWMP, the applicant will submit a proposed construction and inspection control-schedule. DDOEDOEE will review the schedule to determine if changes are required. The construction schedule should reflect the construction sequences defined in each BMP section of Chapter 3 Stormwater Best Management Practices (BMPs) of this guidebook. The construction and inspection schedule must be included in the SWMP. DDOEDOEE will conduct inspections at the specified construction stages specified in the provisions, and file reports of inspections during construction of BMPs and site stormwater conveyance systems to ensure compliance with the approved plans.

Note: No stormwater management work may proceed past the stage of construction that DDOEDOEE has identified as requiring an inspection unless

- DDOEDOEE has issued an "approved" or "passed" report;
- DDOEDOEE has approved a plan modification that eliminates the inspection requirement; or
- DDOEDOEE has eliminated or modified the inspection requirement in writing.

DOEDOEE may require that the professional engineer responsible for sealing the approved SWMP, the professional engineer responsible for certifying the "As Built" as-built SWMP, or, for a project entirely in the PROW, the officer of the contracting company responsible for certifying the Record Drawing be present during inspections.

A written notice from DDOE of If DOEE conducts an inspection finding and finds work that is not in compliance with the approved SWMP-requires. DOEE may issue a written notice requiring the applicant too take prompt corrective action. The written notice provides details on the nature of corrections required and the time frame within which corrections must be made. DOEE may also take other enforcement action as authorized by District of Columbia law and 21 DCMR, Chapter 5.

5.3.2 Inspection Requirements Before and During Construction

DDOE's DOEE's construction inspection checklists for each BMP are provided in Appendix K-, "Construction Inspection Checklists."

Preconstruction Meetings. These meetings are required prior to the commencement of any land-disturbing activities and prior to the construction of any on site or off site BMPs.

The applicant is required to contact <u>DDOEDOEE</u> to schedule preconstruction meetings 3 days prior to beginning any construction activity subject to the requirements of 21 DCMR, Chapter 5.

Inspections During Construction. The applicant is required to contact <u>DDOEDOEE</u> to schedule inspection 3 days prior to any stage of BMP construction, or other construction activity, requiring an inspection. For large, complicated projects, the applicant and <u>DDOEDOEE</u> may agree during the preconstruction meeting to an alternative approach such as a weekly notification schedule. Any such agreement must be made in writing and signed by all parties. <u>DDOEDOEE</u> will revert to the 3—day notification procedure if the agreement is not followed.

DOEDuring construction DOEE may require the <u>presence of the professional</u> engineer responsible for sealing the approved SWMP, or; the professional engineer responsible for certifying the "As Built" as built SWMP; or for a project entirely in the PROW, the officer of the contracting company responsible for certifying the Record Drawing be present during inspections.

Final Inspection. The applicant is required to contact <u>DDOEDOEE</u> to schedule a final inspection <u>lone</u> week prior to the completion of a BMP construction to schedule a final inspection of the BMP.

A final inspection will be conducted by DDOE upon Upon completion of the BMP-, DOEE will conduct a final inspection to determine if the completed work is was constructed in accordance with approved plans.

Inspection Requirements by BMP Type. Chapter 3, "Stormwater Best Management Practices (BMPs)" of this Guidance Manualguidebook provides details about the construction sequences for each BMP. After holding a preconstruction meeting, regular inspections will be made at the following specified stages of construction:

- Infiltration Systems and Bioretention Areas. shall be inspected at the following stages so as to ensure proper placement and allow for infiltration into the subgrade:
 - (a) During on-site/<u>or</u> off-site percolation/<u>or</u> infiltration testtests;
 - (b) Upon completion of stripping, stockpiling, <u>or</u> construction of temporary sediment control and drainage facilities:
 - (c) Upon completion of excavation to the subgrade;
 - (d) Throughout the placement of perforated PVC/HDPE pipes (for underdrains and observation wells) including bypass pipes (where applicable), geotextile materials, gravel, or crushed stone course and backfill; and

(a)

(b)(e) Upon completion of final grading and establishment of permanent stabilization;

- Flow Attenuation Devices, such as open vegetated swales upon completion of construction:
- **Retention and Detention Structures**, at the following stages:
 - (a) Upon completion of excavation to <u>the</u> sub-foundation and, where required, installation of structural supports or reinforcement for structures, including but not limited to the following:
 - Core trenches for structural embankments.
 - Inlet-outlet structures and anti-seep structures:
 - Watertight connectors on pipes; and
 - Trenches for enclosed stormwater drainage facilities:
 - (b) During testing of the structure for watertightness;
 - (c) During placement of structural fill, and concrete and installation of piping and catch basins:
 - (d) During backfill of foundations and trenches;
 - (e) During embankment construction; and
 - (f) Upon completion of final grading and establishment of permanent stabilization:
- Stormwater Filtering Systems, at the following stages:
 - (a) Upon completion of excavation to <u>the</u> sub-foundation and installation of structural supports or reinforcement for the structure;
 - (b) During testing of the structure for watertightness;

- (c) During placement of concrete and installation of piping and catch basins;
- (d) During backfill around the structure;
- (e) During prefabrication of the structure at the manufacturing plant;
- (f) During pouring of floors, walls, and top slab;
- (g) During installation of manholes/trap doors, steps, orifices/weirs, bypass pipes, and sump pit (when applicable));
- (h) During placement of the filter bed;
- (i) Upon completion of final grading and establishment of permanent stabilization:

Green Roof Systems, at the following stages:

- (a) During placement of the waterproofing layer, to ensure that it is properly installed and watertight;
- (b) During placement of the drainage layer and drainage system:
- (c) During placement of the growing media, to confirm that it meets the specifications and is applied to the correct depth (certification for vendor or source must be provided));
- (d) Upon installation of plants, to ensure they conform to the planting plan (certification from vendor or source must be provided)); and
- (e) At the end of the first or second growing season, to ensure desired surface cover specified in the Care and Replacement Warranty has been achieved

5.3.3 Final Construction Inspection Reports

DDOEDOEE will conduct a final inspection to determine if the completed work is constructed in accordance with approved plans and the intent of 21 DCMR, Chapter 5. A registered professional engineer licensed in the District is required to certify "As Built" plans and state that the BMP has been constructed in accordance with the approved plans and specifications (the As-Built Certification by Professional Engineer form is provided in Appendix A. The "As Built" certification must be on the original SWMP. Upon completion, these plans will be submitted to the DDOE for processing. The estimated time for processing will be two weeks (ten working days), after which the plans will be returned to the engineer. DDOE will provide the applicant with written notification of the final inspection results. DDOE will maintain a permanent file of inspection reports. Inspection for Preventive Maintenance Within 21 days of the final inspection, the applicant must submit an as-built package, including one PDF copy of the as-built SWMP certified by a registered professional engineer licensed in the District of Columbia and one As-Built Form from Section 5.6 Supporting Forms. Both documents should be uploaded to the Stormwater Database per DOEE requirements. For a project consisting entirely of work in the PROW, the submission of a Record Drawing certified by an officer of the project contracting company is acceptable if it details the as-built construction of the BMPs, related stormwater infrastructure, and land covers.

A registered professional engineer licensed in the District is required to certify as-built SWMPs and state that all activities including clearing, grading, site stabilization, the preservation or

creation of pervious land cover, the construction of drainage conveyance systems, the construction of BMPs, and all other stormwater-related components of the project were accomplished in strict accordance with the approved SWMP and specifications. As stated in Section 5.2.4, "Resubmission of Stormwater Management Plans," all plan changes are subject to DOEE approval. The as-built certification must be on the original SWMP.

<u>Upon completion</u>, these plans will be submitted to DOEE for processing. The estimated time for processing will be two weeks (10 working days), after which the plans will be returned to the engineer. DOEE will provide the applicant with written notification of the final inspection results. DOEE will maintain a permanent file of inspection reports.

5.3.4 Inspection for Preventive Maintenance

DOEE requires maintenance will be ensured through inspection of all BMPs by DDOE.inspections for BMPs and landcovers to ensure their ongoing performance in compliance with 21 DCMR, Chapter 5. The inspection will occur at least once every three3 years.

Maintenance inspection forms are provided in Appendix L. "Maintenance Inspection Checklists." DOEE will conduct these maintenance inspections, though it may in certain circumstances, allow a property to self-inspect and provide documentation.

Preventive DOEE will maintain maintenance inspection reports will be maintained by DDOE on for all BMPs. The reports will evaluate BMP functionality based on the detailed BMP requirements of Chapter 3 Stormwater Best Management Practices (BMPs) and inspection forms found in Appendix L., "Maintenance Inspection Checklists."

If, after an inspection by DDOEDOEE, the condition of a BMP presents an immediate danger to the public safety or health because of an unsafe condition or improper maintenance, the DDOEDOEE will take such action as may be necessary to protect the public and make the BMP safe. Any costs incurred by DDOEDOEE will be assessed against the owner(s).

5.4 Maintenance

5.4.1 Maintenance Responsibility

A site with an approved SWMP must maintain the BMPs and land covers according to the maintenance schedule in the SWMP- and this guidebook. Land covers must be maintained in type and extent as approved. Approved BMPs must be kept in good condition, including all the engineered and natural elements of each practice, as well as conveyance features (e.g., grade surfaces, walls, drains, structures, vegetation, soil erosion and sediment control measures, and other protective devices). All repairs or restorations must be in accordance with the approved SWMP.

A declaration of covenants including an exhibit stating the owner's specific maintenance responsibilities must be recorded with the property deed, at the Record of Deeds. A maintenance schedule for any BMP will be developed for the life of the project and shall state the maintenance to be completed, the time for completion, and who will perform the maintenance

including provisions for normal and abnormal maintenance. The maintenance schedule will be printed on the SWMP and will appear as an exhibit in the declaration of covenants.

5.4.2 Maintenance Agreement

DOEMaintenance obligations are binding on current and future owners of a property subject to 21 DCMR, Chapter 5. DOEE will not issue final approval of a complete set of the SWMP for private parcels until the applicant has executed a declaration of covenants binding providing notice of this obligation to current and subsequent owners of the land served by the BMP(s) and land covers to an inspection and maintenance agreement. Such agreement shall provide for. Maintenance agreements by major regulated projects include providing access to the site and the BMP(s) at reasonable times, and for regular inspection by DDOE, DOEE and for regular or special assessments of property owners, as needed, to ensure that the BMP(s) is maintained in proper working condition and the land covers are retained as approved in the SWMP. An example of the declaration of covenants for a site with BMPs and designated land covers is provided at the end of this chapter.

The applicant must record the agreement must be recorded as a declaration of covenants with the District of Columbia Recorder of Deeds of the District by the applicant. The agreement must also provide that, if after written notice by DDOEDOEE to correct a violation requiring maintenance work, satisfactory corrections are not made by the owner(s) of the land served by the BMP within a reasonable period of time, not to exceed 45-to 60 days unless extended for good cause shown, DDOEDOEE may perform all necessary work to place the BMP in proper working condition. The owner(s) of property served by the BMP will be assessed the cost of the work and any penalties, and there will be a lien on any property served by the BMP, which may be placed on the tax bill and collected as ordinary taxes by the District.

5.5 Exemptions

If a major substantial improvement activity demonstrates that it is not part of a common plan of development with a major land disturbing activity, then it is exempt from the 2 year and 15 year storm control requirements.

If DDOE determines that a land disturbing activity is conducted solely to install a BMP or land cover for any of the following six reasons:

- 5. To generate a Stormwater Retention Credit,
- 6. To earn a stormwater fee discount under the provisions of this chapter,
- 7. To provide for off site retention through in lieu fee payments,
- 8. To comply with a Watershed Implementation Plan established under a Total Maximum Daily Load for the Chesapeake Bay, or
- 9. To reduce Combined Sewer Overflows (CSOs) in compliance with a court approved consent decree, including court approved modifications, for reducing CSOs in the District of Columbia, or in compliance with a National Pollutant Discharge Elimination System permit.

10. then these SWMPs are exempt from stormwater performance requirements for major land disturbing activities and stormwater performance requirements for major substantial improvements activities, as well as requirements for covenants and easements. The stormwater obligations for these sites generating SRCs are detailed in Chapter 7 of this guidance manual.

Note: While the declaration of covenants and easements are not required with these projects, an executed maintenance contract or a signed promise to follow the Department approved maintenance plan for the period of time for which the certification of SRCs is requested is required for SWMP approval. If the site fails to maintain these retention practices DDOE has recourse that is spelled out in Chapter 5 and Chapter 7 of this guidance manual.

Land-disturbing activities that consist solely of cutting a trench for utility work and related replacement of sidewalks and ramps are exempt from stormwater management requirements if the activity does not involve the reconstruction of a roadway from curb to curb or curb to centerline of roadway.5.45.45.55.55.65.6

Land-disturbing activities conducted solely to respond to an emergency need to protect life, limb or property or to conduct emergency repairs are exempt from most stormwater management requirements. These activities are not required to submit a SWMP, but they are subject to inspections to ensure the proper use of soil erosion and sediment control measures.

5.65.5 Supporting Forms

Site Development Submittal Information Form

You must submit the following forms to support DOEE review and approval of SWMPs. These forms should be submitted to DOEE using the Stormwater Database, as directed by DOEE (see Figures 5.4 through 5.13).

- DC Water-DDOE WPD/DOEE Storm Sewer Verification Form
- -As-Built Certification Stamp
- by Professional Engineering Design StampEngineer Form
- Maintenance Responsibility Stamp
- Off Site Retention Responsibility Stamp
- Declaration of Covenants Template

GOVERNMENT OF THE DISTRICT OF COLUMBIA District Department of the Environment



Site Development Submittal Form

Development Review Ty	pe:		
Lot #	Square #	Parcel #	
☐ Apartment Building	Single Family, □ Duplex, □ Town □ Industrial Building □ Parking L □ District land/property □ Distri	ot Greign Govt. Office/Re	esidence
roperty Owner:			
Name:	Phone	#:Fax#	:
pplicant:			
	(Last):	Phone#	
Fax#:	E-Mail:		
Street Address:	City:	State:	Zip:
Firm:	hitect: (Check one or more)Phone# City:		
	City		
Signed Department of Consu y signature attests that the a	o sets of civil drawings umer Regulatory Affairs (DCRA) p mer Regulatory Affairs (DCRA) En ttached application package is com iew of this plan depends upon the en my firm, or agent may delay this p	nvironmental Intake Form applete and accurate to the best accuracy of the information, a	
	Signature:	Date:	
			*

Figure 5.1 Site Development Submittal Information form.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY AND ENVIRONMENT Application for Discharge from New Stormwater Management BMP Proposed Discharge from Stormwater Best Management Practice (BMP) A. BMP Type(s): _ B. Project Location: ___ Square: ___ C. Pre-Project Peak Flow: 15-Year____ Post-development Peak Flow: 15-Year____cfs D. Receiving Sewer System - Type, Location, Slope, and Depth: ☐ Combined Sewer ☐ Separate Storm Sewer ☐ Open Channel Receiving Sewer: Pipe Size: ____ in. Pipe Material: ____ Pipe Slope: ___ Depth of Receiving Sewer (FG to pipe invert): ____ ft. Approximate Groundwater Depth (FG to groundwater): Discharge Location or Name of Surface Waterway (if open channel): E. Size of Proposed Storm Lateral(s): F. Invert Elevation of Proposed Storm Lateral Connection(s): _____ft. Requested By:_ _ Agent Downer Address: Date Requested: Tel: ((OFFICIAL USE ONLY) Hydraulic Sewer System Verification By DC Water: A. Combined Sewer Separate Storm Sewer Open Channel Clean Rivers Bloomingdale Area Other B. Receiving Sewer: Pipe Size: in. Pipe Material: C. Depth of Receiving Sewer (FG to pipe invert): ft. Pipe Slope: D. Estimated Manning's Capacity (full pipe flow) of Receiving Sewer E. Is the Estimated Available Hydraulic Capacity Exceeded? Yes No DC Water Verification By: Name _____ Plans Approved? Yes No Maximo #: _____ Tel: () ____ DOEE WPD Verification By: (Name) ___ _, Title __ Fax: () _______ Date Verified:______ Tel: ()____ DOEE SWDB PLAN #: DCRA Permit #:

Figure 5.75.75.2 DC Water DDOEWPD storm sewer verification form.

	pletion of construction of a wers (collectively the "Fac			
	nt of Energy and Environm		page to the Watershed I	rocction
1. Facility informa	tion:			
Source Name: _				
Source Location	Street:			
	City:			
	mit No.:			
Date	Issued:			
 As Built Certific 	ation			
Signature of Engin	on. I have enclosed one set	Name (Please Type)	_	
Affix Seal:		Company Name		
		Company Address		
		Date:	Phone No.:	
Substantial deviations fro	m the approved plans and s	specifications (attach ac	lditional sheets if required	d).

STATEN	ENT BY PROFESSIONA THE DISTRICT (L ENGINEER REGISTERED IN OF COLUMBIA
infrastructure, and land o conformity with modern e further certify that the Fa Title 21 of the District of	overs (collectively the "Facility") l ngineering principles applicable t cility has been designed in accorde	ater best management practices (BMPs), stormwater nave been designed/examined by me and found to be in o the treatment and disposal of stormwater pollutants. I noce with the specification required under Chapter 5 of It is also stated that the undersigned has furnished the operation of the site's Facility.
	Name and Title (please	type)
	Address	
Affix Seal:	D ate	Phone No:

Figure 5.95.95.4 Professional engineering design stamp.

PROPOSED REVISION PROPOSED REVISION

STATEMENT BY PERSON RESPONSIBLE FOR MAINTENANCE

The undersigned agrees to maintain compliance with the performance requirements and other provisions of Chapter 5 of Title 21 of the District of Columbia Municipal Regulations (DCMR). This includes maintaining and operating stormwater best management practices (BMPs), stormwater infrastructure, and land covers as specified in the Stormwater Management Plan approved by the District Department of Energy and Environment (DOEE).

Responsibility for maintenance and operation may be transferred to another entity upon written notice to the Watershed Protection Division of DOEE from the undersigned and the entity assuming responsibility. This notice must certify that the transfer of responsibility for maintenance and operation is in compliance with 21 DCMR Chapter 5.

Name and Title (please	type)	
Address		
Date	Phone No:	

Figure 5.105.105.5 Maintenance responsibility stamp. XXX

STATEMENT BY PERSON RESPONSIBLE FOR ACHIEVING OFF-SITE RETENTION		
This site has an off-site retent per year.	ion volume (Offv) obligation.	The Offv for this site equals(gallons)
of Chapter 5 of Title 21 of the	District of Columbia Municip other entity upon written notice	Offy, in such a manner as to comply with the provisions all Regulations (DCMR). Responsibility for achieving to the Department of Energy and Environment from the
	Signature of the person r	responsible for achieving Offv
	Name and Title (please t	type)
	Address	
	Date	Phone No:

- <u>Figure 5.11</u> <u>Statement By Professional Engineer Registered In the District of Columbia</u>
 Form
- Statement By Person Responsible For Maintenance Form
- Statement By Person Responsible For Achieving Off-Site Retention formForm

• Figure X Anacostia Waterfront Development Zone Site Form

GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT ENERGY AND ENVIRONMENT



APPLICATION FOR VESTING STATUS UNDER CHAPTER 5 OF TITLE 21 OF THE DISTRICT OF COLUMBIA MUNICIPAL REGULATIONS DCMR §§ 552.2-552.3

Square:	Parcel:	Lot:
Select the project	submission type that you believe	re vests the project:
☐ Building (B) I complete building		nent Plan (SWMP) submission as a part of a
☐ Foundations grade permit appli		IP submission as a part of a complete foundation to
, ,	Permit-A SWMP submission as will not subsequently require a b	s a part of a complete civil permit application,
☐ Multi-Phased	Project- A multi-phased project	ct in which stormwater infrastructure and BMPs a
_		y DOEE during an earlier phase of construction (AD) submission for which approval has not
		CMR §552.4]: sent (PUD) application to the District Zoning
	ation for design review under the	e Capitol Gateway Overlay District to the District
		l Capital Planning Commission (NCPC)
2. Identify under what	t transition period you submitted	I the project:
☐ Transition Pe	riod 1 (TP1)- Projects submitte	ed through January 15, 2014
 Project shape 	all comply with stormwater regu	ulations in place before the 2013 Stormwater Rule
☐ Transition Pe	eriod 2 (TP2A)- Projects submit	tted from January 15, 2014 through January 15,
 Project shape 	all comply with the 2013 Stormy	water Rule
 Minimum off site) 	on-site retention requirement w	raived (the entire retention volume may be achieved
 Minimum 	on-site treatment is required per	r the 2013 Stormwater Rule, as applicable
☐ Transition Pe	riod 2 (TP2B)- Projects submit	tted from January 15, 2014 through July 14, 2015
 Project shape 	all comply with the 2013 Stormy	water Rule
 Minimum achieved of 	-	waived (the entire retention volume may be
Minimum	on-site treatment is required per	r the 2013 Stormwater Rule, as applicable
		C 20002 phone 202-535-2600 fax 202-535-2881

Figure 5.125.125.7 Application for vesting status.

	e transition period, attach the application and approval the identified transition period. Submit documentation that the
	references to both the property and the public right-of-way.
BMP:	oard approval that conflicts with the installation of a retention
☐ Historic Preservation Rev	
☐ Commission on Fine Arts	Commission preliminary or final design submission
	ent variance or special exception
☐ District Office of Planning	
□ Not Applicable	y may 2 may
language or sections in the co	nees to the application and approval documents, citing specific ommission approval that conflict with the installation of d cover changes. Be sure to address both the property and the
Applicant	Telephone
Address	
Signature	Date

Figure 5. 5.7 (continued)

GOVERNMENT OF THE DISTRICT OF COLUMBIA Department of Energy and Environment

Office of the General Counsel



Procedure for Obtaining Legal Sufficiency Review of the Declaration of Covenants from the Department of Energy and Environment (DOEE) Office of the General Counsel (OGC)

The DOEE Natural Resources Administration must:

- Provide name and e-mail address of technical reviewer so that OGC may discuss technical issues. If necessary, OGC will provide a PDF of the signed Declaration of Covenants to the DOEE reviewer.
- Provide attached template of the Declaration of Covenants to the owner/developer.

Review Engineer:

E-mail address:

- The owner or developer must:

 1. Draft the Declaration of Covenants.
 - Subordinate all prior liens to the Declaration.

 - Produce evidence of title and all liens on the property (i.e., copy of deed and full title search). Provide a site plan (Exhibit B) as approved by DOEE, showing all required Stormwater Best Management Practices (BMPs) and land covers and documenting any Off-Site Retention 4
 - Provide a maintenance plan of all stormwater best management practices (BMPs), stormwater infrastructure, and land covers for District approval pursuant to 21 DCMR § 519
 - Submit all of the above to:

Department of Energy and Environment Office of the General Counsel 1200 First Street, NE, 5th Floor

- Washington, DC 20002
 Return OGC-approved and signed original to the Natural Resources Administration for 7. technical sufficiency review and approval.
- Provide copy of recorded Declaration of Covenants to DOEE. 8

Contact Person:

Caroline Burnett

Assistant General Counsel Office of the General Counsel Department of Energy and Environment 1200 First Street, NE, 5th Floor Washington, DC 20002 Tel: (202) 535-2609 caroline.burnett@dc.gov

- Figure 5.4 Application for Exempt Land-Disturbing Activity
- Declaration of Covenants Template

- Amendment to Declarations of Covenants
- Termination and Release of Declaration of Covenants template.



THE GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment NATURAL RESOURCES ADMINISTRATION WATERSHED PROTECTION DIVISION

DECLARATION OF COVENANTS

For a Stormwater Management Facility

THIS DECLARATION OF COVENANTS (the "Declaration") is made as of this day of ______, and its successors and assigns ("Owner"), for the benefit of the DISTRICT OF COLUMBIA, a municipal corporation (the "District").

RECITALS

- A. The Owner is the owner in fee simple of certain real property and improvements (collectively, the "**Property**") located in the District of Columbia and more particularly described in **Exhibit A** attached hereto and made a part hereof. No other person or entity has an ownership interest in the Property.
- B. In order to manage stormwater flow conditions resulting from certain improvements Owner will make to the Property, the regulations of the District, found at Title 21, Chapter 5, of the District of Columbia Municipal Regulations ("DCMR") require that Owner develop and submit for approval a Stormwater Management Plan ("SWMP") for the installation and maintenance of all stormwater best management practices ("BMPs"), stormwater infrastructure, and land covers on the Property (collectively, the "Facility"), and including any obligation to achieve Off-Site Retention Volume (Offv).
- C. Section 529 of Title 21 of the DCMR requires that Owner execute and record, with the District of Columbia Recorder of Deeds, a declaration of covenants running with the land that set forth Owner's responsibilities under the SWMP.

NOW, THEREFORE, for and in consideration of the issuance of building permits and approval of Owner's plans by the District, and other good and valuable consideration the sufficiency of which is hereby acknowledged, for the benefit of and limitation upon Owner and all future owners of the Property, and for the benefit of the District, Owner for itself, its successors and assigns, does hereby acknowledge, represent, covenant, agree, and warrant to the District as follows:

The foregoing Recitals and attached Exhibits are all hereby incorporated in and
made a part of this Declaration to the same extent as if herein set forth in full, provided
however, that said Recitals shall not be deemed to modify the express provisions hereinafter set
forth.

Figure 5.4 These forms are subject to change with the latest versions available at https://doee.dc.gov/swguidebook.



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY AND ENVIRONMENT

Application for Discharge from New Stormwater Management BMP

	A. BMP Type(s):
	B. Project Location:
	B. Project Location:
	C. Pre-Project Peak Flow:
	15-Yearcfs Post-development Peak Flow:
	15-Yearcfs
	D. Receiving Sewer System - Type, Location, Slope, and Depth:
	□ Combined Sewer □ Separate Storm Sewer □ Open Channel Receiving Sewer: Pipe Size: in. Pipe Material: Pipe Slope: Depth of Receiving Sewer (FG to pipe invert): ft. Approximate Groundwater Depth (FG to groundwater): ft. Discharge Location or Name of Surface Waterway (if open channel):
	E. Size of Proposed Storm Lateral(s):in. F. Invert Elevation of Proposed Storm Lateral Connection(s):ft.
	Agent Owner
Audi Caa.	
Tel: ()	Fax: () Date Requested:
OFFICIAL U 2. H A B C D	Fax: () Date Requested:
(OFFICIAL U 2. H A B C D E	Fax: () Date Requested:
OFFICIAL U 2. H A B C D E	Fax: () Date Requested: SE ONLY) Nydraulic Sewer System Verification By DC Water: Combined Sewer Separate Storm Sewer Open Channel Clean Rivers Bloomingdale Area Other Receiving Sewer: Pipe Size: in. Pipe Material: Pipe Slope: % Depth of Receiving Sewer (FG to pipe invert): ft. Estimated Manning's Capacity (full pipe flow) of Receiving Sewer cfs
OFFICIAL U 2. H A B C D E DC Water Veri	Fax: () Date Requested:
OFFICIAL U 2. H A B C D E DC Water Veri Plans Approved	Fax: () Date Requested:
Tel: ()	Fax: () Date Requested:
(OFFICIAL U 2. H A B C D E DC Water Veri Plans Approved	Fax: () Date Requested:

<u>Figure 5.4</u> <u>DC Water/DOEE Storm Sewer Verification form.</u>

Within 21 days after completion of construction	ction of all stormwater best management practices (BMPs), stormwater
	the "Facility"), please send this page to the Regulatory Review Division
Facility information:	
Source Name:	
Source Location: Street:	
City:	
DCRA Permit No.:	
Date Issued:	
As Built Certification	
	struction, scheduled and conducted by me or by a project representative done set of as-built engineering drawings. Name (Please Type) D.C. Reg. No.
Affix Seal:	
	Company Name
	Company Address
	Date: Phone No.:
substantial deviations from the approved pl	lans and specifications (attach additional sheets if required).

<u>Figure 5.5 As-Built Certification By Professional Engineer form.</u>

This is to certify that the en	THE DISTRICT Of gineering features of all stormwait	ter best management practices (BMPs), stormwater
infrastructure, and land covers (collectively the "Facility") have been designed/examined by me and found to be in conformity with modern engineering principles applicable to the treatment and disposal of stormwater pollutants. I further certify that the Facility has been designed in accordance with the specification required under Chapter 5 of Title 21 of the District of Columbia Municipal Regulations. It is also stated that the undersigned has furnished the applicant with a set of instructions for the maintenance and operation of the site's Facility.		
	Name and Title (please t	type)
	Address	
Affix Seal:	Date	Phone No:

Figure 5.6 Statement By Professional Engineer Registered In the District of Columbia form.

STATEMENT BY PERSON RESPONSIBLE FOR MAINTENANCE

The undersigned agrees to maintain compliance with the performance requirements and other provisions of Chapter 5 of Title 21 of the District of Columbia Municipal Regulations (DCMR). This includes maintaining and operating stormwater best management practices (BMPs), stormwater infrastructure, and land covers as specified in the Stormwater Management Plan approved by the District Department of Energy and Environment (DOEE).

Responsibility for maintenance and operation may be transferred to another entity upon written notice to the Regulatory Review Division of DOEE from the undersigned and the entity assuming responsibility. This notice must certify that the transfer of responsibility for maintenance and operation is in compliance with 21 DCMR Chapter 5.

Signature of the person r	sponsible for maintenance (it may be the applicant))
Name and Title (please t	pe)	_
Address		_
Date	Phone No:	

Figure 5.7 Statement By Person Responsible For Maintenance form

SIAILMI	ENT BY PERSON RESPONSIBLE FOR ACHIEVING OFF-SITE RETENTION
This site has an off-site retenti	on volume (Offv) obligation. The Offv for this site equals(gallons).
	sfy the obligation to achieve Offv, in such a manner as to comply with the provisions District of Columbia Municipal Regulations (DCMR).
Division of the Department of	offy may be transferred to another entity upon written notice to the Regulatory Review Energy and Environment from the undersigned and the entity assuming st certify that the transfer of responsibility for Offy is in compliance with 21 DCMR
	Signature of the person responsible for achieving Offv
	Name and Title (please type)
	Address
	DatePhone No:

Figure 5.8 Statement By Person Responsible For Achieving Off-Site Retention form



REGULATED ANACOSTIA WATERFRONT DEVELOPMENT ZONE (AWDZ) SITE

~4.	nare: Lot:			
1.	Is the project located within the Anacostia Waterfront Development Zone (AWDZ)? See Stormwater Management Guidebook Figure 2.1 <i>Map of Anacostia Waterfront Development Zone</i> for reference. ☐ Yes (continue to next question)			
	☐ No (This is not a regulated AWDZ site, you can skip the rest of this form)			
2.	Is the site District owned or District-instrumentality owned? Check the District Office of Tax and Revenue Real Property Assessment Database for site owner (https://www.taxpayerservicecenter.com/RP_Search_isp?search_type=Assessment). Yes (this site is a regulated AWDZ site and shall employ Best Management Practices (BMPs) and land cover necessary to meet the requirements of 21 DCMR §524 Stormwater Management Performance Requirements for Major Regulated Projects in the Anacostia Waterfront Development Zone) No (continue to next question)			
3.	Is fifteen percent (15%) or more of the project's total cost District-financed or District instrumentality-financed?			
	 ☐ Yes (this site is a regulated AWDZ site and shall employ Best Management Practices (BMPs) and land cover necessary to meet the requirements of 21 DCMR §524 Stormwater Management Performance Requirements for Major Regulated Projects in the Anacostia Waterfront Development Zone) ☐ No (continue to next question) 			
4.	Does the project include a gift, lease, or sale from District-owned or District instrumentality-owned property to a private entity? Yes (this site is a regulated AWDZ site and shall employ Best Management Practices (BMPs) and land cover necessary to meet the requirements of 21 DCMR §524 Stormwater Management Performance Requirements for Major Regulated Projects in the Anacostia Waterfront Development Zone) No (This is not an AWDZ site, you can skip the rest of this form)			
cor	ertify that all statements on this form are true and complete to the best of my knowledge and belief. I agree to mply with all applicable District of Columbia laws and regulations. The making of false statements on this m is punishable by criminal penalties (D.C. Official Code § 22-2405).			
_	Signature of Owner or Authorized Agent Date			

Figure 5.9 Anacostia Waterfront Development Zone Site form

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Application for Exempt Land-Disturbing Activity

Acronyms

DOEE Department of Energy and E	Environment SWMP Stormwater Management Plan
Application date:	
Lot:Square	::Ward:
Is the site in a publicly accessible	e area (Yes or No)?
Plan Number:	
Name of site owner:	
Address:	
E-Mail:	Phone:
Name of owner's agent (if applic	cable):
Address:	
E-Mail:	Phone:
Indicate the type of land-disturb	oing activity:
☐ Trails for pedestrians or nor	n-motorized vehicles
☐ Athletic playing fields, perm	meable athletic tracks, or permeable playground surfaces
☐ Pavilion, shed, dugout, or s	imilar structure

 $\underline{Figure~5.10~Application~for~exempt~land-disturbing~activity.}$

Provide description of	f project and prim	ary use. Include o	description of pub	lic accessibility
of the site:				
Indicate the pre-proje	ect land cover area	:		
Land Cover Type	Natural Cover	Compacted Cover	Impervious Cover	BMP
Area (square feet)				
Provide related SWM	IP number(s) for r	elated developmen	nt at this site (if a	oplicable):
		,		
	Appl	icant's Signature		
Owner of regulated and that this applic	I property: I hereby ation is correct to th			ulated property
Signature of Owne	r:		Date:	
B. Agent: I hereby cer application. I decla	rtify that I have the a			
Signature of Agent	:		Date:	
F	OR DEPAR	TMENT U	SE ONLY	
	Approv	ed in part:	Disappro	oved:
Approved:	Signature:		Date:	
Approved:				
Approved:				

Figure 5.10 (continued)

Instructions for Application for Exempt Land-Disturbing Activity

Purpose of form: This form provides DOEE with the necessary information to determine if a land-disturbing activity is exempt from stormwater management requirements.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site: Enter the street address for the regulated site that is applying for exemption. Lot, square, and ward information is available from the building permit.

Is the site in a publicly accessible area (Yes or No)? Select "yes" or "no".

Plan Number: Provide the plan number for this regulated project.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information.

Name of owner's agent: If applicable, enter the name of a representative whom the owner has designated.

Indicate the type of land-disturbing activity: Check the applicable box that describes the land-disturbing activity. Complete a separate form if there is more than 1 type of land-disturbing activity at the site.

Provide description of project and primary use. Include description of public accessibility of the site: Provide a brief description of the project and its intended primary use. Include a description of how the site is accessible to the public.

Indicate the pre-project land cover area: Enter the area in square feet of the pre-project land cover type. This is area of the proposed land-disturbance.

Provide related SWMP number(s) for related development at this site (if applicable): If the regulated site is part of a common plan of development or if there are other recent projects on the property, provide the SWMP number of the related projects. This is to provide DOEE with information on the entire scope of work at the site.

Page 3 of 3

Figure 5.10 (continued)

- 2. The Facility and any responsibility to achieve Off-Site Retention Volume (Offv), as stated in gallons, is shown on the plans approved by the District attached hereto as Exhibit B, the Site Plan, as the same may be amended pursuant to the District's approval.
- 3. Owner, at its sole expense, shall construct and perpetually operate and maintain the Facility in such manner as to comply with the provisions of Title 21, Chapter 5 of the DCMR and in strict accordance with the SWMP, including the Maintenance Plan, attached hereto as **Exhibit C**, as the same may be amended pursuant to the District's approval.
- 4. Owner shall, at its sole expense, make such changes or modifications to the Facility as the District, in its discretion, may determine necessary to ensure that the Facility is maintained in good condition and continues to operate as designed and approved.
- 5. The District and its agents, employees, and contractors shall have the right to enter the Property for the purpose of inspecting the Facility in accordance with established inspection procedures and Section 16 of the Water Pollution Control Act of 1984 (D.C. Law 5-188; 32 DCR 919; D.C. Official Code § 8-103.01, et seq. (2013 Repl.), as amended (the "Act"), at reasonable times and in a reasonable manner, in order to ensure that the Facility is being properly maintained and is continuing to perform in the manner approved by the District.
- 6. Should Owner fail to perform its responsibilities as required herein, or fail to operate and restore the Facility in accordance with approved design standards, as the same may be amended from time to time, the District shall be entitled to pursue any and all enforcement actions available to it pursuant to the Act, and Title 21, Chapter 22 of the DCMR, as the same may be amended from time to time. Without limiting the generality of the foregoing, in the event that a discharge or threat of discharge from the Facility poses an imminent and substantial danger to the environment or the public health or welfare, the District may take immediate action against Owner pursuant to D.C. Official Code § 8-103.08(b).
- 7. If Owner's failure or refusal to maintain the Facility in accordance with the covenants and warranties contained in this Declaration ultimately results in corrective action by the District, Owner shall bear all costs incurred by the District for such corrective measures, such costs may be assessed against the Property, and Owner may be fined in accordance with the Act and Title 21, Chapter 5 of the DCMR.
- 8. The provisions of this Declaration shall be deemed warranties by Owner and covenants running with the land and shall bind and inure to the benefit of Owner and the District, their respective heirs, successors and/or assigns. When Owner ceases to own an interest in the Property, the rights, warranties, and obligations under this Declaration shall become the rights, warranties, and obligations of the successor-in-ownership and interest to the Property.
- 9. Owner shall, at its cost and expense, properly record this Declaration with the Recorder of Deeds and provide the Department of Energy and Environment with a copy of this Declaration, certified by the Recorder of Deeds as a true copy of the recorded instrument.
- Owner shall indemnify, save harmless, and defend the District, and all its officers, agents, and employees from and against all claims or liabilities that may arise out of or in

Figure 5.4

GOVERNMENT OF THE DISTRICT OF COLUMBIA Office of the Attorney General

Commercial Division



Procedure and Protocol for obtaining legal sufficiency review of a Stormwater Management Declaration of Covenants from the Office of the Attorney General (OAG)

DC Official Code Section 8-103.01 provides for the promulgation of rules to implement the provision. Section 529 of Title 21 of the District of Columbia Municipal Regulations (DCMR) requires that, under certain circumstances, owners of real property execute a stormwater declaration of covenants containing a stormwater management plan (SWMP) and an easement in favor of the Department of Energy and Environment (DOEE) insuring access. Section 529.3 of the DCMR provides that the declaration of covenants and easement shall "be determined legally sufficient by the Attorney General or the Department's [DOEE's] Designee."

DOEE and OAG have agreed that OAG shall determine legal sufficiency.

Department of Energy and Environment must:

- Provide name and e-mail address of technical reviewer so that OAG may discuss technical issues. If necessary, OAG will provide a PDF of the signed Declaration of Covenants to the
- Provide attached template of the Declaration of Covenants to the owner/developer.

Review Engineer: E-mail address:

Owner/developer must:

- Draft the Declaration of Covenants.
- Subordinate all prior liens to the Declaration.
- Produce evidence of title and all liens on the property (i.e. copy of deed and full title search). Provide a site plan (Exhibit B) as approved by DOEE, showing all required stormwater Best Management Practices (BMPs) and land covers and documenting any Off-Site Retention Volume (Offv), as well as the Required Plan Compliance Sheet generated from the Stormwater Database.
- Provide a maintenance plan of all stormwater BMPs, stormwater infrastructure, and land covers for District approval pursuant to 21 DCMR § 519 (Exhibit C). 5.
- Submit a pdf of the covenant based on the attached form and modified and completed for execution (with Exhibits A, B, and C) and the information set forth in 3 above to the Contact Person at OAG [the submission need not be executed]. Once the OAG Contact Person has approved the form of your covenant and Exhibit A, send by mail or hand delivery the complete, original covenant signed by the Declarant.

 After receiving notification of OAG approval for legal sufficiency, return the OAG approved
- 7. and signed original covenant to DOEE with all exhibits for technical sufficiency review and
- 8. Provide copy of recorded Declaration of Covenants to DOEE.

Contact Person at OAG:

Lawrence Wolk Assistant Attorney General Commercial Division D.C. Office of the Attorney General 441 4th Street, NW, Suite 1010 South Washington, DC 20001 Tel: (202) 724-5094

Fax: (202) 741-0420 lawrence.wolk@dc.gov

Updated May 1, 2018

Figure 5.11 Declaration of Covenants Template.



GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment NATURAL RESOURCES ADMINISTRATION REGULATORY REVIEW DIVISION

DECLARATION OF COVENANTS

For a Stormwater Management Facility

THIS DECLARATION OF COVENANTS (the "Declaration") is made as of this day of _____, 20__, by and between NAME OF PROPERTY OWNER, a LIST TYPE OF CORPORATE ENTITY (if applicable), and its successors and assigns ("Owner"), for the benefit of the DISTRICT OF COLUMBIA, a municipal corporation (the "District").

RECITALS

- A. The Owner is the owner in fee simple of certain real property and improvements (collectively, the "**Property**") located in the District of Columbia and more particularly described in **Exhibit A** attached hereto and made a part hereof. No other person or entity has an ownership interest in the Property.
- B. In order to manage stormwater flow conditions resulting from certain improvements Owner will make to the Property, the regulations of the District, found at Title 21, Chapter 5, of the District of Columbia Municipal Regulations ("DCMR") require that Owner develop and submit for approval a Stormwater Management Plan ("SWMP") for the installation and maintenance of all stormwater best management practices ("BMPs"), stormwater infrastructure, and land covers on the Property (collectively, the "Facility"), and including any obligation to achieve Off-Site Retention Volume (Offv).
- C. Section 529 of Title 21 of the DCMR requires that Owner execute and record, with the District of Columbia Recorder of Deeds, a declaration of covenants running with the land that set forth Owner's responsibilities under the SWMP.

NOW, THEREFORE, for and in consideration of the issuance of building permits and approval of Owner's plans by the District, and other good and valuable consideration the sufficiency of which is hereby acknowledged, for the benefit of and limitation upon Owner and all future owners of the Property, and for the benefit of the District, Owner for itself, its successors and assigns, does hereby acknowledge, represent, covenant, agree, and warrant to the District as follows:

- The foregoing Recitals and attached Exhibits are all hereby incorporated in and
 made a part of this Declaration to the same extent as if herein set forth in full, provided
 however, that said Recitals shall not be deemed to modify the express provisions hereinafter set
 forth.
- 2. The Facility and any responsibility to achieve Off-Site Retention Volume (Offv), as stated in gallons, is shown on the plans approved by the District attached hereto as Exhibit B, the Site Plan, as the same may be amended pursuant to the District's approval.

connection with, either directly or indirectly, any of Owner's actions or omissions with regard to the construction, operation, maintenance and/or restoration of the Facility.

- 11. Owner warrants, and shall ensure, that all prior liens recorded against the Property are subordinate to this Declaration. Failure to subordinate liens shall, at the District's sole election, give rise to termination of any building permits and/or invalidation of any certificate of occupancy relating to the Property.
- 12. Owner shall, at its sole expense, comply with all provisions of this Declaration regardless of any conflicting requirements in any other covenant, easement, or other legal document recorded or unrecorded against the Property. Neither the entering into of this Declaration nor performance hereunder will constitute or result in a violation or breach by Owner of any other agreement or order that is binding on Owner.
- 13. To the extent Owner is an entity, Owner warrants that it: (i) is duly organized, validly existing and in good standing under the laws of its state of organization; (ii) is qualified to do business in, and is in good standing under, the laws of the District of Columbia; (iii) is authorized to perform under this Declaration; and (iv) has all necessary power to execute and deliver this Declaration.
- 14. The form of this Declaration has been approved by the District of Columbia Office of the Attorney General ("OAG") for legal sufficiency pursuant to Title 21, Section 529.3 of the DCMR. This Declaration, and the provisions contained herein, may not be modified, amended, or terminated without the prior written consent of the District and legal sufficiency approval by OAG, such agreement to be evidenced by a document duly executed and delivered in recordable form and recorded with the Recorder of Deeds at no expense to the District.
 - 15. The District has the right to specifically enforce this Declaration.
- This Declaration shall be governed by, construed under, and enforced in accordance with, the laws of the District of Columbia.
- 17. This Declaration has been duly executed and delivered by Owner, and constitutes the legal, valid, and binding obligations of Owner, enforceable against Owner and its successors and assigns, in accordance with its terms.
- 18. If any of the covenants, warranties, conditions or terms of this Declaration shall be found void or unenforceable for whatever reason by any court of law or of equity, then every other covenant, condition or term herein set forth shall remain valid and binding.

[SIGNATURES FOLLOW]

4

Figure 5.11 (continued)

	caused this Declaration of Covenants to be signed by NAME AND TITLE OF PERSON SIGNING ON BEHALF OF OWNER. By:		
caused this Declaration of Covenants to be signed by NAME AND TITLE OF PERSON SIGNING ON BEHALF OF OWNER. By:	caused this Declaration of Covenants to be signed by NAME AND TITLE OF PERSON SIGNING ON BEHALF OF OWNER. By:		
LIST STATE	LIST STATE		d this Declaration of Covenants to be signed by NAME AND TITLE OF PERSON
LIST STATE	LIST STATE		By:NAME, TITLE
LIST STATE	LIST STATE		ACTIVONAL ENGINEENT
I, NAME OF NOTARY, a Notary Public in and for the jurisdiction aforesaid, do hereby certify that George T. Curtis III, who is personally well known (or satisfactorily proven) to me, an being authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged the same to be the act and deed of Curtis Properties Inc, and that s/he delivered the same as such. GIVEN under my hand and seal this day of, 20 Notary Public My commission expires:	I, NAME OF NOTARY, a Notary Public in and for the jurisdiction aforesaid, do hereby certify that George T. Curtis III, who is personally well known (or satisfactorily proven) to me, and being authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged the same to be the act and deed of Curtis Properties Inc, and that s/he delivered the same as such. GIVEN under my hand and seal this day of, 20		ACKNOWLEDGMEN I
certify that George T. Curtis III, who is personally well known (or satisfactorily proven) to me, an being authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged the same to be the act and deed of Curtis Properties Inc, and that s/he delivered the same as such. GIVEN under my hand and seal this day of, 20 Notary Public My commission expires:	certify that George T. Curtis III, who is personally well known (or satisfactorily proven) to me, and being authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged the same to be the act and deed of Curtis Properties Inc, and that s/he delivered the same as such. GIVEN under my hand and seal this day of, 20		_LIST STATE) _ss: _LIST COUNTY)
My commission expires: Notary Public	My commission expires: [NOTARIAL SEAL]	being	y that George T. Curtis III, who is personally well known (or satisfactorily proven) to me, and authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged
My commission expires:	My commission expires: [NOTARIAL SEAL]		GIVEN under my hand and seal this day of, 20
	[NOTARIAL SEAL]		
	5		
	5		
	5		
	5		
	5		
	5		
	5		
	5		
•	3		

- 3. Owner, at its sole expense, shall construct and perpetually operate and maintain the Facility in such manner as to comply with the provisions of Title 21, Chapter 5 of the DCMR and in strict accordance with the SWMP, including the Maintenance Plan, attached hereto as Exhibit C, as the same may be amended pursuant to the District's approval.
- 4. Owner shall, at its sole expense, make such changes or modifications to the Facility as the District, in its discretion, may determine necessary to ensure that the Facility is maintained in good condition and continues to operate as designed and approved.
- 5. The District and its agents, employees, and contractors shall have the right to enter the Property for the purpose of inspecting the Facility in accordance with established inspection procedures and Section 16 of the Water Pollution Control Act of 1984 (D.C. Law 5-188; 32 DCR 919; D.C. Official Code § 8-103.01, et seq. (2013 Repl.), as amended (the "Act"), at reasonable times and in a reasonable manner, in order to ensure that the Facility is being properly maintained and is continuing to perform in the manner approved by the District.
- 6. Should Owner fail to perform its responsibilities as required herein, or fail to operate and restore the Facility in accordance with approved design standards, as the same may be amended from time to time, the District shall be entitled to pursue any and all enforcement actions available to it pursuant to the Act, and Title 21, Chapter 22 of the DCMR, as the same may be amended from time to time. Without limiting the generality of the foregoing, in the event that a discharge or threat of discharge from the Facility poses an imminent and substantial danger to the environment or the public health or welfare, the District may take immediate action against Owner pursuant to D.C. Official Code § 8-103.08(b).
- 7. If Owner's failure or refusal to maintain the Facility in accordance with the covenants and warranties contained in this Declaration ultimately results in corrective action by the District, Owner shall bear all costs incurred by the District for such corrective measures, such costs may be assessed against the Property, and Owner may be fined in accordance with the Act and Title 21, Chapter 5 of the DCMR.
- 8. The provisions of this Declaration shall be deemed warranties by Owner and covenants running with the land and shall bind and inure to the benefit of Owner and the District, their respective heirs, successors and/or assigns. When Owner ceases to own an interest in the Property, the rights, warranties, and obligations under this Declaration shall become the rights, warranties, and obligations of the successor-in-ownership and interest to the Property.
- 9. Owner shall, at its cost and expense, properly record this Declaration with the Recorder of Deeds and provide the District's Department of the Environment with a copy of this Declaration, certified by the Recorder of Deeds as a true copy of the recorded instrument.
- 10. Owner shall indemnify, save harmless, and defend the District, and all its officers, agents, and employees from and against all claims or liabilities that may arise out of or in connection with, either directly or indirectly, any of Owner's actions or omissions with regard to the construction, operation, maintenance and/or restoration of the Facility.
- Owner warrants, and shall ensure, that all prior liens recorded against the Property are subordinate to this Declaration. Failure to subordinate liens shall, at the District's sole

3

Figure 5.4-11 (continued)

APPROVED AS TO TECHNICAL SUFFICIA	ENCY:
Department of Energy and Environment	
Natural Resources Administration	
Watershed Protection Division	
By: Name:	
Name:	
Title:	
Date:	
APPROVED AS TO LEGAL SUFFICIENCY	:
Department of Energy and Environment	
Office of the General Counsel	
Den	
By: Name:	
Title: Assistant General Counsel	
Date:	
Dute.	
6	
6	

election, give rise to termination of any building permits and/or invalidation of any certificate of occupancy relating to the Property.

- 12. Owner shall, at its sole expense, comply with all provisions of this Declaration regardless of any conflicting requirements in any other covenant, easement, or other legal document recorded or unrecorded against the Property. Neither the entering into of this Declaration nor performance hereunder will constitute or result in a violation or breach by Owner of any other agreement or order that is binding on Owner.
- 13. To the extent Owner is an entity, Owner warrants that it: (i) is duly organized, validly existing and in good standing under the laws of its state of organization; (ii) is qualified to do business in, and is in good standing under, the laws of the District of Columbia; (iii) is authorized to perform under this Declaration; and (iv) has all necessary power to execute and deliver this Declaration.
- 14. The form of this Declaration has been approved by the District of Columbia Office of the Attorney General ("OAG") for legal sufficiency pursuant to Title 21, Section 529.3 of the DCMR. This Declaration, and the provisions contained herein, may not be modified, amended, or terminated without the prior written consent of the District and legal sufficiency approval by OAG, such agreement to be evidenced by a document duly executed and delivered in recordable form and recorded with the Recorder of Deeds at no expense to the District.
 - The District has the right to specifically enforce this Declaration.
- This Declaration shall be governed by, construed under, and enforced in accordance with, the laws of the District of Columbia.
- 17. This Declaration has been duly executed and delivered by Owner, and constitutes the legal, valid, and binding obligations of Owner, enforceable against Owner and its successors and assigns, in accordance with its terms.
- 18. If any of the covenants, warranties, conditions or terms of this Declaration shall be found void or unenforceable for whatever reason by any court of law or of equity, then every other covenant, condition or term herein set forth shall remain valid and binding.

[SIGNATURES FOLLOW]

4

Figure 5.4-11 (continued)

Chapter 6 Use of Off Site Retention by Regulated Sites




Figure 5.4- $\underline{11}$ (continued)

APPROVED AS TO TECHNICAL SUFFICIENCY: District of Columbia Department of Energy and Environment Natural Resources Administration Regulatory Review Division By: Name: Title: Date: APPROVED AS TO LEGAL SUFFICIENCY: District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:		
District of Columbia Department of Energy and Environment Natural Resources Administration Regulatory Review Division By: Name: Title: Date:		
District of Columbia Department of Energy and Environment Natural Resources Administration Regulatory Review Division By: Name: Title: Date:		
District of Columbia Department of Energy and Environment Natural Resources Administration Regulatory Review Division By: Name: Title: Date:		
Natural Resources Administration Regulatory Review Division By:	Al	PPROVED AS TO TECHNICAL SUFFICIENCY:
Natural Resources Administration Regulatory Review Division By:	D	istrict of Columbia Danartment of Energy and Environment
Regulatory Review Division By:		
By: Name:		
Name:		-5
Title:	B	y:
APPROVED AS TO LEGAL SUFFICIENCY: District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:	N	ame:
APPROVED AS TO LEGAL SUFFICIENCY: District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:	Ti	itle:
District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:	Da	ate:
District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:		
District of Columbia Office of the Attorney General Commercial Division By: Assistant Attorney General Date: Property Address [include Square and Lot(s)]:		DEPONIED AGEO LEGAL GUEERGIENGS
By:	A	PPROVED AS TO LEGAL SUFFICIENCY:
By:	D	istrict of Columbia Office of the Attorney General
By:Assistant Attorney General Date: Property Address [include Square and Lot(s)]:	C	ommercial Division
Assistant Attorney General Date: Property Address [include Square and Lot(s)]:		AMINIOTOM DATING
Assistant Attorney General Date: Property Address [include Square and Lot(s)]:	В	v:
Property Address [include Square and Lot(s)]:	As	ssistant Attorney General
	Da	ate:
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
6		
		6

390

Figure 5.4- $\underline{11}$ (continued)

THE GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment NATURAL RESOURCES ADMINISTRATION REGULATORY REVIEW DIVISION

AMENDMENT TO DECLARATION OF COVENANTS

For a Stormwater Management Facility

THIS AMENDMENT TO DECLARATION OF COVENANTS (the "Amendment") is made this __day of ____, 20__, by OWNER and its successors and assigns ("Owner") to amend the Declaration of Covenants dated _____, previously approved and recorded with the Recorder of Deeds as Instrument Number _____ (the "Declaration") for the benefit of the District of Columbia, a municipal corporation (the "District").

RECITALS

- A. The Owner is the owner in fee simple of certain real property and improvements (collectively, the "**Property**") located in the District of Columbia and more particularly described in **Exhibit A** attached hereto and made a part hereof. No other person or entity has an ownership interest in the Property.
- B. In order to manage stormwater flow conditions resulting from certain improvements Owner will make to the Property, the regulations of the District, found at Title 21, Chapter 5, of the District of Columbia Municipal Regulations ("DCMR") require that Owner develop and submit for approval a Stormwater Management Plan ("SWMP") for the installation and maintenance of all stormwater best management practices ("BMPs"), stormwater infrastructure, and land covers on the Property (collectively, the "Facility"), and including any obligation to achieve Off-Site Retention Volume (Offv).
- C. Section 529 of Title 21 of the DCMR requires that Owner execute and record, with the District of Columbia Recorder of Deeds, a declaration of covenants running with the land that set forth Owner's responsibilities under the SWMP.

NOW, THEREFORE, for and in consideration of the issuance of building permits and approval of Owner's plans by the District, and other good and valuable consideration the sufficiency of which is hereby acknowledged, for the benefit of and limitation upon Owner and all future owners of the Property, and for the benefit of the District, Owner for itself, its successors and assigns, does hereby acknowledge, represent, covenant, agree, and warrant to the District as follows:

- The Facility defined in Recital B and referenced throughout the Declaration is now identified as [Stormwater BMPs and land covers].
- 2. Exhibits A, B, and C of the Declaration are deleted and replaced with the attached Exhibit A, Exhibit B, and Exhibit C.

1

Figure 5.12 Amendment to Seclaration of Covenants.

3. The Facility and any responsibility to achieve Off-Site Retention Volume (Offv), as	
stated in gallons, is shown on the plans approved by the District attached hereto as Exhibit B the Site Plan, as the same may be amended pursuant to the District's approval.	,

4. All other provisions of the Declaration shall remain in full force and effect.

2


<u>Figure 5.13</u>

5.7 Flow Diagram of Plan Review Process

of a APlan in the Impact Statement Flow charts, in Figures 5.1 through 5.4 illustrate the five steps in DDOE's review of a Stormwater Management Plan (SWMP) and Soil Erosion and Sediment Control Plan in the context of the overall permitting process, which includes the Environmental Impact Statement Form (EISF) process.

PROPOSED PENISION PROPOSED PRO

DRAFT FOR PUBLIC COMMENT



SWMP: Storm Water Management Plan

ERC: Environmental Review Coordinator

PROW: Public Right of Way SRC: Stormwater Retention Credit

EISF: Environmental Impact Screening Form

TSB: Technical Services Branch MEP: Maximum Exent Practicable

Revision Date: 08/15/2012

.12 (continued)

[SIGNATURES FOLLOW] IN WITNESS WHEREOF, Owner has, as of the day and year first above written, caused this Amendment to be signed by NAME OF PERSON SIGNING. NAME OF OWNER NAME OF PERSON SIGNING TITLE ACKNOWLEDGMENT LIST COUNTY I, NAME OF NOTARY, a Notary Public in and for the jurisdiction aforesaid, do hereby certify that NAME OF PERSON SIGNING ON BEHALF OF OWNER, who is personally well known (or satisfactorily proven) to me, and being authorized to do so, executed the foregoing Declaration of Covenants and has acknowledged the same to be the act and deed of NAME OF OWNER, and that s/he delivered the same as such. GIVEN under my hand and seal this ____ day of ____ Notary Public My commission expires: [NOTARIAL SEAL]

Figure 5.12 (continued)

APPROVED AS TO TECHN	IICAL SUFFICIENCY:	
Department of Energy and Env	ironment	
Natural Resources Administrat	ion	
Regulatory Review Division		
Ву:		
Name:		
Title:		
Date:	_	
APPROVED AS TO LEGAL	SUFFICIENCY:	
District of Columbia Office of	the Attorney General	
Commercial Division		
By:		
Assistant Attorney General		
Date:		
Property Address:		

Figure 5.14.12 (continued)




Figure 5.7.12 (continued)

After recording, please return to:

THE GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY AND ENVIRONMENT REGULATORY REVIEW DIVISION

TERMINATION AND RELEASE OF DECLARATION OF COVENANTS

For a Storm Water Management Facility


THIS TERMINATION AND RELEASE OF DECLARATION OF

COVENANTS ("Termination") is entered into and made effective for all purposes as of this _____ day of ______, 20__, between ______ (the "Declarant") and the District of Columbia, acting by and through the Department of Energy and Environment (the "Beneficiary").

WHEREAS, a Declaration of Covenants was made by Declarant for the benefit of Beneficiary on ______, and recorded in the land records of the District of Columbia as Instrument No. ______ (the "Declaration") against the affected property of the Declarant, which property is more specifically described in Exhibit A attached hereto (the "Property"); and

WHEREAS, the Declarant represented to Beneficiary that Declarant did not construct, nor cause to be constructed, the storm water management facility on the Property as provided in the Declaration and that the development plans for the Property submitted to the District of Columbia, including the Site Plan attached as Exhibit B to the Declaration, as of the date that the Declaration was executed (collectively, the "Site Plans") have been abandoned and are without permit under the laws of the District of Columbia; and

<u>Figure</u> 5.13 Stormwater Management and Soil Erosion and Sediment Control Plan Review, Steps 1 and 2.



Note:

SESCP: Soil Erosion and Sediment Control Plan

SWMP: Storm Water Management Plan

ERC: Environmental Review Coordinator

PROW: Public Right of Way

SRC: Stormwater Retention Credit

DCRA: Department of Consumer and Regulatory Affairs

EISF: Environmental Impact Screening Form

TSB: Technical Services Branch MEP: Maximum Exent Practicable

MEP: Maximum Exent Practicable

Revision Date: 08/15/2012

Termination and Release of Declaration of Covenants

WHEREAS, the Declarant has cancelled any permit that may have been obtained for the Site Plans, and said Declarant has provided evidence of the same attached hereto as **Exhibit B**; and

WHEREAS, Declarant has requested a termination of and release from said

Declaration, and based on the representations and agreements of Declarant, Beneficiary


finds good cause for doing so.

NOW, THEREFORE, in consideration of the foregoing premises, of the mutual covenants and agreements set forth in this Termination, the sufficiency of which hereby are acknowledged, the Declarant and the Beneficiary agree as follows:

- Termination and Release. Declarant, with the consent of the Beneficiary, hereby terminates the Declaration, and Beneficiary hereby releases
 Declarant from all covenants and obligations arising thereunder.
- 2. Declarant's Representations. Declarant hereby represents to the Beneficiary as follows: (i) at no time during Declarant's ownership of the Property has a storm water management facility been constructed on the Property, in whole or in part; (ii) neither Declarant nor its successors or assigns, to the best of Declarant's knowledge, have any intention of constructing a storm water management facility on the Property, (iii) any permits issued by the District of Columbia on the basis of the Site Plans have been cancelled and rendered void on or before the date first written above, and (iv) the Declarant has not transferred or provided copies of the

2

Figure 5.6 Stormwater Management and Soil Erosion and Sediment Control Plan Review, Step 3.



ERC: Environmental Review Coordinator

PROW: Public Right of Way

Relief: Relief for Extraordinarily Difficult Site Conditions

PP: Proprietary Practice

SRC: Stormwater Retention Credit

EISF: Environmental Impact Screening Form

TSB: Technical Services Branch

MEP: Maximum Exent Practicable

Revision Date: 08/15/2012

.13 (continued)


- Site Plans to any prospective successor to the Property and is not bound to do so under any ancillary agreement affecting the Property.
- 3. Indemnification. Declarant shall indemnify, hold harmless and defend the Beneficiary from any claims or liability that may arise on or after the date of this Termination, directly or indirectly as a result of a breach of the representations of the Declarant set forth in Paragraph 2 above.
- 4. Recordation. The Declarant shall, at its sole cost and expense, record this Declaration in the land records of the District of Columbia by filing a fully-executed, notarized original with the Recorder of Deeds within 10 days after the date first written above. Within 10 days after recordation, Declarant shall furnish a copy of the recorded Termination, as certified by the Recorder of Deeds, to the undersigned representative of the Beneficiary.
- Entire Agreement. This Termination constitutes the entire agreement between the parties hereto with respect to the matters contemplated herein.
 No oral modification of this Termination shall be binding upon the parties hereto.
- This Termination shall be governed by, construed and enforced in accordance with the laws of the District of Columbia.

3

Figure 5.13 (continued)

foregoing, Beneficiary has cau	as of the dat sed this Term	
(Nar	ne),	(Title) , and has appointed(Title) its attorney in fact to execute,
		is the act and deed of Beneficiary.
DECLARANT:		
(Signature)		(Signature)
(Printed Name and Title)		(Printed Name and Title)
DISTRICT OF COLUMBIA	SS:	1
		I
bearing date as of the day	01	, with annexed Termination
proven to be, the person who e be his/her free act and deed.	xecuted said	onally well known to me as, or satisfactorily Termination and acknowledged the same to cal this _day of,
proven to be, the person who e be his/her free act and deed. Given under my hand a	xecuted said	Termination and acknowledged the same to
proven to be, the person who e be his/her free act and deed. Given under my hand a	xecuted said	Termination and acknowledged the same to eal this _day of, [SEAL
proven to be, the person who e be his/her free act and deed. Given under my hand a 20	xecuted said	Termination and acknowledged the same to eal this _day of, [SEAL
proven to be, the person who e be his/her free act and deed. Given under my hand a 20	xecuted said	Termination and acknowledged the same to eal this _day of, [SEAL
proven to be, the person who e be his/her free act and deed. Given under my hand a 20	xecuted said	Termination and acknowledged the same to eal this _day of, [SEAL
proven to be, the person who e be his/her free act and deed. Given under my hand a 20	xecuted said	Termination and acknowledged the same to eal this _day of, [SEAL

Figure 5.7 Stormwater Management and Soil Erosion and Sediment Control Plan Review, Step 4.



3 (contin	ued)
	BENEFICIARY:
	Department of Energy and Environment
	By:
	Name: Title:
	DISTRICT OF COLUMBIA SS:
	I
	I,, a Notary Public in and for the District of Columbia, DO HEREBY CERTIFY that, of the District
	DO HEREBY CERTIFY that of the District Department of Energy and Environment, with annexed Termination bearing date as of the
	day of20, personally appeared before me in said District on the date given below, being personally well known to me as, or satisfactorily proven to be, the
	person who executed said Termination and acknowledged same to be the free act and
	deed of the duly authorized of the Department of Energy and Environment.
	Given under my hand and official seal this day of, 20
	Notary Public, D.C.
	My commission expires:
	APPROVED AS TO LEGAL SUFFICIENCY
	D.C. Office of the Attorney General
	By:
	Name:Assistant Attorney General
	Date:
	5

Figure 5.13 (continued)



Figure 5.8 Stormwater Management and Soil Erosion and Sediment Control Plan Review, Step 5.

.13 (continued)



Chapter 5_Administration of Stormwater Management Rules

Chapter 6 Use of Off-Site Retention by Regulated Sites

6.1 Off-Site Retention Overview

A regulated site must Regulated sites may retain a minimum volume on site that is equal to 50 percent of the SWRv. Above that minimum on site volume, the regulated site may use off site retention without having to first demonstrate that it would be infeasible to retain that volume on site. However, in order to retain less than the minimum on site volume, the site must demonstrate that on site retention of that volume is technically infeasible or environmentally harmful.

The portion of athe Stormwater Retention Volume (SWRv) through the use of off site retention. The portion of the SWRv that a regulated site does not retain on-site is termed the Off-Site Retention Volume or (Offv₇), and a regulated site sthe following are options for achieving its Offv-are the following:

- Use Stormwater Retention Credits (SRCs), each of which corresponds to one gallon of retention for one year; or
- Pay DDOE's DOEE's in-lieu fee (ILF), the cost of which corresponds to one gallon of retention for one year; or
- A combination of (a) and (b) the above.

The owner of a regulated site may use SRCs that the owner has earned elsewhere in the District or SRCs purchased on the private market. DDOE will provide the regulated site with Contact information for SRC sellers is available in the SRC and Offv Registry at https://doee.dc.gov/src.Interested buyers may also list their contact information for SRC owners who wish to sell their SRCs.-in the SRC and Offv Registry

SRC buyers and sellers negotiate the terms of a transaction between themselves, but the transaction is not complete until <u>DDOEDOEE</u> has approved it. <u>DDOE's DOEE's</u> approval is required so that <u>DDOEDOEE</u> can effectively track ownership and use, including preventing fraudulent use of SRCs₇ and dso-publicly sharesharing the price at which SRCs sell.

The stormwater management plan (SWMP) for a major regulated project opting to use off-site retention must state the total Offv, but the SWMP need not state whether it will meet the Offv with SRCs or ILF. The site has flexibility to change this option from year to year. This Offv, along with related requirements for sites in the Anacostia Waterfront Development Zone (AWDZ), will be recorded in the declaration of covenants filed for the property. Whether using ILF or SRCs, they must be in use as of the successful completion of DOEE's final inspection at the end of the construction process.

Regulated sites are responsible for their Offv on an ongoing basis beginning with DOEE's final construction inspection, just as they must maintain any on-site stormwater best management

practices (BMPs) on an ongoing basis. In other words, they must continue to use SRCs or pay inlieu feea site's Offv must be achieved for the life of the development, similar to paying a lease or utility fee. A site's Offv must be achieved in a minimum of one-year increments, although it can be achieved for multiple years at once by using sufficient SRCs, paying sufficient ILF, or a combination of the two. However, if in the future a regulated site retrofits and achieves its Offv on--site, then it no longer must achieve that volume off site-

A regulated site may meet its Offv for multiple years by paying up front for sufficient in lieu fee to satisfy its Offv for that time period. Likewise, the regulated site may purchase and commit to use sufficient SRCs to satisfy its Offv for multiple years. on an ongoing basis.

SRCs may be banked indefinitely. The one-1-year lifespan of an SRC or in lieu fee ILF payment begins once it is used to satisfy an-Offv.

Once SRCs have been used or sold, they remain valid, even if the owner of the retention practices for which SRCs were certified fails to maintain them. Note, however, that there are consequences for original SRC owners who fail to maintain retention practices for which SRCs have been certified, as discussed in Chapter 7-and Appendix D., "Generation, Certification, Trading, and Retirement of Stormwater Retention Credits" and Appendix D., "Stormwater Retention Credit Forms (Certification, Trading, and Retirement)".

Each SRC will have has a unique serial number, and DDOE will track how DOEE tracks the generation, transfer, use, and retirement of SRCs. If a regulated site is satisfying fails to satisfy its Offv. DDOE obligation, DOEE will automatically assess an in-hou fee, ILF with penalties for late payment, for any site that does not stay current with its Offv obligation. DDOE. DOEE may also take other action, including enforcement action, against a regulated site for failure to comply with an-Offv.

The Stormwater Management Plan (SWMP) for a regulated site opting to use off site retention must state its Offv. This Offv, along with related requirements for sites in the Anacostia Waterfront Development Zone, will be recorded in the declaration of covenants filed for the property. Whether using in lieu fee or SRC, they must be in use as of the successful completion of DDOE's final inspection at the end of the construction process.

6.2 Minimum On-Site Retention Requirement

The minimum on-site requirement for a project is depends on the site location within:

- Areas served by the Combined Sewer System (CSS) in a sewershed where Combined Sewer Overflows (CSOs) will be reduced with storage tunnels;
- Areas served by the CSS in a sewershed where CSOs will be reduced with green infrastructure; or
- Areas served by the Municipal Separate Storm Sewer System (MS4) or that drain directly to a waterbody.

These areas are shown in Figure 6.1 and in the Stormwater Database.

Regulated projects in areas that drain to the portion of the CSS where CSOs will be reduced with storage tunnels have no on-site minimum requirement if they exclusively use SRCs generated outside the CSS or pay ILF to meet their Offv requirement.

All other sites must achieve at least 50% of the SWRv using on-site stormwater BMPs. If it is technically infeasible or environmentally harmful to achieve this 50% minimum requirement in the MS4, direct drainage areas, or in the CSS areas where CSOs will be reduced with GI, sites may request relief from extraordinarily difficult site conditions, which is subject to approval by DOEE.

Any portion of the SWRv that is not met on site must be met off-site by using SRCs or paying ILF.




Figure 6.1 Areas where 50% of SWRv must be achieved on site.

6.26.3 Off-Site Retention via Stormwater Retention Credits

One SRC satisfies one 1 gallon of Off Site Retention Volume (Offv) for one 1 year. The use of an SRC is not restricted by watershed. However, for every gallon of Offv that an Anacostia

Waterfront Development Zone (AWDZ) site elects to meet with SRCs from outside the Anacostia River watershed, it must use 1.25 SRCs.

A regulated site with an Offv may elect at a future date to install additional stormwater best management practices (BMPs) on site in a sufficient volume to eliminate or reduce the Offv.

To use SRCs to meet an-Offv, a regulated site owner must submit an application to use SRCs to meet its Offv (see DOEE using the Stormwater Database as described in Appendix C)., "Off-Site Retention Forms for Regulated Sites." The application must identify the SRCs that are owned by the site ownerwill be used and may cover multiple years of Offv. The application must be submitted 30 days4 weeks in advance of the planned date of use. SRCs (and/or in lieu fee) must be in use as of the successful completion of DDOE's final inspection at (e.g. 4 weeks prior to the Final Construction Inspection or 4 weeks prior to the end of the construction process and thereafter on an ongoing basis-current Offv compliance period).

After DOEE will approve the use of the SRCs after verifying the SRCs ownership of the SRCs and other information in the application to use SRCs, DDOE will approve the use of the SRCs. DDOE. For sites with an Offv requirement, DOEE will not sign off on a regulated site's final inspection at the end of the construction process until it has approved the application and verified that any Offv is achieved. The one1-year lifespan of the SRCs begins as of the date that it is used to meet the Offv.

At least 30 days before SRCs are used to satisfy an Offv are set to expire, the regulated site owner must submit an application identifying additional SRCs that will be used to satisfy the Offv or pay in lieu fee.meet the Offv (i.e. the final construction inspection and every year thereafter).

If DDOE does not receive an application to use SRCs of an in lieu fee payment and a lapse in Offv compliance with an Offv occurs, DDOE shall charge an in lieu fee, with a 10 percent late fee, to the regulated site owner and because DOEE has not received an ILF payment or an application to use SRCs, DOEE shall provide notice to the regulated site owner accordingly. For and charge ILF with a 10% late fee. If the site owner who does not complysatisfy the Offv obligation within 30 days of DDOE's DOEE's notice of a lapse in satisfaction of an Offv obligation and who owns an SRC that has not been used to satisfy the Offv for another site, DDOE, DOEE may apply that SRC any unused SRCs the site owner has to the Offv that is out of compliance. DDOEDOEE may also take enforcement action against a regulated site that fails to comply with an Offv.

Generally, the use of an SRC is not restricted by watershed. However, AWDZ sites that use SRCs that were generated outside the Anacostia Watershed must use 1.25 SRCs for every gallon of Offv. The watershed where SRCs are generated is stated in the SRC and Offv Registry and included in the SRC Serial Number.

The use of an SRC may be restricted by sewershed. The sewershed where SRCs are generated is stated in the SRC and Offv Registry and included in the SRC Serial Number. Areas that do not drain to the CSS will drain either to the MS4 or drain directly to a waterbody. For simplicity in

<u>Chapter 6 Use of Off-Site Retention by Regulated Sites</u>Chapter 6_Use of Off-Site Retention by Regulated Sites

the following list and in Table 6.1, these areas are all referred to as MS4 areas. This is also how they are labeled in the SRC and Offv Registry. Projects are subject to the following restrictions:

- Projects that use SRCs to meet Offv for a site in the CSS that achieves at least 50% of the SWRv on site may use any SRC.
- AWDZ projects that use SRCs to meet Offv must use SRCs generated in the MS4.
- Projects that use SRCs to meet Offv for a site in the MS4 must use SRCs generated within the MS4 area. This provision will take effect upon the publication of DOEE's final rulemaking. This requirement is waived if the SRCs were self-generated from a SWMP approved within 6 months of the effective date of this provision and used to meet an Offv approved by DOEE within 6 months of the effective date of this provision. This requirement is also waived if the SRCs are purchased in accordance with a contract signed within 6 months of the effective date of this provision.
- Projects that use SRCs to meet Offv for a site in the CSS areas where CSOs will be reduced with storage tunnels and that achieve less than 50% of the SWRv on site must use SRCs generated within the MS4 area.
- Projects that use SRCs to meet Offv for a site in the CSS areas where CSOs will be reduced with green infrastructure that achieve less than 50% of the SWRv on site must use either:
 - ♦ SRCs generated within the MS4 area; or
 - ◆ SRCs generated within the CSS areas where CSOs will be reduced with green infrastructure.

The following table summarizes the SRCs from each sewershed that a regulated site may use.

Table 6.1 SRCs that a Site Can Use

Regulated Site Location	Amount of SWRv Achieved On-Site	SRCs that may be Used
AWDZ sites*		SRCs from MS4**
MS4	>=50%	SRCs from MS4***
MS4	<u><50%*</u>	SRCs from MS4***
~	<u>>=50%</u>	Any SRC
CSS areas where CSOs are reduced with GI	<u><50%*</u>	SRCs from MS4 SRCs from CSS areas where CSOs are reduced with GI
CSS areas where CSOs are reduced	<u>>=50%</u>	Any SRC
with storage tunnels	<u><50%</u>	SRCs from MS4

^{*} Relief from extraordinarily difficult site conditions is required.

**AWDZ sites must use 1.25 SRCs for every gallon of Offv if SRCs are generated outside the Anacostia River watershed. Refer to Chapter 2 to determine if the site is an AWDZ site. Relief from extraordinarily difficult site conditions is required.

***Any SRC may be used in the MS4 if the SRC was self-generated from a SWMP approved within 6 months of the effective date of this provision and used to meet an Offv approved by DOEE within 6 months of the effective date of this provision. This requirement is also waived if the SRCs are purchased in accordance with a contract signed within 6 months of the effective date of this provision.

Summary of Key Steps for Using SRCs

- Step 1: Apply to use SRCs to satisfy Offv 30 days4 weeks in advance of final construction inspection.
- Step 2: Receive DDOEDOEE approval of use of SRCs.
- **Step 3:** Schedule final construction inspection with DDOE (Steps 2 and 3 can be reversed).
- Step 4: Pass final construction inspection and start use of SRCs.
- Step 5: 30 days Four weeks before SRC expiration, apply to use additional SRCs to satisfy Offv.
- **Step 6:** Receive DDOEDOEE approval of use of SRCs.
- Step 7: Repeat Steps 5 and 6 as necessary.

6.36.4 Off-Site Retention via In-Lieu Fee

In lieu fee corresponds to one gallon of retention for one year. Payment of one gallon worth of in-lieu fee satisfies one gallon of Off-Site Retention Volume (Offv) for one year. A regulated site may elect to install additional BMPs on site in a sufficient volume to eliminate or reduce the Offv.

Payment of 1-gallon-worth of ILF satisfies 1 gallon of Offv for 1 year. The fees rate is posted on DOEE's website at https://doee.dc.gov/swregs and is adjusted for inflation annually using the Urban Consumer Price Index published by the United States Bureau of Labor Statistics. The fee rate is also available in 21 DCMR § 501.

To use in lieu feeILF to meet an Offv, a regulated site must submit payment to the District, along with a notification DOEE and submit the Notification of ILF Payment form (see , using the Stormwater Database as described in Appendix C). The notification and payment may be, "Off-Site Retention Forms for multiple years. Regulated Sites." The notification and payment must be submitted 30 days four weeks in advance of the planned date of use. In lieu fee (and/or SRCs) must be in use as of the successful completion of DDOE's final inspection at the end of the construction process and thereafter on an ongoing basis.

DOE will confirm receipt of in lieu fee. DDOE an ILF payment. DOEE will not sign off on a regulated site's final inspection at the end of the construction process until it has verified that its Offv is achieved. The one1-year lifespan of the in-lieu fee ILF begins as of the date that it is used to meet Offv. At least 4 weeks before the end of the compliance period achieved with ILF

<u>Chapter 6 Use of Off-Site Retention by Regulated Sites</u>Chapter 6_Use of Off-Site Retention by Regulated Sites

payment, the regulated site owner must submit proof of payment of additional ILF or an application to use SRCs.

If DDOE does not received lapse in Offv compliance occurs because DOEE has not received an ILF payment or an application to use SRCs or an in lieu fee payment and a lapse in compliance with an Offv occurs, DDOE, DOEE shall provide notice to the regulated site owner and charge an in lieu fee ILF, with a 10 percent% late fee, to the regulated site owner and provide notice to the If the site owner accordingly. For a site owner who does not complysatisfy the Offv obligation within 30 days of DDOE's DOEE's notice of a lapse in satisfaction of an Offv obligation and who owns an SRC that has not been used to satisfy the Offv for another site, DDOE, DOEE may apply that SRCany unused SRCs the site owner has to the Offv that is out of compliance. DDOEDOEE may also take enforcement action against a regulated site that fails to comply with an-Offv.

6.46.5 Forms for Use of Off-siteSite Retention

See Appendix C for the following forms for use by the applicant:

Applicants must submit forms online using the Stormwater Database (https://doee.dc.gov/swdb).

Appendix C, "Off-Site Retention Forms for Regulated Sites" contains paper applications that may also be submitted or viewed for reference:

- Application to Use Stormwater Retention Credits for Off-Site Retention Volume
- -- Notification of In-Lieu Fee Payment

7.1 Stormwater Retention Credits Overview

This chapter provides details on the eligibility requirements for certification of Stormwater Retention Credits (SRCs); the administrative process for certifying SRCs; the format for SRC serial numbers; the consequences for failure to maintain SRC-generating retention capacity; buying and selling SRCs; and voluntary retirement of SRCs. The chapter also explains how to calculate SRCs using DDOE's SRC Calculatoreligibility and provides some example calculations. Additional resources and incentives related to the SRC program are available at https://doee.dc.gov/src.

The following background, covered elsewhere in this <u>Guidebookguidebook</u> and the regulations, may be helpful in reviewing this chapter:

- One Stormwater Retention Credit (SRC) is equal to one 1 gallon of retention for one 1 year.
- One SRC can be used by a major regulated project to achieve one gallon of its Off-Site Retention Volume (Offv) for one year.
- The clock starts on an SRC's one1-year lifespan when it is used to satisfy an Offv.
- An unused SRC can be banked for future use without expiring.
- An SRC can be traded.
- An SRC can be voluntarily retired without being used.

7.2 Eligibility Requirements

DDOEDOEE will certify Storm ater Retention Credits (SRCs) for eligible stormwater best management practices (BMPs) and land cover in the District of Columbia. To be eligible, the retention capacity in a BMP or land cover must do the following:

- Achieve retention volume in excess of regulatory requirements, but less than the SRC ceiling;
- For unregulated projects or voluntary stormwater retrofits, achieve retention volume in excess of preprojectpre-project retention but less than the SRC ceiling;
- For regulated projects (see Chapter 2, "Minimum Control Requirements"), achieve retention volume in excess of regulatory requirements, but less than the SRC ceiling;
- Be designed and installed in accordance with a DOEDOEE-approved Stormwater Management Plan (SWMP) and thethis Stormwater Management Guidebook;

- Pass a post-construction inspection and ongoing maintenance inspections; and
- Provide a maintenance contract or maintenance agreement(s) for ongoing maintenance.

In addition, retention capacity installed must have been installed after May 1, 2009 in order to be eligible.

For the first six months following the publication of DOEE's final rulemaking, any SRC-eligible BMP or land cover change installed since May 1, 2009, may apply to generate SRCs. After the first 6 months following the publication of DOEE's final rulemaking, the BMP or land cover change providing retention capacity must have been installed on or after July 1, 2013, in order to be eligible. In addition, the first complete application for certification of SRCs must be submitted within 3 years of DOEE's final construction inspection of the BMP or land cover change. Once a project receives SRC certification from DOEE, the project shall be eligible to generate additional SRCs in future years as long as subsequent applications for certification of SRCs are submitted no later than 6 months after the end of the preceding period of SRC certification. Figure 7.1 includes a flowchart to assist in determining whether a project is eligible to generate SRCs based on its installation date and prior certification of SRCs.




Figure 7.1 SRC Eligibility Cutoff Dates.

7.2.17.2.2 Eligibility Requirements: Retention Volume

To be eligible, retention capacity must achieve retention in excess of stormwater management regulatory requirements or, for unregulated sites, in excess of preproject retention.

For sites required to achieve a Stormwater Retention Volume (SWRvFor sites that are unregulated (all voluntary BMP installations, including those that are 5,000 square feet or greater), eligible retention volume is the volume must be achieved in excess of the SWRv, but less than the SRC ceilingpre-project retention, as shown in Figure 7.42.

For sites required to treat a water quality treatment volume (prior to establishment of SWRv requirements), eligible retention volume is the volume retained in excess of the stormwater treatment requirements in place at that time. For example, for a regulated site that provided treatment for the 0.5 inch storm by installing BMPs capable of retaining the 0.9 inch storm, the eligible retention volume would be the difference between the 0.9 inch storm volume and the 0.5 inch storm volume (i.e., 0.4 inch storm volume).


For sites that are unregulated or that would only trigger the regulations because of the voluntary installation of retention capacity, eligible retention volume is the volume achieved in excess of preproject on site retention, as shown in Figure 7.1.

Guidance on calculating volume eligibility of retention capacity for certification of SRCs is below, and an SRC calculation spreadsheet is available on DDOE's website.

For all Major Land Disturbing and Major Substantial Improvement activities, the retention volume must exceed the stormwater management regulatory requirements, as shown in Figure 7.2.

For sites that triggered the District's 1988 stormwater management regulations, the retention volume must exceed the treatment requirement for that project.

In all cases, <u>DDOEDOEE</u> shall not certify SRCs for retention capacity in excess of the runoff volume expected to occur from a 1.7-inch rainfall event ("SRC Ceiling") (;" see Figure 7.1),2).



This chapter provides guidance on calculating the volume of retention capacity that is eligible for SRC certification. An SRC-calculation spreadsheet is available at https://doee.dc.gov/src, and SRC calculations are performed by the Stormwater Database.




Figure 7.27.1 Retention volume eligible to earn SRCs.

7.2.27.2.3 Eligibility Requirements: Design and Installation

To be eligible for SRC certification, retention BMPs or land covers must be designed and installed according to a DDOEDOEE-approved SWMP, with an as-built SWMP submitted to DDOEDOEE.

DDOE recognizes that some retention capacity, voluntarily installed prior to the establishment of retention standards, was If voluntary BMPs or land cover changes were installed without obtaining DDOEDOEE approval of a SWMP prior to installation. This, this retention capacity may still be eligible to earn SRCs. In such cases, DDOEDOEE will require an as-built SWMP stamped by a professional engineer licensed in the District of Columbia, as well as documentation of existing site conditions prior to the installation of the retention capacity. DDOEDOEE will consider such Applications for Certification of SRCs on a case-by-case basis and will determine eligible retention capacity in accordance with the specifications in this Stormwater Management Guidebookguidebook.

Field Code Changed

7.2.37.2.4 Eligibility Requirements: Inspection

To be eligible for SRC certification, retention BMPs and land covers must pass DOEE's post-construction inspection and continue to pass inspections on an ongoing basis. DOEEDOEE typically inspects BMPs every three3 years but may also conduct unscheduled inspections of retention capacity, on a random basis or as a result of a potential problem that is identified by DDOEEDOEE or the public.

7.2.47.2.5 Eligibility Requirements: Maintenance

To be eligible for SRC certification, retention capacity must be maintained in good working order, as specified by DOEDOEE. In an application for certification of SRCs, the proposed SRC owner (who becomes the original SRC owner once DDOEDOEE certifies the SRCs) signs a statement swearing to maintain the retention capacity for the period of time for which SRC certification is requested. (1 to 3 years at a time, as requested by the applicant). To demonstrate the commitment to maintenance, the applicant must submit a current maintenance contract for the time period for which SRC certification is requested. Alternatively, applicants may conduct this maintenance, but they must demonstrate that they have the expertise and capacity to conduct the maintenance. The applicant shall submit the maintenance contract or other documentation of expertise and capacity as an attachment to the application for certification of SRCs. The maintenance contract or documentation is subject to review and a proval by DOEE to ensure that it meets requirements outlined in the approved SWMP and Chapter 3 Stormwater Best Management Practices (BMPs) of this guidebook and must be in place for the entire period of SRC certification beginning with the date of the application.

7.3 Certification of Stormwater Retention Credits

7.3.1 DDOE will accept applications for certification Certification of SRCs once the regulations related to certification and ownership of SRCs are finalized in the D.C. Register.: Process

Required supporting documentation for the initial application includes the completed SRC ealculation spreadsheet, written DOEE approval of an SWMP, as-built SWMP, and a signed maintenance agreement or contract. Applications for retention capacity installed without prior DDOEDOEE approval of a SWMP must also provide documentation of site conditions prior to installation, including land cover type and existing retention BMPs. (See Chapter 2 and Appendix A for Stormwater Retention Volume calculations.) The BMP or land cover change providing eligible retention capacity must pass its most recent DOEE post-construction inspection, and the application to certify SRCs must be submitted within 6 months of the date of that inspection.

Appendix D contains the <u>The application form for certification of SRCs.</u> is available in the <u>Stormwater Database (https://doee.dc.gov/swdb)</u>. Through the form, <u>DDOEDOEE</u> receives

information that is necessary to track and record generated SRCs. Such information includes the address of the site with eligible retention capacity, the owner of proposed SRCs, and the owner's agent, among other information. Applicants should note the format for submitting information on the drainage areas and BMPs that will generate SRCs on a site. Applicants should assign each drainage area a letter (e.g., A, B, C) and each BMP a corresponding number (e.g., A1, B2, C3). All SWMP and BMP information must be approved by DOEE and BMPs must pass DOEE inspection prior to the application for certification of SRCs.

DDOEDOEE will review the application and supporting documentation to make a determination as to the number of SRCs to certify. DDOEDOEE will send its response to the proposed SRC owner who is listed on the application for certification. DDOEDOEE expects that the proposed SRC owner would very oftenlikely be both the owner of the retention capacity and the owner of the property, but recognizes that this may not always be the case. If the proposed SRC owner is not the property owner, the proposed SRC owner must include documentation of the right to own the SRC applied for.

DOEDOEE will certify up to three3 years' worth of SRCs for eligible retention capacity (the three3-year period is based on DOE's DOEE's typical three3-year inspection cycle).

DOEDOEE will assign each SRC a unique serial number for tracking purposes. At the end of that three3-year period, the owner may apply for another three3 years' worth of SRCs. For example, for 1,000 gallons of eligible retention capacity, DOOEDOEE will certify up to 3,000 SRCs initially and an additional 3,000 SRCs at the beginning of each subsequent three3-year period, as long as the eligibility requirements continue to be met.

An applicant should only apply for certification of SRCs corresponding to the period for which maintenance is planned. For example, if requesting 3 years' worth of SRCs, the application should provide a maintenance contract that lasts for 3 years. In applying for SRCs, an applicant commits to the maintenance of the retention capacity for the time period for which SRC certification is requested. Failure to maintain SRC-generating retention capacity is discussed below.

An applicant who wishes to have SRCs certified after the initial period of certification shall resubmitresubmit an application for certification of SRCs. The required supporting documentation for this resubmittal is a current maintenance contract or documentation of ongoing expertise and capacity to conduct the maintenance. DDOEDOEE expects to issue additional SRCs for retention capacity that has passed reinspection reinspection within the 6 months prior to the date on which the application to certify SRCs was submitted and for which a submitted the commitment to maintain has been demonstrated for the requested period of SRC certification.

Key Milestones for the Generation of SRCs:

- 1. Receive DDOEDOEE approval of the proposed SWMP-;
- 2. Install BMPs and/or land covers-;
- 3. Pass DOEE's post-construction inspection:
- 4. Submit an as-built SWMP;

- 4. Within 3 years of passing DOEE's post-construction inspection submit an application for DDOEDOEE certification of SRCs, including:
- 5. As built SWMP;
- 6. Current a current maintenance contract or documentation of expertise and capacity to conduct maintenance; and
- 7.5. Documentation of the legal right to (if more than 6 months has passed since the SRCs applied for, if the proposed SRC ownerpost-construction inspection, then another DOEE inspection is not the property owner.required);
- **8.6.** Receive DDOEDOEE certification for up to three 3 years' worth of SRCs.
- 9.7. Maintain retention capacity and pass subsequent inspections.*;*
- 10. SubmitWithin 6 months of passing a subsequent maintenance inspection, submit an application for DDOEDOEE certification of SRCs, including:
- 11.8. <u>Current a current</u> maintenance contract or documentation of expertise and capacity to conduct maintenance; and.*
- 12. Documentation of the legal right to the SRCs applied for, if the proposed SRC owner is not the property owner.*
- 13.9. Receive DDOEDOEE certification for up to three3 years' worth of additional SRCs.*
- *Steps 6, 7, 8 and 89 can be repeated indefinitely as long as the project does not lapse in SRC certification for more than 6 months.

7.3.2 Certification of SRCs: DOEE-Funded Projects

If a project received funding from DOEE, then DOEE shall limit the SRC eligibility. DOEE will certify only 50% of the SRCs for which the project would otherwise be eligible. For that period of certification, DOEE will multiply the number of SRCs that would have otherwise been certified by the annual average SRC market price to determine the amount of funds recouped by DOEE (although no payment to DOEE is made). Once DOEE recoups its funding in full, the project may generate 100% of the SRCs for which it is eligible.

For example, if DOEE provided \$5,000 to fund a project eligible to generate 1,000 SRCs per year, DOEE would apply the limitations policy until it recouped \$5,000. See Table 7.1.

Table 7.1 Example DOEE-Funded Project and SRC Certification

Year	SRC Eligibility	SRCs Certified	SRCs Withheld	Average Price (Hypothetical)	Value Recouped	Value Recouped to Date
1	<u>1,000</u>	<u>500</u>	<u>500</u>	<u>\$1.50</u>	<u>\$750</u>	<u>\$750</u>
2	1,000	500	500	\$2.00	\$1,000	\$1,750
<u>3</u>	1,000	500	<u>500</u>	\$2.00	\$1,000	\$2,750
4	1,000	<u>500</u>	<u>500</u>	<u>\$1.50</u>	<u>\$750</u>	\$3,500
<u>5</u>	1,000	<u>500</u>	<u>500</u>	\$1.00	<u>\$500</u>	\$4,000


<u>Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits</u>Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits

	Year	SRC Eligibility	SRCs Certified	SRCs Withheld	Average Price (Hypothetical)	Value Recouped	Value Recouped to Date
	6	1,000	500	500	\$2.00	\$1,000	\$5,000
Ì	7	1,000	1,000	=	=	=	=

<u>DOEE's policy of certifying SRCS for DOEE-funded projects is summarized here for the reader's convenience</u>. The policy is available at https://doee.dc.gov/src and is subject to revision.

7.4 Format of SRC Serial Numbers

RCSRC serial numbers are based on the following format:



For example, a proposed SRC owner submits a complete application for certification of SRCs on January 1-, 2014, for 1,000 gallons of eligible retention capacity located in the Watts Branch subdrainage of the Anacostia River. The retention capacity was installed in accordance with a DDOEDOEE-approved SWMP with "1400" as the identification number. After approving the application for three3 years' worth of SRCs, DDOEDOEE would issue 3,000 SRCs as follows:

This example assumes Watts Branch has been assigned "19" as an identifying number, but the numbering of sub-drainages has not been finalized. When the list of each sub-drainage's identifying number is final, DDOE will post it on its website.

7.5 Failure to Maintain Retention after Certification of Stormwater Retention Credits

Sites need not file a declaration of covenants for the maintenance of retention capacity for which DDOEDOEE has certified SRCs. However, DDOEDOEE will not certify additional SRCs for retention capacity that is not maintained. Furthermore, An original SRC owners will be owner who fails to maintain a BMP or land cover that generates SRCs is required to compensate for the associated retention failure during SRCs certified for the time period for which of the maintenance did not occur failure by doing one of the following: 1) for feiting those SRCs (if they have not been sold or used); 2 purchasing replacement SRCs that DDOE will then retire; or 3) paying in lieu fee to DDOE. means:

- 1. Forfeiting those SRCs by applying to retire them (if they have not been sold or used);
- 2. Purchasing and retiring replacement SRCs; or
- **3.** Paying ILF to DOEE.

7.6 Buying and Selling Stormwater Retention Credits on the Market

Each SRC has a unique serial number, and DDOE will trackDOEE tracks the ownership and use of each SRC. SRC owners may list SRCs for sale in the SRC and Offv Registry in the Stormwater Database. Before the ownership of an SRC can be officially transferred, DDOEDOEE must approve a completed application for transfer of SRC ownership in order to verify the ownership and status of the SRCs. The new owner of the SRCs cannot use the SRCs to meet an Offv until DDOEDOEE has approved the application.

SRCs can be banked for future use without expiring. The one1-year lifespan of an SRC begins once it is used to achieve an Offv.

Key Milestones in Transfer of SRC Ownership:

- 1. Advertise SRCs for sale through the SRC and Offv Registry in the Stormwater Database.
- 14.2. Negotiate terms of transfer/contract between buyer and seller.
- **15.3.** Submit application for transfer of SRC ownership to DDOEDOEE.
- 16.4. Receive DDOEDOEE confirmation of transfer of SRC ownership.

SRCs may also be sold to DOEE through the SRC Price Lock Program, subject to the availability of funds. Full details are available at https://doee.dc.gov/src.

7.7 Voluntary Retirement of Stormwater Retention Credits

An SRC owner can request that an SRC be retired by submitting an application to retire SRCs.

7.8 Quitting the Obligation to Maintain Retention for Stormwater Retention Credits

An original SRC owner can quit the obligation to maintain retention capacity for which an SRC is certified. If the SRC has not been sold or used to satisfy an Offv, the owner may submit an application to retire the SRC. If the SRC was sold or used, the original owner may request that

Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits

DDOE retire another SRC in its place or pay the in-lieu fee ILF to compensate for the retired SRC.

7.9 Calculation of Stormwater Retention Credits

A person should<u>may</u> use <u>DDOE's DOEE's</u> <u>SRC</u> <u>ealculator spreadsheet, available on DDOE's website, Financial Return Calculator</u> to <u>ealculateestimate</u> the retention capacity on that is eligible for SRC certification. The SRC spreadsheet is available at https://doee.dc.gov/src. The calculator is a site that meets the planning and estimation tool only. DOEE does not guarantee financial return, SRC eligibility, or other results.

Use of the SRC calculator spreadsheet is discussed below. Calculation of the storage and retention volume eligibility requirement.of BMPs and land cover changes are described in Chapter 3 and Appendix A. If complete site, construction, and financial information is not available, the tool will use assumptions to provide a rough estimate.

The final calculation of SRC eligibility must be determined using the Stormwater Database when the SWMP information is submitted for review. Use of the Stormwater Database is discussed in Appendix A, "Compliance Calculations and Design Examples" and at https://doee.dc.gov/swdb.

As discussed above, retention capacity must also meet eligibility requirements for design and installation; inspection; and maintenance in order for DDOEDOED to certify SRCs.

Use of the SRC calculator spreadsheet is discussed below. The calculator allows SRC calculation for multiple drainage areas on a site.

Note that major regulated projects that are interested in exceeding the required SWRv in order to generate SRCs should input data in the SRC calculator's Existing Retention section based on the proposed site conditions upon achievement of the SWRv. Any changes to land cover and retention above and beyond the SWRv should be input in the Proposed Retention section. Secnario 3 in Section 7.9 is an example of a major regulated project that exceeds the SWRv in order to generate SRCs.

On the SRC calculator spreadsheet, cells highlighted in blue are user input cells. Cells highlighted in gray are calculation cells, and cells highlighted in yellow are constant values.

The steps given below are meant to be followed while working with DDOE's DOEE's SRC calculator spreadsheetFinancial Return Calculator. Note that only entry of input data is required by users—no manual calculations are required except when more than 4 BMPs. In several sections, you may leave entries blank

Additional instructions are presentavailable within the Financial Return Calculator.

Step 1: Enter General Project Information

- Input the type of project (voluntary retrofit or proposed regulated)
- For voluntary projects, identify whether the project is in each drainagethe MS4, receives

 DOEE funding, and/or participates in the SRC Price Lock Program. For regulated projects, identify the type of activity the site is undergoing (as described in Chapter 2).

Identify the total project area for Steps 1(e) and 2(e) (adding up BMP retention). The
equations utilized in the spreadsheet are given below for informational purposes.or limit of
disturbance.

Step 8: Determine Preproject Retention for Drainage Area 1.

Step 2: Enter the pre- and post-project land cover.

- Input the area of each preprojectpre- and post-project land cover, including Impervious Cover, Compacted Cover, and Natural Cover in lines 14—16.natural cover, compacted cover, impervious cover, and BMP cover. Guidance for various land covers is provided in Appendix N, "Land Cover Designations" and Table A.1 of Appendix A-, "Compliance Calculations and Design Examples."
- Automatic ealculation of background calculations determine retention provided by preproject land cover. This is equivalent to the abstraction provided by the land, determined by modifying the formula for calculating the SWRv. The calculation applies a retention coefficient (0.05 for Impervious Cover, 0.75 for Compacted Cover, and 1.0 for Natural Cover) to each of the land cover areas, using the 1.7 inch storm depth. (line 17).

$$ER_{LC} = (0.05 \times EIA + 0.75 \times ECCA + 1.0 \times ENA) \times \frac{PC}{12} \times 7.48$$

where:

 ER_{LC} = retention from the existing (preproject) land cover (gal) (line 17) EIA = existing (preproject) impervious cover area (ft²) (line 14) ECCA = existing (preproject) compacted cover area (ft²) (line 15) EN = existing (preproject) natural cover area (ft²) (line 16) PC = precipitation ceiling (in.) (line 10)

- Input each existing retention BMP in lines 20–23. If there are more than four existing BMPs, sum the additional BMP retention volumes (for example, BMP 4 + BMP 5 + BMP 6 + ...) by drainage area in the last row (line 23).
- * Automatic calculation of the total existing retention as sum of existing retention by land (line 17) and existing retention by BMPs (lines 20 through 23). (line 25).

$$ER_T = ER_{LC} + ER_{P1} + ER_{P2} + ER_{P3} + ER_{P4.5,6,etc.}$$

where:

 ER_T = total existing (preproject) retention (gal) (line 25) ER_{LC} = retention from the existing (preproject) land cover (gal) (line 17)

```
ER_{P1} = retention from first existing (preproject) BMP (gal) (line 20)

ER_{P2} = retention from second existing (preproject) BMP (gal) (line 21)

ER_{P3} = retention from third existing (preproject) BMP (gal) (line 22)

ER_{P4, 5, 6, etc.} = retention from third existing (preproject) BMP (gal) (line 23)
```

Step 9: Determine Proposed Retention for Drainage Area 1.

- Input the proposed land cover including Impervious Cover, Compacted Cover, and Natural Cover in lines 28-30. Guidance for various land covers is provided in Table A.1 and Appendix N.
- Automatic calculation of retention provided by proposed land cover. This is equivalent to the abstraction provided by the land, determined by modifying the formula for calculating the SWRv. The calculation applies a retention coefficient (1.0.05 for Impervious Covernatural cover, 0.75 for compacted cover, 0.05 for impervious cover, and 1.0.05 for natural BMP cover) to each of the land cover areas, using the 1.7-inch storm depth. (line 31).
- If the site has pre-project BMPs, they will need to be entered (following the instructions for proposed BMPs, below).

Step 3: Enter proposed BMPs

Selec

$$PR_{LC} = (0.05 \times PIA + 0.75 \times PCCA + 1.0 \times PNA) \times \frac{PC}{12} \times 7.48$$

where:

 PR_{LC} = retention from the proposed land cover (gal) (line 31)

 PIA = proposed impervious cover area (ft²) (line 28)

 PCCA = proposed compacted cover area (ft²) (line 29)

 PNA = proposed natural cover area (ft²) (line 30)

 PC = precipitation ceiling (in.) (line 10)

- Input each proposed retention BMP in lines 34-37. If there are more than four existing BMPs, sum the additional BMP retention volumes (for example, BMP 4 + BMP 5 + BMP 6 + ...) by drainage area in the last row (line 37).
- Automatic calculation of the total proposed retention as a sum of proposed retention by land (line 31) and proposed retention by BMPs (lines 34 through 37). (line 39).

$$PR_{T} = PR_{LC} + PR_{P1} + PR_{P2} + PR_{P3} + PR_{P4,5,6,etc.}$$

where:

 PR_{T} = total proposed retention (gal) (line 39)

```
PR_{LC}= retention from the proposed land cover (gal) (line 31)PR_{PI}= retention from first proposed BMP (gal) (line 34)PR_{P2}= retention from second proposed BMP (gal) (line 35)PR_{P3}= retention from third proposed BMP (gal) (line 36)PR_{P4, 5, 6, cic}= retention from third proposed BMP (gal) (line 37)
```

Step 10: Calculate SRCs for Drainage Area 1.

Automatic calculation of SRC eligible volume. The total preproject retention (line 25) is subtracted from the total proposed retention (line 39) providing an initial calculation of SRCs in line 42.

$$PAR_T = PR_T - ER_T$$

where:

PAR_T	_	proposed additional retention (gal) (line 42)
171K4	_	
PR_T		total proposed retention (gal) (line 39)
ER _T	-	total existing (preproject) retention (gal) (line 25)

Step 11: Verify SRC-Eligible Volume Against Maximum Allowable for Drainage Area 1.

• Automatic calculation of SRC_{Ceiling}, based on runoff from preproject land cover, with P = 1.7 inches (line 45).

$$SRC_{Ceiling} = (0.95 \times EIA + 0.25 \times ECCA + 0 \times ENA) \times \frac{PC}{12} \times 7.48$$

where:

 Automatic calculation of maximum allowable number of SRCs. SRCs shall not exceed maximum allowable SRCs, as defined by the difference between the SRC Ceiling and the sum of Preproject BMP Retention (line 46).

$$SRC_{\textit{Maximum}} = SRC_{\textit{Ceiling}} - \left(ER_{P1} + ER_{P2} + ER_{P3} + ER_{P4,5,6,etc.}\right)$$

where:

SRC_{Maximum} = maximum Stormwater Retention Credit allowable (gal) (line 46) SRC_{Ceiline} = Stormwater Retention Credit ceiling (gal) (line 45) = retention from first existing (preproject) BMP (gal) (line 20) = retention from second existing (preproject) SBMP (gal) (line 21) ER_{P3} = retention from third existing (preproject) BMP (gal) (line 22) $ER_{P4.5.6.etc}$ = retention from third existing (preproject) BMP (gal) (line 23)

Automatic output of SRC eligible volume for drainage area 1 by comparing initial calculation of SRCs against maximum allowable (line 48).

if:

$$PAR_{T} < SRC+$$
, then $SRC_{Eligible} = PAR_{T}$

$$SRC_{Eligible} = SRC_{Maximum}$$

otherwise:

$$SRC_{Eligible} = SRC_{Maximum}$$

where:

Step 12: Repeat Steps 1-4 for Each Applicable Drainage Area.

Five drainage area columns are provided. Sites with more than five drainage areas will require additional spreadsheets.

Step 13: Total SRC-Eligible Volume.

Automatic calculation of the total eligible SRC gallons for the site by summing SRC eligible volume for each drainage area in line 50.

$$SRC_{\textit{Eligible-Site}} = SRC_{\textit{Eligible-A}} + SRC_{\textit{Eligible-B}} + SRC_{\textit{Eligible-C}} + SRC_{\textit{Eligible-D}}$$

where:

SRC_{Eligible-Site} = total eligible SRC for the entire site (gal) (line 50) SRC_{Eligible A} = total eligible SRC for Drainage Area 1 (gal) (line 48)

```
SRC=total eligible SRC for Drainage Area 2 (gal) (line 48)SRC=total eligible SRC for Drainage Area 3 (gal) (line 48)SRC=total eligible SRC for Drainage Area 4 (gal) (line 48)
```

- the type(s) of BMPs that are proposed and identify the contributing drainage area (CDA) to the BMPs, including natural cover, compacted cover, impervious cover, and BMP cover. Guidance for various land covers is provided in Table A.1 and Appendix N, "Land Cover Designations."
- Automatic background calculations determine runoff from the CDA. The calculation applies a runoff coefficient (0.00 for natural cover, 0.25 for compacted cover, 0.95 for impervious cover, and 0.95 for BMP cover) to each of the land cover areas, using the 1.7-inch storm depth.
- Enter the storage volume, receiving area, or number of trees planted, as appropriate for the BMP type. Refer to Chapter 3, "Stormwater Best Management Practices (BMPs)" for more information about determining these inputs.
- Automatic background calculations determine the retention volume achieved by the BMP.

Step 4: Enter SRC Project Costs

- Input your own financial data to improve the estimate of financial return on your SRC project.
- Input your own estimated SRC selling prices or use the calculator-populated estimates.

Step 5: SRC Eligibility and Financial Summary

- The Financial Summary is not an official determination by DOEE. DOEE does not guarantee financial return, SRC eligibility, or other results.
- The SRC calculation is based on the proposed BMPs and land cover changes as entered into the calculator. Final calculation of the project's SRC eligibility will be performed in the Stormwater Database.


7.10 Stormwater Retention Credit Calculation Scenarios

This section includes SRC calculation scenarios for voluntarily-installed projects. Each scenario is accompanied by an example of how the design can be entered into the current version of the SRC Financial Return Calculator. Sites that trigger the stormwater management regulations should refer to Appendix A, "Compliance Calculations and Design Examples."

Scenario 1

The site has a single <u>drainage area.SDA</u>. The parcel is a 5,000-square foot rectangle-<u>(see Figure 7.3)</u>. There are two land covers on the site: a 4,000-square foot parking lot and an adjacent 1,000-square foot grass area that is regularly mowed-<u>(see Figure 7.4)</u>. The parking lot is defined as impervious surface and the mowed grass area is defined as compacted cover. The owner contemplates converting 1,000 square feet of parking surface into a bioretention, which is

defined as impervious. Using <u>ChapterSection</u> 3.56 Bioretention, the proposed BMP is designed to retain 1,500 gallons (200.5 cubic feet) of runoff from the parking lot (see Figure 7.5). This project is eligible for 1,500 SRCs.



Step 1: Pre-Project Retention	Drainage Area	В	С	D	Е
Impervious Area (ft²)	A 4 000	0	0	0	- 0
Compacted Cover Area (ft²)	1,000	0	0	0	0
Natural Area (ft²)	0	0	0	0	- 0
Retention from Pre-Project Land Cover (gal)	1,007	0	0	0	0
Retention from Pre-Project Best Management P	Practice (BMP)	916	iii.	32 -	
BMP 1 (gal)	O O	0	0	0	0
BMP 2 (gal)	0	0	0	0	0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
Total Pre-Project Retention (gal)	1.007	ol	0	0	0
AND THE PROPERTY AND ADDRESS OF THE PROPERTY ADDRESS OF TH					
Step 2: Proposed Retention	4.000	ما	٥١	0	-
Impervious Area (ft²)	4,000	0	0	0	0
Compacted Cover Area (ft²)	1,000	0	0	0	0
Natural Area (ft²)	1,007	0	0	0	0
Retention from Proposed Land Cover (gal)	1,007	U]	U	U	
Retention from Proposed BMP - include BMPs r					
BMP 1 (gal)	1,500	0	0	0	0
BMP 2 (gal)	0	0	0	0	0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
Total Proposed Retention (gal)	2,507	0	0	0	0
Step 3: Calculate SRCs (internal calculation)					
Total Additional Retention Proposed	1,500	0	0	0	0
Step 4: Verify SRCs (internal calculation)					
SRC Ceiling	4,292	0	0	0	0
Maximum SRCs (based on Pre-Project BMP)	4,292	0	0	0	0
SRC Eligible Volume (gal)	1,500	0	0	0	(
Site Total SRC Eligible Volume (gal)	1,500				

<u>Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits</u>Chapter 7 Generation, Certification, Trading, and Retirement of Stormwater Retention Credits



Figure 7.3 Scenario 1.




Figure 7.4 Land Cover Type.




Figure 7.5 BMP Design Information.

Scenario 2

The site has a single drainage areaSDA. The parcel is a 5,000-square foot rectangle and is divided between a 4,500-square foot parking lot and an adjacent 400-square foot grass area that is regularly mowed, (see Figure 7.6). There is an existing bioretention (the land areas of all BMPs are considered impervious) covering 100 square feet and determineddesigned to retain 1,000 gallons (133.7 cubic feet) using ChapterSect on 3.56 Bioretention. The parking lot is defined as impervious surface and the mowed grassy area is defined as compacted cover, (see Figure 7.7). The owner contemplates converting the grass area into bioretention and reducing the parking lot size by 1,000 square feet, with that area converted into mowed grass. Using Chapter 3.5 Bioretention, the proposed 400 square foot BMP is designed to retain 1,500 gallons of runoff from the parking lot in addition to the 1,000 gallons retained by the original BMP.

		5,000 square foot parcel	
400 square foot mowed grass area		4,500 square foot parking	Pre-Project
100 square foot BMP		lot	
400 square foot BMP	1,000 square foot mowed	3,500 square foot parking	Proposed
100 square foot BMP	grass area	lot	

	Drainage Area				
Step 1: Pre-Project Retention	Α	В	С	D	E
Impervious Area (ft²)	4,600	0	0	0	0
Compacted Cover Area (ft2)	400	0	0	0	0
Natural Area (ft²)	0	0	0	0	0
Retention from Pre-Project Land Cover (gal)	562	0	0	0	0
Retention from Pre-Project Best Management	Practice (BMP)				
BMP 1 (gal)	1,000	0	0	0	0
BMP 2 (gal)	0	0	0	0	0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
Total Pre-Project Retention (gal)	1,562	0	0	0	0
0. 0 B					•
Step 2: Proposed Retention Impervious Area (ft²)	4,000	0	0	0	0
Compacted Cover Area (ft²)	1,000	0	0	0	0
Natural Area (ft²)	0	0	0	0	0
Retention from Proposed Land Cover (gal)	1,007	0	0	0	0
Retention from Proposed BMP - include BMPs	rotainad from pro	project cond	litions	6.	
BMP 1 (gal)	1,000	-project cond 0	0	0	0
BMP 2 (gal)	1,500	0	0	0	0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
				- 1	-1
Total Proposed Retention (gal)	3,507	0	0	0	0
Step 3: Calculate SRCs (internal calculation	1)				
Total Additional Retention Proposed	1,945	0	0	0	0
Step 4: Verify SRCs (internal calculation)					
SRC Ceiling	4,737	0	0	0	0
Maximum SRCs (based on Pre-Project BMP)	3,737	0	0	0	0
SRC Eligible Volume (gal)	1,945	0	0	0	0
and the second of the second					
Site Total SRC Eligible Volume (gal)	1,945				

Scenario 3

The site is a proposed development with land disturbance activities that trigger the stormwater regulation. We limit the scenario to one of several drainage areas within the project's limits of disturbance. The drainage area is 5,000 square feet. It will contain a newly constructed 4,000-square foot parking lot and an adjacent existing 700 square foot grass area that is regularly mowed. A proposed bioretention will manage parking lot runoff and cover 300 square feet. This bioretention will retain 3,186 gallons based on Chapter 3.5. In this scenario, these gallons are the regulated Stormwater Retention Volume (SWRv) for this drainage area. The parking lot and the bioretention are defined as impervious surface, and the mowed grass area is defined as

compacted cover. The owner contemplates converting 700 square feet of parking lot into bioretention to gain additional retention gallons above the regulatory obligation. Using Chapter 3.5 Bioretention, the additional 700 square feet will provide 3,000 gallons of additional retention.

5,000 square foot parcel



Step 1: Pre-Project Retention	Drainage Area	В	С	D	E
Impervious Area (ft²)	A 4,300	0	0	0	- 0
Compacted Cover Area (ft²)	700	0	0	0	0
Natural Area (ft²)	0	0	0	0	0
Retention from Pre-Project Land Cover (gal;	784	0	0	0	0
Retention from Pre-Project Best Management P	ractice (BMP)				
BMP 1 (gal)	3.186	0	0	0	0
BMP 2 (gal)	0,100	0	0	0	0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
Total Pre-Project Retention (gal)	3,970	0	0	0	0
Step 2: Proposed Retention					
Impervious Area (ft²)	4.300	0	0	0	0
Compacted Cover Area (ft²)	700	0	0	0	0
Natural Area (ft²)	0	0	0	0	0
Retention from Proposed Land Cover (gal)	784	0	0	0	0
resemble in the representation of the resemble in the resemble		-		-	
Retention from Proposed BMP - include BMPs r	etained from pre-	project cond	tions		
BMP 1 (gal)	3,186	0	0	0	0
BMP 2 (gal)	3,000	0	0	0	-0
BMP 3 (gal)	0	0	0	0	0
Add together BMP 4, 5, 6, etc.(gal)	0	0	0	0	0
Total Proposed Retention (gal)	6,970	0	0	0	0
Step 3: Calculate SRCs (internal calculation)				3.4	-
Total Additional Retention Proposed	3,000	0	0	0	0
Ston 4. Varify CDC a finternal calculation		12000			
Step 4: Verify SRCs (internal calculation) SRC Ceiling	4,514	0	0	0	0
Maximum SRCs (based on Pre-Project BMP)	1,328	0	0	0	0
waxiiiuiii SRCS (based oli Fle-Floject BWF)	1,320	U	U	0	
SRC Eligible Volume (gal)	1,328	0	0	0	(

<u>Using Section 3.6 Bioretention</u>, the proposed 400-square foot BMP is designed to retain 1,500 gallons (200.5 cubic feet) of runoff from the parking lot in addition to the 1,000 gallons (133.7 cubic feet) retained by the original BMP. While the two BMPs retain a total of 2,500 gallons, only the 1,500 gallons of new retention is eligible for SRC certification.

In addition, the project reduces stormwater runoff through land cover changes. The removal of 1,000 square feet of impervious surface, adjusted by the installation of a 400 square foot BMP in existing compacted land cover, results in a net conversion of 600 square feet of impervious

<u>surface to compacted land cover. This achieves a retention volume of 445 gallons. Altogether, this project is eligible for 1,945 SRCs (see Figure 7.8).</u>




Figure 7.6 Scenario 2.




Figure 7.7 Land Cover and Pre-Project BMP Information.




Figure 7.8 BMP Design Information.

7.11 Forms for Stormwater Retention Credits

See Appendix D for the following forms for use by the applicant:

Applicants must submit forms online using the Stormwater Database. Appendix D, "Stormwater Retention Credit Forms (Certification, Trading, and Retirement)" contains paper applications that may also be viewed for reference:

Application for Certification of Stormwater Retention Credits

- Application for Transfer of Stormwater Retention Credit Ownership
- Application to Retire Stormwater Retention Credits

PROPOSED PREVIOUS

Appendix A Compliance Calculations and Design Examples

A.1 -Stormwater Database and General Retention Compliance Calculator

The General Retention Compliance Calculator is an Excel file located on the DDOE website at http://ddoe.dc.gov/swregs.

Each regulated project must use the General Retention Compliance CalculatorStormwater

Database for Stormwater Management Plan (SWMP) submittal to DOEE to demonstrate proper

stormwater best management practice (BMP) selection and sizing to achieve the required

amountvolume of stormwater retention and/or water quality treatment. The completed

worksheets from this calculator must be submitted withOnline submittal through the Stormwater

Database is required. While the Stormwater Management Plan (SWMP). Database is used to

provide site and plan information for SWMPs, Soil Erosion and Sediment Control Plans, Green

Area Ratio (GAR) plans, and allow participation in the Stormwater Retention Credit (SRC)

trading and RiverSmart Rewards discount program, this appendix only discusses SWMP

submittal.

The Required Plan Compliance Sheet from the database must be included as part of the SWMP. All major regulated projects are required to address the Stormwater Retention Volume (SWRv), and major regulated projects in the Anacostia Waterfront Development Zone (AWDZ) are required to address the Water Quality Treatment Volume (WQTv), as described in Chapter 2-

The General Retention Compliance Calculator, "Minimum Control Requirements." The Stormwater Database can also be used, in addition to other hydrologic methods and models, to demonstrate compliance with detention obligations (see Section 2.6 and Appendix H)., "Control of 2-Year Storm," Section 2.7, "Control of 15-Year Storm," and Appendix H, "Acceptable Hydrologic Methods and Models)."

Instructions for Compliance Calculations

The following guidance explains how to use each of the worksheet tabs in the General Retention Compliance Calculator.

Note: All cells highlighted in blue are user input cells. Cells highlighted in gray are calculation cells, and cells highlighted in yellow are constant values that generally should not be changed.

This appendix discusses concepts and equations related to the Required Plan Compliance Sheets and provides several SWMP design examples.

Full instructions for the use of the Stormwater Database can be found at http://doee.dc.gov/swdb.

DOEE also provides a General Retention Compliance Calculator (GRCC) spreadsheet which can be used as both a learning and design tool for project engineers. The GRCC is an Excel file located on the DOEE website at https://doee.dc.gov/swguidebook. Instructions for using the spreadsheet can be found there as well.

A.2 Compliance Calculations and Concepts

The following guidance explains calculations and concepts related to demonstrating compliance with DOEE's stormwater management requirements. Many of these calculations and concepts are used on the Required Plan Compliance Sheets from the Stormwater Database. Several calculations are conducted internally in the Stormwater Database based on plan information entered into a project's database record.

Site <u>Drainage Area Compliance</u> Data Sheet

- 17. Input the name of the proposed project on line 9.
- 18. Determine if the site is located in the AWDZ and note in cell E13.
- 19. Determine if the site is located in the MS4 and note in cell E14.
- 20. The regulatory rain event for calculation of the SWRv varies depending upon the type of development. For major land disturbing activities, the SWRv is based upon the 90th percentile depth (1.2 inches). For major substantial improvements, the SWRv is based upon the 80th percentile depth (0.8 inches). If the site is in the AWDZ and undergoing major substantial improvement, the SWRv is based upon the 85th percentile depth (1.0 inches). Choose the type of development on line 15. The regulatory rain event for SWRv will be shown on line 16, and the regulatory rain event for the WQTv (if applicable) will be shown on line 17.
- 1. For the site, indicate the area (in square feet) Regulatory Activities: As described in Section 2.2, "Regulated Site Definition and Examples," major land disturbing activities and major substantial improvement activities will trigger the stormwater management requirements. Further descriptions of these activities can be found in that section.
- 2. Site Drainage Area Tabulation: Each site must be divided into individual site drainage areas (SDAs). Each SDA drains stormwater from the site to a single discharge point or sheet flows from a single area off the site. All area within a project's Limit of Disturbance (LOD) must be counted in a SDA, along with the footprint of buildings or structures which are designated as major substantial improvement activities.
- 21. Site Drainage Area Land Cover: SDAs track the amount of pre-project and post-development Natural Cover, Compacted Cover, and best management practice (BMP) surface area in cells D22 D25.project land cover. Guidance for various land covers is provided in Table A.1. Efforts to reduce impervious cover on the site and maximize Natural Cover will reduce the required Stormwater Retention Volume (SWRv). Portions of a project located in the public right of way should be considered separately from the rest of the site and surface area by cover type should be indicated in cells E22-E25.

- 22.3. Note: This step will be Appendix N, "Land Cover Designations." Note: Counting the post-project land cover will be iterative as BMP sizing is performed; and the area of both BMPs and other land cover types are adjusted. Vehicular access areas should be identified only if the site is in the MS4. Vehicular access areas are a sub-category of impervious cover; therefore, they must be included as a part of the total impervious cover area. The post-project land cover is used to determine the SWRv and WQTv (if applicable) as described in Table 2.1. The SWRv of each SDA is summed and used to determine the project's retention requirement.
- 4. Public Right-of-Way SDAs and the Maximum Extent Practicable Process: SDAs in the public right-of-way (PROW) must be tabulated, and their SWRv summed, separately from SDAs not in the PROW. If the SWRv or WQTv is not met for a SDA in the PROW, the site may still comply if it follows the maximum extent practicable (MEP) process as described in Appendix B, "Maximum Extent Practicable Process for Existing Public Right-of-Way."
- 5. Vehicular Access Area Required Volume: As noted in Section 2.3 Stormwater Retention

 Volume, for all vehicular access areas in the MS4, a minimum of 50% of the SWRv must
 also be retained or treated. This volume is calculated for each SDA as follows:

$$V = \frac{P \times Rv_I \times Av \times 0.5}{12}$$

where:

<u>V</u> = volume within the SDA from vehicular access areas that must be retained or treated (ft³)

P = regulatory rain event for SWRv (in.)

 Rv_I = runoff coefficient for impervious cover (0.95)

Av =area of vehicular access area (ft²)

12 = conversion factor, converting inches to feet

6. Site Drainage Area Location Data: SDAs are assigned location designations depending on which sewershed it drains to: the Municipal Separated Stormwater Sewer System (MS4), the Combined Sewer System (CSS) where combined sewer overflows (CSOs) will be reduced with green infrastructure, or the CSS from a sewershed where CSOs will be reduced with storage tunnels. Section 2.3, "Stormwater Retention Volume" describes how SWRv can be achieved depending on the sewershed location of the site.

Best Management Practice (BMP) Compliance Data

- 1. BMP Tabulation and Land Cover: Proposed stormwater BMPs are assigned to the SDA where the BMP is located. Land cover area within the BMP's contributing drainage area (CDA) is tabulated the same as for a SDA.
- 2. Maximum Retention Volume Received by the BMP, V_{max} : The maximum retention volume received by the BMP (V_{max}) represents the greatest retention volume for which a BMP can be

credited. Regardless of the regulatory rainfall event that applies to the site, the volume calculated is based on a rainfall depth of 1.7 inches.

$$V_{max} = \frac{1.7 \times \left[(Rv_N \times N) + (Rv_C \times C) + (Rv_I \times (I + A_{BMP})) \right]}{12}$$

where:

 $\underline{V_{max}}$ = volume received by the BMP from 1.7-inch rain event (ft³) $\underline{Rv_N}$ = runoff coefficient for natural cover (0.00)

23. From the land cover input, weighted site runoff coefficients (*Rv*) will be calculated (line 33) for both the site and the public right of way based upon the land cover *Rv* values of 0.00 for Natural Cover, 0.25 for Compacted Cover, and 0.95 for Impervious Cover.

 $0/N - AN/SA \times 100$

 $%C = AC/SA \times 100$

 $\frac{\%I = AI/SA \times 100}{}$

 $Rv = (Rv_L \times \%I) + (Rv_C \times \%C) + (Rv_M \times \%N)$

where:

%N = percent of site in natural cover

AN = area of post-development natural cover (ft²) Rv_C = runoff coefficient for compacted cover (0.25)

%C = percent of site in compacted cover

ACC = area of post-development compacted cover (ft²)

 Rv_I = runoff coefficient for impervious cover (0.95)

%I = percent of site in impervious cover

AHI = area of post-development impervious cover- (ft^2)

 $SA = total site area (ft^2)$

Rv = weighted site runoff coefficient

 $Rv_N = \text{runoff coefficient for natural cover } (0.00)$

 Rv_{ϵ} = runoff coefficient for compacted cover (0.25)

 Rv_{\neq} = runoff coefficient for impervious cover (0.95)

24. The SWRv that must be retained on the site and in the PROW will be calculated on line 37.

 $SWRv = P/12 \times Rv \times SA$

where:

 $SWRv = Stormwater Retention Volume (ft^3)$

P = regulatory rain event (in.)

 \underline{A}_{BMP} = area of BMP (ft²)

12 = conversion from factor, converting inches to feet

Rv = weighted site runoff coefficient

SA = total site area (ac)

25. If the site is in the AWDZ, the WQTv that must be treated on site and in the PROW will be calculated on **line 39**. The regulatory rain event for calculation of the WQTv is based upon the 95th percentile depth (1.7 inches).

where:

WQTv = stormwater treatment volume (ft)

P = regulatory rain event (1.7 in.)

12 = conversion from inches to feet

Rv = weighted site runoff coefficient

SA = total site area (ac)

SWRv = Stormwater Retention Volume (ft³)

Table A.1 Land Cover Guidance for General Retention Compliance Calculator, consult Appendix N for more details.

Natural Cover

Land that will remain undisturbed and exhibits hydrologic properties equal to or better than meadow in good condition OR land that will be restored to such a condition. This includes:

- Portions of residential yards in forest cover that will NOT be disturbed during construction.
- Community open space areas that will not be mowed routinely, but left in a natural vegetated state (can include areas that will be rotary mowed no more than two times per year).
- Utility rights of way that will be left in a natural vegetated state (can include areas that will be rotary moved no more than two times per year).
- Other areas of existing forest and/or open space that will be protected during construction and that will remain
 undisturbed.

Operational and Management Conditions in Natural Cover Category:

- Undisturbed portions of yards, community open space, and other areas that will be considered as forest/open space must be shown outside the Limits of Disturbance (LOD) on an approved Soil Erosion and Sediment Control Plan (SESCP) AND demarcated in the field (e.g., fencing) prior to commencement of construction.
- Portions of roadway rights of way that will count as natural cover are assumed to be disturbed during construction, and must follow the most recent design specifications for soil restoration and, if applicable, site reforestation, as well as other relevant specifications if the area will be used as a BMP.
- All areas that will be considered natural cover for stormwater purposes must have documentation that prescribes that the area will remain in a natural, vegetated state. Appropriate documentation includes: subdivision covenants and restrictions, deeded operation and maintenance a reements and plans, parcel of common ownership with maintenance plan, third party protective easement, within public right of way or easement with maintenance plan, or other documentation approved by DDOE.
- While the goal is to have natural cover areas femalin undisturbed, some activities may be prescribed in the appropriate documentation, as approved by DDOE: forest management, control of invasive species, replanting and revegetation, passive recreation (e.g., trail), limited bush hogging to maintain desired vegetative community, etc.
- Land that will undergo conversion from compacted cover or impervious cover to natural cover must follow the guidelines for compost amended so its in Appendix J.

Compacted Cover

Land disturbed and/or graded for eventual use as managed turf or landscaping. Managed turf comprises of areas that are graded or disturbed, and maintained as turf, including yard areas, septic fields, residential utility connections, and roadway rights of way. Landscaping includes areas that are intended to be maintained in vegetation other than turf within residential, commercial, industrial, and institutional settings.

Impervious Cover

Roadways, driveways, rooftops, parking lots, sidewalks, and other areas of impervious cover. While they are noted separately in the spreadsheet, the surface area of all BMPs, except disconnection areas are included with impervious cover in the spreadsheet's calculations.

Drainage Area Sheets 1-10

If the site has multiple discharge points, or complex treatment sequences, it must be divided into individual drainage areas (DAs). For each DA, a minimum of 50 percent of the SWRv must be retained. In the MS4, if 50 percent of the SWRv cannot be retained, that volume (or equivalent 24 hour storm) must be captured and treated with an accepted TSS treatment practice.

For each DA sheet:

- 26. Indicate the specific area of post development Natural Cover, Compacted Cover, Impervious Cover, Vehicular Access, and BMP surface area in lines 6–10. The SWRv for the DA will be calculated in cell G12, and the WQTv (if in the AWDZ) will be calculated in cell G17.
 - Note: This step will be iterative as BMP sizing is performed, and the area of both BMPs and other land cover types is adjusted. Vehicular Access Areas are a sub-category of Impervious Cover. Therefore, the Vehicular Access Areas must be included as a part of the total Impervious Cover area.
- 27. Apply BMPs to the drainage area to address the required SWRv and WQTv by indicating the area in square feet of compacted cover, impervious cover, and vehicular access areas (see not above) to be treated by a given BMP in columns B, D, and F (or the number of trees in the case of tree preservation or planting). This will likely be an iterative process. The available BMPs include the following:
 - ◆ Green Roofs
 - **◆** Rainwater Harvesting
 - ◆ Simple Disconnection to a Pervious Area (Compacted Cover)
 - ◆ Simple Disconnection to a Conservation Area (Natural Cover)
 - ◆ Simple Disconnection to Amended Soils
 - ◆ Permeable Pavement Systems Enhanced
 - ◆ Permeable Pavement Systems Standard
 - **♦** Bioretention Enhanced
 - **♦** Bioretention Standard
 - **◆** Stormwater Filtering Systems
 - ◆ Stormwater Infiltration
 - ◆ Grass Channels
 - ◆ Grass Channel with Amended Soils
 - ◆ Dry Swales
 - ♦ Wet Swales
 - ◆ Stormwater Ponds
 - **♦** Stormwater Wetlands

Appendix A Compliance Calculations and Design Examples

- ◆ Storage Practices
- Proprietary Practices
- ◆ Tree Planting
- ◆ Tree Preservation
- 28. Based upon the area input for a given BMP, the spreadsheet will calculate the Maximum Retention Volume Received by BMP in column H. Regardless of the Regulatory Rainfall Event that applies to the site, the volume calculated in column F is based on a rainfall depth of 1.7 inches. Therefore, the value in column H represents the greatest retention volume for which a BMP can be valued, rather than the volume that must be retained to achieve compliance. In other words, it is possible to "oversize" BMPs in one drainage area and "undersize" others to achieve compliance. However, as noted above, in the MS4, a minimum of 50 percent of the SWRv must be retained in each drainage area. Otherwise, treatment of the remaining runoff to reach 50 percent of the SWRv must be provided by an accepted TSS treatment practice.

$$V_{max} = 1.7/12 \times (Rv_N \times A_N + Rv_C \times A_C + Rv_I \times (A_I + A_{IMP}))$$

- 3. BMP Storage Volume: This value refers to the total volume that can be retained by the BMP, determined using the related BMP storage volume calculations found in Chapter 3. This value is not necessarily the amount of volume which will receive retention credit.
- 4. BMP Retention Value: Depending on the category and sub-category of the BMP, a modifier value is applied to the BMP storage volume. For example, standard bioretention practices are assigned a retention value of 0.6.
- 5. Volume Retained: The stormwater volume that is credited for retention. This value is the lesser of V_{max} or the BMP storage volume multiplied by the BMP retention value.

where:

 V_{max} = volume received by the BMP from 1.7 inch rain event (ft³) Rv_N = runoff coefficient for natural cover (0.00)

 $A_{A'}$ = area of post development natural cover (ft²)

 Rv_C = runoff coefficient for compacted cover (0.25)

 A_C = area of post development compacted cover (ft²) Rv_F = runoff coefficient for impervious cover (0.95)

 $A_{\rm f}$ = area of post development impervious cover (ft²)

 $A_{BMP} = \operatorname{area of } \underline{BMP} (\operatorname{ft}^2)$

29. As noted in Chapter 2, for all vehicular access areas, a minimum of 50percent of the SWRv must also be retained or treated. This volume is calculated for each BMP in **column G** as follows:

$$V = RRE/12 \times Rv_L \times Av \times 0.5$$

where:

V = volume received by the BMP from vehicular access areas that must be retained or treated (ft³)
RRE = Regulatory Rain Event for SWRv (in.)
Treatment Rv. = runoff coefficient for impervious cover (0.95)

 $Av = \text{area of vehicular access area (ft}^{\frac{2}{3}})$

- 30. If more than one BMP will be employed in series, any overflow from upstream BMPs will be accounted for in column L, and the total volume directed to the BMP will be summed in column M.
- 31. For most BMPs it is necessary to input the surface area of the BMP and/or the storage volume of the BMP in columns N and O. These should be calculated using the equations provided in Chapter 3.
- **32.** The spreadsheet calculates a retention volume value in columnP, based on the value descriptions in columns I–K. Regardless of the storage volume of the BMP, the retention volume value cannot be greater than the total volume received by the BMP (column M).
- 33. The Potential Retention Volume Remaining (column Q) equals the total volume received by the BMP minus the retention volume value.
- 34.6. : BMPs that have a less than 100-percent / retention value and are accepted TSS treatment practices are assigned additional treatment volume. This volume is based upon the lesser of the runoff volume received by the BMP and the actual storage volume minus the retention value. This additional treatment volume is indicated in column Ryolume retained.
- 35. Any potential retention volume remaining (column Q)Downstream BMPs and Treatment Trains: If more than one BMP is employed in series, any overflow volume from the 1.7-inch storm from upstream BMPs can be directed to a downstream BMP in column S by selecting from the pull down menu. Selecting a BMP from and applied to the menu will automatically direct the retention volume remaining to column L for the appropriate BMP.
- 36. Column T calculates whether or not the vehicular access area directed to each BMP is adequately addressed, via retention or treatment. To do this, the required runoff volume from the vehicular access area is compared to the retention and treatment volumes provided by the BMP, as well as from a downstream BMP, if selected. For each BMP that receives vehicular access runoff, "Yes" or "No" will be displayed. It should be noted that while this column does take downstream BMPs into account, it is not a precise enough check to ensure that all possible design variations are accounted for. Sufficient retention or treatment from vehicular access areas must be clearly shown on the design plans.

- 37.7. From the selected BMPs, the total BMP's volume retained will be summed in cell P66. The retention volume remaining will then be calculated as the difference between the SWRv and the total volume retained in cell P68 (in cubic feet) and cell P69 (in gallons). Cell P71 indicates if at least 50 percent of the SWRv has been retained for the DA.if any storage volume remains.
- 38. Cell P72 indicates whether or not all of the vehicular access areas have been adequately addressed. This is accomplished with two checks. First, the cell checks that the entire vehicular access area for the drainage area indicated in cell B9 has been included in column F, by comparing cell F66 to cell B9. Second, the cell checks that sufficient retention or treatment volume has been provided in each BMP by searching for "No's" in column T. As noted above, this check is not precise enough to ensure that all possible design variations are accounted for. Sufficient retention or treatment from vehicular access areas must be clearly shown on the design plans.
- **39.** If in the MS4, if 50 percent of the SWRv has not been retained, **cell P73** indicates that treatment is required.
- 40. From the selected BMPs, cell T66 is the sum of the total volume treated. If treatment is required due to a shortage of retention, cells T68 (cubic feet) and T69 (gallons) indicate how much more runoff must be treated. If treatment is required because the site is located in the AWDZ, cells T71 (cubic feet) and T72 (gallons) indicate how much runoff must be treated to meet WOTv requirements.
- 41. Cell P75 will indicate compliance for the DA with a "Yes" or "No," depending on retention and treatment volume provided in the drainage area.

Note: Since only 50 percent of the SWRv must be retained in any individual DA, compliance in each draining carea does not automatically mean that compliance for the entire site has been

Public Right-of-Way Sheet

The Public Right of Way sheet is functionally identical to the Drainage Area sheet; therefore, Steps 1–16 should be followed as stated above. If SWRv or WQTv is not met, the site may still comply if it follows the Maximum Extent Practicable (MEP) process as described in Appendix B.

Compliance Worksheet Tab

The Compliance workshed summarizes the stormwater retention and treatment results for each DA as well as the whole site. For all sites, in order to comply with the stormwater management requirements, each DA must indicate that the vehicular access areas volume has been addressed. In the MS4, each DA must either indicate that 50 percent of the SWRv has been retained, or that there are 0 inches of remaining volume to treat 50 percent of the SWRv. Key values for each drainage area are described on this worksheet, with site compliance and the public right of way summarized at the bottom.

Cell B206 indicates the total volume retained on site. Cell B208 (cubic feet) and cell B209 (gallons) indicate the remaining retention volume (if any) to meet the SWRv. If the SWRv has not been fully met, cell B215 indicates the required Off site Retention Volume (Offv). The Offv may be addressed through the use of Stormwater Retention Credits (SRCs) and/or payment of an

in-lieu fee. If the SWRv has been exceeded, cell B214 indicates the volume that may be available to generate SRCs

This sheet also summarizes the stormwater retention results from the Public Right of Way (PROW) sheet. Cell B224 indicates the Total Volume Retained on site. Cells B225 and B226 show the remaining retention volume (if any) in cubic feet and gallons, respectively. Cells B232–B235 show the remaining treatment volume (if any) to meet SWRv and WQTv requirements.

Channel and Flood Protection

This sheet assists with calculation of Adjusted Curve Numbers that can be used to calculate peak flows associated with the 2-year storm, 15-year storm, or other storm events.

42. Indicate the appropriate depths for the 1 year, 2 year, and 100 year 24 hour storms (or other storms as needed) on **line 5**.

Each cove

Detention Calculations and Concepts

Detention requirements are discussed in Section 2.6, "Control of 2-Year Storm" and Section 2.7, "Control of 15-Year Storm." DOEE accepts the Adjusted Curve Number method for determining compliance with detention requirements, which takes into account the detention benefits of retention BMPs during storm events. The Stormwater Database automatically calculates these adjusted curve numbers for the 2-year, 15-year, and 100-year storms according to the storage BMPs proposed for a project. The procedure for performing these calculations is provided below:

1. Calculate a Weighted Curve Number for both pre-project and post-project conditions. Each land cover type is associated with a Natural Resource Conservation Service (NRCS) curve number. Cells D54, D56, and D58 show the curve number for D.A. 1. Using these curve numbers (or other curve numbers if appropriate), a weighted curve number and the total runoff volume for D.A. 1 is calculated (cell E58). (CN). Additional information on the NRCS CN method can be found in Appendix H.

Weighted Curve Number

$$CN = \frac{(N \times 70) + (C \times 74) + (I \times 98)}{SA}$$

where:

CN = weighted curve number

2. Line 61 calculates the runoff volume without regard to the BMPs employed in D.A. 1. Line 62 subtracts the storage volume provided by the BMPs in D.A. 1 from these totals.

3. The spreadsheet then determines the curve number that results in the calculated runoff volume with the BMPs. This Adjusted Curve Number is reported on line 63.

These steps are repeated for Drainage Areas 2 10.

Weighted Curve Number

$$CN = \frac{(AN \times 70) + (AC \times 74) + (AI \times 98)}{SA}$$

where:

CN = weighted curve number

ANN = area of post development natural cover (ft²) ACC = area of post development compacted cover (ft²) AII = area of post-development impervious cover (ft²)

SA = total site area (ft²)

2. Calculate the runoff without regard to BMPs.

Potential Abstraction

 $S = 1000/(CN \cdot 10)$

$$S = \frac{1000}{CN} - 10$$

where:

S = potential abstraction (in.) CN = weighted curve number

Runoff Volume-with no Retention

$$Q = \frac{(P - 0.2 \times S)^2}{(P + 0.8 \times S)}$$

where:

Q = runoff volume with no BMPs (in.)

P = precipitation depth for a given 24-hour storm (in.)

= 2-year storm (3.14 inches) = 15-year storm (5.23 inches) = 100-year storm (8.34 inches) S = potential abstraction (in.) **Runoff Volume with BMPs**

$$QBMP = Q - CvDA \times 12/DA$$

3. Calculate the runoff with BMPs. This value is the runoff without BMPs minus the total storage volume provided by BMPs.

Runoff with BMPs

$$Q_{BMP} = Q - \frac{Sv_{DA} \times 12}{SA}$$

where:

 Q_{BMP} = runoff volume with BMPs (in.) Q = runoff volume with no BMPs (in.) $Cv_{DA}Sv_{DA}$ = total storage volume provided by BMPs for the drainagesite area (ft³) 12 = unit adjustment factor, feet to inches DA = drainageSA = total site area (ft²)

Adjusted Curve Number

The adjusted curve number is calculated using a lookup table of curve number and runoff volumes so that:

$$\frac{\text{CN}_{\text{adjusted}}, \text{ SO } (\text{P} - 0.2 \times \text{S}_{\text{adjusted}}) \times 2/(\text{P} + 0.8 \times \text{S}_{\text{adjusted}}) = \text{QBMP}}{\text{QBMP}}$$

4. The Adjusted Curve Number is the CN that results in the calculated runoff with the BMPs.

This Adjusted Curve Number can be determined by a table lookup. The user finds the corresponding CN that results in *Q*_{BMP} runoff calculated in Step 3. The lookup table to determine the Adjusted Curve Number is provided in the GRCC. The table can also be usergenerated in a spreadsheet program such as Excel.

Adjusted Curve Number

$$\frac{(P-0.2 \times S_{adjusted})^2}{(P+0.8 \times S_{adjusted})} = Q_{BMP} \rightarrow lookup \ table \rightarrow CN_{adjusted}$$

$$S_{adjusted} = \frac{1000}{CN_{adjusted} - 10} \frac{1000}{CN_{adjusted}} - 10$$

where:


- 5. If the Adjusted Curve Number for the entire project for the 2-year storm event is less than or equal to pre-development conditions, then the 2-year detention requirement is met. If the Adjusted Curve Number for the entire project for the 15-year storm event is less than or equal to the pre-project Adjusted Curve Number, then the 15-year detention requirement is met.
- 6. If the Adjusted Curve Number is not less than its comparison CN, then additional storage is required. A project must demonstrate meeting detention requirements using an acceptable method from Appendix H.

A.2A.3 Design Examples

Design Example 1

Step 1: Determine Design Criteria.

Site Name	Anacostia Offices
Total Site Area	40,000 ft ²
Natural Cover Area	8,000 ft ²
Compacted Cover	$2,000 \text{ ft}^2$
Impervious Cover	30,000 ft ²
Vehicular Access Areas	10,000 ft ²
Is site located within the AWDZ?	No
Is site located within the MS4?	No Yes
What type of activity is site undergoing?	Major LandDisturbing



Step 2: Step 1: Input Design Criteria to Determine the Retention and Treatment Requirements.

The General Retention Compliance Calculator will calculate a Stormwater Retention Volume (SWRv), once the natural cover, compacted cover, and impervious cover areas are put into cells **D22 D25** on the Site Data sheet.

Step 2: Determine the Retention and Treatment Requirements.

Based on the design criteria above, Anacostia Offices has the following requirements:

$$SWRv = \text{cell D37} = 2,900 \text{ ft}^3$$

 $SWRv = 2,900 \text{ ft}^3$

Step 3: Identify Site Constraints and BMP Restrictions.

Key considerations for Anacostia Offices include the following:

- Site soils are contaminated, so infiltration is not allowed, and impermeable liners will be required for most BMPs.
- The commercial land use means that most BMPs are otherwise acceptable.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

While there are numerous options for treatment of this site, two BMPs were selected: rainwater harvesting (R+R-1) for the rooftop and traditional bioretention (B+B-1) for any remaining rooftop runoff and the rest of the site. Since the site is contaminated, a liner is required and the enhanced bioretention option is not available.

The site will ultimately have one outlet point, and the selected treatment train is relatively simple, so the calculations can be performed on one Drainage Area tab. D.A. 1. Therefore, all of the same values from the Site Data tab for the various cover types (plus the vehicle access area) should be put into cells B6 B10 on the D.A. I tab, with one SDA.

The first BMP selected is rainwater harvesting for runoff from the rooftop. The Rainwater Harvesting Retention Calculator should be used to determine the eistern size and the associated retention value. The Rainwater Harvesting Retention Calculator should be used to determine the eistern size and the associated retention value. In the Rainwater Harvesting Retention Calculator, input 20,000 square feet should be put in as the Contributing Drainage Area (CDA) (cell L7). For utilization of the rainwater, flushing toilets/urinals is selected as the use, and the appropriate values are entered. In this case, 500475 people will use the building per day (cell L21). Monday through Friday (cells L30 and L32). 8 hours per day (cell L34). On the Storage Volume Results—Retention Value sheet, the retention values are Available Storage Volume (Sv) is given for various tank sizes. The tables and graphs show that a 30,000—gallon underground tank (or series of tanks) would meet much of the demand and have a very high retention value—94 percentan available storage volume of 2,501 cubic feet.

The next stepBMP is assigned to return to the D.A.SDA 1 tab and input the with a 20,000-square foot CDA into cell D25 for rainwater harvesting and input the efficiency (94%) into cell K25 and a storage volume of 2,501 cubic feet. The result is that 2,530501 cubic feet of runoff are is retained and 162191 cubic feet remain. Since Standard Bioretention will be the next BMP in the series, it should be selected from the pull down menu in cell S25. The the remaining runoff volume will then be directed to this BMP.

In addition to the overflow from the rainwater harvesting BMP, the bioretention area will receive runoff from the rest of the site. Initially, these land uses can be input into cells B39—D40. However, the surface area of the bioretention area must be accounted for as well. Through trial and error, it was determined that a 1,000-square-foot bioretention area would be sufficient to meet the retention requirement. This area will be taken from the compacted cover area and will need to be changed on the Site Data Tab as well as at the top of DA. 1-replaced by BMP cover. Compacted cover will now be 1,000 square feet, and BMP will be 1,000 square feet. The 8,000 square feet of natural cover will remain. Impervious cover directed to the bioretention area (cell D39) will be 10,000 square feet (the remaining impervious area after 20,000 square feet was removed for rainwater harvesting). There will also be 1,000 square feet of compacted cover and 1,000 square feet of BMP surface area will also be directed to the bioretention area (cells B40 and D40). Since the 10,000 square feet of impervious cover is made up of driveway and parking area, it is all classified as vehicular access area, so 10,000 should be put into cell F39 as well.

The vehicular access retention/treatment requirement is 475 cubic feet (cell G39), and the total volume directed to the bioretention area, including the "overflow" from the rainwater harvesting BMP, will be 1,677707 cubic feet (cell M39). Inputting 800 cubic feet for the The bioretention storage volume in the spreadsheet (cell O39) of 800 cubic feet is more than sufficient to address the vehicular access volume and leads to an exceedance of 30082 gallons for the SWRv (cell Q69). This information is also summarized on the Compliance worksheet tab.

Step 5: Size the BMPs According to the Design Equations.

The size of the rainwater-harvesting cistern was already determined to be 30,000 gallons, although additional volume may be necessary for dead storage for a pump, and/or freeboard.

To meet the bioretention criteria, the bioretention area is sized with 1.5 feet of filter media, 0.75 feet of gravel, and a 0.5-foot ponding depth. The bioretention cell sizing goal is 800 cubic feet.

Step 5.1: Check the Filter Media Depth.

Ensure that the filter media depth does not exceed the maximum in Table 3.2120. The ratio of the surface area of the BMP $(1,000 \text{ ft}^2)$ to the contributing drainage area CDA $(32,000 \text{ ft}^2)$ is 3.1%. The Rv for the contributing drainage area CDA to the bioretention practice is 0.93. The maximum filter media depth allowed is 5.04 feet. As the bioretention was sized with 1.5 feet of filter media, it passes this check.


Table 3.21-20	Determining	Mavimum	Filtor	Madia	Donth (fa	ωt)
Table 3. ∠ ⊢∠0	Determining	wiaximum	rinter	viedia	Debin (16	eu)

SA:CDA					Rv _{CDA}				
(%)	0.25	0.3	0.40	0.50	0.60	0.70	0.80	0.90	0.95
0.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5
1.0	5.0	5.5	6.0	6.5	6.5	6.5	6.5	6.5	6.5
1.5	3.5	4.0	5.0	6.0	6.0	6.5	6.5	6.5	6.5
2.0		3.0	4.0	4.5	5.5	6.0	6.0	6.5	6.5

2.5		3.5	4.0	4.5	5.0	5.5	6.0	6.0
3.0			3.5	4.0	4.5	5.0	5.5	5.5
3.5			3.0	3.5	4.0	4.5	5.0	5.0
4.0				3.0	3.5	4.0	4.5	4.5
4.5					3.5	3.5	4.0	4.0
5.0						3.5	4.0	4.0
5.5							3.5	3.5
6.0							3.0	3.5
6.5								3.0
7.0 <u>+</u>								
7.5								
8.0								
8.5								
9.0								
9.5								
10.0								

Step 5.2: Determine Storage Volume.


Equation 3.5



<u>d</u> media	=	depth of the filter media, including mulch layer (ft)
$\eta_{media}^{\overline{}}$	=	effective porosity of the filter media (typically 0.25)
d_{gravel}	=	depth of the underdrain and underground storage gravel layer,
ŭ		<u>including choker stone</u> (ft)
η_{gravel}	=	effective porosity of the gravel layer (typically 0.4)
$SA_{average}$	=	the average surface area of the bioretention (ft ²)
		typically, where SA_{top} is the top surface area of bioretention,
		$SA_{average} = \frac{SA_{bottom} + SA_{top}}{2} SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$
$d_{ponding}$	=	maximum ponding depth of the maximum ponding depth of the bioretention (ft)

Solving Equation 3.5 often requires an iterative approach to determine the most appropriate bottom surface area and average surface area to achieve the desired Sv. bioretention (ft)

Solving Equation 3.5 often requires an iterative approach to determine the most appropriate bottom surface area and average surface area to achieve the desired Sv. In this case, a bioretention with a 40–foot by 25–foot top area and 3:13H:1V side slopes will provide $\underbrace{\text{aan}}_{\text{SA}_{\text{top}}}$ SA_{top} of 1,000 square feet, $\underbrace{\text{aan}}_{\text{SA}_{\text{bottom}}}$ of 814 square feet, $\underbrace{\text{aan}}_{\text{SA}_{\text{average}}}$ of 907 square feet, and achieve $\underbrace{\text{aan}}_{\text{SA}}$ Sv of 1,003 cubic feet. This more than meets the goal of 800 cubic feet. If desired, the surface area of the practice could be reduced accordingly, or more SRCs could be generated with the excess volume.



Step 6: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include the following:

- Based upon the above design, the rainwater harvesting cistern will be 30,000 gallons, and the bioretention cell will require at least 1,000 square feet of surface area. The designer would need to ensure that space would be available for these BMPs on the site.
- The <u>contributing drainage areaCDA</u> for traditional bioretention must be 2.5 acres or less and this site is less than 1 acre.
- The required head for the above design will be <u>253.5</u> feet, including ponding depth (9 inches), mulch (3 inches), filter media (18 inches), choking layer (about 3 inches), 3 inches), and gravel layer (about 9 inches). (See: see Figure 3.4816). The outlet for the underdrain must be at least this deep.
- The water table must be at least 2 feet below the underdrain, or 5.5 feet below the surface. According to the Soil Survey, Beltsville soils have a 1.5- to 2-foot depth to seasonally high groundwater table, Croom soils have greater than a 5-foot depth, and Sassafras soils have a 4-foot depth. On-site soil investigations will be needed to determine if the 5.5-foot depth to the groundwater table can be met on this site.
- Due to soil contamination and the bioretention area's proximity to the building (less than 10 feet), an impermeable liner is required.

Since all of these assumptions and requirements can be met in this design example (pending groundwater table investigations), this step is complete.

Step 7: Use the Adjusted Curve Number to Address Peak Flow Requirements.

On the Channel and Flood Protection tab, enter values for C soils in cells **D54**, **D56**, and **D58** (70 for natural areas, 74 for turf, and 98 for impervious cover, respectively). The original site curve number The original site CN of 92 is reduced for the 2-year, 15-year, and 100-year storms to 79, 82, and 83, respectively, by the retention to requirements for this site.

Step 8: Determine Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the preproject-project-peak discharge rate. Appendix H, "Acceptable Hydrologic Methods and Models" includes details on the procedure for calculatinghow to calculate the detention volume. In this example, the proposed impervious cover and the proposed runoff curve number is CN are less than the <a href="mailto:preproject-p

The peak inflow (q_{i2}) and the peak outflow (q_{o2}) can be calculated using the WinTR-55 Small Watershed Hydrology program, the area of the site, the time of concentration $(Tc)_{5a}$ assumed to

be 10 minutes), and the <u>eurve numbers.CNs</u>. The reduced <u>eurveCN</u> of 79, determined above, generates a q_{i2} of 1.61 cubic feet per second (cfs). The <u>eurve numberCN</u> for meadow in good condition, 71, generates a q_{o2} of 1.07 cfs.

The ratio of 1.07 cfs to 1.61 cfs equals $0.63\underline{66}$. Using Figure H.1, the ratio of storage volume (Vs_2) to runoff volume (Vr_2) is 0.22.




Figure A.1 Approximate detention basin routing for rainfall types I, IA, II and III.

The runoff volume (Vr_2) determined from the General Retention Compliance Calculator with BMPs is 1.3334 inches, (Q_{BMP}), which equates to 4,333358 cubic feet. (Vr_2). Using the calculated ratio of Vs_2/Vr_2 , the storage volume required for the site (Vs_2) is 1,020959 cubic feet.

With appropriate orifice design to ensure that outflows are properly restricted, this detention volume can be incorporated below the proposed bioretention area or located elsewhere on the site as a standalone detention practice.

Design Example 2

Step 1: Determine Design Criteria.

Design Example 2 includes the following proposed design criteria:

Site Name	Downtown Multi-Story Renovation
Total Site Area	15,000 ft ²
Natural Cover Area	0 ft ²
Compacted Cover	0 ft^2
Impervious Cover (Rooftop)	15,000 ft ²
Vehicular Access Areas	$0 ext{ ft}^2$
Is site located within the AWDZ?	No
Is site located within the MS4?	Yes
What type of activity is the site undergoing?	Major Substantial Improvement

Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

The Compliance Calculator Spreadsheet will calculate a Stormwater Retention Volume (SWRv), once the above values are put into the Site Data sheet.

Based on the design criteria above, the Multi-Story Renovation project is required to treat 0.8 inches of rainfall for the SWRy:

$$SWRv = cell D37 = 950 \text{ ft}^3 SWRv = 950 \text{ ft}^3$$

Step 3: Identify Site Constraints and BMP Restrictions.

Key considerations for the Multi-Story Renovation project include the following:

- Since this is a rooftop-only site, very few treatment options are available.
- As a renovation, the structure of the existing roof will be a factor for any rooftop practice.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

As an initial estimate, 75-percent of the rooftop is proposed to be converted to a green roof, with the remaining 25-percent of draining to it. Therefore, the land use values need to be changed to account for the green roof: 3,750 square feet should be entered as impervious cover in cell D24 on the Site Data sheet, and 11,250 square feet should be entered in cell D25 as "BMP." As there. There will be only one drainage area SDA for the site, these same values should be entered into cells B8 and B10 on sheet D.A. 1. and as the Green Roof drainage area (cells D23 and D24).

._The goal of this design is to capture the entire retention volume (950 ft³) in the Green Roof. This can be shown on the spreadsheet by entering 950 cubic feet in cell O23 on sheet D.A. A. Cell Q69 shows that the SWRv has been met for the site. This information is also summarized on the Compliance worksheet tab.green roof.

Step 5: Size the BMPs According to the Design Equations.

The green roof needs to be sized according to Equation 3.1. Since green roofs are typically manufactured systems, several of the parameters, such as the drainage layer depth and maximum water retention of all layers, need to be provided by the manufacturer. The values for the roof used in this design are provided in the variable descriptions below Equation 3.1 (with each layer illustrated in Figure 3.1).

Equation 3.1 Storage Volume for Green Roofs

$$Sv = \frac{SA \times [(d \times \eta_1) + (DL \times \eta_2)]}{12}$$

$$Sv = \frac{SA \times [(d \times \eta_1) + (DL \times \eta_2)]}{12}$$

where:

Sv = storage volume (ft³) (goal is 950 ft³) SA = green roof area (ft²) (need to determine)

d = media depth (in.) (6 in.)

 η_1 = verified media maximum water retention (0.25)

DL = drainage layer depth (in.) (1 in.)

 η_2 = verified drainage layer maximum water retention (0.4)




Figure 3.1 Typical layers for a green roof.

Rearranging Equation 3.1 to find finds the minimum required surface area:

Or:
$$SA = Sv/[(d \times \eta \ 1) + (DL \times \eta \ 2)] \times 12$$

$$SA = 950/(6 \times 0.25 + 1 \times 0.4) \times 12$$

$$SA = \frac{Sv \times 12}{[(d \times \eta_1) + (DL \times \eta_2)]}$$
 or:
$$SA = \frac{950}{[(6 \times 0.25) + (1 \times 0.4)] \times 12} = 6,000 \text{ ft}^2$$

Therefore, the green roof must be sized to be at least 6,000 square feet, given the proposed depths. The original assumption was that an 11,250-square-foot roof would be used. Since a smaller roof is feasible, the drainage areas in the spreadsheet may be revised accordingly.

Note: The drainage area If the CDA to the green roof is only 25 percent larger than increased beyond the area of the green roof itself, so the maximum design details will need to be provided that show how runoff from the additional drainage CDA will be sufficiently distributed over the

green roof. The absolute maximum CDA to the green roof shall be no more than 100% larger than the area to a 6,000 square foot roof is 1,500 square feet.of the green roof. Alternatively, thea larger green roof may be utilized, and the increased storage volume can be used to reduce peak flow volume requirements (see Step 8) or sold as Stormwater Retention Credits SRCs.

Step 6: Check Design Assumptions and Requirements.

Step 6:Step 1: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include the following:

- A structural analysis of the building is needed to determine that the green roof can be supported by the existing structure.
- Ensure that there is sufficient space on the rooftop (allowing for structures such as vents, steep areas of the roof, and other panels). In this case, the minimum roof area of 6,000 square feet is less than half of the entire roof area, and most roofs can accommodate this area.
- At least 1,500 square feet of the rooftop not covered by green roof needs to be designed so
 that it drains to the green roof without damaging it.

Since all of these assumptions and requirements can be met in this design example, this step is complete.

Step 7:Step 1:Use the Adjusted Curve Number to Address Peak Flow Requirements.

The initial curve number for this site is 98, but retention provided by the green roof changes this number. The Channel and Flood Protection tab notes the reduced curve numbers for the 2 year, 15 year, and 100 year storms: 90, 91, and 92, respectively. These curve numbers can be used to help determine detention requirements for this site.

Step 8:Step 1: Determine Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the preproject peak discharge rate. Appendix H includes details on the procedure for calculating the detention volume. In this example, since the proposed land cover is the same as the preproject conditions, detention is not required for the 15-year storm. However, detention is required for the 2-year storm.

The peak inflow, q_{i2} and the peak outflow, q_{o2} can be calculated using the WinTR 55 Small Watershed Hydrology program, the area of the site, the time of concentration (Tc, assumed to be 10 minutes), and the curve numbers. The reduced curve of 90, determined above, generates a q_{i2} of 1.00 cubic foot per second (cfs). The curve number for meadow in good condition, 71, generates a q_{o2} of 0.39 cfs.

The ratio of 0.39 cfs to 1.00 cfs equals 0.39. Using Figure H.1, this equates to a ratio of storage volume (Vs_2) to runoff volume (Vr_2) of 0.33.

The runoff volume (Vr₂) determined in the Compliance Calculator spreadsheet is 2.21 inches, which equates to 2,763 cubic feet. Using the calculated ratio of Vs₂/Vr₂, the storage volume required for the site (Vs₂) is912 cubic feet.


Rooftop Storage (see Appendix I) may be the most cost effective method for achieving this detention volume in this example.

Design Example 3

Step 1: Determine Design Criteria.

Design Example 3 includes the following proposed design criteria:

Site Name	Ward 5 Low-Rise Commercial
Total Site Area	25,000 ft ²
Natural Cover Area	0 ft^2
Compacted Cover	5,000 ft ²
Impervious Cover	20,000 ft ²
Vehicular Access Areas	10,000 ft ²
Is site located in the AWDZ?	No
Is site located within the MS4?	Yes
What type of activity is site undergoing?	Major LandDisturbing



Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

Step 2:Step 1:Input Design Criteria to Determine the Retention and Treatment Requirements.

The Compliance Calculator Spreadsheet will calculate a Stormwater Retention Volume (SWRv), once the natural cover, compacted cover, and impervious cover areas are put into cells D22–D25 on the Site Data sheet.

Based on the design criteria above, the project has the following requirement:

SWRv = cell D37 =
$$2,025 \text{ ft}^3$$

SWRv = $2,025 \text{ ft}^3$

Step 3: Identify Site Constraints and BMP Restrictions.

Key considerations for the project include the following:

- Only a small portion of the compacted cover is available for potential BMPs.
- The Multi-Family Residential site is not restrictive of BMP options.

 The relatively permeable Sunnyside-Sassafras-Muirkirk-Christiana soils on this site allow for infiltration into site soils.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

An enhanced bioretention with no underdrain is chosen for this site, primarily to minimize cost. Several other options, such as permeable pavers, would have been acceptable at this site.

The site will ultimately have one outlet point, with only one BMP, so the calculations can be performed on one Drainage Area tab—D.A. 1. Therefore, all of the same values from the Site Data tab for the various cover types (plus the vehicle access area) should be put into cells B6—B10 on the D.A. 1 sheet there is only one SDA.

It is assumed that the entire site will be directed to the bioretention area, so the same values from the top of the DA1 sheet may be input into cells B37—F38 (including the 10,000 square feet of vehicle access area in cell F37. However, the surface area of the bioretention area must be accounted for as well. It was determined that only 1,000 square feet of compacted cover would be available for a bioretention area. This area will be taken from the compacted cover area, and will need to be changed on the Site Data Tab as well as the top of D.A. 1. Compacted cover will now be 4,000 square feet, and "BMP" area will be 1,000 square feet. The rooftop and parking areas will not change. This approach will lead to a total volume of 2,968 cubic feet directed to the BMP.

Since enhanced bioretention receives 100 percentreceives 100% retention value, the required storage volume to meet the SWRv is 2,095 cubic feet (this. This is the required SWRv after changes in land use were made to account for the bioretention surface area). However, the 1,000 square feet available will not be sufficient to provide the entire required storage volume. Through trial and error (see Step 5 below) it was determined that the maximum storage volume is 1,301 cubic feet. This value can be input into cell O37. Cell P68 indicates that While this stormwater management plan achieves at least 50% on-site retention, it does not achieve 100%; there is still 794 cubic feet, or 5,939 gallons (cell 169), remaining. This volume will have to be met through the purchase or generation of SRCs (see Chapter 7, "Generation, Certification, Trading, and Retirement of Stormwater Retention Credits (SRCs) (see Chapter 7" and Step 9 below).

Step 5: Size the BMPs According to the Design Equations.

Assume a filter media depth of 2 feet, a gravel depth of 0.75 feet, and a ponding depth of 1 foot.

Step 5.1: Check the Filter Media Depth.

Ensure that the filter media depth does not exceed the maximum in Table 3.2120. The ratio of the surface area of the bioretention (1,000 ft²) to the contributing drainage areaCDA (25,000 ft²) is 4%. The Rv was previously determined to be 0.84. The maximum filter media depth allowed is 4.0 feet. As the bioretention was sized with 2 feet of filter media, it passes this check.

Table $3.21\underline{20}$ Determining Maximum Filter Media Depth (feet)

SA:CDA	DA Rv _{CDA}								
(%)	0.25	0.3	0.40	0.50	0.60	0.70	0.80	0.90	0.95
0.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5	6.5
1.0	5.0	5.5	6.0	6.5	6.5	6.5	6.5	6.5	6.5
1.5	3.5	4.0	5.0	6.0	6.0	6.5	6.5	6.5	6.5
2.0		3.0	4.0	4.5	5.5	6.0	6.0	6.5	6.5
2.5			3.5	4.0	4.5	5.0	5.5	6.0	6.0
3.0				3.5	4.0	4.5	5.0	5.5	5.5
3.5					3.5	4.0	4.5	5.0	5.0
4.0					3.0	3.5	4.0	4.5	4.5
4.5						3.5	3.5	4.0	4.0
5.0							3.5	4.0	4.0
5.5								3.5	3.5
6.0								3.0	3.5
6.5									3.0
7.0 <u>+</u>									
7.5									
8.0									
8.5									
9.0									
9.5									
10.0)					

Step 5.2: Determine the Storage Volume.

Equation 3.5

$$Sv = SA_{bottom} \times [(d_{media} \times \eta_{media}) + (d_{gravel} \times \eta_{gravel})] + (SA_{average} \times d_{ponding})$$

$$Sv = SA_{bottom} \times \left[(d_{media} \times \eta_{media}) + \left(d_{gravel} \times \eta_{gravel} \right) \right] + (SA_{average} \times d_{ponding})$$

where:

Sv total storage volume of bioretention (ft³) SA_{bottom} bottom surface area of bioretention (ft²) d_{media} depth of the filter media, including mulch layer (ft) = effective porosity of the filter media (typically 0.25) η_{media} = depth of the underdrain and underground storage gravel layer d_{gravel} including choker stone (ft)


= effective porosity of the gravel layer (typically 0.4) η_{gravel} the average surface area of the bioretention (ft²) $SA_{average}$

typically, where SA_{top} is the top surface area of bioretention,

$$SA_{average} = \frac{SA_{bottom} + SA_{top}}{2} SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$$
the maximum ponding depth of the bioretention (ft)

 $d_{ponding}$

Solving Equation 3.5 often requires an iterative approach to determine the most appropriate bottom surface area and average surface area to achieve the desired Sy. In this case, a long, narrow practice with a 50-foot by 20-foot top area and 3:15H: N side slopes was all that would fit on the site. This configuration will provide $\underbrace{\text{aan}}_{SA_{top}}$ of 1,000 square feet, $\underbrace{\text{aan}}_{SA_{bottom}}$ of 616 square feet, $\underbrace{\text{aan}}_{SA_{average}}$ of 808 square feet, and will achieve an Sv of 1,301 cubic feet.



Step 6: Check Design Assumptions and Requirements.

Step 6:Step 1:Cheek Design Assumptions and Requirements.

Key assumptions and requirements for this site include:

Key assumptions and requirements for this site include the following:

- The design will need at least 1,000 square feet of surface area. The designer would need to ensure that this area is available.
- Contributing drainage area The CDA for traditional bioretention must be 2.5 acres areor less, and this site has a total drainage area of less than 0.5 acres.
- Vehicle Vehicular access areas must be addressed. The vehicle vehicular access retention/treatment requirement of 475 cubic feet is met by this design.
- Head requirements are not likely to be an issue, since this is an infiltration design.
- The water table must be at least 2 feet below the bottom of the bioretention, or 4.25 feet below the surface.
- The measured permeability of the underlying soils In order to infiltrate the 1,301-cubic-foot storage volume, the saturated hydraulic conductivity must be at least 0.536 inches/per hour.

Additional SRCs will need to be generated or purchased off-site.

Since all of these assumptions and requirements can be met (pending groundwater table and infiltration rate investigations) in this design example, this step is complete.

Step 7: Use the Adjusted Curve Number to Address Peak Flow Requirements.

On the Channel and Flood Protection tab, enter values for B soils in **cells D54**, **D56**, and **D58** (55 for natural areas, 61 for turf, and 98 for impervious cover, respectively). The original site eurve number CN of 92 is reduced for the 2-year, 15-year, and 100-year storms to 85, 86, and 87, 88, and 89, respectively, by the retention provided by the bioretention cell. These eurve numbers CNs can be used to help determine detention requirements for this site.

Step 8: Determine the Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the preproject-peak discharge rate. Appendix H, "Acceptable Hydrologic Methods and Models" includes details on the procedure-for-ealeulating-how to calculate the detention volume. In this example, the proposed impervious cover and the proposed runoff curve-numberCN is less than the <a href="mailto:preproject-proje

The peak inflow (q_{i2}) and the peak outflow (q_{o2}) can be calculated using the WinTR-55 Small Watershed Hydrology program, the area of the site, the time of concentration (Tc), assumed to be 10 minutes), and the <u>curve numbers.CNs</u>. The reduced <u>curveCN</u> of 87, determined above, generates a q_{i2} of 1.50 cubic feet per 85 second (cfs). The <u>curve numberCN</u> for meadow in good condition, 58, generates a q_{o2} of 0.18 cfs.

The ratio of 0.18 cfs to 1.5085 cfs equals 0.1210. Using Figure H.1, the ratio of storage volume (Vs_2) to runoff volume (Vr_2) is 0.5355.

The runoff volume (Vr_2) determined in the Compliance Calculator spreadsheetwith BMPs is $1.84\underline{73}$ inches, (Q_{BMP}) , which equates to $3,833\underline{604}$ cubic feet. (Vr_2) . Using the calculated ratio of Vs_2/Vr_2 , the storage volume required for the site (Vs_2) is $2,032\underline{1,982}$ cubic feet.

This detention volume, with appropriate orifice design to ensure that outflows are properly restricted, can be incorporated below the proposed bioretention area or located elsewhere on the site, such as underneath the parking lot as a standalone detention practice.

Step 9: Identify Stormwater Retention Credits.

Since the SWRv was short of the requirement by 7,615,939 gallons, 7,615,939 SRCs will need to be purchased or generated annually for this site to achieve compliance (see Chapter 7. "Generation, Certification, Trading, and Retirement of Stormwater Retention Credits" for more details and example calculations).

Design Example 4

Design Example 4 includes the following proposed design criteria:

Site Name	Green St. and Gold St. Intersection
Total Site Area	13,528 ft ²
Natural Cover Area	$0 ext{ ft}^2$
Compacted Cover	185 ft ²
Impervious Cover	13,343 ft ²

The site in this design example is a street reconstruction project. Since it is located in the public right of way (PROW), the maximum extent practicable (MEP) design process applies (see Appendix B), "Maximum Extent Practicable Process for Existing Public Right-of-Way").

Step 1: Calculate SWRv.

This intersection includes four stormwater inlets (one at each corner), so it will be divided into four drainage areas. SDAs. The MEP Verification checklist DDOT Maximum Extent Practicable Design Worksheet requires calculation of the contributing drainage area CDA within the limit limits of disturbance (LOD) as well as calculation of the contributing drainage area CDA outside the LOD.

Site Drainage Area (DA	Contributing AreaCDA (ft²)			'Rv al)
(SDA 1 - N)	within LOD	outside LOD	within LOD	outside LOD
DA1 <u>SDA 1</u>	-3,473	-1,138	-2,371	-809
DA2SDA 2	-2,937	-987	-2,087	-701
DA3SDA 3	-5,285	-1,747	-3,756	-1,241
DA4 <u>SDA 4</u>	-1,833	-1,931	-1,303	-1,372
DATOTAL SDA	-13,528	-5,803	-9,517	-4,123

SWRv can be calculated using the Compliance Calculator spreadsheet. In this case, all All of the drainage areas were 100 percent impervious, except for DA1SDA1, which included 185 square feet of landscaped area within the LOD.

Step 2: Consider Infiltration.

This step requires looking at infiltration options by identifying constraints to infiltration, such as a high water table, soil contamination, or poor infiltration rates, and locating areas that are well suited for infiltration.

In this example, a high water table and soil contamination were not a concern. The soil had only a moderate to low infiltration rate, making an infiltration sump a possibility as part of another BMP (such as enhanced bioretention) but not feasible as a standalone BMP.

Step 3: Demonstrate Full Consideration of Land-Cover Conversions and Optimum BMP Placement.

Opportunities for BMP placement within and adjacent to the PROW include traffic islands, triangle parks, median islands, cul-de-sacs, paper streets, and traffic calming measures, such as median islands, pedestrian curb extensions, bump outs, chicanes, and turning radius reductions.

As this example is a small intersection project, pedestrian curb extensions are the only feasible location for BMP placement. BMP locations in the pedestrian curb extensions will be possible at three of the four corners of the intersection.

Step 4: Demonstrate Full Consideration of Opportunities Within Existing Infrastructure.

This step requires the assessment and documentation of utility locations, storm sewer depths, right-of-way widths, and exiting trees to determine potential conflicts.

In this example, the difference in elevation between the storm sewer inlets and the invert of the pipes is approximately 5 feet. Other utilities will constrain the space available for the proposed BMPs but will not eliminate the pedestrian curb extension spaces entirely.

Step 5: Locate and Choose BMPs.

Although they may be undersized, enhanced bioretention areas will be selected for 3 of the 4 corners in the space available.

Areas for enhanced bioretention are as follows:

Site Drainage Area (DASDA 1 - N)	Area (DASDA 1 LOD		Available Area for BMP (ft²)
DA1 SDA 1	3,473	2,371	72
DA2 SDA 2	2,937	2,087	285
DA3 SDA 3	5,285	3,756	190
DA4 <u>SDA 4</u>	1,833	1,303	0
DATOTAL SDA	13,528	9,517	N/A

Step 6: Size BMPs.

Each bioretention area will be designed with a similar cross section: vertical side slopes for the ponding area, a ponding depth of 0.75 feet, a filter media depth of 2 feet, and a gravel depth (including the infiltration sump) of 1.25 feet.

The storage volume is determined with Equation 3.5

Equation 3.5

$$Sv = SA_{bottom} \times \left[(d_{media} \times \eta_{media}) + (d_{gravel} \times \eta_{gravel}) \right] + (SA_{average} \times d_{ponding}) \right]$$

$$Sv = SA_{bottom} \times \left[(d_{media} \times \eta_{media}) + (d_{gravel} \times \eta_{gravel}) \right] + (SA_{average} \times d_{ponding})$$

where:

= total storage volume of bioretention (ft³) SA_{bottom} = bottom surface area of bioretention (ft²) = depth of the filter media, including mulch layer (ft) d_{media} = effective porosity of the filter media (typically 0.25) η_{media} = depth of the underdrain and underground storage gravel layer, d_{gravel} including choker stone (ft) = effective porosity of the gravel layer (typically 0.4) η_{gravel} = the average surface area of the bioretention (ft²) $SA_{average}$ typically, where SA_{top} is the top surface area of bioretention, $SA_{average} = \frac{SA_{bottom} + SA_{top}}{2} SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$ the maximum ponding depth of the bioretention (ft) $d_{ponding}$

With the cross--section dimensions provided above, Equation 3.5 yields the following results:

Site Drainage Area (DA1-SDA 1 - N)	Available Area for BMP (ft²)	Sv (gal)	Sv (ft ³)
DA1 SDA 1	72	942	126
DA2 SDA 2	285	3,731	499
DA3 SDA 3	190	2,487	332
DA4 SDA 4	0	0	0

The table below indicates that there is a retention deficiency for 3 of the 4 drainage areas with the 3 SDAs that contain proposed BMPs.

Site Drainage Area	Regulated SWRv	SWRv	Retention	Altored	Duoinaga
(DASDA 1 - N)	within L OD (gal)	Achieved (gal)	Deficiency (gal)		e <u>(Y/N)</u>
				¥	N

+	Split Cells
١	Split Cells
١	Split Cells
١	Split Cells

DA1SDA1	2,371	942	1,429		<u>N</u>	X
DA2 SDA 2	2,087	3,731	N/A		<u>N</u>	X
DA3SDA3	3,756	2,487	1,269		<u>N</u>	X
DA4SDA4	1,303	-	1,303	<u>.</u>	X	
DATOTAL SDA TOTAL	9,517	7,160				

Deleted Cells

Deleted Cells

If there is a retention volume deficiency, the MEP design process notes that the designer should consider sizing BMPs to manage the comingled volume on_site, and/or revisit Design Steps 1—6 to increase land conversion areas and BMP facilities.

In this case, the proposed bioretention areas in DA2SDA 2 could treat additional volume, but the proposed bioretention areas in DA1SDA 1 and DA3SDA 3 are at capacity. At this point, the designer should review Steps 1 through 6 to ensure that all opportunities for land conversion and BMP facilities have been maximized. If so, this step is complete.

Step 7: Identify Drainage Areas Where Zero-Retention BMPs are Installed.

Drainage areas that do not include α -retention $\overline{BMPBMPs}$ will require installation of a water-quality catch basin to treat stormwater runoff. This requirement applies only to $\overline{DA4SDA4}$ in this example.

Design Example 5

Step 1: Determine Design Criteria.

Design Example 5 includes the following proposed design criteria:

Site Name	NoMa Office Tower		
Total Site Area	65,340 ft ²		
Natural Cover Area	$0 ext{ ft}^2$		
Compacted Cover	0 ft^2		
Impervious Cover (Rooftop)	65,340 ft ²		
Vehicular Access Areas	$0 ext{ ft}^2$		
Is site located within the AWDZ?	No		
Is site located within the MS4?	Yes		
What type of activity is the site undergoing?	Major Land_Disturbing		

Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

The Compliance Calculator Spreadsheet will calculate a Stormwater Retention Volume (SWRv), once the impervious cover area is put into cell D24 on the Site Data sheet.

Based on the design criteria above, the NoMa Office Tower project is required to treat 1.2 inches of rainfall for the SWRy:

$$SWRv (cell D37) = 6,207 \text{ ft}^3$$

 $SWRv = 6,207 \text{ ft}^3$

Step 3: Identify Site Constraints and BMP Restrictions.

<u>Limitation of space is the The key considerations consideration</u> for the NoMa Office tower project. The is limited space. Construction from lot line to lot line construction means there are limited retention and treatment options. A rooftop approach is selected.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

As an initial estimate, 60-percent of the rooftop is proposed to be converted to a green roof, with an additional 15-percent of the remaining rooftop draining to it. Therefore, the land use values need to be changed to account for the green roof: 26,136 square feet should be entered as counted as impervious area for the rooftop in cell D24 on the Site Data sheet, and 39,204 square feet should be entered in cell D25counted as "BMP." As there, There will be only one drainage area for the site, these same values should be entered into cells B8 and B10 on sheet DA A.SDA. For the Green Roof drainage area (cells D23 and D24), 9801 green roof CDA, 9.801 square feet should be entered counted as impervious cover, and 39,204 should be entered counted as BMP surface area. The goal of this design is to capture the entire retention volume (6,207 ft³) in the green roof.

The goal of this design is to capture the entire retention volume (6,207 ft³) in the Green Roof. This can be shown on the spreadsheet by entering 6,208 cubic feet (1 extra cubic foot to ensure that any rounding losses are covered) in **cell O23** on sheet DA A. **Cell P68** shows that the SWRv has been met for the site. This information is also summarized on the Compliance worksheet tab.

Step 5: Size the BMPs According to the Design Equations.

The green roof needs to be sized according to Equation 3.1. Note that, since green roofs are typically manufactured systems, several of the parameters, such as the drainage layer depth and maximum water retention of all layers, need to be provided by the manufacturer. In this example, a media depth of 6 inches with a-maximum water retention of 0.40 was chosen. The drainage layer has a depth of 1 inch and a-maximum water retention of 0.15. These values are indicated in the variable descriptions below Equation 3.1 (with each layer illustrated in Figure 3.1).

Equation 3.1 Storage Volume for Green Roofs

$$Sv = \frac{SA \times \left[\left(d \times \eta_1 \right) + \left(DL \times \eta_2 \right) \right]}{12}$$

$$Sv = \frac{SA \times [(d \times \eta_1) + (DL \times \eta_2)}{12}$$

where:

SV = storage volume (ft³) SA = green roof area (ft²)

d = media depth (in.) (minimum 3 in.)

n n = verified media maximum water retention

 $\underline{\eta}_{1} \underline{\eta}_{1}$ = verified media maximum water retention

DL = drainage layer depth (in.)

 $\underline{\eta_2}$, $\underline{\eta_2}$ = verified drainage layer maximum water retention




Figure 3.1 Typical layers for a green roof.

Rearranging Equation 3.1 to find the minimum required surface area:

OF:
$$SA = \frac{Sv/[(d \times \eta_1) + (DL \times \eta_2)] \times 12}{SA = 6,208/(6 \times 0.40 + 1 \times 0.15) \times 12}$$

$$SA = \frac{Sv \times 12}{(d \times \eta_1) + (DL \times \eta_2)}$$

or:

$$SA = \frac{6,208 \times 12}{(6 \times 0.40) + (1 \times 0.15)} = 29,214 \text{ ft}^2$$

Therefore, the green roof must be sized to be at least 29,214 square feet (45% of the rooftop surface area), given the proposed depths. The original assumption was that a 39,204-square-foot roof would be used. Since a smaller roof is feasible, the drainage areas in the spreadsheet may be revised accordingly. However, the maximum drainage area to a green roof is only 25% more than the green roof itself. If a smaller roof is used, the design must indicate that the water can be conveyed onto the green roof in a non-crosive manner. If the larger green roof area is used, it could be designed with a lower media depth, or the increased storage volume could be used to reduce peak flow volume requirements (see Step 8) and/or sold as Stormwater Retention CreditsSRCs.

Step 6: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include:

Step 6: Step 1: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include:

- Ensure that there is sufficient space on the rooftop (allowing for structures such as vents, steep areas of the roof, and other panels). In this case, the green roof area of 29,214 square feet is less than half of the entire roof area.
- At least 19,791 square feet of the rooftop not covered by green roof needs to be designed so
 that it drainsto drain to the green roof without damaging or overloading it. This may require
 level spreaders or other devices.

Since all of these assumptions and requirements can be met in this design example, this step is complete.

Step 7: Use the Adjusted Curve Number to Address Peak Flow Requirements.

The initial <u>curve numberCN</u> for this site is 98, but retention provided by the green roof <u>changechanges</u> this number. The <u>Channel and Flood Protection tab notes the reduced curve numbers Adjusted Curve Numbers</u> for the 2-year, 15-year, and 100-year storms; <u>are</u> 86, 88, and 88, respectively. These <u>curve numbersCNs</u> can be used to help determine detention requirements for this site.

Step 8: Determine Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year-storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the preproject peak discharge rate. Appendix H-includes, "Acceptable Hydrologic Methods and Models" details on-the procedure for calculating to calculate the detention volume. In this example, the proposed land cover is the same as the preproject conditions, so detention is not required for the 15-year storm. However, detention is required for the 2-year storm.

The peak inflow, q_{i2} and the peak outflow, q_{o2} can be calculated using the WinTR-55 Small Watershed Hydrology program, the area of the site, the time of concentration (Tc, assumed to be 10 minutes), and the <u>curve numbers.CNs.</u> The reduced <u>curveCN</u> of 9086, determined above, generates a q_{i2} of q_{i3} of q_{i2} of q_{i3} of q_{i4} of q_{i4

The ratio of 0.391.83 cfs to 1.003.92 cfs equals 0.47. Using Figure H.1, this equates to a ratio of storage volume (Vs_2) to runoff volume (Vr_2) of approximately 0.29.

46.-Using Figure H.1, this equates to a ratio of storage volume (Vs₂) to runoff volume (Vr₂) of approximately 0.29.

The runoff volume (Vr_2) determined in the Compliance Calculator spreadsheet with BMPs is 1.83 inches, (Q_{BMP}) , which equates to 9,964 cubic feet (Vr_2) . Using the calculated ratio of Vs_2/Vr_2 , the storage volume required for the site (Vs_2) is 2,890 cubic feet.

-Using the calculated ratio of Vs₂/Vr₂, the storage volume required for the site (Vs₂) is 2,890 cubic feet.

Rooftop Storage (see Appendix I), "Rooftop Storage Design Guidance and Criteria") may be the most cost—effective method for achieving this the detention volume in this example, if space is available, and the design configuration can be created that routes the green roof to the rooftop storage. Alternatively, the required storage could be achieved via a tank located somewhere in the building.

Design Example 6

Step 1: Determine Design Criteria

Design Example 6 includes the following proposed design criteria:

Site Name	Connecticut Ave. Complex
Total Site Area	65,340 ft ²
Natural Cover Area	0 ft ²
Compacted Cover	0 ft ²
Impervious Cover (Rooftop)	65,340 ft ²

Vehicular Access Areas	0 ft ²	
Is site located within the AWDZ?	No	
Is site located within the MS4?	Yes	
What type of activity is the site undergoing?	Major LandDisturbing	

Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

Step 2: Step 1: Input Design Criteria to Determine the Retention and Treatment Requirements.

The General Retention Compliance Calculator will calculate a stormwater retention volume (SWRv) once the impervious cover area is entered in cell **D24** on the Site Data sheet.

Based on the design criteria above, the Connecticut Ave. Complex project is required to treat 1.2 inches of rainfall for the SWRv:

SWRv (coll **D37**) - 6.207 ft²

Step 3:Step 1:Identify Site Constraints and BMP Restrictions.

Key considerations $SWRv = 6.207 \text{ ft}^3$

Step 3: Identify Site Constraints and BMP Restrictions.

The key consideration for the Connecticut Ave. Complex project include the following:

Since this is that since it is a rooftop-only site, very few treatment options are available.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

Rainwater harvesting (R-1) is selected as the most appropriate BMP for this site.

The site will ultimately have one outlet point, so the calculations can be performed on one Drainage Area sheet—D.A. 1. Therefore, the impervious cover value from the Site Data tab should be put into **cell B8** on the D.A.1 sheet and therefore one SDA.

The Rainwater Harvesting Retention Calculator should be used to determine the cistern size and the associated retention value. The Rainwater Harvesting Retention Calculator should be used to determine the cistern size and the associated retention value. In the Rainwater Harvesting Retention Calculator, enter 65,340 square feet should be put in as the Contributing Drainage Area (CDA. For utilization of the rainwater, flushing toilets/urinals is selected as the use, and the appropriate values are entered.) (cell L7). For utilization of the rainwater, flushing toilets/urinals is selected as the use, and the appropriate values are entered. In this case, 1,600 people will use the building per day (cell L21), Monday through Friday (cells L30 and L32), 8 hours per day

(eell L34). On the Storage Volume Results — Retention Value sheet, the retentionstorage volume values are given for various tank sizes. The tablestable and graphsgraph show that an 80,000—gallon tank would have a 74% retention value. Coincidentally, it would also meet 74% of the annual demand 6,823 cubic feet of storage.

The next step is to return to the D.A. 1 tab and input the cistern will have a 65,340-square-foot CDA into cell D25 for rainwater harvesting and input the efficiency (74%) into cell K25. The result is that 6,507 cubic feet of runoff are and a storage volume of 6,823 cubic feet, of which 100% is retained and 2,286 cubic feet remain. Cell P68 shows that the The SWRv has been met for the site, and cell Q69 shows that the SWRv exceedance of 2,2444,605 gallons may be available to generate SRCs.

Step 5: Size the BMPs According to the Design Equations.

The size of the rainwater-harvesting cistern was already determined to be 80,000 gallons, although additional volume may be necessary for detention, as described in Step 8-below, as well as for dead storage for a pump, and/or freeboard.

Step 6: Check Design Assumptions and Requirements.

Step 6:Step 1:Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include the following:

- The rainwater harvesting cistern will be at least 80,000 gallons. The designer would need to
 ensure that space would be available for these BMPs on the site.
- Demand for the water from toilet flushing should be verified.

Since all of these assumptions and requirements can be met in this design example, this step is complete.

Step 7: Use the Adjusted Curve Number to Address Peak Flow Requirements.

The initial <u>curve numberCN</u> for this site is 98, but retention provided by rainwater harvesting changes this number. The Channel and Flood Protection tab notes the The reduced <u>curve numbersCNs</u> for the 2-year, 15-year, and 100-year storms: 85, <u>are 84, 86, and 87, and 88, respectively.</u> These <u>curve numbersCNs</u> can be used to help determine detention requirements for this site.

Step 8: Determine Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year-storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the pre-project peak discharge rate. Appendix H-includes, "Acceptable Hydrologic Methods and Models" details on-the procedure for calculating to calculate the detention volume. In this example, the proposed land cover is the same as the pre-project conditions, so detention is not required for the 15-year storm. However, detention is required for the 2-year storm.

The peak inflow— (q_{i2}) and the peak outflow— (q_{o2}) can be calculated using the WinTR-55 Small Watershed Hydrology program, the area of the site, the time of concentration (Tc, assumed to be 10 minutes), and the <u>curve numbers.CNs.</u> The reduced <u>curveCN</u> of <u>8584</u>, determined above, generates a q_{i2} of 3.64 <u>cubic foot per 61 second</u> (cfs). The <u>curve numberCN</u> for meadow in good condition, 71, generates a q_{o2} of 1.74 cfs.

The ratio of 1.74 cfs to 3.64<u>61</u> cfs equals 0.48. Using Appendix H <u>Acceptable Hydrologic Methods and Models</u>, this equates to a ratio of storage volume (Vs₂) to runoff volume (Vr₂) of approximately 0.29.

The runoff volume (Vr_2) determined in the Compliance Calculator spreadsheetwith BMPs is 1.7771 inches, (Q_{BMP}) , which equates to 9.938295 cubic feet, (Vr_2) . Using the calculated ratio of Vs_2/Vr_2 , the storage volume required for the site (Vs_2) is 2.795696 cubic feet.


Since rainwater harvesting is the selected BMP on this project, the most appropriate means for detaining the 2,795696 cubic feet (20,907163 gallons) may be to increase the size of the cistern to 13,500 cubic feet (101,000 gallons). Alternatively, if stage-storage routing is performed on the tank for a 2-year storm event, beginning with the average daily volume in the tank, the detention volume may be decreased significantly.

Design Example 7

Step 1: Determine Design Criteria

Design Example 7 includes the following proposed design criteria

Site Name	Anacostia School
Total Site Area	77,000 ft ²
Natural Cover Area	<u>0 ft²</u>
Compacted Cover	2,000 ft ²
Impervious Cover	10,000 ft ²
Vehicular Access Areas	<u>0 ft²</u>
Exempt Areas	<u>65,000 ft²</u>
Is site located within the AWDZ?	<u>No</u>
Is site located within the MS4?	No
What type of activity is the site undergoing?	Major Land-Disturbing



Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

Because a portion of the site is exempt from stormwater management requirements, only the impervious cover and compacted cover areas are counted towards calculating the SWR_v for the project. Based on the design criteria above, Anacostia School has the following requirements:

$$SWRv = 1,000 \text{ ft}$$

Step 3: Identify Site Constraints and BMP Restrictions.

Key considerations for Anacostia School include the following:

- Because the permeable athletic field is publically accessible at the school, the athletic field area is exempt from stormwater management requirements.
- The site has poor infiltration rates, so underdrains will be required for any BMPs.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

While there are numerous options for stormwater management of this site, a traditional bioretention (B-1) was selected. Since the site has poor infiltration, an underdrain is required and the enhanced bioretention option is not available.

The site will ultimately have one outlet point and therefore one SDA.

The bioretention area will receive runoff from the impervious area of the site. Through trial and error, it was determined that a 1,000-square-foot bioretention area would be sufficient to meet the retention requirement. This area will be taken from the compacted cover area. Compacted cover will now be 1,000 square feet, and BMP will be 1,000 square feet. Impervious cover

directed to the bioretention area will be 10,000 square feet. There will also be 1,000 square feet of compacted cover and 1,000 square feet of BMP surface area directed to the bioretention area. Because the site is in the CSS, there is no need to consider vehicular access areas.

The total volume directed to the bioretention area will be 1,516 cubic feet. A bioretention storage volume of 1,900 cubic feet would lead to an exceedance of 524 gallons for the SWRv.

Step 5: Size the BMPs According to the Design Equations.

To meet the bioretention criteria, the bioretention area is sized with 3 feet of filter media, 1 foot of gravel, and a 0.75-foot ponding depth. The bioretention cell sizing goal is 1,900 cubic feet.

Step 5.1: Check the Filter Media Depth.

Ensure that the filter media depth does not exceed the maximum in Table 3.20. The ratio of the surface area of the BMP (1,000 square feet) to the CDA (12,000 square feet) is 8.3%. The Rv for the CDA to the bioretention practice is 0.89. There is no maximum filter media depth with this design.

Table 3.20 Determining Maximum Filter Media Depth (feet)

SA:CDA					\underline{Rv}_{CDA}				
(%)	0.25	0.3	0.40	0.50	0.60	0.70	0.80	0.90	0.95
<u>0.5</u>	6.5	6.5	6.5	<u>6.5</u>	6.5	6.5	<u>6.5</u>	6.5	6.5
<u>1.0</u>	5.0	<u>5.5</u>	6.0	6.5	6.5	<u>6.5</u>	<u>6.5</u>	6.5	6.5
<u>1.5</u>	3.5	4.0	5.0	6.0	6.0	6.5	6.5	6.5	6.5
<u>2.0</u>		3.0	4.0	<u>4.5</u>	<u>5.5</u>	6.0	6.0	6.5	6.5
<u>2.5</u>			<u>3.5</u>	4.0	4.5	<u>5.0</u>	<u>5.5</u>	6.0	6.0
3.0				3.5	<u>4.0</u>	4.5	5.0	<u>5.5</u>	<u>5.5</u>
<u>3.5</u>				3.0	3.5	4.0	<u>4.5</u>	5.0	5.0
4.0					3.0	3.5	4.0	4.5	4.5
4.5						<u>3.5</u>	<u>3.5</u>	4.0	4.0
<u>5.0</u>							<u>3.5</u>	4.0	4.0
<u>5.5</u>								3.5	3.5
6.0								3.0	<u>3.5</u>
<u>6.5</u>									3.0
<u>7.0+</u>									

Step 5.2: Determine Storage Volume.


Equation 3.5

$$Sv = SA_{bottom} \times \left[(d_{media} \times \eta_{media}) + \left(d_{gravel} \times \eta_{gravel} \right) \right] + \left(SA_{average} \times d_{ponding} \right)$$

where:

Sv =	=	total storage volume of bioretention (ft ³)
SA_{bottom} =		bottom surface area of bioretention (ft ²)
$d_{media} =$		depth of the filter media, including mulch layer (ft)
<u>media</u> =		effective porosity of the filter media (typically 0.25)
$d_{gravel} =$		depth of the underdrain and underground storage gravel layer,
		including choker stone (ft)
$\underline{\eta}_{gravel} =$		effective porosity of the gravel layer (typically 0.4)
$SA_{average} =$		average surface area of the bioretention (ft ²)
		typically, where SA_{top} is the top surface area of bioretention,
		$SA_{average} = \frac{SA_{bottom} + SA_{top}}{2}$
$d_{ponding} =$		maximum ponding depth of the bioretention (ft)

Solving Equation 3.5 often requires an iterative approach to determine the most appropriate bottom surface area and average surface area to achieve the desired Sv. In this case, a bioretention with a 40-foot by 25-foot top area and 3H:1V side slopes will provide an SA_{top} of 1,312.5 square feet, an SA_{bottom} of 1,000 square feet, an $SA_{average}$ of 1,156 square feet, and achieve an Sv of 2,306 cubic feet. This more than meets the goal of 1,900 cubic feet. If desired, the surface area of the practice could be reduced accordingly, or more SRCs could be generated with the excess volume.



Step 6: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include the following:

- Based upon the above design the bioretention cell will require at least 1,000 square feet of surface area. The designer would need to ensure that space would be available for the bioretention.
- The CDA for traditional bioretention must be 2.5 acres or less and this site is less than 1 acre.
- The required head for the above design will be 4.75 feet, including ponding depth (9 inches), mulch (3 inches), filter media (33 inches), choking layer (about 3 inches), and gravel layer (9 inches). The outlet for the underdrain must be at least this deep.
- The water table must be at least 2 feet below the underdrain, or 6.75 feet below the surface.

 According to the Soil Survey, Croom soils have greater than a 5-foot depth. On-site soil investigations will be needed to determine if the 6.75-foot depth to the groundwater table can be met on this site.

Since all of these assumptions and requirements can be met in this design example (pending groundwater table investigations), this step is complete.

Step 7: Use the Adjusted Curve Number to Address Peak Flow Requirements.

The original site CN of 94 is reduced for the 2-year, 15-year, and 100-year storms to 70, 77, and 80, respectively, by the retention provided by the bioretention cell. These values can be used to help determine detention requirements for this site.


Step 8: Determine Detention Requirements.

Detention is not required.

Design Example 8

Step 1: Determine Design Criteria.

Site Name	Southwest Mixed-Use
	<u>Development</u>
Total Site Area	40,000 ft ²
Natural Cover Area	<u>0 ft²</u>
Compacted Cover	<u>2,000 ft²</u>
Impervious Cover	$38,000 \text{ ft}^2$
Vehicular Access Areas	0 ft^2
Is site located within the AWDZ?	<u>No</u>
Is site located within the MS4?	<u>No</u>
What type of activity is site undergoing?	Major Land-Disturbing



Step 2: Input Design Criteria to Determine the Retention and Treatment Requirements.

Based on the design criteria above, Southwest Mixed-Use Development has the following requirements:

$$SWRv = 3,660 \text{ ft}^3$$

Step 3: Identify Site Constraints and BMP Restrictions.

Key considerations for Southwest Mixed-Use Development include the following:

- Groundwater is high, so any BMPs in the ground will be shallow.
- The soil infiltration rates are poor, so underdrains will be required.
- The building roof has several tenant amenities planned that will restrict the area for any stormwater BMPs.
- This site is part of the CSS that is in a sewershed where CSOs will be reduced with storage tunnels.

Step 4: Select BMPs to Meet the Retention and Treatment Requirements.

Green roof (G-1) and permeable pavers (P-3) were selected to manage the stormwater.

The site will ultimately have one outlet point, and therefore one SDA.

The roof of the building has several amenities that tenants can access; therefore, the green roof size is restricted to 4,600 square feet. No additional roof area drains to the green roof; the CDA is the green roof area. Since green roofs are typically manufactured systems, several of the parameters, such as the drainage layer depth and maximum water retention of all layers, need to

be provided by the manufacturer. The values for the roof used in this design are provided in the variable descriptions below Equation 3.1 (with each layer illustrated in Figure 3.1).




Figure 3.1 Typical layers for a green roof.

Equation 3.1 Storage Volume for Green Roofs

$$Sv = \frac{SA \times [(d \times \eta_1) + (DL \times \eta_2)]}{(d \times \eta_1) + (DL \times \eta_2)}$$

where:

 $Sv = \text{storage volume (ft}^3)$

SA = green roof area (ft²) (4,600 ft²)

d = media depth (in.) (8 in.)

 $\underline{\eta_1}$ = verified media maximum water retention (0.45)

DL = drainage layer depth (in.) (1 in.)

 $\underline{\eta_2}$ = verified drainage layer maximum water retention (0.9)

$$Sv = \frac{4,600 \, ft^2 \times \left[(8 \, in \times 0.45) + (1 \, in \times 0.9) \right]}{12} = 1,725 \, ft^3$$

As designed, the green roof has a storage volume of 1,725 cubic feet.

The permeable pavement requires an underdrain and is categorized as a standard design. When designing permeable pavement, ensure that the permeable pavement is sized to store the SWRv in the reservoir layer. The reservoir depth can be determined by using Equation 3.2.

Equation 3.2 Reservoir Layer or Infiltration Sump Depth

$$d_p = \frac{\left(\frac{P \times Rv_I \times CDA}{A_p}\right) - \left(K_{sat} \times t_f\right)}{\eta_r}$$

where:

 $\underline{d_p}$ = depth of the reservoir layer (or depth of the infiltration sump for enhanced designs with underdrains) (ft)

P = rainfall depth for the SWRv or other design storm (ft)

 $Rv_I = 0.95$ (runoff coefficient for impervious cover)

CDA = total contributing drainage area, including permeable pavement surface area (ft²) (6,000 ft²)

 A_p = permeable pavement surface area (ft²) (6,000 ft²)

 $\frac{K_{sat}}{}$ = field-verified saturated hydraulic conductivity for the subgrade soils (ft/day). If an impermeable liner is used in the design then Ksat = 0.

 t_f = time to fill the reservoir layer (day) (assume 2 hours or 0.083 day)

 $\eta_r = 0.4$ (effective porosity for the reservoir layer)

$$d_p = \frac{\left(\frac{0.1\,ft \times 0.95 \times 6,000\,\text{ft}^2}{6,000\,\text{ft}^2}\right) - (0 \times 2\,hr)}{0.4} = 0.24\,ft = 2.85\,in$$

The permeable paver design requires a reservoir depth of 8 inches to support vehicular traffic, so this 8-inch depth will easily store the SWRv.

To determine the total storage volume provided by the practice, Sv, use Equation 3.4.

Equation 3.4 Permeable Pavement Storage Volume

$$Sv = A_p[(d_p \times \eta_r) + K_{sat} \times t_f]$$

where:

 $Sv = \text{storage volume (ft}^3)$

 $\underline{d_p}$ = depth of the reservoir layer (or depth of the infiltration sump for enhanced designs with underdrains) (ft) (0.67 ft)

 $\eta_r = 0.4$ (effective porosity for the reservoir layer)

 A_p = permeable pavement surface area (ft²) (6,000 ft²)


 $K_{\underline{sat}}$ = field-verified saturated hydraulic conductivity for the subgrade soils (ft/day).

If an impermeable liner is used in the design then Ksat = 0.

 t_f = time to fill the reservoir layer (days) (assume 2 hours or 0.083 days)

$$Sv = 6,000 \, ft^2 \left[(0.67 \, ft \times 0.4) + 0 \, \frac{ft}{day} \times 0.0083 \, days \right] = 1,608 \, ft^2$$

The surface area of 6,000 square feet should be counted as BMP cover. The total stormwater volume retained on-site by the green roof and permeable pavement is 889 cubic feet, well below the SWRv of 3,660 cubic feet. Less than 50% of the SWRv was retained by the BMPs; however, this site is located in a sewershed in the CSS where CSOs will be reduced with storage runnels. Therefore, the remaining SWRv can be obtained through Offv without going through the "relief through extraordinarily difficult site conditions" process.



Step 5: Check Design Assumptions and Requirements.

Key assumptions and requirements for this site include the following:

- No additional roof runoff drains to the green roof.
- Shallow groundwater and poor infiltration means that the permeable pavement will require an underdrain.

Since all of these assumptions and requirements can be met in this design example, this step is complete.

Step 6: Use the Adjusted Curve Number to Address Peak Flow Requirements.

Values for C soils results in a CN of 74 for turf and 98 for impervious cover. The original site CN of 97 is reduced for the 2-year, 15-year, and 100-year storms to 86, 88, and 88, respectively, by the retention provided by the green roof and the permeable pavers. These values can be used to help determine detention requirements for this site.

Step 7: Determine Detention Requirements.

Detention is required to reduce the peak discharge rate from the 2-year storm event to the predevelopment (meadow conditions or better) peak discharge rate and to reduce the peak discharge rate from the 15-year storm event to the pre-project peak discharge rate. Appendix H. "Acceptable Hydrologic Methods and Models" includes details on how to calculate the detention volume. In this example, the proposed runoff CN are less than the pre-project conditions, so detention for the 15-year storm is not required. Detention for the 2-year storm will be required.

The peak inflow (q_{i2}) and the peak outflow (q_{o2}) can be calculated using the WinTR-55 Small Watershed Hydrology program, the area of the site, the time of concentration (Te, assumed to be 10 minutes), and the CNs. The reduced CN of 86, determined above, generates a q_{i2} of 2.40 cubic feet per second (cfs). The CN for meadow in good condition, 71, generates a q_{o2} of 1.07 cfs.

The ratio of 1.07 cfs to 2.40 cfs equals 0.46. Using Figure H.1, the ratio of storage volume (Vs_2) to runoff volume (Vr_2) is 0.29.

The runoff volume is 1.83 inches (Q_{BMP}), which equates to 6,100 cubic feet (Vr_2). Using the calculated ratio of Vs_2/Vr_2 , the storage volume required for the site (Vs_2) is 1,769 cubic feet.

With appropriate orifice design to ensure that outflows are properly restricted, this detention volume may be located elsewhere on the site as a standalone detention practice.

Appendix B Maximum Extent Practicable Process for Existing Public Right-of-Way

B.1 Maximum Extent Practicable: Overview

Maximum extent practicable, or (MEP,) is the language of the Clean Water Act that sets the standards to evaluate efforts pursued to achieve pollution reduction to United States waterbodies. MEP refers to management practices; control techniques; and system, design, and engineering methods for the control of pollutants. It allows for considerations of public health risks, societal concerns, and social benefits, along with the gravity of the problem and the technical feasibility of solutions.

MEP is achieved, in part, through a process of selecting and implementing different design options with various structural and non-structural stormwater best management practices (BMPs), where ineffective BMP options may be rejected, and replaced when more effective BMP options are found. MEP is an iterative standard that evolves over time as urban runoff management knowledge increases. As such, it must be assessed continually and modified to incorporate improved programs, control measures, and BMPs to attain compliance with water quality standards. As a result of this evolution, some end-of-pipe strategies that were considered to meet the MEP standard ten of years ago are no longer accepted as such. Similarly, in cases where just one BMP may have gained project approval in the past, today there are many cases where multiple BMPs will be required to achieve treatment to the MEP.

Many jurisdictions have said of the MEP standard that there "must be a serious attempt to comply, and practical solutions may not be lightly rejected." If project applicants implement only a few of the least expensive BMPs, and the regulated volume has not been retained, it is likely that the MEP standard has not been met. If, on the other hand, a project applicant implements all applicable and effective BMPs except those shown to be technically infeasible, then the project applicant would have achieved retention to the MEP.

B.2 Public Right-of-Way Projects

Public right-of-way (PROW) projects within the District of Columbia are owned and operated by the District Government. They are linear in orientation and are distinct from parcel or lot development.

PROW is defined as the surface, the air space above the surface (including air space immediately adjacent to a private structure located on public space or in a PROW), and the area below the surface of any public street, bridge, tunnel, highway, railway track, lane, path, alley, sidewalk, or boulevard, where a property line is the line delineating the boundaries of public space and private property.

The Public Parking Area or "Public Parking," is important for the following discussion. It is defined as that area of public space devoted to open space, greenery, parks, or parking that lies between the property line (which may or may not coincide with the building restriction line) and the edge of the actual or planned sidewalk that is nearer to the property line, as the property line and sidewalk are shown on the records of the District-(see Figure B.1). This area often includes spaces that appear to be front yards with private landscaping, which create park-like settings on residential streets.




Figure B.1 Diagram of typical residential public right-of-way in the District of Columbia (DDOT Public Realm Design Manual 2011).

Public Space is defined as all the publicly owned property between the property lines on a street, park, or other public property, as such property lines are shown on the records of the District, and includes any roadway, tree space, sidewalk, or parking between such property lines: $\underline{\text{(see Figure B.1)}}$.

Other important terms are the tree box area or planter area and the sidewalk area. These are defined as the area of the roadside that provides a buffer between the pedestrians and vehicles, which primarily contains landscaping such as a continuous planting strip in residential areas. The sidewalk area is sometimes known as the "pedestrian clear zone"... this is the walking zone adjacent to the tree box that must remain clear, both horizontally and vertically.

In the MEP discussion that follows, a PROW project means a land-disturbing activity conducted in the existing PROW and the existing public space associated with the project. The MEP discussion applies only to those PROW projects required for the operation and maintenance of existing commercial and residential streets, existing alleyways, and other existing transportation infrastructure designed and maintained for the safe conveyance of people and commerce. Private subdivision roads or streets shall not be considered PROW projects.

Construction projects to maintain and upgrade the District's PROW are faced with a multitude of unique site constraints that vary widely. Limited space outside of the roadway restricts opportunities for infiltration and evapotranspiration, and in many cases the width of the roadway cannot be reduced to create additional space. In the roadway itself, the structural integrity of the pavement is the prime concern. The weight and volume of traffic loads may limit the use of permeable pavements.

The PROW occupyoccupies approximately 25-percent of the impervious area of the District of Columbia, making the PROW one of the most significant sources of stormwater runoff impacting District waterbodies. Stormwater runoff from roadways can present high pollutant loading. Despite the challenges to stormwater management faced by PROW projects, it is essential for the protection of District waterbodies to strive to achieve full retention of the regulated stormwater volume through the use of BMPs to the MEP on all PROW projects. This means the design process of all PROW projects shall evaluate and implement all applicable and effective BMPs except those shown to be technically infeasible.

The sections that follow, Design Considerations and Decision Design Process, are intended to provide structure for planners, designers, and reviewers to evaluate whether or not a PROW project has exhausted every opportunity to achieve the full retention of the regulated stormwater volume. Achieving the regulated Stormwater Retention Volume (SWRv) in the PROW projects will be technically infeasible on many occasions, even after going through the MEP process. Given this and the compelling interest of the ongoing reconstruction of the PROW for the maintenance of public safety and well-being, PROW projects can be excluded from the requirement to use Stormwater Retention Credits (SRCs) or pay an in-lieu fee to satisfy any shortfall in attaining the SWRv if the MEP is demonstrated. These PROW projects are the only type of projects that are excluded from this requirement.

DDOE's DOEE's MEP process applies to two types of projects. Type 1 projects solely involve reconstruction of the existing PROW, such as when the District of Columbia Department of Transportation DDOT reconstructs multiple blocks of a roadway. Type 2 designates parcel-based development projects that reconstruct the adjacent, existing PROW as portion of the project. Under the MEP process for Type 2 projects, the parcel portion of the application will be reviewed under the full stormwater management performance standards defined in Chapter 2, "Minimum Control Requirements," while the PROW portion of the application will be reviewed under the MEP Type 2 approach defined in this appendix.

The General Retention Compliance Calculator has a separate PROW worksheet that allows Type 2 applicants to separate parcel drainage area obligations from PROW obligations. The compliance tabCompliance sheet also presents these drainage areas separately to simplify the review process and make it transparent. The Stormwater Database has an option on the Plans form to indicate if the SWMP is a "roadway reconstruction or similar project." Also, on the Site Drainage Areas page, there is a check box indicating that the "Site Drainage Area is in the Public Right-of-Way." To request an MEP Type 2 review, an applicant will follow the format used to the request "relief for extraordinarily difficult site conditions" described in Appendix F, which requires submit a request memo with supporting evidence that describes why the full SWRv cannot be retained in addition to the completed worksheets from the General Retention Compliance Calculator.

The memo must address the six designs steps described in Section B.5., "Design Process for PROW." Type 2 applicants can choose to follow the same table, plan view, and narrative approach identified for Type 1 applicants without the multiple-stage review process for the 30 percent%, 65-percent,%, and 90-percent% design phases. Type 1 projects will use a stormwater report that contains information in spreadsheet, plan view, and narrative formats for the submission and review of the 30-percent,%, 65-percent,%, and 90-percent% design stages, typically of DDOT projects. Table B.3 indicates the information and submission format expected at each review stage.

B.3 Codes

DDOT uses a "functional street classification" system that is defined in Chapter 30 of the Transportation Design and Engineering Manual. There are five functional categories including Freeways, Principal arterials Arterials, Minor arterials Arterials, Collector streets Streets, and Local streets Streets. Table B.1 shows relative distribution of roadway classifications in the District. Each type has design criteria that are governed by traffic volumes, land use, and expected growth. These design criteria set the acceptable ranges for geometric design elements that will govern roadway geometry. The MEP process assumes transportation design criteria govern when conflicting demands exist.

Table B.1 Roadway Classification and Extent Relative to Total Roadway System

Type	Approximate Miles	% of District Roadway System
Freeways	46	4
Principal Arterials	92	8
Minor Arterials	178	15

Collectors	152	13
Local Roads	682	60

The MEP process assumes BMP designs will comply with the District of Columbia Department of Transportation DDOT Design and Engineering Manual Chapter 33, Chapter 47,28 and the Design and Engineering Manual supplements for Low Impact Development and Green Infrastructure Standards and Specifications as well as Chapter 3 Stormwater Best Management Practices (BMPs) in this guidebook.

B.4 PROW Design Considerations

B.4.1 Considerations in the Planning Process (limited to Type 1)

The local capital authority for PROW projects is defined in the District of Columbia's Capital Improvement Program (CIP), a six6-year-plan that is updated annually. Federally funded projects are listed in the Transportation Improvement Program (TIP), which is updated every other year according to the Metropolitan Washington Council of Government National Capital Region Transportation Planning Board's (MWCOG TPB) schedule and is also coordinated with the Constrained Long-Range Transportation Plan (CLRP). Each planning stage has an amendment process. Planners shall incorporate the MEP process into all future PROW projects and shall review and revisit, as needed, existing PROW plans for MEP analysis, revisions, and amendments. The TIP and CLRP are able to be amended and modified as allowed by the MWCOG TPB. As projects move from study to design and construction, DDOT will include necessary measures to include MEP analysis and implementation.

B.4.2 Site Assessment Considerations for the Retention Standard in PROW Projects

- 1. Level of Disturbance (Type 1 and Type 2). If a PROW project includes major land-disturbing activity required for the operation and maintenance of existing commercial and residential streets, existing alleyways, and other existing transportation infrastructure designed and maintained for the safe conveyance of people and commerce, it is captured by the stormwater regulatory obligations of Chapter 5 of Title 21, of the District of Columbia Municipal Regulations, Water Quality and Pollution (2012). Routine maintenance such as surface asphalt milling of roadways, where the roadway base is not disturbed, is not considered a level of disturbance that will require compliance with the regulation.
- 2. Available Space (Type 1 and Type 2). A PROW project must first and foremost seek to maximize landscape areas, maximize available space for stormwater retention, and minimize impervious surface, while coordinating with transportation, access, safety, and other applicable requirements, such as the Act (ADA) requirements and emergency vehicle needs. Street widths should be reduced to the appropriate minimum width while maintaining multi-modal transportation needs, parking, and public safety. A rule of thumb used in some cities (e.g., Los Angeles, Portland, Seattle, and Philadelphia) equates the expected landscape space to a minimum percentage of the imperviousness within each site drainage area (SDA) within the PROW project limits of disturbance. This percentage ranges from 4 percent-%-.

In the District of Columbia_ several hundred triangular islands, less than one1_ acre in area, are created by diagonal street intersections. A PROW project must consider the opportunity for stormwater retention within traffic islands, or triangle parks, that fall within, or adjacent to, the project limits of disturbance. Streets that end as cul-de-sacs, are less prevalent in the District; however, when present_cul-de-sacs within, or adjacent to, the limits of disturbance of a PROW project must be evaluated for stormwater retention opportunities. In the District "paper streets" exist throughout, as areas of the City dedicated as streets but not useable as transportation passageways. These areas, under the control of the DDOT, may be created by the intersection of streets with parks and streams, and are often mowed grass areas. "Paper streets" within, or adjacent to, the limits of disturbance of a PROW project must be evaluated for stormwater retention opportunities.

- 3. Impervious Cover Removal (Type 1 and Type 2). The elimination of impervious surface may be accomplished by closing diagonal roadways adjacent to triangle parks to create larger parks. Diagonal roadways that are adjacent to triangle parks and fall within, or are adjacent to, a PROW project must be evaluated for stormwater retention opportunities. PROW projects must evaluate the opportunity to integrate traffic calming measures including but not limited to, median islands, pedestrian curb extensions, bump outs and chicanes, and turning radius reductions that may double as areas for impervious surface removal and BMPs.
 - Replacing impervious cover with landscape area in the contributing drainage area (CDA) converts the runoff coefficient from 95-percent% to 25-percent%, in essence decreasing that area's contribution to stormwater runoff by 70-percent% without the use of an active stormwater facility. If an area can be converted to "natural cover" through conservation and reforestation strategies, that area's contribution to stormwater runoff is reduced to zero. Consult Appendix N Land Cover Designations for minimum thresholds and other required requirements for each land cover designation. Further opportunities to reduce stormwater runoff in these drainage areasCDAs should be explored with adjacent property both public and private as source control may be the most cost-effective approach to managing stormwater runoff; (see Section 3.4 Impervious Surface Disconnection.).
- **4. Drainage Areas (Type 1 and Type 2).** Overall conceptual drainage plans for PROW projects should identify drainage areas DAs outside of the project's limits of disturbance that generate runoff that may comingle with on-site runoff. The project is not required to consider off-site runoff in the calculation for the regulated Stormwater Retention Volume (SWRv); however, BMPs sized for retention of comingled off-site runoff can be used to off-setoffset the inability to capture and retain the SWRv in areas within the project for which significant constraints prevent retention.
 - For example, a typical city block will have at least two distinct drainage areasSDAs created by the crown in the center of the road. While one side of the road may have significant obstacles to the implementation of retention practices, the other may not. If the limits of disturbance are defined by the boundaries of the sidewalks on either side of the roadway, this is the area that is used to calculate the SWRv. However, in many circumstances stormwater runoff is entering the sidewalk and roadway from adjacent properties, both public and private, creating a comingled stormwater runoff. Under these conditions the side of the street that has the greater opportunity to implement retention strategies shall be designed to manage that comingled volume up to the full SWRv.

Type 1 and Type 2 projects must prioritize capturing roadway runoff. For Type 2 projects, where limits of disturbance do not extend into the roadway, the capture of roadway runoff from adjacent roadway drainage areasCDAs may be accomplished with curb cuts or sidewalk trenches used to direct roadway runoff from the curb line into sidewalk BMPs within the project's limits of disturbance. This must be the first consideration to satisfy the SWRv calculated for the project's PROW portion.

- 5. Ownership of Land Adjacent to Right-of-Ways (limited to Type 1). The opportunity to incorporate stormwater retention may depend on the ownership of land adjacent to the right-of-way. Acquisition of additional right-of-way and/or access easements may only be feasible if land bordering the project is publicly owned. PROW projectprojects must identify public lands and public rights—of-way adjacent to the project's limit limits of disturbance. PROW project planners and managers may need to consult with adjacent public property owners and managers to evaluate opportunities to direct stormwater runoff from the project dramage areaSDA to adjacent public lands.
- 6. Location of Existing Utilities (Type 1 and Type 2). The location of existing storm drainage utilities (greygray infrastructure) can influence the opportunities for stormwater retention in PROW projects. Utilizing the existing greygray infrastructure for the conveyance of large events with under drainunderdrain connections and curb line overflows can reduce costs. Using existing greygray infrastructure, where possible, frees funds for drainage areasSDAs within the project limits of disturbance where greygray infrastructure does not exist or is more challenging to utilize. Standard peak-flow curb inlets, such as catch basins, should be located downstream of areas with potential for stormwater retention practices so that water can first flow into the BMP, and then overflow to the downstream inlet if capacity of the BMP is exceeded. It is more difficult to apply retention practices after water has entered the storm drain. The location of other utilities will influence the ability to connect BMPs to storm drains, and may limit the allowable placement of BMPs to only those areas where a clear pathway to the storm drain exists.

The following outlines an approach to take when considering the design and location of BMPs in the existing PROW relative to existing utilities: 1) avoidance; 2) mitigation; 3) relocation; and 4) acceptance.

Avoidance. Whenever possible, locate BMPs to avoid a conflict that either jeopardizes the functionality and longevity of the utility or complicates future utility maintenance. Consult with each utility company on their recommended offsets whichthat will allow utility maintenance work with minimal disturbance to the BMP. A consolidated presentation of the various utility offset recommendations can be found in Chapter 33.14.528.8.4.4 of the District of Columbia Department of Transportation Design and Engineering Manual, latest edition. Consult the District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines, latest edition, for water and sewer line recommendations. Avoidance of utility conflicts may mean one BMP type is selected over another. It may mean the sizing of a BMP is altered.

Mitigation. Under the mitigation approach the BMP design is adjusted to mitigate utility concerns. A BMP design may need to be resized or otherwise altered to satisfy utility offsets.

This may include moving, adding, or deleting a key design feature of the BMP such as check dams, inlets, outlets, and trees.

Relocation. Under the relocation approach an attempt is made to coordinate with utility companies to allow them to replace or relocate their aging infrastructure while BMPs are being implemented. Where the capital budget and priorities of the utility can be aligned with the larger construction in the PROW, there are potential benefits, including cost savings, for both the utility and the entity undertaking the reconstruction of the PROW. The age of the utility line is a factor in selecting this solution. While a utility relocation during a street reconstruction reconstruction project may be advantageous to the utility provider, it is understood that the utility may not be able to align its capital budget or may be otherwise unable or unwilling to take advantage of the relocation opportunity.

Acceptance. When the first three approaches are inadequate to achieve the required stormwater retention, consider a fourth approach, acceptance of conflicts that do not jeopardize the functionality, longevity, and vehicular access to manholes and other key points of utility maintenance. This does not preclude the typical public right of way PROW BMP such as street trees, bioretention, or permeable pavement which that the utility would be expected to replace if maintenance in those areas was required. In this scenario, a BMP location and design that complicates utility maintenance should be considered acceptable if it does not compromise the utility function, longevity, and major access points. When accepting utility conflict into the BMP location and design, it is understood the BMP will be temporarily impacted during utility work but the utility will replace the BMP or, alternatively, install a functionally comparable BMP according to the specifications in the current version of this Stormwater Management Guidebookguidebook and the District of Columbia Department of Transportation DDOT Design and Engineering Manual with special attention to Chapter 33, Chapter 47,28 and the Design and Engineering Manual supplements for Low Impact Development and Green Infrastructure Standards and Specifications. To clarify whether a conflict jeopardizes the functionality, longevity, and access to a utility consider the latest editions of the District of Columbia Department of TransportationDDOT Design and Engineering Manual and the District of Columbia Water and Sewer Authority (DC Water) Green Infrastructure Utility Protection Guidelines.

- 7. Grade Differential Betweenbet ween Road Surface and Storm Drain System (Type 1 and Type 2). Some BMPs require more head from inlet to outlet than others; therefore, allowable head drop may be an important consideration in BMP selection. Storm drain elevations may be constrained by a variety of factors in a roadway project (utility crossings, outfall elevations, etc.) that cannot be overcome and may override Stormwater Retention VolumeSWRv considerations.
- **8.** Longitudinal Slope (limited to Type 1). The suite of BMPs which that may be installed on steeper road sections is more limited. Specifically, permeable pavement and swales are more suitable for gentle grades. Other BMPs may be more readily terraced to be used on steeper slopes. Check dams and weirs should be incorporated into BMP designs on steeper slopes.
- **9. Potential Access Opportunities (limited to Type 1).** A significant concern with the installation of BMPs in high speed, high volume PROW is the ability to safely access the BMPs for maintenance considering traffic hazards. A PROW project involving high speed, high volume PROW should include a site assessment to identify vehicle travel lanes and

areas of specific safety hazards for maintenance crews. Subsequent steps in the preparation of the stormwater management plan Stormwater Management Plan (SWMP) for the PROW project should attempt to avoid placing BMPs in these areas.

- 10. Tree Canopy and Vegetation (Type 1 and Type 2). Concern for the preservation of existing mature trees is a reasonable consideration when determining where and how to direct stormwater runoff from the curb line for retention goals in a PROW project. In general, stormwater retention practices should be installed outside the drip line of existing trees (more specific guidance is provided in Section 3.14)., "Tree Planting and Preservation"). A guiding principal for PROW projects should be the improvement and maintenance of the most robust tree canopy possible along the PROW. The planting of trees and the preservation of trees should look to the latest science on the soil volume requirements, spacing needs, and methods to connect stormwater runoff to tree roots to support healthy vigorous tree growth. PROW projects should clearly identify existing healthy trees and detail how to prevent tree losses during construction. Additionally, diseased and dead trees should be removed. Soils in tree planting areas should be amended and volumes expanded whenever trees are replaced or new trees are planted.
- 11. Infiltration (Type 1 and Type 2). Infiltration practices have very high storage and retention capabilities when sited and designed appropriately. Designers should evaluate the range of soil properties during initial site layout and seek to configure the site to conserve and protect the soils with the greatest recharge and infiltration rates. In particular, areas of Hydrologic Soil Grouphydrologic soil group (HSG) A or B soils shown on NRCS soil surveys should be considered as primary locations for infiltration practices. When designing a PROW project consult Appendix O₇ Geotechnical Information Requirements for Underground BMPs, and Chapter Section 3.7.8 Infiltration, as well as chapter sections on specific BMPs under consideration in this Stormwater Management Guidebook (SWMG)guidebook for specific design details and constraints.

In areas where a qualified professional engineer, soils scientist, or geologist determines during an initial feasibility test the presence of soil characteristics which that support the categorization as D soils, no further investigation is required. A designer of a PROW project should first consider reducing the impervious surface area draining to these poor soil areas. Other soil types may require further analysis to determine infiltration feasibility. It is important to understand that areas with poor soils may still be sites for BMPs that are designed with underdrains.

If the seasonally high water table is determined to be less than two2 feet from the bottom of the proposed BMP, infiltration and some other BMPs may not be appropriate. This may be determined through a comparison of historic and actual elevations. If the site is one of known soil contamination or receiving uncontrolled stormwater runoff from a land use hotspot, as determined by guidance in Appendix P-_."Stormwater Hotspots;" infiltration must not be used

12. Street Profile (limited to Type 1). The profile of an impervious surface such as a street or an alleyway determines how stormwater runoff flows off the surface. District streets follow a crowned design with the high point in the center draining to both sides, alleyways are typically reverse crowned, draining to the center, and sidewalks side shed, draining to one side. Flat drainage is a term used to denote vertical drainage through a permeable

pavingpavement profile. A PROW project should consider all variations of drainage patterns when the standard drainage design does not provide retention for the full regulated Stormwater Retention Volume (SWRv). SWRv. The drainage patterns of the project should be developed so that drainage can be routed to areas with BMP opportunities before entering storm drains. For example, if a median strip is present, a reverse crown should be considered, so that stormwater can drain to a median swale.

13. Pedestrian Circulation (Type 1 and Type 2). The design of stormwater retention facilities should harmonize with effective pedestrian circulation in PROW projects. PROW project BMPs commonly integrate the goals of stormwater retention and pedestrian safety by reducing pedestrian crossing distances, providing more space against vehicular traffic, and improving site angles at intersections. While pedestrian circulation and stormwater retention should not be at odds, conflicts can arise with on street parking. Considerations should be given to provide adequate egress for parking adjacent to a BMP (typically 2 feet). In addition, frequent walkways across BMPs can give pedestrians sufficient access to parking zones.

Retention facilities with vertical drops of greater than six6 inches in a PROW projectsproject should provide pedestrians with visual or physical signals that denote a significant drop in grade, such as a raised curb edge, a detectable warning strip or a raised railing. Railings maybe designed to perform additional functions such as seating or bicycle racks. In areas with the potential for high pedestrian volume, railings may be needed to prevent pedestrians from cutting through landscaped areas, trampling vegetation, and compacting soils.

B.4.3 Fundamental Tenets of MEP for PROW

A PROW project shall demonstrate a design approach that indicates stormwater retention opportunities were evaluated to the MEP, which includes the following:

- Selecting BMPs based on site opportunities to reduce stormwater runoff volumes.
- Sizing BMPs opportunistically to provide the maximum stormwater retention while accounting for the many competing considerations in PROW projects.
- Prioritizing capturing roadway runoff. By (by managing comingled stormwater runoff within some project drainage areas SDAs) to offset minimum retention achieved in other project drainage areas. SDAs).
- Developing innovative stormwater management configurations integrating "green" with "greygray" infrastructure.
- Minimizing street width to the appropriate minimum width for maintaining traffic flow and public safety.
- Maximizing tree canopy by planting or preserving trees/shrubs, amending soils, increasing soil volumes, and connecting tree roots with stormwater runoff.
- Using porous pavement or pavers for low traffic roadways, on-street parking, shoulders, or sidewalks.
- Integrating traffic calming measures that serve as stormwater retention BMPs.

- Reducing stormwater runoff volume by converting impervious surfaces to land cover types that generate little or zero stormwater runoff.
- Reducing stormwater runoff volume by employing impervious surface disconnection strategies within and adjacent to the project's limits of disturbance.

B.4.4 Minor Disturbances in the PROW

Some PROW disturbances, particularly Type 2 disturbances, may be considered minor disturbances in which there is little or no opportunity for the incorporation of stormwater BMPs. Utility trenches and driveways are two of the most common occurrences of this type of disturbance.

In the case of utility trenches, as noted in Section 2.12.7, "Utility Work," "land-disturbing activities that consist solely of cutting a trench for utility work and related replacement of sidewalks and ramps are exempt from stormwater management requirements if the activity does not involve the reconstruction of a roadway from curb to curb or curb to centerline of roadway." This means that MEP requirements do not apply if the PROW disturbance is limited to the utility work, unless the work requires reconstruction of at least half the roadway (curb to centerline).

For disturbance that involves only the installation or replacement of a driveway there are no exemptions, and MEP requirements still apply, even if the disturbance is minor. However, it is understood that disturbance limited solely to a driveway will generally yield little or no opportunity for stormwater BMPs. In these cases, a statement on the SWMP that no disturbance will occur beyond the limits of the driveway, leaving no space for BMP installation, may be considered sufficient to meet the MEP process requirements. If the disturbance extends beyond the limits of the driveway, a more thorough MEP analysis will be necessary.

B.4.5 Potential Design Modifications for Infiltration-Based PROW BMPs

The MEP process allows PROW projects to comply with stormwater management volume requirements by demonstrating through the design iteration process that all practicable opportunities for BMPs have been exhausted, and the project is providing as much green infrastructure as is reasonably possible. Because of this, the MEP process can allow for some alternatives with regard to design of infiltration-based BMPs. More specifically, with the design modifications described below infiltration-based BMPs can be designed and installed without first determining a field-verified hydraulic conductivity, which may lead to cost savings for the project.

Sidewalk Permeable Pavement. Permeable pavement in pedestrian areas can be installed without an underdrain, regardless of the saturated hydraulic conductivity of the soils below. This type of design will provide an opportunity for infiltration of as much runoff as possible, and any runoff that cannot infiltrate will either be held in the reservoir or run off the surface like regular pavement. Since this design modification is for pedestrian areas only, concerns over saturated soils and pavement or frost heave are minimized.

<u>Sidewalk</u> permeable pavement that has been designed without field-verified saturated hydraulic conductivity value will be considered a standard design with respect to retention

- value calculations, receiving the conservative standard design value of 5.0 cubic feet per 100 square feet of practice area.
- Bioretention with Capped Underdrain. Bioretention can be installed in the PROW regardless of the saturated hydraulic conductivity of the soils below. In order to do this, the bioretention area must include an underdrain and a 6-inch deep (minimum) infiltration sump, and the underdrain must be capped. By capping the underdrain, infiltration from the bioretention area will be maximized. If the actual infiltration capacity of the soils proves insufficient for proper function of the bioretention area, the underdrain can be un-capped in the future.

The underdrain must be capped in an accessible location (a manhole or catch basin). An underdrain valve accessible from the surface is also an option, particularly for underdrains that are directly connected to the storm sewer. The underdrain should only be opened if standing water has been observed in the bioretention area more than 48 hours after a rainfall event.

Bioretention with a capped underdrain will be considered a standard design with respect to retention value calculations, receiving the conservative standard design value of 60% of the storage volume of the practice.

With the design modifications described above, permeable pavement and bioretention will automatically achieve as much retention as is reasonably possible. Therefore, assuming that all practicable locations for BMPs have been utilized, they are consistent with the MEP philosophy.

B.5 Design Process for PROW

Step 1: Identify Site Drainage Areas and Calculate SWRv.

- Define the limits of disturbance for the PROW project.
- Delineate all drainage areas SDAs both within, and contributing to, the limits of disturbance for the PROW project. Prioritize drainage areas SDAs conveying roadway runoff.
- Identify proposed land covers within the limits of disturbance for the PROW project, including impervious cover, compacted cover, and natural cover. Area under proposed BMPs counts as impervious cover. A continuous planter strip may be eonsidered compacted cover, or natural cover; consult Appendix N Land Cover Designations for the minimum thresholds an area needs to qualify for each designation. Individual street trees may count as compacted cover or as a BMP. Use the General Retention Compliance Calculator PROW worksheet to determine which approach provides the greatest SWRv reduction. Input the results from the General Retention Compliance Calculator into the Stormwater Database.
- Calculate the regulated <u>Stormwater Retention Volume (SWRv)</u> based on land cover and area within the limits of disturbance for the entire PROW project. Calculate the portion of the SWRv for each <u>drainage areaSDA</u> within the limits of disturbance of the PROW project. Calculate any "unregulated" off-site <u>stormwater retention volumeSWRv</u> contributing to the project limits of disturbance.
 - Note: When off-site stormwater runoff volumes are managed, their reduction will count toward a reduction in the SWRv. Off-site stormwater runoff volumes may be managed at the

- source or within the project's limits of disturbance. Prioritize <u>drainage areasSDAs</u> conveying roadway runoff.
- Consider land conversion and BMP designations in adjacent public lands. While these
 volumes are not counted in the calculation of the site's SWRv, if controlled they will count
 towards the reduction of the site's SWRv. Identify opportunities for land cover conversions
 or other source control measures that would reduce these off-site volumes.
- Consider altering the drainage profile if that alteration would increase runoff capture
 opportunities. This consideration will typically be set aside until all other considerations have
 been exhausted (limited to Type 1).

Step 2: Evaluate Infiltration.

- Determine historical and actual water table elevations to evaluate opportunities and restrictions for locating infiltration practices.
- Consult a qualified professional engineer, soil scientist, or geologist usingto do initial infiltration feasibility tests; to identify the areas within the limits of disturbance with Hydrologic Soil groups that should be preserved and targeted for infiltration BMPs; and areas where infiltration BMPs will require amended soils and under drains underdrains.
- Identify any areas within the limits of disturbance where there is a known issue of soil contamination. Infiltration BMPs in these areas are not allowed. Use the guidance in Appendix P-, "Stormwater Hotspots" to evaluate adjacent land use hotspots that may be a source of uncontrolled contaminates in stormwater runoff.

Step 3: Demonstrate Full Consideration of Opportunities with Existing Infrastructure.

- Review substructure maps and utility plans; delineate areas of potential conflict as well as areas without conflict.
- Identify the location and elevation of the existing storm drainage system (greygray infrastructure), including catch basins, drain inlets, and manholes in both the drainage areas SDAs within, and those drainage areas SDAs contributing stormwater runoff to, the limits of disturbance for the PROW project.
- Identify all existing trees to be preserved. Identify and record tree species, size, and preservation status condition.

Step 4: Demonstrate Full Consideration of Land Cover Conversions and Optimum BMP Placement.

- Identify traffic islands, triangle parks, median islands, cul-de-sacs, and paper streets within and adjacent to the PROW project's limits of disturbance. These areas can be the focus of land cover conversions and BMP locations (unless within LOD of Type 2; this is limited to Type 1).
- Evaluate the opportunity to integrate traffic calming measures including but not limited to, median islands, pedestrian curb extensions, bump outs and chicanes, and turning radius reductions. Delineate these areas out for consideration for impervious surface removal and

BMP facilities. Delineate areas available for additional tree planting. Note whether soil volume increases and amended soils are required (unless within LOD of Type $2_{\frac{1}{2}}$ this is limited to Type 1).

- Evaluate right-of-way widths; identify minimum requirements for trails, alleys, roadways, and sidewalks. Delineate sections where existing conditions exceed minimum requirements.
 These areas can be the focus of land cover conversions and BMP locations (limited to Type 1).
- Select areas delineated as optimum opportunities for land conversion or BMP location.
 - Note: Land conversions can significantly reduce the project's SWRv without the use of an active stormwater facility. Designate land conversions and recalculate SWRv at the full project scale and the scale of the individual drainage areas SDAs within the project area.
- Select most appropriate BMP types for each area delineated as optimum opportunities for BMP locations. Consult Table B.2 for potential BMPs recommended by US EPA for "Green Streets"," DDOT's AWI Chapter 5 LID, DDOT's LID Action Plan, DDOT's LID Standards and Specifications, and ChaptersChapter 3.1 through 3.12 in of this Guidance Manualguidebook.

Step 5: Size BMPs.

- The following process are is used to size BMPs for PROW projects:
 - 1. Delineate drainage areas CDAs to BMP locations including any area outside the limits
 of disturbance contributing off-site stormwater runoff volume; prioritize roadway runoff;
 consider the land covers to compute optimum Stormwater Retention Volume. SWRv.
 Consider designing to the over control retention volume, above the regulated requirement
 of 1.2 inches, up to the regulated ceiling of 1.7 inches.
 - 2. Look up the recommended sizing methodology for the BMP selected in each drainage areaCDA and usinguse the appropriate BMP chaptersection of this guidance manual guidebook to calculate target sizing criteria.
 - 3. 3. Design BMPs per the appropriate <u>chaptersection</u> of this <u>guidance manual guidebook</u> and the <u>District of Columbia Department of Transportation DDOT</u> Design and Engineering Manual.
 - 4. 4. Attempt to provide the calculated sizing criteria for the selected BMPs.
 - 5. 5. If sizing criteria cannot be achieved, document the constraints that override the application of BMPs, and provide the largest portion of the sizing criteria that can be reasonably provided given constraints.

Note: If BMPs cannot be sized to provide the calculated volume for the drainage areaCDA, it is still essential to design the BMP inlet, energy dissipation, and overflow capacity for the full drainage areaCDA, including any area contributing off-site stormwater runoff volume, to ensure that flooding and scour is avoided. It is strongly recommended that BMPs whichthat are designed to less than their target design volume be designed to bypass peak flows.

- Aggregate the retention values achieved with the BMPs and compare with the regulated Stormwater Retention Volume (SWRv) for PROW project. If the aggregate retention value meets or exceeds the SWRv, the project has meet its regulatory obligation.
- If there is a retention volume deficiency, consider sizing BMPs to manage the comingled volume on- site.
- If there is a retention volume deficiency, revisit Design Steps 1—<u>through 4</u>. Increase land conversion areas and BMP facilities. Depending on the extent and complexity of the PROW project, this may require several iterations.

It is possible, despite following the design considerations, fundamental tenants, and the iterative Steps 1—through 5 of the design process, that drainage areas SDAs within the proposed limits of disturbance may emerge without any retention practices. If these cases occur in the Municipal Separate Storm Sewer System (MS4), those drainage areas SDAs must incorporate water quality catch basins or other emergent technologies that provide water quality treatment for the SWRv of those drainage areas SDAs.

Table B.2 Potential BMPs for Green Streets Projects (modified US EPA)

BMP Type	Opportunity Criteria for PROW Projects
Street Trees, Canopy	 Access roads, residential streets, local roads, and minor arterials
Interception	Drainage infrastructure, sea walls/break water
	Effective for projects with any slope
	■ Trees may be prohibited along high speed roads for safety reasons or must be setback behind the clear zone or protected with guard rails and barriers; planting setbacks may also be required for traffic and pedestrian lines of sight-
Stormwater Curb Extensions / Stormwater Planters	Access roads, residential streets, and local roads with parallel or angle parking and sidewalks
	Can be designed to overflow back to curb line and to standard inlet
	Shape is not important and can be integrated wherever unused space exists
	Can be installed on relatively steep grades with terracing
Bioretention Areas	 Low density residential streets without sidewalks; along roadways adjacent to park space; well suited for the District's triangle parks; ramp, slipways and road closings can make good conversion—sites
	May require more space than curb extensions/ planters, consider combing with minimized road widths to maximize bioretention area-
Permeable Pavement	Parking and sidewalk areas of residential streets- and local roads
	If significant run-on from major roads is a possibility, ensure deigndesign and maintenance protocols to accommodate potential TSS loads
	Should not be subject to heavy truck/-equipment traffic
	Light vehiclevehicular access roads and alleyways
Permeable Friction Course	High speed roadways unsuitable for full cepth permeable pavement
Overlays	Suitable for parking lots and all roadway types
Vegetated Swales (compost	■ Roadways with low to moderate slope or terraced systems
amended were where possible)	Residential streets with minimal driveway access
	Minor to major arterials with medians or mandatory sidewalk set-backs
	Access roads
	Access roads
	 Swales running parallel to <u>the</u> storm drain can have intermittent discharge points to reduce required flow capacity
Filter strips Strips (amended	■ Access roads
road shoulder)	 Major roadways with excess PROW Not practicable in most PROWs because of width requirements
Proprietary Biotreatment	-Constrained PROWs
Troprieury Broweninent	Typically; typically have small footprint to drainage areaCDA ratio
	Simple install and maintenance
	Can be installed on roadways of any slope
	Can be designed to overflow back to curb line and to standard inlet
Infiltration Trench	Constrained PROWs
	Can require small footprint where soils are suitable
	 Low to moderate traffic roadways Infiltration trenches are not suitable for high traffic roadways
	Inflitration trenches are not suitable for high traffic roadways Requires robust pretreatment
	- Requires rooust pretreatment

B.6 Summary of MEP Type 1 Submission Process

Table B.3 MEP Type 1Submission Elements and Review Points

			Storn	ıwater 🛚	Repor	t Design P	hases		
		30%	,		65%)		90%	
Process Steps	Table	Plan	Narrative	Table	Plan	Narrative	Table	Plan	Narrative
Step 1: Identify <u>Site</u> Drainage Areas and Calculate SWRv									
DASDA count	I		I	R		R	F		F
DASDA list and SWRv per DASDA	I			R			F)
Project LOD		I			R			F	
DAsSDAs within LOD		I			R			F	
DAsSDAs outside LOD		I			R		7	F	
Land cover in LOD	I			R			F		
Volume calculated per <u>DASDA</u> inside LOD	I			R			F		
Volume calculated per <u>DASDA</u> outside LOD	I			R			F		
Will altered drainage profile increase SWRV?		I	I		R	R			F
Consider adjacent public lands		I	C_{\bullet}		R	R			F
Step 2: Evaluate Infiltration									
Water table conflict per $\triangle ASDA$ (Y/N)	I		I	R		R	F		F
Bedrock conflict per $\overline{\text{DA}}\underline{\text{SDA}}$ (Y/N)	I) '	I	R		R	F		F
Hydro soil group per $\triangle A \underline{SDA}$ (Y/N)	I		I	R		R	F		F
Hotspot concern noted (Y/N)	I		I	R		R	F		F
Water table impact (Y/N)					R	R	F	F	
Initial infiltration feasibility tests— opportunities and restrictions? (Y/N)					R	R		F	
Identify adjacent land use hotspots (Y/N)		I			R	R		F	
Step 3: Demonstrate Full Consideration of -Existing Infrastructure									
Utility plans		I			R			F	
Utility conflicts		I			R			F	
Existing sewer infrastructure elevations		I			R			F	
Existing Trees	I	I			R			F	
Step 4: Demonstrate Full Consideration of Land Cover									

			Storn	ıwater l	Repor	t Design P	hases		
		30%			65%	•		90%	
Process Steps	Table	Plan	Narrative	Table	Plan	Narrative	Table	Plan	Narrative
Conversions and Optimum BMP Placement									
Land conversion and BMP placement		I	I		R	R		F	F
Count of BMPs and land conversions	I			R			F		
Step 5: Size BMPs									
BMP drainage areasCDAs within LOD and outside LOD (Y/N)					I			R	
Consider over control of $\frac{SWRV}{SWRv}$ (Y/N)						I			R
Achieve BMP sizing criteria (Y/N)						I			R
Design sizing achieved (under/over)				I			R		
Sizing constraints						I			R
Step 6: Address DAsSDAs with Zero- Retention Practices Installed									
SWRv achieved per DASDA				I		I	F		F

Notes:

- I = Initial findings and presentation; this should define known facts and best opportunities.
- R = Revisions based on further investigations and review comments; this will include some firm commitments.
- F = Final design decisions based on initial commitments, interim reviews, and final findings.

The process outlined in this table leads to a final submission of 100 percent design SWMP as required for the building permit.

 $\underline{DA = drainage\ area}\underline{SDA = Site\ Drainage\ Area}, LOD = limits\ of\ disturbance,\ SWRv = stormwater\ retention\ volume$

B.7 References

District of Columbia Department of Transportation, 2010, Anacostia Waterfront Transportation Architecture Design Guidelines, Chapter 5: Low Impact Development (LID). Washington D.C. http://www.scribd.com/doc/83991242/Anacostia-Waterfront-Transportation-Architecture-Design-Guidelines

CityCounty Council for Montgomery County, Maryland. 2007. Streets and Roads—comprehensive revision. Enacted July 3, 2007. Montgomery County, MD. http://www.montgomerycountymd.gov/council/pdf/bill/2007/48-06e.pdf

District of Columbia Department of Transportation (DDOT). Public Realm Design Manual 2011. <a href="http://dc.gov/DC/DDOT/Projects+and+Planning/Standards+and+Guidelines/Public+Realm+Design+Manual+

Environmental Services City of Portland, 2008, Green Streets Construction Guide. Portland, OR. http://www.portlandoregon.gov/bes/article/228860

- Philadelphia Water Department, Office of Watersheds, 2009, Stormwater Manual v2.0 Chapter 6.1 Street Design. Philadelphia, PA. http://www.scribd.com/doc/13322624/Stormwater-Management-Guidance-Manual-Ver-20
- Environmental Services City of Portland, 2008, Green Streets Construction Guide. Portland, OR. http://www.portlandonline.com/bes/index.cfm?c=34602&https://www.portlandoregon.gov/b es/34602
- City of Los Angeles, 2009, Green Streets & Green Alleys: design guidelines standards. Los Angeles, CA. http://www.lastormwater.org/wp-content/files_mf/greenstreetguidelines.pdf
- Santa Ana Regional Water Quality Control Board, May 19, 2011. Exhibit 7.III Technical guidance document for the preparation of conceptual/preliminary and/or project water quality management plans (WQMPs); Santa Ana County, CA.

http://www.cityoforange.org/civicax/filebank/blobdload.aspx?blobid=9653http://www.cityof orange.org/534/Water-Quality-Management-Plans

- San Francisco Planning Department, 2010, San Francisco Better Streets Plan, Final Draft, 2010, http://www.sf-planning.org/ftp/BetterStreets/proposals.htm#Final Plan
- San Mateo Countywide Water Pollution Prevention Program, San Mateo County Sustainable Green Streets and Parking Lots Guide, 2009; San Mateo, CA. http://www.flowstobay.org/ms_sustainable_guidebook.phphttp://www.flowstobay.org/node/ 412
- U.S. Environmental Protection Agency, Managing Wet Weather with Green Infrastructure Municipal Handbook, Green Streets, EPA Publication 833-F-08-009, 2008; http://water.epa.gov/infrastructure/greeninfrastructure/upload/gi_munichandbook_green_stre

ets.pdfhttps://www.epa.gov/sites/production/files/2015-

10/documents/gi munichandbook green streets.pdf

PROPOSED PRINCIPAL PROPOSED PR

Appendix C Off-Site Retention Forms for Regulated Sites

This appendix includes the following off site retention forms for regulated sites:

A site may comply with its Off-Site Retention Volume (Offv) by using Stormwater Retention Credits (SRCs), paying In-Lieu Fee (ILF), or through a combination of SRCs and ILF. The annual obligation to meet the site's Offv is described in Chapter 6, "Use of Off-Site Retention by Regulated Sites." Use the following forms to meet Offv:

Application to Use Stormwater Retention Credits for Off-Site Retention Volume
 Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

PROPOSED PENISION PROPOSED PRO



GOVERNMENT OF THE DISTRICT OF COLUMBIA District Department of the Environment 1200 First Street NE, Fifth Floor, Washington, DC 20002



Application to Use Stormwater Retention Credits for Off-Site Retention Volume

Acronyms

AWDZ CSS DDOE ILF MS4	Anacostia Waterfront Development Zone Combined Sewer System District Department of the Environment In-Lieu Fee Municipal Separate Storm Sewer System		Off-Site Retention Volume Stormwater Retention Credit Stormwater Management Plan Stormwater Retention Volume
	ation date:ss of regulated site for which SRC use is prop	osed:	
Lot:	Square:Ward:Storm Sewer	System	(CSS or MS4):
Is the s	ite an AWDZ site (Yes or No)?		
Name o	of site owner:		
Address	S:		
E-Mail:	Phone:		
Name o	of owner's agent (if applicable):		
Address	S:		
	Phone:		
	Information from DDOE-Approved S	SWMP f	or Regulated Site
SW	MP tracking number		
SW	Rv		
	On-site retention volume achieved		
	Offy		

Applicants must submit Offv forms through the Stormwater Database at https://doee.dc.gov/swdb. Paper forms are also available in this appendix for reference (see Figures C.1 and C.2).

When submitting a notification of ILF payment, mail a check payable to the DC Treasurer to the following address and indicate the Stormwater Management Plan Number on the memo line, PROPOSED PREVIOUS unless DOEE approves an alternate form of payment.

Regulatory Review Division / Offv Department of Energy and Environment 1200 First Street NE, 5th Floor Washington, DC 20002

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Application to Use Stormwater Retention Credits for Off-Site Retention Volume

Acronyms

DOEE	Department of Energy and Environment	SRC	Stormwater Retention Credit
GI CSS	Green Infrastructure Combined Sewer System	MS4 Offv	Municipal Separate Storm Sewer System Off-Site Retention Volume
CSO	Combine Sewer Overflow	SWMP	Stormwater Management Plan
AWDZ	Anacostia Waterfront Development Zone	SWRv	Stormwater Retention Volume
ILF	In-Lieu Fee		
Applic	ation date:		
Addres	is of regulated site for which SRC u	se is proposed	1:
Lot:	Square: V	Ward:	
will be	Sewer System (MS4, CSS where CS reduced with storage tunnels):		
is the s	tte all A WDZ site (1 es of No):		
Name	of site owner:		
Addres	s:		
E-Mail		Phone:	
Name	of owner's agent (if applicable):		
Addres	s:		
E-Mail	:	Phone:	
	Information from DOEE-A	pproved SWI	MP for Regulated Site
SW	MP Number		
SW	'Rv		
On-	site retention volume achieved		
Off	v		
Wa	s at least 50% of the SWRv generated	l on site? (Yes	or No)

Figure C.1 Application to Use Stormwater Retention Credits for Off-Site Retention Volume.

fv to be met with SRC r an AWDZ site, how			ith SRCs from outside the
nacostia River watersh			THE PARCE IT OF THE PARCE THE
ffv to be met with payn	ent of ILF (number	of gallons);
RCs proposed for use (A	Attach additional sheet	if necess	ary):
Starting dat (Indicate date or "as o Multiple dates m	f final inspection."	(May	Serial numbers ndicate as range, where appropriate)
	Applicant's	s Signatu	re
			the owner of the regulated property pplication is correct to the best of my
Signature of Owner:			Date:
	has assured me that h	e/she owr	regulated property owner to make this is the SRCs proposed for use herein. I knowledge.
Signature of Agent:			Date:
FO	R DEPARTM	ENT I	USE ONLY
Approved:	Approved in	part:	Disapproved:
Si	nature:		Date:

2

Offer to be met	(number of gallons):		\.		
Offv to be met with paymo	•				
RCs proposed for use (A applicants must submit a co- sage date. The obligation to uccessful completion of the following the final construc-	ompleted application a to use off-site retention e final construction in	at least for n to achie	ur (4) weeks before Offv begins o	on the date of	
Starting date (Indicate date or "as of Multiple dates ma	final inspection."	(May i	Serial nu ndicate as range		oriate)
	Applicant's	Signatuı	re		
A. Owner of regulated prop and of the SRCs propos knowledge.	perty: I hereby certify	that I am	the owner of the	e regulated pro	perty of my
and of the SRCs propos	perty: I hereby certify	that I am	the owner of the	regulated pro rect to the best	perty of my
and of the SRCs propos knowledge.	perty: I hereby certify ed for use herein and that I have the authori has assured me that h	that I am that this a ty of the r e/she own	the owner of the pplication is con Date: egulated properts the SRCs prop	rect to the best	of my
and of the SRCs propos knowledge. Signature of Owner: Agent: I hereby certify application. The owner	perty: I hereby certify ed for use herein and that I have the authori has assured me that h	that I am that this a ty of the r e/she own	the owner of the pplication is con Date: egulated properts the SRCs prop	rect to the best	of my
and of the SRCs propos knowledge. Signature of Owner: Agent: I hereby certify tapplication. The owner declare that this application. Signature of Agent:	perty: I hereby certify ed for use herein and that I have the authori has assured me that h	that I am that this a tty of the r e/she own pest of my	Date: Begulated properts the SRCs propknowledge. Date:	y owner to ma	of my
and of the SRCs propos knowledge. Signature of Owner: Agent: I hereby certify tapplication. The owner declare that this application. Signature of Agent:	perty: I hereby certify ed for use herein and that I have the authori has assured me that he tion is correct to the b	that I am that this a that this a ty of the residue own the ty of the residue of my	Date: egulated properts the SRC's propknowledge. Date:	y owner to ma	of my
and of the SRCs propos knowledge. Signature of Owner: Agent: I hereby certify the application. The owner declare that this application of Agent: FOF Approved:	perty: I hereby certify ed for use herein and that I have the authori has assured me that he tion is correct to the b	that I am that this a that this a ty of the residue own the ty of the residue of my	Date: egulated properts s the SRCs propknowledge. Date: Date: Date:	y owner to ma	of my

Figure C.1 (continued)



GOVERNMENT OF THE DISTRICT OF COLUMBIA District Department of the Environment 1200 First Street NE, Fifth Floor, Washington, DC 20002



Instructions for Application to Use Stormwater Retention Credits for Off-Site Retention Volume

Purpose of form: This form provides DDOE with the necessary information to track compliance with an Offv by use of SRCs.

NOTE: Buyers, sellers, or their agents must complete an Application for Transfer of Stormwater Retention Credit Ownership before SRCs may be used to satisfy an Offv requirement.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site for which SRC use is proposed: Enter the street address for the regulated site that seeks to use SRCs to meet an Offv requirement. Lot, square, and ward information is available from the building permit and the approved SWMP for the site.

Is the site an AWDZ site (Yes or No)? Select "yes" or "no". AWDZ sites must purchase SRCs generated outside of the Anacostia River watershed at a 1.25:1 ratio.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information.

Name of owner's agent: If applicable, enter the name of a representative whom the owner has charged with achieving the Offv.

Information from DDOE-approved SWMP for regulated site: Enter information from the SWMP including the Plan's tracking number, total required stormwater retention volume in gallons, on-site volume achieved, and required Offv.

Offv to be met with SRCs: Enter the number of gallons of the Offv requirement that a site owner seeks to achieve through SRCs.

For an AWDZ site, how much of the Offv will be met with SRCs from outside the Anacostia River watershed? AWDZ sites must purchase SRCs generated outside of the Anacostia River watershed at a 1.25:1 ratio. This information assists DDOE in calculating the correct number of SRCs for the regulated site to achieve its Offv requirement.

Offv to be met with payment of ILF: Enter the number of gallons of the Offv to be achieved through payment of the ILF. To use an ILF payment for compliance, sites must also submit a Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume.

SRCs proposed for use: Enter the effective date when SRCs will be used to satisfy an Offv requirement. Also list the serial numbers of purchased SRCs.

3

Instructions for Application to Use Stormwater Retention Credits for Off-Site Retention Volume

Purpose of form: This form provides DOEE with the necessary information to track compliance with an Offv by use of SRCs.

NOTE: Buyers, sellers, or their agents must complete an Application for Transfer of Stormwater Retention Credit Ownership before SRCs may be used to satisfy an Offv requirement.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site for which SRC use is proposed: Enter the street address for the regulated site that is applying to use SRCs to meet an Offv requirement. Lot, square, and ward information is available from the building permit and the approved SWMP for the site.

Storm Sewer System (MS4, CSS targeted for GI, CSS with storage tunnels): Choose one of the listed options. Sites in the MS4 must have SRCs generated in the MS4. If a site in the CSS achieves at least 50% of the SWRv on site, then the SRCs needed can be generated anywhere in the District. If a site in the CSS achieves less than 50% of the SWRv on site, then the following applies: sites in the CSS targeted for green infrastructure (GI) implementation must have SRCs generated either in the MS4 or in the CSS targeted for GI implementation; sites in the CSS with storage tunnels must have SRCs generated in the MS4.

Is the site an AWDZ site (Yes or No)? Select "yes" or "no". AWDZ sites using SRCs generated outside of the Anacostia River watershed must use SRCs at a 1.25:1 ratio.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information

Name of owner's agent: If applicable, enter the name of a representative whom the owner has charged with achieving the Offv.

Information from DOEE-approved SWMP for regulated site: Enter information from the SWMP including the Plan's tracking number, total required SWRv in gallons, on-site volume achieved, and required Offv. Indicate if the site achieved at least 50% of the SWRv on site.

Offv to be met with SRCs: Enter the number of gallons of the Offv requirement that a site owner seeks to achieve through SRCs. AWDZ sites using SRCs generated outside of the Anacostia River watershed must use SRCs at a 1.25:1 ratio.

Offv to be met with payment of ILF: Enter the number of gallons of the Offv to be achieved through payment of the ILF. To use an ILF payment for compliance, sites must also submit a Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume.

SRCs proposed for use: Enter the effective date when SRCs will be used to satisfy an Offv requirement. List the serial numbers of purchased SRCs.

Page 3 of 3

Figure C.1 (continued)





Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

	Acronyn	ns					
CSS	DDOE District Department of the Environment SWMP Stormwater Management Plan In-Lieu Fee SWRv Stormwater Retention Volume						
	ation date:						
Is the s	Lot:Square:Ward:Storm Sewer System (CSS or MS4): Is the site an AWDZ site (Yes or No)?						
Name	Name of site owner:						
Addres	Address:						
E-Mail	E-Mail: Phone:						
Name	Name of owner's agent (if applicable):						
Addres	s:						
E-Mail	E-Mail: Phone:						
	Information from DDOE-Approved SWMP for Regulated Site						
	MP tracking number						
SW	/Rv						
<u> </u>	On-site retention volume achieved						
	Offv						

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment

Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

Acronyms

ILF	Department of Energy and Environment In-Lieu Fee Anacostia Waterfront Development Zone Combined Sewer System Municipal Separate Storm Sewer System		Stormwater Retention Credit Off-Site Retention Volume Stormwater Management Plan Stormwater Retention Volume			
Applica	ation date:					
Addres	s of regulated site for which ILF use is propo	sed:				
Lot:	Square:Ward:Storm Sewe					
Is the s	Is the site an AWDZ site (Yes or No)?					
Name of site owner:						
Address	s:					
E-Mail:	Phone:					
Name o	of owner's agent (if applicable):					
Address	s:					
	Phone:					
	Information from DOEE-Approved	SWMP f	or Regulated Site			
SW	MP Number					
SW	70					
On-	site retention volume achieved					
Off	v					





GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

Acronyms

ILF I AWDZ A	Department of Energy and Environment In-Lieu Fee Anacostia Waterfront Development Zone Combined Sewer System Municipal Separate Storm Sewer System	SRC Offv SWMP SWRv	Stormwater Retention Credit Off-Site Retention Volume Stormwater Management Plan Stormwater Retention Volume
Applicat	tion date:		
Address	of regulated site for which ILF use is propo	osed:	
Lot:	Square:Ward:Storm Sewe	r System	(CSS or MS4):
Is the sit	te an AWDZ site (Yes or No)?		
Name of	site owner:		
Address:			
E-Mail:	Phone:		
Name of	f owner's agent (if applicable):		
Address:			
	Phone:		
	Information from DOEE-Approved	SWMP f	or Regulated Site
SWN	MP Number		
SWR	Rv		
On-si	ite retention volume achieved		
Offv			

Figure C.2 Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume.

Starting Date (Indicate date or "as of a Multiple years ma	final inspection."		Total Payment
Applicant's Signature			
A. Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge.			
Signature of Owner:			Date:
			gulated property owner to make this he best of my knowledge.
Signature of Agent:			Date:
FO	R DEPARTM	ENT U	SE ONLY
Payment Received:	Payment Received	in Part:	Payment Not Received:
Si	gnature:		Date:

application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Starting Date For Use (Indicate date or "as of final inspection." Multiple years may be listed.) Applicant's Signature Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Date:	ffv to be met with payment of ILF (number of gallons):			
Applicant's Signature Applicant's Signature Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Applicant's Signature Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Received: Date:	Proposed use of ILF (atta	nch additional sheet i	f necessary).	
Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	(Indicate date or "as of	final inspection."		Total Payment
Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:				
Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:				
Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:				
Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Owner of regulated property: I hereby certify that I am the owner of the regulated property and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:				
and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	and that this application is correct to the best of my knowledge. Signature of Owner: Date: Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Applicant's Signature			
Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	Agent: I hereby certify that I have the authority of the regulated property owner to make thi application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Received: Signature: Date:				
application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received: Payment Not Received: Signature: Date:	application. I declare that this application is correct to the best of my knowledge. Signature of Agent: Date: FOR DEPARTMENT USE ONLY Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Signature of Owner:	Signature of Owner: Date:		
FOR DEPARTMENT USE ONLY Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	FOR DEPARTMENT USE ONLY Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Agent: I hereby certify that I have the authority of the regulated property owner to make this application. I declare that this application is correct to the best of my knowledge.			
Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Payment Received: Payment Received in Part: Payment Not Received: Signature: Date:	Signature of Agent:			Date:
Signature: Date:	Signature: Date:	FO	R DEPARTI	MENT U	JSE ONLY
		Payment Received:	Payment Receive	ed in Part:	Payment Not Received:
Notes:	Notes:	S	ignature:		Date:
		Notes:			

Proposed use of ILF (attach addit Starting Date For Use	2	Total Payment
(Indicate date or "as of final ins Multiple years may be list		
	Applicant's Signatur	ro
A. Owner of regulated property: I and that this application is corr		the owner of the regulated property owledge.
Signature of Owner:		Date:
 Agent: I hereby certify that I has application. I declare that this ε 		regulated property owner to make this the best of my knowledge.
Signature of Agent:		Date:
FOR DE	PARTMENT U	USE ONLY
Payment Received: Paym	nent Received in Part:	Payment Not Received:
Signature:		Date:
Notes:		

Figure C.2 (continued)





Instructions for Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

Purpose of form: This form provides DDOE with the necessary information to track compliance with an Offv by use of ILF

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site for which ILF is proposed: Enter the street address for the regulated site that seeks to make an ILF payment to meet an Offv. Lot, Square, Ward, and Storm Sewer System information is available from the building permit and the approved SWMP for the site.

Is the site an AWDZ site (Yes or No)? Select "yes" or "no". AWDZ sites must purchase SRCs generated outside of the Anacostia River watershed at a 1.25:1 ratio.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information.

Name of owner's agent: If applicable, enter the name of a representative whom the owner has charged with achieving the Offv.

Information from DDOE-Approved SWMP for regulated site: Enter information from the SWMP including the Plan's tracking number, total required stormwater retention volume in gallons, on-site volume achieved, and required Offv.

Offv to be met with SRCs: Enter the number of gallons of the Offv requirement that a site owner seeks to achieve through SRCs.

Offv to be met with payment of in-lieu fee: Enter the number of gallons of the Offv that a site owner seeks to achieve through payment of the ILF. To use an ILF payment for compliance, sites must also submit a Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume.

Proposed use of in-lieu fee: Enter the effective date when in-lieu fee will be used to satisfy an Offv requirement.

Instructions for Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

Purpose of form: This form provides DOEE with the necessary information to track compliance with an Offv by use of ILF

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site for which ILF is proposed: Enter the street address for the regulated site that seeks to make an ILF payment to meet an Offv. Lot, Square, Ward, and Storm Sewer System information is available from the building permit and the approved SWMP for the site.

Is the site an AWDZ site (Yes or No)? Select "yes" or "no". AWDZ sites must purchase SRCs generated outside of the Anacostia River watershed at a 1.25:1 ratio.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information.

Name of owner's agent: If applicable, enter the name of a representative whom the owner has charged with achieving the Offv.

Information from DOEE-Approved SWMP for regulated site: Enter information from the SWMP including the Plan's tracking number, total required SWRv in gallons, on-site volume achieved, and required Offv.

Offv to be met with SRCs: Enter the number of gallons of the Offv requirement that a site owner seeks to achieve through SRCs. AWDZ sites using SRCs generated outside of the Anacostia River watershed must user SRCs at a 1.25:1 ratio. To use SRCs for compliance, sites must also submit an Application to Use Stormwater Retention Credits for Off-Site Retention Volume.

Offv to be met with payment of in-lieu fee: Enter the number of gallons of the Offv that a site owner seeks to achieve through payment of the ILF.

Proposed use of in-lieu fee: Enter the effective date when in-lieu fee will be used to satisfy an Offv requirement.

Page 3 of 3

Instructions for Notification of In-Lieu Fee Payment to Meet Off-Site Retention Volume

Purpose of form: This form provides DOEE with the necessary information to track compliance with an Offv by use of ILF.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of regulated site for which ILF is proposed: Enter the street address for the regulated site that seeks to make an ILF payment to meet an Offv. Lot, Square, Ward, and Storm Sewer System information is available from the building permit and the approved SWMP for the site.

Is the site an AWDZ site (Yes or No)? Select "yes" or "no". AWDZ sites must purchase SRCs generated outside of the Anacostia River watershed at a 1.25:1 ratio.

Name of site owner: Enter the name of the site owner. Also provide the site owner's contact information.

Name of owner's agent: If applicable, enter the name of a representative whom the owner has charged with achieving the Offv.

Information from DOEE-Approved SWMP for regulated site: Enter information from the SWMP including the Plan's tracking number, total required SWRv in gallons, on-site volume achieved, and required Offv.

Offv to be met with SRCs: Enter the number of gallons of the Offv requirement that a site owner seeks to achieve through SRCs. AWDZ sites using SRCs generated outside of the Anacostia River watershed must user SRCs at a 1.25:1 ratio. To use SRCs for compliance, sites must also submit an Application to Use Stormwater Retention Credits for Off-Site Retention Volume.

Offv to be met with payment of in-lieu fee: Enter the number of gallons of the Offv that a site owner seeks to achieve through payment of the ILF.

Proposed use of in-lieu fee: Enter the effective date when in-lieu fee will be used to satisfy an Offv requirement.

In addition to the notification of ILF payment, please send a check made out to the DC Treasurer to:

Regulatory Review Division/Offv Department of Energy and Environment 1200 First Street NE, 5th Floor Washington, DC 20002

Page 3 of 3

Figure C.2 (continued)

Appendix D Stormwater Retention Credit Forms (Certification, Trading, and Retirement)

This appendix includes <u>Use</u> the following <u>forms to certify, transfer, and retire</u> Stormwater Retention <u>Credit forms:</u> <u>Credits (SRCs):</u>

- Application for Certification of Stormwater Retention Credits
- Application for Transfer of Stormwater Retention Credit Ownership
- Application to Retire Stormwater Retention Credits

PROPOSED PENISION PROPOSED PRO





Application for Certification of Stormwater Retention Credits

Acronyms

BMP	Best Management Practice	MS4	Municipal Separate Storm Sewer System				
CSS DDOE	Combined Sewer System District Department of the Environment	SRC SWMP	Stormwater Retention Credit Stormwater Management Plan				
Applie	ation date:						
			_				
Addres	ss of site with eligible retention capaci	ty:					
Lot:	Square:Ward:Storm	n Sewer Sy	ystem (CSS or MS4):				
Name	of owner of proposed SRCs:						
	Address:						
E-Mail	: Pl	none:					
Name	of site owner (if different from propos	ed SRC o	wner):				
Addres	s:						
E-Mail	: Ph	none:					
Name	of owner of retention capacity (if diffe	rent from	site owner):				
Addres	s:						
			_				
15-IVIAII	: Pł	ione.					

D-1

Applicants must submit forms through the Stormwater Database at https://doee.dc.gov/swdb. Paper forms are also available in this appendix for reference (see Figures D.1 through D.3).



GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Application for Certification of Stormwater Retention Credits

Acronyms

DOEE BMP CSS CSO	Department of Energy and Environment Best Management Practice Combined Sewer System Combined Sewer Overflow	GI SRC MS4 SWMP	Green Infrastructure Stormwater Retention Credit Municipal Separate Storm Sewer System Stormwater Management Plan			
Applic	ation date:		_			
Addres	ss of site with eligible retention capaci	ty:				
Lot:	Square:Wa	rd:				
	Sewer System (MS4, CSS where CSO reduced with storage tunnels):					
Name	of owner of proposed SRCs:					
Addres	s:					
E-Mail	: Ph	one:				
Name of site owner (if different from proposed SRC owner):						
Addres	s:					
E-Mail	: Ph	one:				
Name	of owner of retention capacity (if diffe	rent from	site owner):			
Addres	s:					
E-Mail	: Ph	one:				

Figure D.1 Application for Certification of Stormwater Retention Credits-

Name of agent for own	er of proposed SRCs (if applicable):
Address:	
E-Mail:	Phone:
Should the agent be list	ted as the contact person for interested SRC buyers in DDOE's SRC
DDOE tracking number	er for SWMP:
Identification number(s) for each BMP for which SRCs are requested:
SRC-eligible retention	capacity for each BMP or land cover for which SRCs are requested
Has DDOE previously	certified SRCs for the retention capacity (Yes or No)
If no, attach the followin	g:
☐ As-built SWMP,	including site plan showing pre-project site conditions and retention.
	nce contract or documentation of capacity and expertise to conduct the time period for which SRCs are requested.
Documentation of not the property of	of the legal right to the SRCs applied for, if the proposed SRC owner is owner.
	E SRC calculator spreadsheet.
If yes, attach the following	ng:
	nce contract or documentation of capacity and expertise to conduct the time period for which SRCs are requested.
Documentation of not the property of	of the legal right to the SRCs applied for, if the proposed SRC owner is owner.
Is this application for S	RCs for the maximum three-year period (Yes or No)?
If no, what is the period	d for which SRCs are requested?
What is the listing price	e for each SRC (optional)?
	SRCs and corresponding name and contact information in

Name of agent for owner	r of proposed SRCs (if applicable):
Address:	
E-Mail:	Phone:
DOEE SWMP Number:	
BMP ID Numbers for w	hich SRCs are requested:
SRC-eligible retention c	apacity for each BMP or land cover for which SRCs are requested:
Has DOEE previously co	ertified SRCs for the retention capacity (Yes or No)?
If no, attach the following	:
	ncluding site plan showing pre-project site conditions and retention as roved in the Stormwater Database.
	ce contract or documentation of capacity and expertise to conduct ne time period for which SRCs are requested.
If yes, attach the following	g:
	ce contract or documentation of capacity and expertise to conduct ne time period for which SRCs are requested.
What is the period for w	which SRCs are requested (circle an option): $1 \text{ year} / 2 \text{ years} / 3 \text{ years}$
	SRCs and corresponding name and contact information in indicate Yes or No and, if yes, who should be listed):
What is the asking price	for each SRC? (optional)

Figure D.1 (continued)





Applicant's Signature

A. Proposed SRC Owner: I hereby certify that I have the legal right to the SRCs proposed for certification above; that the application, including supporting documentation, is complete and correct to the best of my knowledge; that access will be provided for DDOE inspections; that the retention capacity will be maintained in accordance with the maintenance plan for the period for which SRCs are requested; that, if the retention capacity is not maintained, I will, for the volume from the period of failed maintenance, forfeit the SRCs, purchase replacement SRCs, or pay in-licu fee to DDOE.; and that, if during the period of time for which an SRC is certified, the property is sold or otherwise transferred to another person, the owner of the property on which the BMP or land cover is located will notify DDOE.

Signature of Proposed SRC Owner:

Date:

B. Agent: I hereby certify that I have the authority of the proposed SRC owner to make this application and that the application and plans are complete and correct to the best of my knowledge. The owner has assured me that access will be provided for DDOE inspections and that the retention capacity will be maintained in accordance with the maintenance plan for the period for which SRCs are requested. If the retention capacity is not maintained in good working order, the proposed SRC owner has assured me that, for the volume from the period of failed maintenance, he will forfeit the SRCs, purchase replacement SRCs, or pay in-lieu fee to DDOE. Finally, the proposed SRC owner has assured me that, if during the period of time for which an SRC is certified, the property is sold or otherwise transferred to another person, the owner of the property on which the BMP or land cover is located will notify the Department.

Signature of Agent:

Date:

FOR DEPARTMENT USE ONLY					
Approved:	Approved in part:	Disapproved:			
Signa	nture:	Date:			
Total SRCs certified:	Total time period for which SRCs are certified:				
SRCs certified year 1:	Serial numbers:				
SRCs certified year 2:	Serial numbers:				
SRCs certified year 3		Serial numbers:			
Notes:					

3

Applicant's Signature

A. Proposed SRC Owner: I hereby certify that I have the legal right to the SRCs proposed for certification above; that the application, including supporting documentation, is complete and correct to the best of my knowledge; that access will be provided for DOEE inspections; that the retention capacity will be maintained in accordance with the maintenance plan for the period for which SRCs are requested; that, if the retention capacity is not maintained, I will, for the volume from the period of failed maintenance, forfeit the SRCs, purchase replacement SRCs, or pay in-lieu fee to DOEE; and that, if during the period of time for which an SRC is certified, the property is sold or otherwise transferred to another person, the owner of the property on which the BMP or land cover is located will notify DOEE.

Signature of Proposed SRC Owner:

Date

B. Agent: I hereby certify that I have the authority of the proposed SRC owner to make this application and that the application and plans are complete and correct to the best of my knowledge. The owner has assured me that access will be provided for DOEE inspections and that the retention capacity will be maintained in accordance with the maintenance plan for the period for which SRCs are requested. If the retention capacity is not maintained in good working order, the proposed SRC owner has assured me that, for the volume from the period of failed maintenance, the proposed SRC owner will forfeit the SRCs, purchase replacement SRCs, or pay in-lieu fee to DOEE. Finally, the proposed SRC owner has assured me that, if during the period of time for which an SRC is certified, the property is sold or otherwise transferred to another person, the owner of the property on which the BMP or land cover is located will notify the Department.

Signature of Agent:

Date:

FOR DEPARTMENT USE ONLY						
Approved:	Approved in part:	Disapproved:				
Signa	Date:					
Total SRCs certified:	Total time period for which SRCs are certified:					
SRCs certified year 1:	Serial numbers:					
SRCs certified year 2:	Serial numbers:					
SRCs certified year 3	Serial numbers:					
Notes:	Notes:					

Page 3 of 5

Figure D.1 (continued)

Instructions for Application for Certification of Stormwater Retention Credits

Purpose of form: This form provides DDOE with the necessary information to certify SRCs.

NOTE: Buyers, sellers, or their agents must complete an Application for Transfer of Stormwater Retention Credit Ownership before an SRC transaction may occur.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of site with eligible retention capacity: Enter the street address for the site with retention capacity that complies with the eligibility requirements for SRC certification. Lot, square, and ward information is available from the building permit and the approved SWMP for the site.

Name of owner of proposed SRCs: Enter the name and contact information for the person proposed as the owner of the SRCs. Once DDOE certifies the SRCs, this person will become the original SRC owner, with associated maintenance obligation. This person or their agent signs the application form. Once SRCs are certified or the agent signs the application, DDOE will notify the proposed SRC owner of its determination for the application. DDOE will list the original SRC owner (or the owner's agent) and contact information in a public registry posted to the DDOE website.

Name of site owner: If different from the proposed SRC owner, enter the name and contact information for the person who owns the site where practices are installed to generate SRCs. DDOE recognizes that a site owner could assign the right to the SRCs to an SRC aggregator or other person. In such a case, the SRC aggregator or other person would presumably be the proposed SRC owner.

Name of owner of retention capacity: If different from site owner, enter the name and contact information for the owner of the retention capacity generating SRCs on a site. DDOE expects that typically the site owner would also be the owner of the retention capacity, but this may not always be the case.

Name of agent for owner of proposed SRCs (if applicable): Enter the name and contact information for a person who is authorized to represent the proposed SRC owner in applying for certification of SRCs. If the agent is also authorized to represent (and take the place of) the proposed SRC owner in DDOE's SRC registry as the contact for interested SRC buyers, that should be indicated.

Instructions for Application for Certification of Stormwater Retention Credits

Purpose of form: This form provides DOEE with the necessary information to certify SRCs.

NOTE: Buyers, sellers, or their agents must complete an Application for Transfer of Stormwater Retention Credit Ownership before an SRC transaction may occur.

Instructions

Application date: Enter the date that the applicant completes the application.

Address of site with eligible retention capacity: Enter the street address for the site with retention capacity that complies with the eligibility requirements for SRC certification. Lot, square, and ward information is available from the building permit and the approved SWMP for the site.

Storm Sewer System (MS4, CSS where CSOs will be reduced with GI, CSS where CSOs will be reduced with storage tunnels): Choose one of the listed options. Sites in the MS4 must have SRCs generated in the MS4. If a site in the CSS achieves at least 50% of the SWRv on site, then the SRCs needed can be generated anywhere in the District. If a site in the CSS achieves less than 50% of the SWRv on site, then the following applies: sites in the CSS where CSOs will be reduced with green infrastructure (GI) implementation must have SRCs generated either in the MS4 or in the CSS where CSOs will be reduced with GI implementation; sites in the CSS where CSOs will be reduced with GI implementation in the MS4.

Name of owner of proposed SRCs: Enter the name and contact information for the person proposed as the owner of the SRCs. Once DOEE certifies the SRCs, this person will become the original SRC owner, with associated maintenance obligation. This person, or their agent, signs the application form. Once SRCs are certified or the agent signs the application, DOEE will notify the proposed SRC owner of its determination for the application. DOEE will list the original SRC owner (or the owner's agent) and contact information in a public registry posted to the DOEE website.

Name of site owner: If different from the proposed SRC owner, enter the name and contact information for the person who owns the site where BMPs are installed to generate SRCs. DOEE recognizes that a site owner could assign the right to the SRCs to an SRC aggregator or other person. In such a case, the SRC aggregator or other person may be the proposed SRC owner.

Name of owner of retention capacity: If different from site owner, enter the name and contact information for the owner of the retention capacity generating SRCs on a site. DOEE expects that, typically, the site owner would also be the owner of the retention capacity, but this may not always be the case.

Page 4 of 5

Figure D.1 -(continued)





DDOE tracking number for SWMP: Enter the tracking number assigned to the SWMP by DDOE.

Identification number(s) for each BMP for which SRCs are requested: Enter the tracking number for the BMP, as identified in the SWMP. This will allow DDOE to identify the specific BMP on a site for which SRCs are being requested and for which maintenance will be required. Some sites may have multiple BMPs.

SRC-eligible retention capacity for each BMP or land cover for which SRCs are requested: Enter the SRC-eligible volume, as identified in the as-built SWMP for a site. For a site with one SRC-eligible BMP or land cover, this will typically correspond to cell B:50 of the SRC calculator.

Has DDOE previously certified SRCs for the retention capacity? Select "yes" or "no". DDOE certifies SRCs for three-year periods. If the retention capacity continues to be maintained and function properly, applicants may apply for an additional three years of SRCs.

Is this application for SRCs for the maximum three-year period? Select "yes" or "no". DDOE certifies SRCs for three year periods, but applicants should apply for fewer years if they do not intend to maintain the retention capacity for the entire three-year time period.

If no, what is the period for which SRCs are requested? Enter the period of time for which the applicant requests SRCs.

What is the listing price for for each SRC (optional)? If the applicant would like DDOE to include an SRC price in the SRC registry, indicate that here. This is not binding, and the final price will be determined by the SRC seller and buyer.

Should DDOE list these SRCs and corresponding name and contact information in DDOE's SRC registry? Indicate whether the proposed SRC owner or the owner's agent would like the SRCs to be listed in DDOE's SRC registry. Also indicate whether contact information for the owner or agent should be listed.

Name of agent for owner of proposed SRCs (if applicable): Enter the name and contact information for a person who is authorized to represent the proposed SRC owner in applying for certification of SRCs. If the agent is also authorized to represent (and take the place of) the proposed SRC owner in DOEE's SRC registry as the contact for interested SRC buyers, that should be indicated.

DOEE SWMP Number: Enter the tracking number assigned to the SWMP by DOEE.

Identification number(s) for each BMP for which SRCs are requested: Enter the tracking number for the BMP, as identified in the SWMP. This will allow DOEE to identify the specific BMP on a site for which SRCs are being requested and for which maintenance will be required. Some sites may have multiple BMPs.

SRC-eligible retention capacity for each BMP or land cover for which SRCs are requested: Enter the SRC-eligible volume, as identified in the as-built SWMP for a site. For a site with one SRC-eligible BMP or land cover, this will typically correspond to cell B:50 of the SRC calculator.

Has DOEE previously certified SRCs for the retention capacity? Select "yes" or "no". DOEE certifies up to three years' worth of SRCs at one time. If the retention capacity is maintained and the BMP continues to function properly, applicants may apply for additional SRCs after the initial certification term is complete.

What is the period for which SRCs are requested? Select the number of years for which SRCs are requested. DOEE may certify up to three years' worth of SRCs at one time, but applicants should apply for fewer years if they do not intend to maintain the retention capacity for the entire three-year time period.

Should DOEE list these SRCs and corresponding name and contact information in the SRC Registry? Indicate whether the proposed SRC owner or the owner's agent would like the SRCs to be listed in the SRC Registry. Also indicate whether contact information for the owner or agent should be listed.

What is the asking price for each SRC? (optional) If the applicant would like DOEE to include an SRC price in the SRC registry, indicate that here. This is not binding, and the final price will be determined by the SRC seller and buyer.

Page 5 of 5

Figure D.1 (continued)





Application for Transfer of Stormwater Retention Credit Ownership

Acronyms DDOE District Department of the Environment SRC Stormwater Retention Credit Application date: ___ Number of SRCs to transfer: Serial numbers of SRCs (may be listed as a range): Purchase price for SRCs: Name of current owner of SRCs: Address_ Phone: _____ Name of new owner of SRCs: Address: ___ Phone: E-Mail: ___ Name of agent for new owner of SRCs (if applicable): E-Mail: _____ Phone: ____

1

D-12

GOVERNMENT OF THE DISTRICT OF COLUMBIA Department of Energy and Environment Application for Transfer of Stormwater Retention Credit Ownership Acronyms DOEE Department of Energy and Environment SRC Stormwater Retention Credit Application date: ___ Number of SRCs to transfer: Serial numbers of SRCs (may be listed as a range): Purchase price for SRCs: _____ Name of current owner of SRCs: Address Phone: Name of new owner of SRCs: Address: _ Phone: E-Mail: Name of agent for new owner of SRCs (if applicable): E-Mail: _____ Phone: ___

Figure D.2 Application for Transfer of Stormwater Retention Credit Ownership.

Should	DDOE list these SRCs and the name and contact information for the owner or
owner's	agent in DDOE's SRC registry? (Indicate Yes or No and, if yes, who should be
listed)	

Signature of Current Owner

I hereby certify that I am the owner of the above SRCs; that I request the ownership of these SRCs to be transferred as stated above; and that this application is complete and correct to the best of my knowledge.

Signature: Date:

Signature of New Owner (or Owner's Agent)

I hereby certify that this application is complete and correct to the best of my knowledge.

Signature: Date:

FOR DEPARTMENT USE ONLY			
Approved:	Approved in part:	Disapproved:	
Sig	gnature:	Date:	
Notes:			

	Signature of Curren	t Owner
	as stated above; and that this ap	that I request the ownership of these plication is complete and correct to the
Signature:		Date:
F	OR DEPARTMENT	Γ USE ONLY
Approved:	Approved in part:	Disapproved:
	Signature:	Date:

Figure D.2 (continued)





Instructions for Application for Transfer of Stormwater Retention Credit Ownership

Purpose of form: This form provides DDOE with the necessary information to verify and track ownership of SRCs and the price at which SRCs are traded.

Instructions

Application date: Enter the date that the applicant completes the application.

Number of SRCs to transfer: Enter the number of SRCs that are proposed for transfer from a seller to buver.

Serial numbers of SRCs (may be listed as a range): Enter the serial numbers for SRCs to be transferred. Individually list serial numbers for SRCs that are not in sequential order. Use a range for sequential SRCs.

Purchase price for SRCs: Enter the price for each SRC to be transferred. If prices vary for different SRCs being transferred, enter each of the prices and the corresponding SRCs. DDOE will share price information on its website.

Name of current owner of SRCs: Enter the name and contact information for the current owner of SRCs to be transferred to the new owner.

Name of new owner of SRCs: Enter the name and contact information for the person to whom the SRCs will be transferred. DDOE will list the new owner on its SRC registry, unless the new owner requests not to be listed.

Name of agent for new owner: If applicable, enter the name and contact information for the agent of the new owner.

Should DDOE list these SRCs and the new owner's name and contact information in DDOE's SRC registry? Indicate whether the new SRC owner or the owner's agent would like the SRCs to be listed in DDOE's SRC registry. Also indicate whether the listed contact information should be for the new owner or the agent.

Instructions for Application for Transfer of Stormwater Retention Credit Ownership

Purpose of form: This form provides DOEE with the necessary information to verify and track ownership of SRCs and the price at which SRCs are traded.

Instructions

Application date: Enter the date that the applicant completes the application.

Number of SRCs to transfer: Enter the number of SRCs that are proposed for transfer from a seller to buyer.

Serial numbers of SRCs (may be listed as a range): Enter the serial numbers for SRCs to be transferred. Individually list serial numbers for SRCs that are not in sequential order. Use a range for sequential SRCs.

Purchase price for SRCs: Enter the price for each SRC to be transferred. If prices vary for different SRCs being transferred, enter each of the prices and the corresponding SRCs. DOEE will share price information on its website.

Name of current owner of SRCs: Enter the name and contact information for the current owner of SRCs to be transferred to the new owner.

Name of new owner of SRCs: Enter the name and contact information for the person to whom the SRCs will be transferred. DOEE will list the new owner on its SRC registry, unless the new owner requests not to be listed.

Name of agent for new owner: If applicable, enter the name and contact information for the agent of the new owner.

Should DOEE list these SRCs and the new owner's name and contact information in DOEE's SRC registry? Indicate whether the new SRC owner or the owner's agent would like the SRCs to be listed in DOEE's SRC registry. Also indicate whether the listed contact information should be for the new owner or the agent.

Page 3 of 3

Figure D.2 (continued)





Application to Retire Stormwater Retention Credits				
	Acronyms			
DDOE District Departme	nt of the Environment SRC	Stormwater Retention Credit		
A Post Post Astro				
Number of SRCs to reti	re:			
Serial numbers of SRCs	s (may be listed as a range):			
Name of current owner	of SRCs:			
Address:				
E-Mail:	Phone:			
	Signature of SRC	Owner		
	the owner of the above SRCs; is complete and correct to the l	that I request these SRCs to be retired; best of my knowledge.		
Signature:		Date:		
FC	OR DEPARTMENT	Γ USE ONLY		
Approved:	Approved in part:	Disapproved:		
Signature:		Date:		
Notes:				

GOVERNMENT OF THE DISTRICT OF COLUMBIA Department of Energy and Environment

	Acronyms		
OEE Department of Energ	gy and Environment SRC S	Stormwater Retention Credit	
pplication date:			
umber of SRCs to retire	:		
erial numbers of SRCs (may be listed as a range):		
Jame of current owner of	SRCs.		
			-
			-
Retired in honor of (optio	nal): Name:	E-Mail:	
	Signature of SRC Own	ner	
	te owner of the above SRCs; that complete and correct to the best	at I request these SRCs to be retired; of my knowledge.	
ignature:		Date:	
FOI	R DEPARTMENT U	JSE ONLY	
Approved:	Approved in part:	Disapproved:	1
Sign	ature:	Date:	i
Notes:			-
. 101401			



GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Application to Retire Stormwater Retention Credits

	Acro	onyms		
DOEE Department of Energ	gy and Environment	SRC	Stormwater Retention Credit	
Application date:				
Number of SRCs to retire	:			
Serial numbers of SRCs (may be listed as a range):				
Name of current owner of	f SRCs:			
Address:				
E-Mail:	Pho	one:		
Retired in honor of (optio	nal): Name:		E-Mail:	
	Signature of	f SRC O	Owner	
I hereby certify that I am the owner of the above SRCs; that I request these SRCs to be retired; and that this application is complete and correct to the best of my knowledge.				
Signature:			Date:	
FOR DEPARTMENT USE ONLY				
Approved:	Approved in pa	rt:	Disapproved:	
Sign	ature:		Date:	
Notes:				

Figure D.3 Application to Retire Stormwater Retention Credits.





Instructions for Application to Retire Stormwater Retention Credits

Purpose of form: This form provides DDOE with the necessary information to retire SRCs and track accordingly.

Instructions

Application date: Enter the date that the applicant completes the application.

Number of SRCs to retire: Enter the number of SRCs that are proposed for retirement.

Serial numbers of SRCs (may be listed as a range): Enter the serial numbers for SRCs to be retired. Individually list serial numbers for SRCs that are not in sequential order. Use a range for sequential SRCs.

Name of current owner of SRCs: Enter the name and contact information for the owner of the SRCs.

Instructions for Application to Retire Stormwater Retention Credits

Purpose of form: This form provides DOEE with the necessary information to retire SRCs and track accordingly.

Instructions

Application date: Enter the date that the applicant completes the application.

Number of SRCs to retire: Enter the number of SRCs that are proposed for retirement.

Serial numbers of SRCs (may be listed as a range): Enter the serial numbers for SRCs to be retired. Individually list serial numbers for SRCs that are not in sequential order. Use a range for sequential SRCs.

Name of current owner of SRCs: Enter the name and contact information for the owner of the SRCs.

Retired in honor of: Enter the name of person being honored.

Page 2 of 2

Instructions for Application to Retire Stormwater Retention Credits

Purpose of form: This form provides DOEE with the necessary information to retire SRCs and track accordingly.

Instructions

Application date: Enter the date that the applicant completes the application.

Number of SRCs to retire: Enter the number of SRCs that are proposed for retirement.

Serial numbers of SRCs (may be listed as a range): Enter the serial numbers for SRCs to be retired. Individually list serial numbers for SRCs that are not in sequential order. Use a range for sequential SRCs.

Name of current owner of SRCs: Enter the name and contact information for the owner of the SRCs.

Retired in honor of: Enter the name of person being honored.

Page ${\bf 2}$ of ${\bf 2}$

Figure D.3 (continued)

PROPOSED PENISION PROPOSED PRO

Appendix E Relief for from Extraordinarily Difficult Site Conditions

E.1 Relief from Extraordinarily Difficult Site Conditions

Regulated development sites may request relief from extraordinarily difficult site conditions if they are unable to meet the performance requirements of the stormwater management regulations as described in Chapter 2 Minimum Control Requirements. This request is subject to DOEE review.

This process can be used to seek relief from the following:

- The stormwater management performance requirements for single-family and two-family affordable housing;
- The requirement to achieve 50% of the Stormwater Retention Volume (SWRv) on-site for projects located in Combined Sewer System (CSS) areas where combined sewer overflows (CSOs) will be reduced with green infrastructure (CI);
- The requirement to achieve 50% of the SWRv on-site for projects located in the Municipal Separate Storm Sewer System (MS4);
- The requirement to retain or treat at least 50% of the SWRv from each site drainage area (SDA) for projects in the MS4; or
- The requirement to retain or treat at least 50% of the SWRv from the entire vehicular access area for each SDA for projects in the MS4.

There is no requirement to achieve 50% of the SWRv on-site for projects located in CSS areas where CSOs will be reduced with storage tunnels.

Note that major land-disturbing activityactivities in the existing public right-of-way (PROW) uses use the maximum extent practicable (MEP) process detailed in Appendix B, "Maximum Extent Practicable Process for Existing Public Right-of-Way" to determine sizing criteria used to achieve the stormwater management performance requirements for regulated activity. These projects are not required to apply for relief from extraordinarily difficult site conditions. Regulated activity located in the Anacostia Waterfront Development Zone (AWDZ) that are governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012 (see D.C. Official Code §§ 2-1226.36(c)(1)) must have all off-site retention and all off-site water quality treatment volume Water Quality Treatment Volume (WQTv) approved by DDOEDOEE through the process defined in this appendix, even if the District-wide minimum 50-percent% on-site retention requirement is met. All regulated development sites are required to address the Stormwater Retention Volume (SWRv). as described in Chapter 27 Minimum Control

Requirements. All development sites in the Anacostia Waterfront Development Zone (AWDZ), governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, are required to address the Water Quality Treatment Volume (WQTv), WQTv, as described in Chapter 2-, "Minimum Control Requirements." If compliance with the minimum on-site retention requirement or on or treatment requirements for the site water quality treatment requirement, for individual SDAs, or for vehicular access areas, is technically infeasible or environmentally harmful, the applicant may apply for relief from extraordinarily difficult site conditions. Additionally, if the regulated activity is in the Anacostia Waterfront Development Zone (AWDZ), governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, consideration for a request for relief will include the limited appropriateness of onsite compliance in terms of impact on surrounding landowners or overall benefit to District waterbodies. In cases where an applicant claims extraordinarily difficult site conditions, it is the responsibility of the applicant to provide sufficient evidence to support the claim.

Once granted relief from extraordinarily difficult site conditions, an applicant is allowed to provide less than the minimum compliance requirements on-site by managing a greater retention volume or water quality treatment volume WOTv through off-site mitigation. This or provide less than the minimum compliance requirements in each SDA or vehicular access area by retaining or treating a greater volume in other areas of the site, up to the 1.7-inch rainfall event. Except for qualifying affordable housing projects, this process does not relieve the applicant from the obligation to manage the full SWRv or the WQTv determined through compliance calculations. Additionally, stormwater runoff not receiving the minimum on site retention must receive treatment to remove 80 percent of total suspended solids based on the treatment practices, as defined in Chapter 3 of this guidance manual. When DDOE, but allows the applicant to satisfy a larger portion of these requirements off-site or in a different SDA. When DOEE finds the evidence presented is sufficient and compelling to grant relief, the Stormwater Management Plan (SWMP) for the project must the two conditions for relief have been satisfied: (1) removing 80 percent of total suspended solids from 50 percent of the SWRv and (2) identifyingidentify the requirement for the use of off-site retention to offset the entire on-site retention deficit- (if applicable).

E.2 Submission requirements for Relief from Extraordinarily Difficult Site Conditions

A request for relief is made through a "relief request memo." The memo is submitted in advance of a final SWMP, but not before the 65-percent% design stage of the SWMP, of the SWMP with supporting evidence to demonstrate the claim of technical infeasibility or environmental harm. The memo shall provide a detailed explanation of each opportunity for on-site installation of retention BMPs that was considered and rejected, and the reasons for each rejection. The applicant shall address each retention practice specified in this guidance manual in BMP groups 1 through 13, specifically,

BMP Group 1 Green Roofs

BMP Group 2 Rainwater Harvesting

BMP Group 3 Impermeable Surface Disconnection

BMP Group 4 Permeable Pavement Systems

BMP Group 5 Bioretention

BMP Group 7 Infiltration

BMP Group 8 Open Channel Systems

BMP Group 13 Tree Planting

Evidence of site conditions limiting each opportunity for a retention BMP include the following:

- 1. Data on soil and groundwater contamination;
- 2. -Data from soils testing consistent with the geotechnical requirements in Appendix O: "Geotechnical Information Requirements for Underground BMPs;"
- 3. Documentation of the presence of utilities requiring impermeable protection or a setback;
- **4.** Evidence of the applicability of a statute, regulation, court order, preexisting covenant, or other restriction having the force of law;
- **5.** Evidence that the installation of a retention BMP would conflict with the terms of a non-expired approval, applied for prior to the end of Transition Period Two A for a major land-disturbing activity or before the end of Transition Period Two B for a major substantial improvement activity, of a:
 - (a) Concept review by the Historic Preservation Review Board;
 - (b) Concept review by the Commission on Fine Arts;
 - (c) Preliminary or final design submission by the National Capital Planning Commission;
 - (d) Variance or special exception from the Board of Zoning Adjustment; or
 - (e) Large Tract Review by the District Office of Planning; and
- **6.** For a utility, evidence that a property owner on or under whose land the utility is conducting work objects to the installation of a BMP; and
- 7. For a major substantial improvement activity, evidence that the structure cannot accommodate a BMP without significant alteration, because of a lack of available interior or exterior space or limited load-bearing capacity, and
- 8. For single-family and two-family affordable housing, evidence of the high cost of a BMP relative to the overall cost of the project or impracticability of a BMP with respect to impact on the usability of the indoor or outdoor living space.

Projects in the AWDZ, governed by the Anacostia Waterfront Environmental Standards Amendment Act of 2012, may also discuss the limited appropriateness of on-site compliance verses a combination of off-site and on-site retention and or water quality treatment in terms of the impact on surrounding landowners or the overall benefit to District waterbodies.

E.3 Review of Requests for Relief from Extraordinarily Difficult Site Conditions

In an application for Relief from Extraordinarily Difficult Site Conditions, a completed application and proof of payment of the applicable fee are required to begin the review of the request. DDOEDOEE cannot render a final decision until an application for relief is considered complete. However, if an application is substantially complete, DDOEDOEE may begin consideration of the request for relief. Upon accepting an application, DDOEDOEE will review and determine whether the application meets the requirements of this section, including the following:

- 1. Require additional information;
- 2. Grant relief;
- 3. Grant relief, with conditions;
- 4. Deny relief; or
- 5. Deny relief in part.

In determining whether to grant relief, DDOEDOEE may consider the following:

- 1. The applicant's submittal;
- 2. Other site-related information;
- 3. An alternative design;
- 4. DDOE's DOEE's Stormwater Management Guidebook (SWMG);
- 5. Another BMP that meets the SWMG's approval requirements; and
- 6. Relevant scientific and technical literature, reports, guidance, and standards.

7.

Appendix F Stormwater Conveyance System Design

F.1 Introduction

The focus of this <u>SWMGguidebook</u> is to define standards and specifications for design, construction, and maintenance of <u>best management practices</u> (BMPs) required to meet stormwater performance objectives. The components and considerations of the accompanying stormwater conveyance system are outlined in this appendix.

F.2 Clearance with Other Utilities

- All proposed and existing utilities crossing or parallel to designed storm sewer systems must be shown on the plan and profile.
- Storm drain and utility crossings must not have be-less than a 45-degree angle between them.
- Minimum vertical and horizontal clearances, wall to wall, must be provided between storm drainage lines and other utilities as defined by the District of Columbia Water and Sewer Authority (DC Water). Consult DC Water's Project Design Manual and Green Infrastructure Utility Protection Guidelines, latest additions, for details. Exceptions may be granted by the DC Water on a case-by-case basis when justified.

F.3 Design of Stormwater Conveyance Systems

The Chezy-Manning formula is to be used to compute the system's transport capacities:

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

where:

Q = channel flow (cfs)

n = Manning's roughness coefficient (Table F.1)

 $A = \text{cross-sectional area of flow (ft}^2)$

R = hydraulic radius (ft) = A/P

S = channel slope (ft/ft)

Wp = wetlandP = wetted perimeter(ft)

 $R = \Lambda/W$

Table F.1 Manning's Roughness Coefficient (n) Values for Various Channel Materials

Channel Materials	Roughness Coefficient
Concrete pipe and precast culverts	
≤24 inches and smallerin diameter	0.015
≥27 inches and largerin diameter	0.013
Monolithic concrete in boxes, channels	0.015
Corrugated metal	0.022
PVC pipes	0.011
Sodded channel with water depth < 1.5 feet	0.050
Sodded channel with water depth >1.5 feet	0.035
Smooth earth channel or bottom of wide channels with sodded slopes	0.025
Rip rapRiprap channels	0.035

Note: Where drainage systems are composed of more than one of the above channel materials, a composite roughness coefficient must be computed in proportion to the wetted perimeter of the different materials.

Also, the computation for the flow velocity of the channel must use the continuity equation as follows:

$$Q = A \times V$$

where:

V = velocity (ft/s)

 $A = \text{cross-sectional area of the flow (ft}^2)$

F.4 Gutters

With uniform cross slope and composite gutter section use the following equation:

$$Q = \frac{0.50}{n} \times S_x^{1.67} \times S^{0.5} \times T^{2.67}$$

$$Q = \frac{0.50}{n} \times S_x^{1.67} \times S^{0.5} \times T^{2.67}$$

where:

Q = flow rate (cfs)

n = Manning's roughness coefficient (Table F.1)

 S_x = cross slope (ft/ft)

S = longitudinal slope (ft/ft) T = width of flow (spread) (ft)

F.5 Inlets

In accordance with the current requirements of the District of Columbia Plumbing Code, all inlets on private or public parcels, but outside the public right-of-way (PROW), must be sized to ensure safe conveyance of stormwater flows exceeding the capacity of the approved on-site stormwater management practices and the designated pervious land cover areas. These stormwater flows must not flow over property lines onto adjacent lots unless these flows run into an existing natural water course. Stormwater inlets in the PROW must be designed in accordance with the current requirements in Chapter 33 of the District of Columbia Department of Transportation (DDOT) Design and Engineering Manual and be approved for use by the District of ColumbiaDC Water-and Sewer Authority.

F.6 Street Capacity (Spread)

Design of the conveyance of stormwater runoff within the <u>public right of wayPROW</u> must follow the current requirements in the <u>DDOT</u> Design and Engineering Manual of the <u>District of Columbia Department of Transportation</u>. The roadway drainage design criteria for existing streets is a 15-year storm, 5-minute duration, and a maximum spread of 6 feet from the face of the curb (32.3.13 DDOT Design and Engineering Manual 2009). Proposed streets must use AASHTO Chapter VI for their design criteria.

F.7 Manhole and Inlet Energy Losses

The following formulas must be used to calculate headloss:

$$HL = \frac{V_{outlet}^2 - V_r^2}{2g} + SL$$

$$V_r = \frac{Q(V\cos\frac{a}{2})(inlet1) + Q(V\cos\frac{a}{2}(inlet2) + ...}{Q(outlet)}$$

$$HL = \frac{V_{outlet}^2 - V_r^2}{2g} + SL$$

$$V_r = \frac{Q(V\cos\frac{a}{2})_{(inlet\;1)} + Q(V\cos\frac{a}{2})_{(inlet\;2)} + \; \dots}{Q_{(outlet)}}$$

where:

 $HL = \frac{\text{headloss}}{\text{head loss}}$ in the structure

 $\frac{V_{outlet}}{V_r}$ = outlet velocity V_r = resultant velocity

g = gravitational acceleration (32.2 ft/s²)

SL = minimum structure loss

Q = flow rate (cfs)

a = angle between the inlet and outlet pipes (180°)

Table F.2 provides the minimum structure loss for inlets, manholes, and other inlet structures for use in the headloss calculation.

Table F.2 Minimum Structure Loss to Use in Hydraulic Grade Line Calculation

Velocity, Voutlet (ft/s)*	Structure Loss, SL
2	0.00
3	0.05
4	0.10
5	0.15
6	0.20
6	0.25

^{*} Velocities leaving the structure.

Headloss at the field connection is to be calculated like those structures, eliminating the structure loss. For the angular loss coefficient, cos-(a/2) is assumed to be 1.

F.8 Open Channels

• Calculations must be provided for all channels, streams, ditches, swales-and, etc., including a typical section of each reach and a plan view with reach locations. In the case of existing natural streams/swales, a field survey of the stream (swale) cross sections may be required prior to the final approval.

- The final designed channel must provide a 6-inch minimum freeboard above the designated water surface profile of the channel.
- If the base flow exists for a long period of time or velocities are more than five feet per second in earth and sodded channel linings, gabion or rip rapriprap protection must be provided at the intersection of the inverts and side slopes of the channels unless it can be demonstrated that the final bank and vegetation are sufficiently erosion-resistant to withstand the designed flows, and the channel will stay within the floodplain easement throughout the project life.
- Channel inverts and tops of bank are to be shown in plan and profile views.
- For a designed channel, a cross section view of each configuration must be shown.
- For proposed channels, a final grading plan must be provided.
- The limits of a recorded 100-year floodplain easement or surface water easement sufficient to convey the 100-year flow must be shown.
- The minimum 25-foot horizontal clearance between a residential structure and 100-year floodplain must be indicated in the plan.
- For designed channels, transition at the entrance and outfall is to be clearly shown on the site plan and profile views.

F.9 Pipe Systems

- Individual stormwater traps must be installed on the storm drain branch serving each structural best management practice, storm water BMPs or a single trap must be installed in the main storm drain after it leaves the structural best management practicestormwater BMP and before it connects with the city's combined sewer. Such traps must be provided with an accessible cleanout. The traps must be required for storm drains which that are connected to a separate storm sewer system.
- The pipe sizes used for any part of the storm drainage system within the <u>public right of wayPROW</u> must follow <u>District of ColumbiaDC</u> Water and <u>Sewer Authority</u> Standard and Specifications. The minimum pipe size to be used for any part of a private storm drainage system must follow the current requirements of the District of Columbia Plumbing Code.
- The material and installation of the storm drain for any part of public storm sewer must follow District of Columbia DC Water and Sewer Authority Standard and Specifications.
- An alternative overflow path for the 100-year storm is to be shown on the plan view if the path is not directly over the pipe. Where applicable, proposed grading must ensure that overflow will be into attenuation facilities designed to control the 100-year storm.
- A pipe schedule tabulating pipe lengths by diameter and class is to be included on the drawings. Public and private systems must be shown separately.

Profiles of the proposed storm drains must indicate size, type, and class of pipe, percent grade, existing ground and proposed ground over the proposed system, and invert elevations at both ends of each pipe run. Pipe elevations and grades must be set to avoid hydrostatic surcharge during design conditions. Where hydrostatic surcharge greater than one-1-foot of head cannot be avoided, a rubber gasket pipe is to be specified.

F.10 Culverts

Culverts must be built at the lowest point to pass the water across embankment of pond or highway. Inlet structure must be designed to resist long_term erosion and increased hydraulic capacities of culverts. Outlet structures must be designed to protect outlets from future scouring. The following formulas are to be used in computing the culvert:

If the outlet is submerged, then the culvert discharge is controlled by the tail water elevation:

$$h = h_e + h_f + h_v$$

$$h = h_e + h_f + h_v$$

where:

 h = head required to pass given quantity of water through culvert flowing in outlet control with barrel flowing full throughout its length

 h_e = entrance loss h_f = friction loss h_v = velocity head

and:

$$\begin{split} \underline{h} &= k_e \bigg(\frac{V^2}{2g}\bigg) + \frac{n^2 V^2 L}{2.21 R^{4/3}} + \frac{V^2}{2g} \\ \underline{h} &= \bigg[k_e + \frac{n^2 L}{2.21 R^{4/3}} \times 2g + 1\bigg] \times \bigg(\frac{V^2}{2g}\bigg) \\ \underline{h} &= \bigg[k_e + \frac{n^2 L}{2.21 R^{4/3}} \times 2g + 1\bigg] \times \bigg(\frac{8Q^2}{9.87 g D^4}\bigg) \\ h &= k_e \bigg(\frac{V^2}{2g}\bigg) + \frac{n^2 V^2 L}{2.21 R^{\frac{4}{3}}} + \frac{V^2}{2g} \end{split}$$

$$h = \left[k_e + \frac{n^2 L}{2.21 R^{\frac{4}{3}}} \times 2g + 1 \right] \times \left(\frac{V^2}{2g} \right)$$

$$h = \left[k_e + \frac{n^2 L}{2.21R^{\frac{4}{3}}} \times 2g + 1 \right] \times \left(\frac{8Q^2}{9.87gD^4} \right)$$

where:

 k_e = entrance loss coefficient = 0.5 for a square-edged entrance entrance loss coefficient = 0.1 for a well-rounded entrance

V = mean or average velocity in the culvert barrel (ft/s)

 $g = \frac{32.2 \text{ft/s}^2}{\text{(gravitational acceleration)}} (32.2 \text{ ft/s}^2)$

n = Manning's roughness coefficient = 0.012 for concrete pipe

L = length of culvert barrel (ft) R = 0.25D = hydraulic radius (ft)

Q = flow (cfs) D = diameter (ft)

If the normal depth of the culvert is larger than the barrel height, the culvert will flow into a full or partially full pipe. The culvert discharge is controlled by the entrance conditions or entrance control.

$$Q = C_d A (2gh)^{0.5}$$
$$Q = C_d A (2gh)^{0.5}$$

where:

Q = discharge (cfs)

C_d = discharge coefficient = 0.62 for square-edged entrance
 discharge coefficient = 0.1 for well-rounded entrance

A = cross sectional area (ft²)

 $g = \frac{32.2 \text{ft/s}^2}{\text{gravitational acceleration } (32.2 \text{ ft/s}^2)}$ = hydrostatic head above the center of the orifice (ft)

If the hydrostatic head is less than 1.2D, the culvert will flow under no pressure as an open channel system. If the flows are submerged at both ends of the culvert, use Figure F.1.




Figure F.1 Typical nomograph for culverts under outlet control.

If the flows are submerged at both ends of the culvert, use Figure F.1.

F.11 Hydraulic Grade Line

A hydraulic grade line (HGL) must be clearly indicated on the system profiles and identified with the initials HGL on the line and identified in the legend key. This grade line HGL must take into consideration pipe and channel friction losses, computing structures losses, tail water conditions, and entrance losses. All pipe systems must be designed so that they will operate without building up a surcharged hydrostatic head under design flow conditions. It is recommended that the HGL be no more than 1 foot above the pipe crown. If pipes have an HGL more than 1 foot above the pipe crown, rubber gaskets are required.

If the structural best management practice stormwater BMP discharges into a storm sewer or a combined sewer system, a detailed HGL analysis of the system including the receiving system must be submitted with the final stormwater management plans Stormwater Management Plans (SWMPs) for the 15- and 100-year flow frequencies. If the time characteristics of the HGL are unknown, the designed structural best management practice stormwater BMP must be functional under expected minimum and maximum grade lines.

F.12 Manholes and Inlets

- District of Columbia DC Water and Sewer Authority Standards and Specifications must be
 used. All structures are to be numbered and listed in the structure schedule and must include
 type, standard detail number, size, top elevation, slot elevation and locations, and
 modification notes.
- Access structures must be spaced according to the <u>District of ColumbiaDC</u> Water and <u>Sewer Authority</u> Standards and Specifications and the <u>DDOT</u> Design and Engineering Manual of the <u>District of Columbia Department of Transportation</u>.
- Where two or more pipes enter a structure maintain, a minimum of 9 inches of undisturbed concrete between holes in precast concrete is required to ensure sufficient steel. -Consult the District of Columbia Water and Sewer Authority (DC Water) for more specifics.
- A minimum drop of 0.1 foot must be provided through the structure invert.
- Drainage boundary and contours must be shown around each inlet to ensure that positive drainage to the proposed inlet is provided.
- Invert elevations of the pipes entering and leaving the structures must be shown in the profile view.
- Yard or grate inlets must show the 15-year and 100-year ponding limits (if applicable). A depth of not more than <u>two2</u> feet is allowed from the throat or grate to the 100-year storm elevation.
- Public street inlets must follow District of Columbia Water and Sewer Authority and District of Columbia Department of Transportation DC Water and DDOT criteria.
- Additional structures are recommended and may be required on steep slopes to reduce excessive pipe depths and/or to provide deliberate drops in the main line to facilitate safe

conveyance to a proper outfall discharge point. In order to provide an outfall at a suitable slope (i.e., less than 5-percent% slope), drop structures may need to be used to reduce the velocity before discharging on a rip rapriprap area.

- Curb inlets located on private cul-de-sacs must have a maximum 10 linear feet opening.
- For commercial/industrial areas, inlets must be kept at least five feet away from the driveway aprons.






Figure F.1 Typical nomograph for culverts under outlet control.

The determination of the minimum width of a structure based on incoming pipes is based on the following formula:

$$\underline{W = \frac{D}{\sin \theta} + \frac{T}{\tan \theta}}$$

$$W = \frac{D}{\sin \theta} + \frac{T}{\tan \theta}$$

where:

W = minimum structure width (inside)

D = pipe diameter (outside)

T = inlet wall thickness

W - minimum structure width (inside)

 θ = angle of pipe entering structure

Appendix G Design of Flow Control Structures

G.1 Design of Flow Control Structures

Flow control devices are orifices and weirs. The following formulas shall be used in computing maximum release rates from the designed structural <u>BMP.best management practice</u> (BMP).

G.2G.1 Circular Orifices

$$Q = CA(2gh)^{0.5}$$

$$Q = CA(2gh)^{0.5}$$

where:

Q = orifice discharge (cfs)

 \tilde{C} = discharge coefficient = 0.6

A = orifice cross-sectional area (ft²) = 3.1416(D2/4), $3.1416 \times \frac{D^2}{4}$

D = diameter of orifice (ft)

g = gravitational acceleration (32.2 ft/s²) = 32.

h = hydraulic head above the center of the orifice (ft)

When h < D, the orifice shall be treated as a weir:

$$Q = CLH^{3/2}$$

$$O = CLH^{3/2}$$

where:

Q = flow through the weir (cfs)

 $C = \frac{\text{discharge coefficient}}{2}$

L = diameter of orifice (ft)

H = hydraulic head above bottom of weir opening (ft)

G.2.1 Flow Under Gates

Flow under a vertical gate can be treated as a square orifice. For submerged conditions:

When outflow is not influenced by downstream water level:

Appendix G Design of Flow Control Structures

$$Q = b \times a \times C \times \left[2g \times \left(\frac{H_0}{H_0 + H_i} \right) \right]^{0.5}$$

where

Q = flow through the gate (cfs)

b =width of gate (ft)

a = gate opening height (ft)

C = discharge coefficient

 $G = 32.2 \text{ ft/s}^2 \text{ (gravitational acceleration)}$

When outflow is influenced by downstream water level

Q' = KQ

PENSION .

whore

Q = flow through the gate (cfs)
K = coefficient found in Figure G.1




Figure G.1 Absolute downstream control of flow under gate.

G.3G.2 Weirs

Rectangular:

$$Q = 3.33H^{1.5}(L - 0.2H)$$

$$Q = 3.33H^{1.5}(L - 0.2H)$$

60° V-notch:

$$Q = 1.43H^{2.5}$$

$$Q = 1.43H^{2.5}$$

90° V-notch:

$$0 = 2.49H^{2.48}$$

where:

$$Q = 2.49H^{2.48}$$

Q = lowflow through the weir (cfs)

Н = hydraulic head above the bottom of the weir (ft)

L = length of the weir crest (ft) PROPOSED PENISION PROPOSED PRO

Appendix H Acceptable Hydrologic Methods and Models

H.1 Acceptable Hydrologic Methods and Models

The following are the acceptable methodologies and computer models for estimating runoff hydrographs before and after development. These methods are used to predict the runoff response from given rainfall information and site surface characteristic conditions. The design storm frequencies used in all of the hydrologic engineering calculations will be based on design storms required in this guidebook unless circumstances make consideration of another storm intensity criterion appropriate:

- Urban Hydrology for Small Watersheds TR-55 (TR-55)
- Storage-Indication Routing
- HEC-1, WinTR-55, TR-20, and SWMM Computer Models
- Rational Method (limited to sites under <u>five5</u> acres)

These methods are given as valid in principle, and are applicable to most stormwater management design situations in the District. Other methods may be used when the District reviewing authority approves their application.

Note: Of the above methods, TR-55 and SWMM allow for the easiest correlation of the benefits of retention best management practices (BMPs) used to meet the SWRv with peak flow detention requirements, and are therefore strongly recommended. The Rational Method is not recommended, as it cannot account for the detention benefits of smaller retention BMPs applied on a site. However, the Rational Method is useful for quickly and easily calculating peak flows and detention requirements. Appendix A, "Compliance Calculations and Design Examples" includes more information on using the General Retention Compliance Calculator and Stormwater Database to account for retention BMPs in calculating peak flow detention requirements.

The following conditions should be assumed when developing predevelopment, <u>preproject preproject</u>, and post-development hydrology, as applicable:

- Predevelopment runoff conditions (used for the 2-year storm) shall be computed independent
 of existing developed land uses and conditions and shall be based on "Meadowmeadow in
 good condition" or better, assuming good hydrologic conditions and land with grass cover.
- Preproject Pre-project runoff conditions (used for the 15-year storm) shall be based on the existing condition of the site.
- Post-development <u>conditions</u> shall be computed for future land use assuming good hydrologic and appropriate land use conditions. If <u>an</u> NRCS CN Method-based approach,

such as TR-55, is used, this curve number <u>(CN)</u> may be reduced based upon the application of retention BMPs, as indicated in the General Retention Compliance Calculator <u>and Stormwater Database</u> (see Appendix A)-, "Compliance Calculations and Design Examples"). This <u>curve number CN</u> reduction will reduce the required detention volume for a site, but it should not be used to reduce the size of conveyance infrastructure.

- The rainfall intensity duration frequency curve should be determined from the most recent version of the Hydrometeorological Design Studies Center's Precipitation Frequency Data Server (NOAA Atlas 14, Volume 2).
- Predevelopment time of concentration shall be based on the sum total of computed or estimated overland flow time and travel in natural swales, streams, creeks and rivers, but never less than six6 minutes.
- Post-development time of concentration shall be based on the sum total of the inlet time and travel time in improved channels or storm drains, but shall not be less than six6 minutes.
- Drainage Site drainage areas exceeding 25 acres that are heterogeneous with respect to land use, soils, RCNCN or Timetime of Concentration (Te)concentration shall require a separate hydrologicalhydrologic analysis for each sub-area.
- Hydrologic Soil Groupssoil groups (HSGs) approved for use in the District are contained in the Soil Survey of the District of Columbia Handbook. Where the Hydrologic Soil Group HSG is not available through the Soil Survey due to the listed soil type being "Urban Soils" or similar, a Hydrologic Soil Groupan HSG of C shall be used.

H.2 Urban Hydrology for Small Watersheds TR-55

Chapter 6 of Urban Hydrology for Small Watersheds TR-55, Storage Volume for Detention Basins, or TR-55 shortcut procedure, is based on average storage and routing effects for many structures; and can be used for multistage outflow devices. Refer to TR-55 for more detailed discussions and limitations.

Information Needed

To calculate the required storage volume using TR-55, the predevelopment hydrology for the 2-year storm, and the preproject project hydrology for the 15-year storm are needed, along with post-development hydrology for both the 2-year and 15-year storms. The predevelopment hydrology for the 2-year storm is based on natural conditions (meadow), and will determine the site's predevelopment peak rate of discharge, or allowable release rate, qo_2 , for the 2-year storm, whereas the preproject pre-project hydrology for the 15-year storm is based on existing conditions, and will determine the site's preproject pre-project peak rate of discharge, or allowable release rate, qo_{15} , for the 15-year storm.

The post-development hydrology may be determined using the reduced <u>curve numbersCNs</u> calculated in the General Retention Compliance Calculator <u>and Stormwater Database</u> (See Appendix A), "Compliance Calculations and Design Examples") or more detailed routing calculations. This will determine the site's post-development peak rate of discharge, or inflow for both the 2-year and 15-year storms, qi_2 and qi_{15} , respectively, and the site's post-developed

runoff, Q_2 and Q_{15} , in inches. (Note that this method does not require a hydrograph.). Once the above parameters are known, the TR-55 Manual can be used to approximate the storage volume required for each design storm. The following procedure summarizes the TR-55 shortcut method.

Procedure

1. Determine the peak development inflows, q_{i_2} and $q_{i_{15}}$, and the allowable release rates, q_{o_2} and q_{o_1} and q_{o_1} , from the hydrology for the appropriate design storm.

Using the ratio of the allowable release rate, q_0 -, to the peak developed inflow, q_i , or q_0/q_i , for both the 2-year and 15-year design storms, use Figure H.1 (or Figure 6.1 in TR-55) to obtain the ratio of storage volume, Vs-, to runoff volume, Vr-, or Vs $_2$ /Vr $_2$ and Vs $_{15}$ /Vr $_{15}$ for Type II storms.




Figure H.1 Approximate detention basin routing for rainfall types I, IA, II and III.

2. Determine the runoff volumes, Vr_2 and Vr_{15} .

$$Vr_2 = 53.33 \times Q_2 \times Am$$

$$Vr_2 = \frac{Q_2}{12} \times SDA$$

where:

 $53.33 = \text{conversion factor from in mi}^2 \text{ to acre feet}$

 Q_2Vr_2 = post-development runoff, in inches for the 2-year storm (ft³)

Am = drainage area, in square miles

$$Vr15 = 53.33 \times O_{15} \times Am$$

Q2where:

53.33 = conversion factor from in mi² to acre feet

 Q_{15} = post-development runoff for the $\frac{152}{2}$ -year storm (in.)

 $Am = \text{drainage area (mi}^2)$

12 = conversion factor from inches to feet

SDA = Site Drainage Area (ft²)

$$Vr_{15} = \frac{Q_{15}}{12} \times SDA$$

where:

 Vr_{15} = post-development runoff for the 15-year storm (ft³)

 Q_{15} = post-development runoff for the 15-year storm (in.)

= conversion factor from inches to feet

SDA = Site Drainage Area (ft²)

3. Multiply the Vs-/Vr ratios from Step 1 by the runoff volumes, Vr_2 and Vr_{15} , from Step 2, to determine the required storage volumes, Vs_2 and Vs_{15} , in acre-feet.

$$(\frac{Vs_2}{Vr_2})Vr_2 = Vs_2$$

$$\frac{(Vs_{15})Vr_{15}}{Vr_{15}})Vr_{15} = Vs_{15}$$

$$\left(\frac{Vs_2}{Vr_2}\right)Vr_2 = Vs_2$$

$$\left(\frac{Vs_{15}}{Vr_{15}}\right)Vr_{15} = Vs_{15}$$

Note: In most cases, Vs_{15} represents the total storage required for the 2-year storm and the 15-year storm, and the outflow, qo_{15} , includes the outflow q_{o2} . In some cases, Vs_{15} may be less than Vs_2 . In these cases, the storage volume provided for the 2-year storm (Vs_2) may or may not be sufficient to meet the 15-year requirements, and must be checked via stage-storage curve analysis.

The design procedure presented above may be used with Urban Hydrology for Small Watersheds TR-55 Worksheet 6a. The worksheet includes an area to plot the stage-storage curve, from which actual elevations corresponding to the required storage volumes can be derived. The characteristics of the stage-storage curve are dependent upon the topography of the proposed storage practice and the outlet structure design (see Appendix G), "Design of Flow Control Structures"), and may be best developed using a spreadsheet or appropriate hydraulics software.

Limitations

This routing method is less accurate as the qo/qi ratio approaches the limits shown in Figure H.1. The curves in Figure H.1 depend on the relationship between available storage, outflow device, inflow volume, and shape of the inflow hydrograph. When storage volume (Vs) required is small, the shape of the outflow hydrograph is sensitive to the rate of the inflow hydrograph. Conversely, when Vs is large, the inflow hydrograph shape has little effect on the outflow hydrograph. In such instances, the outflow hydrograph is controlled by the hydraulics of the outflow device and the procedure therefore yields consistent results. When the peak outflow discharge (qo) approaches the peak inflow discharge (qi) parameters that affect the rate of rise of a hydrograph, such as rainfall volume, curve number CN, and time of concentration, become especially significant.

The procedure should not be used to perform final design if an error in storage of 25 percent cannot be tolerated. Figure H.1 is biased to prevent undersizing of outflow devices, but it may significantly overestimate the required storage capacity. More detailed hydrograph development and storage indication routing will often pay for itself through reduced construction costs.

H.3 Storage-Indication Routing

Storage-Indication Routing may be used to analyze storage detention practices. This approach requires that the inflow hydrograph be developed through one of the methods listed in this appendix (TR-55, WinTR-55, SWMM, etc.), as well as the required maximum outflows, q_{o2} and qo_{15} . Using the stage-discharge relationship for a given combination outlet devices, the detention volume necessary to achieve the maximum outflows can be determined.

H.4 HEC-1, WinTR-55, TR-20, and SWMM Computer Models

If the application of the above computer models is needed, the complete input data file and printout will be submitted with the stormwater management plansStormwater Management Plans (SWMPs) at the 85-percent% submittal stage. Submission of stormwater management plansSWMPs shall include the following computer model documentation:

- For all computer models, supporting computations prepared for the data input file shall be submitted with the stormwater management plansSWMPs.
- Inflow-outflow hydrographs shall be computed for each design storm presented graphically
 and submitted for all plans.
- Schematic (node) diagrams must be provided for all routings.

H.5 Rational Method

While this method is not recommended, as it cannot account for the retention/detention benefits of the BMPs applied on a site, this method will be permitted for use in a development of five5 acres or less. When applying this method, the following steps must be taken in the design consideration:

- In the case of more than one <u>site</u> sub-drainage area, the longest time of concentration shall be selected.
- Individual <u>site</u> sub-drainage flows shall not be summed to get the total flow for the watershed.site drainage area (SDA).
- The runoff coefficient, C, shall be a composite of the future site development conditions for all contributing areas to the discharge point. Runoff coefficient factors for typical District land uses are provided in Table H.1.
- The flow time in storm sewers shall be taken into account in computing the <u>watershedSDA</u> time of concentration.
- The storm duration shall be dependent upon the <u>watershedSDA</u> time of concentration.
- The storm intensity can be selected from the selected storm duration.

Table H.1 Runoff Coefficient Factors for Typical District of Columbia Land Uses

	e Predominant Use	Minimum Lot Dimensions		Runoff
Zone		Width (ft)	Area (ft²)	Coefficient C

	Predominant Use	Minimum Lot Dimensions		Runoff
Zone		Width (ft)	Area (ft²)	Coefficient C
R-1-A	One-family detached dwelling	75	7,500	0.60
R-1-B	One-family detached dwelling	50	5,000	0.65
R-2	One-family semi-detached dwelling	30	3,000	0.65
R-3	Row dwelling	20	2,000	0.70
R-4	Row dwelling	18	1,800	0.75
R-5-A	Low density apartment	_	-	0.70
R-5-B	Medium density apartment house	-	-	0.75
R-5-C	Medium high density apartment house	_	-	0.80
R-5-D	High density building	_	-	0.80
С	Commercial	_	-	0.85-0.95
M	General Industry	_		0.80-0.90
Park	Open green space	_	Q-V	0.35

H.6 Stormwater-Retention Volume Peak Discharge

The peak rate of discharge for individual design storms may be required for several different components of water quality BMP design. While the primary design and sizing factor for most stormwater retention BMPs is the design Stormwater Retention Volume (SWRv), several design elements will require a peak rate of discharge for specified design storms. The design and sizing of pretreatment cells, level spreaders, by-pass diversion structures, overflow riser structures, grass swales and water quality swale geometry, etc., all require a peak rate of discharge in order to ensure non-erosive conditions and flow capacity.

The peak rate of discharge from a drainage areaSDA can be calculated from any one of several calculation methods discussed in this appendix. The two most commonly used methods of computing peak discharges for peak runoff calculations and drainage system design are NRCS TR-55 Curve Number (CN) methods (NRCS TR-55, 1986) and the Rational Formula. The Rational Formula is highly sensitive to the time of concentration and rainfall intensity, and therefore should only be used with reliable Intensity-Duration-Frequency (IDF) curves or tables for the rainfall depth and region of interest (Claytor and Schueler, 1996). Unfortunately, there are no IDF curves available at this time for the 1.2-inch rainfall depth.

The NRCS CN methods are very useful for characterizing complex sub-watersheds and drainage areasSDAs and estimating the peak discharge from large storms (greater than two2 inches), but can significantly under estimate underestimate the discharge from small storm events (Claytor and Schueler, 1996). Since the TySWRy is based on a one1.2-inch rainfall, this underestimation

of peak discharge can lead to undersized diversion and overflow structures, potentially bypassing a significant volume of the design SWRv around the retention practice. Undersized overflow structures and outlet channels can cause erosion of the BMP conveyance features <a href="https://www.whichgung.com/whichg

In order to maintain consistency and accuracy, the following Modified CN Method is recommended to calculate the peak discharge for the SWRv 1.2-inch rain event. The method utilizes the Small Storm Hydrology Method (Pitt, 1994) and NRCS Graphical Peak Discharge Method (USDA_ 1986) to provide an adjusted curve numberCN that is more reflective of the runoff volume from impervious areas within the drainage-areaSDA. The design rainfall is a NRCS type II distribution so the method incorporates the peak rainfall intensities common in the eastern United States, and the time of concentration is computed using the method outlined in TR-55.

The following provides a step by step procedure for calculating steps describe how to calculate the Stormwater Retention Volume \underline{SWRv} peak rate of discharge (q_{pSWRv}):

Step 1: Calculate the adjusted curve number <u>CN</u> for the site or contributing drainage area_r (CDA).

The following equation is derived from the NRCS CN Method and is described in detail in the National Engineering Handbook Chapter 4: Hydrology (NEH-4), and NRCS TR-55 Chapter 2: Estimating Runoff:

$$CN = \frac{1,000}{[10 + 5P + 10Q_a - 10(Q_a^2 + 1.25Q_aP)^{0.5}]}$$

where:

CN = adjusted curve number

P = rainfall (in.), (1.2 in.)

 Q_a = runoff volume (watershed inches), equal to SWRv divided by drainage area CDA

Note: When using hydraulic/hydrologic model for sizing a retention BMP or calculating the SWRv peak discharge (), designers must use this modified CN for the <u>drainage areaCDA</u> to generate runoff equal to the SWRv for the 1.2-inch rainfall event.

Step 2: Compute the site or drainage area CDA Time of Concentration (Tc).

TR-55 Chapter 3: Time of Concentration and Travel Time provides a detailed procedure for computing the Tc.

Step 3: Calculate the Stormwater Retention Volume peak discharge (qp_{SWRv})

Step 4: The qp_{SWRv} is computed using the following equation and the procedures outlined in TR-55, Chapter 4: Graphical Peak Discharge Method. Designers can also use WinTR-55 or an equivalent TR-55 spreadsheet to compute qp_{SWRv} :

- Read initial abstraction (I_a) from TR-55 Table 4.1 or calculate using $I_a = 200/\text{CN} 2$
- Compute I_a/P (P = 1.02)
- Read the Unit Peak Discharge (q_u) from exhibit 4-II using Tc and I_q/P
- Compute the $qp_{SWR\nu}$ peak discharge:

$$qp_{SWRv} = q_u \times A \times Qa$$

$$qp_{SWRv} = \frac{q_u \times A \times Q_a}{27,878,400}$$

where:

$qp_{\mathrm{SWR}v} =$	Stormwater Retention Volume peak discharge (cfs)		
q_u	_ =	unit peak discharge (cfs/mi ² /in.)	
$\tilde{A} = -$		= contributing drainage area (mi ² ft ²)	
Q_a	_ =	runoff volume (watershed inches = $SWRv/A$)	
27,878,40	0 =	conversion from square miles to square feet	

This procedure is for computing the peak flow rate for the 1.2-inch rainfall event. All other calculations of peak discharge from larger storm events for the design of drainage systems, culverts, etc., should use published <u>curve numbersCNs</u> and computational procedures.

H.7 References

Claytor, R. and T. Schueler. 1996. Design of Stormwater Filtering Systems. Chesapeake Research Consortium and the Center for Watershed Protection. Ellicott City, MD. http://www.cwp.org/online-watershed-library?view=docmanhttps://owl.cwp.org/

Pitt, R., 1994, Small Storm Hydrology. University of Alabama - Birmingham. Unpublished manuscript. Presented at design of stormwater quality management practices. Madison, WI, May 17-19 1994.

"Precipitation-Frequency Atlas of the United States" NOAA Atlas 14, Volume 2, Version 3.0, G. M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley, NOAA, National Weather Service, Silver Spring, Maryland, 2006.

http://hdsc.nws.noaa.gov/hdsc/pfds/https://hdsc.nws.noaa.gov/hdsc/pfds/

<u>United States Army Corps of Engineers. "Hydrologic Modeling System (HEC-HMS)."</u> https://www.hec.usace.army.mil/software/hec-hms/

<u>United States Department of Agriculture Natural Resources Conservation Service. "WinTR-55."</u> https://www.nrcs.usda.gov/wps/portal/nrcs/detailfull/national/water/?cid=stelprdb1042901

United States Department of Agriculture Natural Resources Conservation Service. "WinTR-20." http://go.usa.gov/cZeg9

United States Department of Agriculture Natural Resources Conservation Service Urban Hydrology for Small Watersheds TR-55. June 1986.

OR U.S. Environmental Protection Agency. "Storm Water Management Model (SWMM)." https://www.epa.gov/water-research/storm-water-management-model-swmm

Virginia Department of Conservation and Recreation DRAFT 2009 Virginia Stormwater Management Handbook. September 2009.

Appendix I Rooftop Storage Design Guidance and Criteria


I.1 Rooftop Storage Design Guidance and Criteria

Rooftop storage, as described in this Appendix is intended as a detention practice only. The rules and guidelines presented in this Appendix do not apply to green roofs (Section 3.2 Green Roofs).

- 1. Rooftop storage may be used to provide detention for the 2-year and 15-year storms, as applicable. Detention calculations must follow the procedures identified in Chapter 2.

 "Minimum Control Requirements" and Appendix H₋, "Acceptable Hydrologic Methods and Models."
- 2. Rainfall from the 2-year, 24-hour storm results in an accumulated rainfall of approximately 3.2 inches, and rainfall from the 15-year, 24-hour storm results in an accumulated rainfall of approximately 5.2 inches. Peak flow detention calculations for either of these storms will require less than these depths (assuming there is no run-on from other rooftop areas.).
 - (a) Based on a snow load of 30 pounds per square foot or 5.8 inches of water, properly designed roofs must be structurally capable of holding the required detention volume with a reasonable factor of safety.
 - (b) Roofs calculated to store depths greater than three3 inches shall be required to show structural adequacy of the roof design.
- **3.** No less than two roof drains shall be installed in roof areas of 10,000 square feet or less, and at least four drains shall be installed in roof areas over 10,000 square feet in area. Roof areas exceeding 40,000 square feet shall have one drain for each 10,000–square–foot area.
- **4.** Emergency overflow measures adequate to discharge the 100-year, 45-minute storm must be provided.
 - (a) If parapet walls exceed 5 inches in height, the designer shall provide openings (scuppers) in the parapet wall sufficient to discharge the design storm flow at a water level not exceeding 5 inches.
 - (b) One scupper shall be provided for every 20,000 square feet of roof area, and the invert of the scupper shall not be more than 5 inches above the roof level. (If such openings are not practical, then detention rings shall be sized accordingly).
- Detention rings shall be placed around all roof drains that do not have controlled flow-(see Figures I.1 and I.2).
 - (a) The number of holes or size of openings in the rings shall be computed based on the area of roof drained and run-offrunoff criteria.
 - (b) The minimum spacing of sets of holes is 2 inches center-to-center.

- (c) The height of the ring is determined by the roof slope and detention requirements, and shall be 5 inches maximum.
- (d) The diameter of the rings shall be sized to accommodate the required openings and, if scuppers are not provided, to allow the 100-year design storm to overtop the ring (overflow design is based on weir computations with the weir length equal to the circumference of the detention ring).
- (e) Conductors and leaders shall also be sized to pass the expected flow from the 100-year design storm.
- **6.** The maximum time of drawdown on the roof shall not exceed 17 hours.
- 7. Josam Manufacturing Company and Zurn Industries, Inc. market "controlled-flow" roof drains. These products, or their equivalent, are acceptable.
- **8.** Computations required on plans:
 - (f) Roof area in square feet.
 - (g) Storage provided at design depth.
 - (h) Maximum allowable discharge rate.
 - (i) Inflow-outflow hydrograph analysis or acceptable charts (for Josam Manufacturing Company and Zurn Industries, Inc. standard drains, the peak discharge rates as given in their charts are acceptable for drainage calculation purposes without requiring full inflow-outflow hydrograph analysis).
 - (j) Number of drains required.
 - (k) Sizing of openings required in detention rings.
 - (l) Sizing of ring to accept openings and to pass 100-year design storm.







Figure I.1 Rooftop stormwater detention.






Figure I.2 Typical rainfall ponding ring sections.

Appendix J Soil Compost Amendment Requirements

J.1 Introduction

Soil amendment (also called soil restoration) is a technique applied after construction to deeply till compacted soils and restore their porosity by amending them with compost. These soil amendments can be used to enhance the performance of impervious cover disconnections and grass channels.

J.2 Physical Feasibility and Design Applications

Amended soils are suitable for any pervious area where soils have been or will be compacted by the grading and construction process. They are particularly well suited when existing soils have low infiltration rates (HSGhydrologic soil group (HSG) C and D) and when the pervious area will be used to filter runoff (downspout disconnections and grass channels). The area or strip of amended soils should be hydraulically connected to the stormwater conveyance system. Soil restoration is recommended for sites that will experience mass grading of more than a foot of cut and fill across the site.

Compost amendments are not recommended where any of the following exists:

- Existing soils have high infiltration rates (e.g., HSG A and B), although compost amendments may be needed at mass-graded B soils in order to maintain infiltration rates.
- The water table or bedrock is located within 1.5 feet of the soil surface.
- Slopes exceed 10 percent (compost can be used on slopes exceeding 10 percent as long as proper soil erosion and sediment control measures are included in the plan).
- Existing soils are saturated or seasonally wet.
- They would harm roots of existing trees (keep amendments outside the tree drip line).
- The downhill slope runs toward an existing or proposed building foundation.
- Areas that will be used for snow storage.

J.3 Design Criteria

Performance When Used in Conjunction with Other Practices. As referenced in several of the Chapter 3 Stormwater Best Management Practices (BMPs) specifications, soil compost amendments can be used to enhance the performance of allied practices by improving runoff infiltration. The specifications for each of these practices contain design criteria for how compost amendments can be incorporated into those designs:

Impermeable Surface Disconnection – See Section 3.4 Impervious Surface Disconnection.

Grass Channels –See Section 3.9, Open Channel Systems.

Soil Testing. Soil tests are required during two stages of the compost amendment process. The first testing is done to ascertain preconstruction soil properties at proposed amendment areas. The initial testing is used to determine soil properties to a depth 1 foot below the proposed amendment area, with respect to bulk density, pH, salts, and soil nutrients. These tests should be conducted every 50005,000 square feet, and are used to characterize potential drainage problems, and determine what, if any, further soil amendments are needed.

The second soil test is taken at least <u>one1</u> week after the compost has been incorporated into the soils. This soil analysis should be conducted by a reputable laboratory to determine whether any further nutritional requirements, pH adjustment, and organic matter adjustments are necessary for plant growth. This soil analysis must be done in conjunction with the final construction inspection to ensure tilling or subsoiling has achieved design depths.

Determining Depth of Compost Incorporation. The depth of compost amendment is based on the relationship of the surface area of the soil amendment to the contributing area of impervious cover that it receives. Table J.1 presents some general guidance derived from soil modeling by Holman-Dodds (2004) that evaluates the required depth to which compost must be incorporated. Some adjustments to the recommended incorporation depth were made to reflect alternative recommendations of Roa Espinosa (2006), Balousek (2003), Chollak and Rosenfeld (1998). and others.

Table J.1 Method to Determine Compost and Incorporation Depths

Ratio of Area of Contributing Impervious Cover to Soil Amendment ^a (IC/SA)	Average Compost Depth Depth (in.)	Incorporation Depth (in.)	Incorporation Method
0.5	3-6 ^e	8-12 ^e 12	Tiller
0.75	4-8 ^e	15 18 ^e <u>18</u>	Subsoiler
$1.\theta^{d}\underline{0^{b}}$	6 —10°	18 24 ^e <u>24</u>	Subsoiler

^a IC = contrib.contributing impervious cover (ft²) and SA = surface area of compost amendment (ft²)

Once the area and depth of the compost amendments are known, the designer can estimate the total amount of compost needed, using an estimator developed by TCC, (1997):

$$C = A \times D \times 0.0031$$

$$C = A \times D \times 0.0031$$

where:

Average depth of compost added

Lower end for B soils, higher end for C/D soils

^{4b} In general, IC/SA ratios greater than 1 should be avoided

C = compost needed (yd³) A = area of soil amended (ft²) D = depth of compost added (in.)

Compost Specifications. The basic material specifications for compost amendments are outlined below:

- Compost shall be derived from plant material and provided by a member of the U.S.
 Composting Seal of Testing Assurance (STA) program. See www.compostingcouncil.org/see https://compostingcouncil.org/ for a list of local providers.
- Alternative specifications and/or certifications, such as those administered by the Maryland Department of Agriculture or other agencies, may be substituted, as authorized by DDOEDOEE. In all cases, compost material must meet standards for chemical contamination and pathogen limits pertaining to source materials, as well as reasonable limits on phosphorus and nitrogen content to avoid excessive leaching of nutrients.
- The compost shall be the result of the biological degradation and transformation of plant-derived materials under conditions that promote anaerobic decomposition. The material shall be well composted, free of viable weed seeds, and stable with regard to oxygen consumption and carbon dioxide generation. The compost shall have a moisture content that has no visible free water or dust produced when handling the material. It shall meet the following criteria, as reported by the U.S. Composting Council STA Compost Technical Data Sheet provided by the vendor:
 - (a) 100 percent% of the material must pass through a half-inch screen
 - (b) The pH of the material shall be between 6 and 8
 - (c) Manufactured inert material (plastic, concrete, ceramics, metal, etc.) shall be less than 1.0 percent by weight
 - (d) The organic matter content shall be between 35-and-%-65-percent%
 - (e) Soluble salt content shall be less than 6.0 mmhos/cm
 - (f) Maturity must be greater than 80-percent%
 - (g) Stability shall be 7 or less
 - (h) Carbon/nitrogen ratio shall be less than 25:1
 - (i) Trace metal test result = "pass"
 - (j) The compost must have a dry bulk density ranging from 40 to 50 lb/ft³

J.4 Construction Sequence

The construction sequence for compost amendments differs depending whether the practice will be applied to a large area or a narrow filter strip, such as in a rooftop disconnection or grass channel. For larger areas, a typical construction sequence is as follows:

- **Step 1:** Soil Erosion and Sediment Control. When areas of compost amendments exceed 25002,500 square feet, install soil erosion and sediment control measures, such as silt fences, are required to secure the area until the surface is stabilized by vegetation.
- **Step 2:** Deep Till. Deep till to a depth of 12 to 18 inches after the final building lots have been graded prior to the addition of compost.
- Step 3: Dry Conditions. Wait for dry conditions at the site prior to incorporating compost.
- **Step 4:** Compost. Incorporate the required compost depth (as indicated in Table J.1) into the tilled soil using the appropriate equipment.
- **Step 5:** Level the site. Seeds or sod are required to establish a vigorous grass cover. To help the grass grow quickly, lime or irrigation is recommended...
- Step 6: Vegetation. Ensure surface area is stabilized with vegetation.
- **Step 7:** Construction Inspection. Construction inspection by a qualified professional involves digging a test pit to verify the depth of amended soil and scarification. A rod penetrometer should be used to establish the depth of uncompacted soil at a minimum of one location per 10,000 square feet.

J.5 Maintenance

First-Year Maintenance Operations. In order to ensure the success of soil compost amendments, the following tasks must be undertaken in the first year following soil restoration:

- **Initial inspections.** For the first <u>six6</u> months following the incorporation of soil amendments, the site should be inspected by a qualified professional at least once after each storm event that exceeds 1/2-inch of rainfall.
- **Spot Reseeding.** Inspectors should look for bare or eroding areas in the contributing drainage area (CDA) or around the soil restoration area and make sure they are immediately stabilized with grass cover.
- **Fertilization.** Depending on the amended soils test, a one-time, spot fertilization may be needed in the fall after the first growing season to increase plant vigor.
- Watering. Water once every three 3 days for the first month, and then weekly during the first year (April-through October), depending on rainfall.

Ongoing Maintenance. There are no major ongoing maintenance needs associated with soil compost amendments, although the owners may want to de-thatch the turf every few years to increase permeability. The owner should also be aware that there are maintenance tasks needed for filter strips, grass channels, and reforestation areas. $\frac{\text{DDOE'sDOEE's}}{\text{DOEE's}}$ maintenance inspection checklist for an area of Soil Compost Amendments can be accessed in Appendix $L_{7.2}$ "Maintenance Inspection Checklists."

Declaration of Covenants. A maintenance covenant is required for all stormwater management practices. The covenant specifies the property owner's primary maintenance responsibilities, and authorizes DOEE staff to access the property for inspection or corrective action in the event the proper maintenance is not performed. The covenant is attached torecorded in the

deed <u>District</u> of the <u>property Columbia land records</u> (see standard form, variations exist for scenarios where stormwater crosses property lines). The covenant is between the property and the Government of the District of Columbia. It is submitted through the Office of the Attorney General. All SWMPs have a maintenance agreement stamp that must be signed for a building permit to proceed. There may be a maintenance schedule on the drawings themselves or the plans may refer to the maintenance schedule (Exhibit C in the covenant).

Covenants are not required on government properties, but maintenance responsibilities must be defined through a partnership agreement or a memorandum of understanding.

J.6 References

- Balusek. 2003. Quantifying decreases in stormwater runoff from deep-tilling, chisel-planting and compost amendments. Dane County Land Conservation Department. Madison, Wisconsin.
- Chollak, T. and P. Rosenfeld. 1998. Guidelines for Landscaping with Compost-Amended Soils. City of Redmond Public Works. Redmond, WA. Available online at:

 www.redmond.gov/common/pages/UserFile.aspx?fileId=14766Available online at:

 http://www.redmond.gov/common/pages/UserFile.aspx?fileId=14766
- The Composting Council (TCC). 1997. Development of a Landscape Architect Specification for Compost Utilization. Alexandria, VA. http://www.cwc.org/organics/org972rpt.pdfhttp://infohouse.p2ric.org/ref/13/12551.pdf
 - http://www.ewe.org/organies/org/7/21pt.pdf
- Holman-Dodds, L. 2004. Chapter 6. Assessing Infiltration-Based Stormwater Practices. PhD Dissertation. Department of Hydroscience and Engineering. University of Iowa. Iowa City, IA.
- Low Impact Development Center. 2003. Guideline for Soil Amendments. Available online at: http://www.lowimpactdevelopment.org/epa03/soilamend.htm
- Roa-Espinosa. 2006. An Introduction to Soil Compaction and the Subsoiling Practice. Technical Note. Dane County Land Conservation Department. Madison, Wisconsin

PROPOSED PENISION PROPOSED PRO

Appendix K Construction Inspection Checklists

Inspections before, during, and after construction are required to ensure that <u>Stormwater Management Plans (SWMPs)</u> are built in accordance with the approved plan specifications. Inspectors will use detailed inspection checklists that require sign-offs by qualified individuals at critical stages of construction to ensure the contractor's interpretation of the plan is consistent with the designer's intent.

This appendix includes the following construction phase inspection checklists: (see Figures K. through K.13):

- Green Roof Construction Inspection Report
- Rainwater Harvesting Construction Inspection Report
- Impervious Surface Disconnection Construction Inspection Report
- Permeable Pavement System Construction Inspection Report
- Bioretention Construction Inspection Report
- Filtering SystemSand Filter Construction Inspection Report
- Infiltration <u>Practice Device</u> Construction Inspection <u>Report</u>
- Open Channel System Construction Inspection Report
- PondsPond, Wetland, and Storage PracticePractices Construction Inspection Report
- Generic Structural BMP Construction Stormwater Management Facilities Inspection Report
- Tree Planting and Preservation Construction Inspection Report
- Stormwater Facility Leak TestManagement Standard Testing Record

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Green Roof Construction Inspection Report

Building Permit #:	Plan #:	Lot:	Square:
Project Name and Address:			Ward
Contractor:		Te	elephone:
Engineer:		Te	dephone:
Date Started:	Final Inspection Date:		
Green Roof Type: Extensive Inte	nsive New Co	nstruction	Retrofit of Existing Roof
If this is a retrofit green roof, attach a copy of	the Roof Structural Certific	ation	
As-Built Plan Due Date:			

Inspection Item	No	Yes	Remarks	Date
Deck Preparation:				
Is the deck free of all trash, debris, grease, oil, water and moisture?				
Are all concrete surfaces properly cured, dry and free of voids, cracks, or holes?				
For retrofitted roofs, are all existing membranes and flashing removed to the bare concrete or deck?				
Are all expansion joints free of broken edges or loose aggregate and sealed to a depth at least twice as wide as the joint?				
Is a leak detection device installed? (Include manufacturer and testing information.)				
Water Proofing:				
Certification: identify type: Hot or Cold applied?				
Does the waterproofing system require an applicator "certified" by the manufacturer? (Attach certifications.)				
Are site conditions appropriate for application of water proofing materials? (Note temperature and moisture conditions.)				
Have the correct number of water proofing layers been installed as per the approved green roof plan?				
Does the membrane reinforcement and flashing meet plan specifications? (Attach invoice and/or manufacturer's certifications.)				
Is protection provided for water proofing membrane? (Specify membrane type and indicate the duration between installation of membrane and media.)				

• Green Area Ratio Landscape Checklist
The checklists are subject to change.





Natural Resources Administration Inspection & Enforcement Division

Green Roof Construction Inspection Report

Building Permit #:	_ Plan #:	_ Lot:_	Square:	
Project Address:			Ward	_
Contractor:			Email:	_
Engineer:			Email:	_
Date Started: Final Inspection l	Date:	As-B	uilt Plan Due Date:	
Green Roof Type: Extensive Intens	ive New Constru	ction	Retrofit of Existing Roof	
Inspection Item	No	Yes	Remarks	Date
Deck Preparation:		\top		\top
Is the deck free of all trash, debris, grease, oil, moisture?	water and			
Are all concrete surfaces properly cured, dry ar cracks, or holes?	nd free of voids,			
For retrofitted roofs, are all existing membran removed to the bare concrete or deck?	es and flashing			
Are all expansion joints free of broken edges or and sealed to a depth at least twice as wide as the				
Is a leak detection device installed? (Include metesting information.)	anufacturer and			
Water Proofing:				
Certification: identify type: Hot or Cold applied	d?			
Does the waterproofing system require an appli- by the manufacturer? (Attach certifications.)	icator "certified"			
Are site conditions appropriate for application of materials? (Note temperature and moisture con				
Have the correct number of water proofing layer as per the approved green roof plan?	ers been installed			
Does the membrane reinforcement and flashing specifications? (Attach invoice and/or manufac				
Is protection provided for water proofing memi- membrane type and indicate the duration betwee membrane and media.)				

Figure K.1 Green Roof Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Green Roof Construction Inspection Report—Continued

Project Name and Address:	File and WPD No:
---------------------------	------------------

Inspection Item	No	Yes	Remarks	Date
Water Test:				
Has a water test been conducted? Verify the water test is conducted according to test standards demonstrating two inches of water ponding for a 24- 48 hour period. (Attach water test report.)				
Green Roof Components:				
Do the over flow drains meet plan specifications? Verify dimensions, materials and locations.				
Do drain boxes, vent pipes and other penetrations meet plan specifications? Verify locations, water proofing details, flashing details and finish details. Verify materials selection and construction.				
Identify if this is a tray system or a built in place system.				
Do the root barrier, insulation, moisture retention layer, filter fabric, and drainage layers meet plan specifications? (Attach invoice and manufactures' certifications)				
Does the growing media meet plan specifications? Verify depth of growing material. (Attach invoice and manufacturer's certifications.)				
Does the vegetation layer meet plan specifications? Verify vegetation source—plugs, seeds, pre grown mat, species mixture, coverage. (Attach invoice and laboratory certification.)				
Does the metal curbing and flashing meet plan specifications? (Attach invoice and manufacturer's certifications.)				
Are all seems, joints and edges caulked and sealed with approved grade of caulk or sealant? (Attach invoice.)				
Do pedestals and pavers and non-vegetated areas meet plan specifications (type and location)?				
Irrigation:				
Is there an irrigation system?				
Is the system installed to plan specifications? Verify water source, location, service access, and pressure.				
Plantings and Housekeeping:				
Modular System Vegetated Mats Plugs Other				
Do plants meet size and variety specifications?				
Are all plants installed as per plan specifications? Note the planting distribution, the depth of media, and whether or not adequate watering was provided.				
Is temporary netting or wind uplift protection required?				
Have all planting waste materials, and construction trash and debris been pickup and removed from the roof?				
Contractor/Engineer	inspecto	or	Date	



Natural Resources Administration Inspection & Enforcement Division

Green Roof Construction Inspection Report—Continued

Project Address:		File a	ile and WPD No:	
Inspection Item	No	Yes	Remarks	Date
Water Test:				
Has a water test been conducted? Verify the water test is conducted according to test standards demonstrating two inches of water ponding for a 24-48 hour period. (Attach water test report.)				
Green Roof Components:				
Do the over flow drains meet plan specifications? Verify dimensions, materials and locations.				
Do drain boxes, vent pipes and other penetrations meet plan specifications? Verify locations, water proofing details, flashing details and finish details. Verify materials selection and construction.				
Identify if this is a tray system or a built in place system.				
Do the root barrier, insulation, moisture retention layer, filter fabric, and drainage layers meet plan specifications? (Attach invoice and manufactures' certifications)				
Does the growing media meet plan specifications? Verify depth of growing material. (Attach invoice and manufacturer's certifications.)				
Does the vegetation layer meet plan specifications? Verify vegetation source—plugs, seeds, pre grown mat, species mixture, coverage. (Attach invoice and laboratory certification.)				
Does the metal curbing and flashing meet plan specifications? (Attach invoice and manufacturer's certifications.)				
Do pedestals and pavers and non-vegetated areas meet plan specifications (type and location)?				
Irrigation:				\vdash
Is there an irrigation system?				
Plantings and Housekeeping:				\vdash
Do plants meet size and variety specifications?				
Have all planting waste materials, and construction trash and debris been pickup and removed from the roof?				

Figure K.1 (continued)

PROPOSITION RIV

GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Rainwater Harvesting Construction Inspection Re

Building Permit #:	Plan #:	Lot:
Project Name and Address:		
Contractor:		Telep
Engineer:		Telep
Responsible for Maintenance:		Telep
Secondary Practice (discharging to): pervious area	bioretention	infiltration practic
Date Started: Final Inspection	ı Date:	As-Built Plan Du

Inspection Items	Yes	No	Rema
Subgrade Preparation:			
Has the subgrade been properly prepared and tank foundation installed as shown on plans?			
Contributing Drainage Area:			
Does the rooftop area draining to the tank match the plans?			
Conveyance and First Flush Diversion:			
Do the gutters meet specifications with the correct sizing, elevation, and slope?			
Is the first flush diversion system properly sized and installed?			
Are mosquito screens properly installed on all tank openings?			İ
Pump System (where applicable):			
The pump and piping to end-uses (indoor, outdoor irrigation, or tank dewatering release) has been properly installed			
Overflow System:			
Overflow device is directed as shown on plans?			
Catchment area and overflow area are stabilized?			
Secondary stormwater treatment practice(s) (if applicable) is installed as shown on plans?			
Final Inspection:			
Is water conveyed into tank and to end-uses appropriately?			

Owner/Acoust	Inconcetor	



Natural Resources Administration Inspection & Enforcement Division

Rainwater Harvesting - CONSTRUCTION INSPECTION REPORT

Building Permit # Plan and File #			Lot:	Square:
Project Name and Address:			War	d:
Contractor:			Email	
Engineer:			Email	
Responsible For Maintenance:			Email	
Date Started: Final Inspection Date:			As-Built Plan Due D	Date:
Inspection Items	Yes	No	Remarks	Date Completed
Subgrade Preparation:				
Has the subgrade been properly prepared and tank foundation installed as shown on plans?				
Contributing Drainage Area:	-			
Does the rooftop area draining to the tank match the plans?				
Conveyance and First Flush Diversion:				
Do the gutters meet specifications with the correct sizing,				
elevation, and slope?				
Is the first flush diversion system properly sized and installed?				
Are mosquito screens properly installed on all tank openings?	-			
Pump System (where Applicable): The pump and piping to end-uses (indoor, outdoor irrigation,				
or tank dewatering release) has been properly installed				
Overflow System:	_			
Overflow System: Overflow device is directed as shown on plans				
Catchment area and overflow area are stabilized				
Secondary stormwater treatment practice(s) (if applicable) is				
installed as shown on plans				
Final Inspection:				
Is water conveyed into tank and to end-uses appropriately?				
Owner/AgentInspector			Date	
DOEE/IED 2019				

Figure K.2 Rainwater Harvesting Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



		Lot: Square:	
		Ward_	
		Telephone:	
		Telephone:	
F	lain G	arden Other	
		As-Built Plan Due Date:	
Yes	No	Remarks	Date
\top			
	Yes	Yes No	Telephone: Telephone: Telephone: Telephone: Rain Garden As-Built Plan Due Date: Yes No Remarks



Natural Resources Administration Inspection & Enforcement Division

Impervious Surface Disconnection Construction Inspection Report

Project Address:			Ward	_
Contractor:			Email:	_
Engineer:			Email:	_
Responsible for Maintenance:			Email:	_
Disconnection Type: Simple Dry Well	F	Rain G	arden Other	
Date Started: Final Inspection Date:			As-Built Plan Due Date:	
Inspection Items	Yes	No	Remarks	Date
Site Preparation:				+
Have erosion and sediment controls been properly installed and maintained according to approved plans?				
Do site excavation and grading conform to the site plans?				
Has the pervious receiving area avoided compaction during excavation?				
Contributing Drainage Area:				\top
Does the impervious area draining to the receiving pervious area match the plans?				
Practice Geometry:				
Does the receiving pervious area match the dimensions and slopes shown on the plan?				
Has a secondary practice been installed according to plan (if required)?				
Vegetation:				\top
Does the pervious area vegetation comply with the approved planting plan and specification?				
Topsoil mixture, soil amendments, and soil compaction comply with plan (if required)				
Final Inspection:				
Have the contributing impervious area and the receiving pervious area been stabilized?				
Can water flow properly into the receiving pervious area?				

Figure K.3 Impervious Surface Disconnection Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Permeable Pavement System Construction Inspection Report

Building Permit #:	Plan and File#:	Lct: Square:	_
Project Name and Address:		Ward	_
Contractor:		Telephone:	_
Engineer:		Telephone:	_
Responsible for Maintenance:		Telephone:	_
Permeable Pavement Type: Porous Aspl	nalt Pervious Concrete	Permeable Pavers	_
Date Started: Fina	al Inspection Date:	As-Built Plan Due Date:	_

Inspection Items	Yes	No	Remarks	Date
Site Preparation:				
Have erosion and sediment controls been properly installed and maintained according to approved plans?				
Is stormwater runoff being diverted around the practice?				
Has the contributing drainage area been fully stabilized?				
Subgrade Preparation:				
Is subgrade suitable free of debris, standing water, proper grading?				
If design is for infiltration, verify soils have not been compacted.	İ			
Excavated soil stockpile is located away from practice with erosion and sediment controls in place?				
Filter Layer or Geotextile Fabric (where applicable):				
The filter layer and/or geotextile fabric have been installed according to the specifications?				
Underdrain and Reservoir Layer:				
Does the underdrain meet specifications with correct perforation pattern, elevation, and slope?				
Caps are placed on the upstream (but not the downstream) ends of the underdrains?				
Does the stone reservoir meet specifications (clean, washed, free of fines) and is it installed to design depth?				
Is at least 2 inches of aggregate provided above and below the underdrains?				



Natural Resources Administration Inspection & Enforcement Division

Permeable Pavement - CONSTRUCTION INSPECTION REPORT

		Email_ As-Bu	ilt Plan Due Date:	
		As-Bu	ilt Plan Due Date:	Date
				Date
Yes	No	1	Remarks	
	_			
			Date	

Figure K.4 Permeable Pavement System Construction Inspection Report.



Project Address:

GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

Bioretention Construction Inspection Report

______Ward_____

Building Permit #: _____ Plan and File#: _____ Lot: ____ Square: _____

Contractor:			Email:	
Engineer:			Email:	
Responsible For Maintenance:			Email:	
Date Started: Final Inspection Date:		As-Bu	ilt Plan Due Date:	
Inspection Items	Yes	No	Remarks	Date
Inflow/Overflow:				
Is inflow/overflow/outflow invert at correct elevation?				
Is stormwater runoff being diverted around practice during construction (if possible)?				
Is inflow pipe to practice covered with filter fabric to prevent debris from entering?				
Grading:				
Has bioretention area been graded as indicated in the plan?				
Is the bioretention bottom scarified and loosened prior to placement of fill?				
Underdrain and Aggregate Layer:				\top
Does the underdrain have at $3/8$ ° minimum holes spaced at least every 6 °?				
Does the underdrain meet plan specifications for elevation and slope?				
Are cleanouts/observation wells and caps installed according to the plan specifications?				
Does the aggregate meet plan specifications?				
Does the aggregate depth match the plan?				
Filter Media:	T			\top
Does the filter media meet specifications? (Attach lab report and material certification.)				
Does the filter media depth match plan specifications?				

Figure K.5 Bioretention -Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Bioretention Construction Inspection Report—Continued

Project Name and Address:	File and WPD No:

Inspection Item	1	No	Yes	Remarks	Date
Bioretention Plant Materials:					
Do plants meet size and variety specifi	cations?				
Are all plants installed as per landscape	e plan?				
Is mulch and cover crop installed as pe	r plan specifications?				
Are plant/ trees staked as per specificat	tions?				
Has watering of plant material been policy during first two months for fourteen coplanting has been completed, then as a growing season?	nsecutive days after				
Observation Well Inlets:					
Is observation well free of construction	debris and soil?				
Is outflow pipe invert at the design ele-	vation?				
Notes:					
A qualified professional must treat	t disease plants.				
2. Deficient stakes and wires must be	replaced.				
Dead plants or plants diseased bey replaced by plant meeting original					
New plants must be watered every after planting.	day for the first 14 days				

_____ Inspector____



Project Address: ____

GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

Bioretention Construction Inspection Report—Continued

File and WPD No:

Inspection Item	No	Yes	Remarks	Date
Plant Materials:				
Are all plants installed as per landscape plan?				
Is mulch/top soil installed as per plan specifications?				
Has the contributing drainage area been fully stabilized?				
Observation Well:				
Are cleanouts/observation wells free of construction debris and soil?				

Figure K.5 (continued)

GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Filtering System Construction Inspection Repo

Building Permit #:	Plan #:	Lot:
Project Name and Address:		
Contractor:		Tele
Engineer:		Tele
Structure Type: Cast in Place	Prefabricated	Name of Plant
Date Started:	Final Inspection Date:	As-Built Plan

Inspection Item	No	Yes	Ren
Subgrade:			
Is subgrade suitable (free of debris, standing water)?			
Is a subgrade Suitability Certification provided?			
Prefabricated Structure:			
Are shop drawings provided?			
Do type and location of openings meet specifications?			
Cast-In-Place Structure:			
Are structural drawings provided?			
Is a certification provided on steel placement?			
Provide load ticket showing concrete plant mix, strength certification, and load time.			
Is a certification provided for concrete placement?			
Do the 28 day break results meet design specifications?			
Access:			
Is access for each chamber provided (manholes, doors, steps, and ladder)?			
Leak Test:			
Does the leak test meet specifications? (attach form)			
Inflow Chamber:			
Does the orifice/submerged weir opening meet specifications of the approved plan? (dimensions)			
Is overflow/bypass installed per approved plan?			
(size, support, sealed)			



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT Natural Resources Administration

Page 1 of 2

Building Permit #Pl	an and File #	Lot:	Square:	
Project Address:				
Sewer Type: CSSMS4	Other		Ward:	
Contractor:		Email		
Engineer:		Email		
Responsible For Maintenance:				
Date Started:				
Structure Type: Cast in placed Prefabr	icated Name of Pla	nt:		
As-Built Plan Due Date:				
				Date
nspection Items:	Yes No		Remarks	Completed
Subgrade:				
s sub grade suitable? (free of debris, standing water)				
s a subgrade Suitability Certification provided?				
Prefabricated Structure:				
Are shop drawings provided?				
Do type and location of openings meet specifications?				
Contra None Contra				
Cast-In-Place Structure:				
Are structural drawings provided?				
s a certification provided on steel placement?				
s a load ticket provided showing concrete strength and mi	X?			
s a certification provided for concrete placement?				
Access:				
Access for each chamber provided? (manholes, doors, step	s, ladder)			
Leak Test:				

Owner/Agent ____

Figure K.6	Filtering SystemSan	<u>d Filter</u>	Construction	Inspection	Report.K.6
------------	---------------------	-----------------	--------------	------------	------------

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Filtering System Construction Inspection Report—Continued

Inspection Item	No	Yes	Remarks	Date
Inflow Chamber:				
Does the orifice/ submerged weir opening meet specifications of the approved plan? (dimensions)				
Is overflow/bypass installed per approved plan?				
(size, support, sealed)				
Filter Chamber:				
Is under drain installed per approved plan?				
(specifications, number size and spacing of holes)				
Is filter bed installed per approved plan?				
(specifications of sand, gravel and filter cloth)				
(attach materials invoice)				
Outflow Chamber:				
Dewatering valve installed per approved plan?				
Are perforated pipe openings installed?				
Sump pit required?				
Back Fill:				
Does backfill soil conform to specifications?				
Is a certification for lift, thickness and density test provided?				

_____ Inspector ______ Date ____

K-18



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT Natural Resources Administration Inspection & Enforcement Division

Page 2 of 2

Sand Filter Inspection Report

Inspection Items:	Yes	No	Remarks	Date Completed
Inflow Chamber:				
Does the orifice/ submerged weir opening meet specifications of approved plan? (dimensions)	the			
Is overflow/bypass installed per approved plan? (size, support, sealed)				
Filter Chamber :				
Is underdrain installed per approved plan? (specifications, number size and spacing of holes)				
Is filter bed installed per approved plan? (specifications of sand, gravel and filter cloth)				
(Attach Materials Invoice)				
Outflow Chamber:				
Dewatering valve installed per approved plan?				
Are perforated pipe openings installed?				
Sump pit required?				
Back Fill: Does backfill soil conform to specifications?				
Is a certification for lift, thickness and density test provided?				
Owner/ Agent In	spector_		Date	
DOEE/IED 2019				

Figure K.6 (continued)



GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Infiltration Practice Construction Inspection Rep

Building Permit #:	Plan and File#:	Lot:
Project Name and Address:		
Contractor:		Telej
Engineer:		Telej
Responsible for Maintenance:		Telep
Infiltration Practice Type: Dry Well	Infiltration Trench	Infiltration Bas
Date Started: Fina	al Inspection Date:	As-Built Plan I

Inspection Items	Yes	No	Rema
Site Preparation:			
Have erosion and sediment controls been properly installed and maintained according to approved plans?			
Is stormwater runoff being diverted around the practice?			
Has the contributing drainage area been fully stabilized?			
Subgrade Preparation:			
Is subgrade suitable? (free of debris, standing water, properly graded)			
Has compaction of the soils been avoided?			
Excavated soil stockpile is located away from practice with erosion and sediment controls in place?			
Practice Bottom:			
Has a 6 to 8 inch sand layer been installed beneath the practice according to the approved plans?			
Geotextile Fabric:			
Have the filter layer and/or geotextile fabric been installed on the sides of the practice <u>only</u> according to the specifications?			
Stone Reservoir Layer:			
Does the stone reservoir meet specifications (clean, washed, free of fines) and is it installed to design depth?			



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT Natural Resources Administration Inspection & Enforcement Division

B	uilding Permit #	Plan #		Lot:	Square:	
P	roject Address:					
_					Ward:	
				_	Email	_
E	ngineer:			_ I	Email	_
		Σ				
		Final Ins				
		renchDry Well				
Λ	s-Built Plan Due Date:					
			1			la.
nspection	ı Items:		Yes	No	Remarks	Date Completed
nfiltration	device:					
s the infiltrati	on device located as per a	innroyed plan?				
	•					
	s per approved plan spec length or diameter and d					
		sults and are infiltration test				
oles location	s indicated?					
	fabrics meet the approve e approved plan specifica	d plan specifications and is ations?				
Does all sand, pecifications?	stone or aggregate types	meet the approved plan				
		rncture meet the approved plan d to MS4 or CSS?				
	installed per approved pla rovided for all materials?					
	nd Stabilization: fill comply with the appr	oved plan specifications?				
ntractor/Eng	ineer	Inspector			Date	
г	OEE/IED Infiltration 2019					

Figure K.7 Infiltration Practice Device Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Infiltration Practice Construction Inspection Report—Continued

Inspection Item	No	Yes	Remarks	Dat e
Surface Material:	\top			
Does the surface material meet the specification and has it been properly installed?				
Is the surface free of fines and areas of clogging?				
Pretreatment:				
Are the pretreatment facilities installed according to the approved plans?				
Over Flow (where Applicable):	\top			
Is overflow invert at correct elevation?				
Has the outfall been constructed with adequate protection as specified on the plans?				
Final Inspection:	\top			
Can water infiltrate properly into the practice?				
Does the practice include an observation well?				
Does the reservoir storage layer drains within 72 hours?	1			

Figure K.7 (continued)

Records to the second s

GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Open Channel System Construction Inspection Re

Building Permit #:	Plan and File#: _		Lot:	_
Project Name and Address: _				_
Contractor:			Telep	p
Engineer:			Teleş	p
Responsible for Maintenance:			Telep	p
Open Channel System Type:	Grass Channel	Dry Swale	Wet Swale	
Date Started:	Final Inspection Date:		As-Built Plan I	D

Inspection Items	Yes	No	Rema
Site Preparation:			
Have erosion and sediment controls been properly installed and maintained according to approved plans?			
Is stormwater runoff being diverted around the practice?			
Has the contributing drainage area been fully stabilized?			
Practice Geometry:			
Are the practice dimensions and longitudinal slope correct as shown on the plans?			
Are the channel side slopes no steeper than 3:1?	i		İ
Have the check dams been properly installed and to the correct elevations (where applicable)?			
Pretreatment:			
Are the pretreatment facilities installed according to the approved plans?			
Vegetation:	\top		
Does the channel surface vegetation comply with the approved planting plan and specification?			
Topsoil mixture, soil amendments, and soil compaction comply with plan (if required)			
Over Flow (where Applicable):			
Is overflow invert at correct elevation?			
Has the outfall been constructed with adequate protection as specified on the plans?			

Building Permit #: _____

Project Name and Address: ____



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

Open Channel System Construction Inspection Report

_____ Plan and File#: _____ Lot:_____ Square: ____

Contractor:			Telephone:	
Engineer:			Telephone:	
Responsible for Maintenance:			Telephone:	
Open Channel System Type: Grass Channel Dry Swale _		Wet S	Swale Other	
Date Started: Final Inspection Date:		As-Bu	ilt Plan Due Date:	
Inspection Items	Yes	No	Remarks	Date
Site Preparation:				
Have erosion and sediment controls been properly installed and maintained according to approved plans?				
Is stormwater runoff being diverted around the practice?	1			
Has the contributing drainage area been fully stabilized?	İ			
Practice Geometry:	1			
Are the practice dimensions and longitudinal slope correct as shown on the plans?				
Are the channel side slopes no steeper than 3:1?				
Have the check dams been properly installed and to the correct elevations (where applicable)?				
Pretreatment:				
Are the pretreatment facilities installed according to the approved plans?				
Vegetation:				
Does the channel surface vegetation comply with the approved planting plan and specification?				
Topsoil mixture, soil amendments, and soil compaction comply with plan (if required)				
Over Flow (where Applicable):				
Is overflow invert at correct elevation?				
Has the outfall been constructed with adequate protection as specified on the plans?				

Open Channel System Construct oject Name and Address: Inspection Items Ory Swale Designs (where Applicable): Oces planting soil meet design specifications? Oces the underdrain meet specifications with correct hotattern, elevation, and slope? Are at least 2 inches of aggregate provided above and	Yes			
nspection Items Pry Swale Designs (where Applicable): Ooes planting soil meet design specifications? Ooes the underdrain meet specifications with correct howattern, elevation, and slope? Are at least 2 inches of aggregate provided above and	Yes			
Ory Swale Designs (where Applicable): Ones planting soil meet design specifications? Ones the underdrain meet specifications with correct howattern, elevation, and slope? Are at least 2 inches of aggregate provided above and		No	Remarks	
Oces planting soil meet design specifications? Oces the underdrain meet specifications with correct hotattern, elevation, and slope? Are at least 2 inches of aggregate provided above and				Date
Ooes the underdrain meet specifications with correct ho attern, elevation, and slope? Are at least 2 inches of aggregate provided above and				
attern, elevation, and slope? Are at least 2 inches of aggregate provided above and				
are at least 2 inches of aggregate provided above and	le			
elow the underdrains?				
Oces the reservoir storage layer drains within 72 hours?				



Project Name and Address: Fr			File and WPD N	File and WPD No:		
Inspection Items	Yes	No	Remarks	Date		
Dry Swale Designs (where Applicable):	100	1.0		2		
Does planting soil meet design specifications?						
Does the underdrain meet specifications with correct hole pattern, elevation, and slope?						
Are at least 2 inches of aggregate provided above and below the underdrains?						
Does the reservoir storage layer drains within 72 hours?						
wner/Agent Inspec	tor			Date		

Figure K.8 (continued)

GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Pond, Wetland, and Storage Practice Construction Inspe

Building Permit #:	Plan and File#:	Lot:	
Project Name and Address:			
Contractor:			_ Telep
Engineer:			Telep
Responsible for Maintenance:			_ Telep
Practice Type: Wet Pond	Dry Pond	_ Underground Detention _	
Date Started:	Final Inspection Date: _	As-Bui	t Plan I

Inspection Items	Yes	No	Remarks
Contributing Drainage Area:			
Does the area draining to the practice match the plans?			
Practice Geometry:			
Are the practice dimensions correct as shown on the plans?			
Are the pond side slopes no steeper than 3:1?	İ		
Is a geotextitle or clay lining provided (where appropriate)?			
Is the practice installed to the proper depth as shown on the plans?			
Pretreatment:			
Has the forebay been properly sized and designed as according to the plans?			
Outfall:			
Has the outfall been constructed with adequate protection as specified on the plans?			
Is the outfall channel lined with filter cloth and is large rip-rap provided?			
Is an emergency spillway provided?			





Natural Resources Administration Inspection & Enforcement Division

Pond, Wetland, and Storage Practices - CONSTRUCTION INSPECTION REPORT

Building Permit # Plan and File #			L	ot:	_ Square:	
Project Address:	Ward:					
Contractor:			Email			
Engineer:			Email			
Responsible For Maintenance:			Email			
Type of Facility: Wet PondWetlandDry Pond	_ Under	ground	Detention_	Other		
Date Started: As-Built Plan Due Date: As-Built Plan Due Date:						
Inspection Items	Yes	No		Remarks	Date Completed	
Contributing Drainage Area: Does the area draining to the practice match the plans?						
Practice Geometry:						
Are the practice dimensions correct as shown on the plans?						
Are the pond side slopes no steeper than 3:1?						
Is a geotextitle or clay lining provided (where appropriate)?						
Is the practice installed to the proper depth as shown on the plans?						
Pretreatment: Has the forebay been properly sized and designed as according to the						
plans?						
Outfall: Has the outfall been constructed with adequate protection as						
specified on the plans? Is the outfall channel lined with filter cloth and is large rip-						
rap provided?						
Is an emergency spillway provided?						
Overflow and Trash Rack:						
Has the riser or outflow structure been properly installed and						
to the correct elevations?	-					
Has a trash rank been properly installed according to the approved SWM plan?						
Pond Buffer/Vegetation (where applicable): Do the buffer dimensions match the plans?						
Is an aquatic bench properly installed?						
Does the vegetation comply with the approved planting plan						
and specification?						
Final Inspection:						
Has the contributing drainage area been properly stabilized?						
Does the site have proper maintenance and inspection access?						
Owner/AgentInspector				Date		
DOTE TED 2010						
DOEE/IED 2019						

Figure K.9	Pond,	Wetland, and	Storage	Practice Practices	Constructi	on Inspection	ı Report.
------------	-------	--------------	---------	--------------------	------------	---------------	-----------

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Pond, Wetland, and Storage Practice Construction Inspection Report—Continued

Project Name and Address:			File and WPD No:			
Inspection Item	No	Yes	Remarks		Date	
Overflow and Trash Rack:						
Has the riser or outflow structure been properly installed and to the correct elevations?						
Has a trash rank been properly installed according to the approved SWM plan?						
Pond Buffer/Vegetation (where applicable):						
Do the buffer dimensions match the plans?						
Is an aquatic bench properly installed?						
Does the vegetation comply with the approved planting plan and specification?						
Final Inspection:						
Has the contributing drainage area been properly stabilized?						
Does the site have proper maintenance and inspection access?						
Owner/Agent Insp	ector_			Date		

PROPOSED REVISION PROPOSED REVISION

Figure K.9 (continued)

\star	\star	*

GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Storm Water Manage	ement	Fac	cilities Inspection	Report
Building Permit #Plan #			Lot:	Square:
roject Address:				Ward:
Contractor:			Email	
ingineer:			Email	
esponsible For Maintenance:			Email	
ate Started:		_Fina	Inspection Date:	
tructure Type:		s	Serial #	
Cast in Place: Pre- Cast Plant Location:			Cert	fication
as-Built Plan Due Date:				
Inspection Items	Yes	No	Remarks	Date Completed
Site Preparation: Is subgrade suitable?(free of debris, standing water)				
Is a subgrade suitability certification provided?				
Inlets:				
Do inlets meet plan specifications? (type, number and size)				
Structure:				
Do type and location of openings meet plan				
specifications?				
Are all components installed as per plan				
specifications? (media cartridges, weirs, inverted pipes, tees and ports)				
Access:				
Access for each chamber, including inlets where applicable provided? (manholes, doors, steps,				
ladders)				
Backfill: Does back fill meet specifications?				
•				
Is a certification for lift, thickness and density test provided?				
System Cleaned:				

K-31

 $\label{eq:Figure K.10 Storage Practice and Underground Detention Construction} \underline{Stormwater\ Management} \\ \underline{Facilities}\ Inspection\ Report.$

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT

Building Permit #: Plan and File#:	1	Let:	Square:	
Project Name and Address:			Ward	
Contractor:			Telephone:	
Engineer:			Telephone:	
Responsible for Maintenance:				
Device Type: Hydrodynamic treatment Filtering treat	tment _		Retention _	
Date Started: Final Inspection Date:		As-Bu	ilt Plan Due Date:	
Inspection Items	Yes	No	Remarks	Date
Site Preparation:				
Have erosion and sediment controls been properly installed and maintained according to approved plans?				
Is stormwater runoff being diverted around the practice?				
Has the contributing drainage area been fully stabilized?				
Structure:				
Do type and location of openings meet plan specifications?				
Are all components installed as per plan specifications? (media cartridges, weirs, inverted pipes, tees and ports)				
Access:	\top			
Access for each chamber, including inlets where applicable provided? (manholes, doors, steps, ladders)				
Backfill:	\top			
Does back fill meet specifications?				
Is a certification for lift, thickness and density test provided?				
System Cleaned:				



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

TREE PLANTING AND PRESERVATION CONSTRUCTION INSPECTION REPORT

Project Address:				Ward:	_
Contractor:			_ Email		
Engineer:			Email	·	
Responsible For Maintenance:			Email		
Tree Type(s): New		Preser	rved:		
Date Started: Final Inspection Date:			As-B	uilt Plan Due Date:	
Inspection Item	No	Yes		Remarks	Date Completed
Inventory of Trees:					
Did a licensed forester or arborist inventory existing trees?					
Were the size, species, condition, ecological value, and location of the trees recorded?					
Identification of Trees to Preserve:					
Average mature spread of at least 35 feet?					
Were the tree selected to be conserved selected based on species, size, condition, and location?					
Protection of Trees and Soil During Construction:					
Did a licensed forester or arborist identify the Critical Root Zone (Caround the trees?					
Were physical barriers properly installed and maintained around the CRZ?					
If excavating next to CRZ, were roots properly pruned to depth of 18 inches?					
Protection of Trees and Soil After Construction:					
Is there a Maintenance Covenant in place to protect the preserved trees?					
Selection of Tree Species:					
Does the tree species have an average mature spread of at least 35 feet?					
Are the trees container grown or ball and burlap?					
Do the trees have a minimum caliper size of 1.5 inches?					
Owner/Agent Inspector				Dat	e

Figure K.11-Generic Structural BMP Construction Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Tree Planting and Preservation Construction Inspection Report

Building Permit #:	Plan and File#:	I	.ct:	Square:	
Project Name and Address:				Ward	
Contractor:				_ Telephone:	
Engineer:				Telephone:	
Responsible for Maintenance:				_ Telephone:	
Tree Type(s): New Preserve	d :				
Date Started: First	al Inspection Date:	A	As-Bui	It Plan Due Date:	
					_
Inspection Item		No	Yes	Remarks	Date
Inventory of Trees:					
Did a licensed forester or arborist i	nventory existing trees?				
Were the size, species, condition, of the trees recorded?	ecological value, and location				

Inspection Item	No	Yes	Remarks	Date
Inventory of Trees:				
Did a licensed forester or arborist inventory existing trees?				
Were the size, species, condition, ecological value, and location of the trees recorded?				
Identification of Trees to Preserve:				
Average mature spread of at least 35 feet?				
Were the trees selected to be conserved selected based on species, size, condition, and location?				
Protection of Trees and Soil During Construction:				
Did a licensed forester or arborist identify the Critical Root Zone (CRZ) around the trees?				
Were physical barriers properly installed and maintained around the CRZ?				
If excavating next to CRZ, were roots properly pruned to depth of 18 inches?				
Protection of Trees and Soil After Construction:				
Is there a Maintenance Covenant in place to protect the preserved trees?				
Selection of Tree Species:				
Does the tree species have an average mature spread of at least 35 feet?				
Are the trees container grown or ball and burlap?				
Do the trees have a minimum caliper size of 1.5 inches?				

Figure K.12	Tree Planting	g and Preservatior	. Construction	n Inspection 1	Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Tree Planting and Preservation Construction Inspection Report—Continued

Project Name and Address:			_ File and WPD No:	
Inspection Item	No	Yes	Remarks	Date
Planting Sites:				
Was the appropriate tree planted in the best location based on urban planting constraints?				
Are clear sight lines provided along street and in parking lots?				
Is there enough overhead clearance for pedestrians and vehicles?				
Is there at least 2 cubic feet of useable soil per square foot of average mature tree canopy?				
Planting Techniques:				
Is the root collar exposed?				
Are erosion control blankets or other appropriate practices in place on steep slopes?				
With slopes steeper than 3:1, are trees planted on a level space on the slope?				
Post-Planting Tree Protection:				
Has 2-4 inches of organic mulch been spread over the soil surface out to the drip line of the tree?				
Are trees staked only if there is a concern of vandalism or windy exposure?				

Owner/Agent	Inspector	Date



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

No	Yes	Remarks	Date Completed
			1
			Date

Figure K.11 (continued)

GOVERNMENT OF THE DISTRICT OF COI DISTRICT DEPARTMENT OF THE ENVIRONM



Stormwater Facility Leak Test

PLAN #	WPD/ FILE #	BUILDING PERM
SQUARE	LOT	PARCEL
	Ň:	
	i	
BUILT: Cast-in place	∟ Precast	⊥ Otl
METHOD OF TESTING	: □ H2O □ Visual	□ Otl
READINGS:	Start	
	Difference	
	Allowable	
	Results	
DURATION:	(24 Hour Reading)	Time:
	(48 Hour Reading)	Time:
	(72 Hour Reading)	Time:
READINGS TAKEN BY	ì	DATE:
WITNESS:		DATE:
TITLE:		
Inspector		



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY & ENVIRONMENT

Natural Resources Administration Inspection & Enforcement Division

STORMWATER MANAGEMENT STANDARD TESTING RECORD

PLAN #	_ WPD/ FILE #		BUILDING PER		
SQUARE	_LOT		PARCEL		
NAME AND LOCATION:					
TYPE OF STRUCTURE:					
BUILT: Castin place] Pre-Cast		☐ Other	
METHOD OF TESTING:	□ H₂O □	Visual		Other	
READINGS:	StartDifference				
	Allowable				
DURATION:	(24 Hour Reading	g)	Time:	Date:	
	(48 Hour Reading	g)	Time:	Date:	
	(72 Hour Reading	g)	Time:	Date:	
READINGS TAKEN BY:			DATE:_		
WITNESS:			DATE:		
TITLE:					
FOR:					
Inspector					
Date					
SWM STANDARD TESTING/ IED 201	9				

Figure K.12 Stormwater Facility Leak Test FormManagement Standard Testing Record.




Figure K.13 Green Area Ratio Landscape Checklist

PROPOSED PENISION PROPOSED PRO

Appendix L Maintenance Inspection Checklists

It is recommended that an annual maintenance inspection and cleanup be conducted at each <u>BMP</u>best management practice (BMP) site, particularly at large-scale applications.

This appendix includes the following maintenance inspection checklists: (see Figures L.1 through L.13):

- Green Roof Maintenance Inspection
- Rainwater Harvesting Maintenance Inspection
- Impervious Surface Disconnection Maintenance Inspection
- Permeable Pavement System Maintenance Inspection
- Bioretention Maintenance Inspection
- Filtering System Maintenance Sandfilter Inspection Report
- Infiltration <u>PracticeFacilities</u> Maintenance Inspection
- Open Channel <u>SystemSystems</u> Maintenance Inspection
- Wet Ponds Pond and Wetlands Wetland Maintenance Inspection
- Storage and Underground Detention Practices Maintenance Inspection
- Generic Structural BMPStormwater Management Facilities Maintenance Inspection
- Tree Planting and Preservation Maintenance Inspection
- Maintenance Service Completion Inspection

PROPOSED PENISION PROPOSED PRO

The checklists are subject to change with the latest versions available at https://doee.dc.gov/swguidebook.

PROPOSED REVISION PROPOSED REVISION

Department of Energy and Environment



	Green Root M	aintenance Inspection Report	
Name/Facility Addres	s:	File/Plan no.	
Owner/Agent:	Ward:		
Mailing Address:			
Phone/Email			
Date/Weather			
Maintenance Item	Yes/No/N/A	Comments	
	1.	. Roof Condition	
Overflow Drains			
Repair needed			
Clear of			
debris/weeds			
Pealing or physical			
damage			
Standing water or			
leaks			
Damage to flashing/roof			
penetrations			
Accessible (railings			
& ladders)			
, and the second		2. Vegetation	
Roof type:		Intensive/Extensive/ Semi-intensive	
Dead or disease			
plants			
Weeds, moss,			
invasive plants			
Erosion or loss of			
media			
At least 80%			
coverage Replanting needed			
Date of last service			
Date of last service			
	3. Irrigat	tion and Leak Detection	
Watering method		Hose or Sprinkler	
Mechanical systems		Timers/Sensors/ Zones	
Leak detection			
provided	I		





Figure L.1 Green Roof Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Rainwater Harvesting Maintenance Inspection Report

		WPD No.	
Mailing Address:			Ward:
Owner / Agent:	Telephone:	Lot	Square:
As-Built Plan Available (Y/N) Last Inspection Date:	Last Service Date: Se	ervice Contract (Y/N), Type: _	
Secondary Practice (discharging to): pervious area	bioretention infiltration pra	ctice channel or swale:	
List all other stormwater management facilities on site	e:		
Review of on-site maintenance logs:			
1. Tank and System Condition:			
Tank ConditionGutter and Pipe Condi Replacement Parts Needed(specify com Observations	aponents):	, , ,	
2. Inflow and Storage: Debris in Gutters/ Downspouts Debris in Mosquito Screens Inadequate Sediment Acc Observations	cumulation in Tank Inadequate T		
3. Overflow: Over flow Device <u>Y/N</u> , Type:Outlet En		verflow Repair Needed	_




Figure L.1 (continued)

Department of Energy and Environment



Name/Facility Address: File/Plan no. Owner/Agent: Ward: Mailing Address: Phone/Email Date/Weather Maintenance Item Yes/No/N/A Comments 1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system Recirculation system installed	Rainwater Harvesting Maintenance Inspection Report					
Mailing Address: Phone/Email Date/Weather Maintenance Item Yes/No/N/A Comments 1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system Resirculation system installed	Name/Facility Addres	SS:	File/Plan no.			
Phone/Email Date/Weather Maintenance Item Yes/No/N/A Comments 1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Owner/Agent:	Ward:				
Maintenance Item Yes/No/N/A Comments 1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Mailing Address:					
Maintenance Item Yes/No/N/A Comments 1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Phone/Email					
1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Date/Weather					
1. Cisterns and Water Quality Treatment Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed						
Cistern in good repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Maintenance Item	Yes/No/N/A	Comments			
repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed		1. Cisterns	and Water Quality Treatment			
repair Pump functioning properly Disinfection system in place and type Filtration system Recirculation system installed	Cistern in good					
properly Disinfection system in place and type Filtration system Recirculation system installed						
Disinfection system in place and type Filtration system Recirculation system installed	Pump functioning					
in place and type Filtration system Recirculation system installed	properly					
Filtration system Recirculation system installed	Disinfection system					
Recirculation system installed	in place and type					
system installed	Filtration system					
	Recirculation					
	system installed					
Recirculation	Recirculation					
schedule (how often	schedule (how often					
is the water	is the water					
recirculated)	recirculated)					
2. Collection, Conveyance, Pre-treatment, Storage		2. Collection, C	onveyance, Pre-treatment, Storage			
Debris in						
gutter/downspouts						
Debris in						
prescreening devices						
Debris in first flush						
diverters						
Debris in						
hydrodynamic						
separator						
Mosquito screens						
inadequate Sediment						
accumulation in tank						
Inadequate tank						
drawdown						
3. Distribution and Overflow	G. G. G. G. G. G. G. G. G. G. G. G. G. G	3. Di	stribution and Overflow			
Discharging to BMP	Discharging to RMP	J. D.				



* * DEPARTMENT
OF ENERGY & 1200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.2 Rainwater Harvesting Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Impervious Cover Disconnection Maintenance Inspection Report

Name/Address: WPD	No
Mailing Address:	Ward:
Owner / Agent: Telephone: Lot	Square:
As-Built Plan Available (Y/N) Last Inspection Date: Last Service Date: Service Contract (Y/N), Typ	e:
Type: Disconnection: Simple Dry Well Rain Garden Other	
List all other stormwater management facilities on site:	
Review of on-site maintenance logs:	
1. Contributing Drainage Area:	
Type of Drainage Area: Rooftop Parking Lot Other	
Observations	
2. Receiving Area:	
Improper Conveyance to Receiving Pervious Area Receiving Area Encroachment	
Compaction in Receiving AreaErosion at Inflow Points Erosion in Flow Path Dead Vege	tation
Exposed Soil Sediment Accumulation Evidence of Standing Water	
Observations	
Inspector Received By Date	

Re-use to (e.g.		
flushing toilets, irrigation, cooling		
irrigation, cooling		
towers)		
Overflow device		
Outlet erosion		
Debris/sediment in		
overflow		
Overflow repair needed		
needed	Actions to be Taken:	
	Page 2 of 2	

Figure L.2 (continued)

Department of Energy and Environment



Impervious Surface Disconnection Maintenance Inspection Report

Projec	t Address:	Plan Numb	er / File Numb	er:
Mailin	g Address:			Ward:
Owner	r/Agent:	Phone:	Lot:	Square:
Y/N 	As-built plan available Service contract Review of on-site maintenance logs Simple disconnection Disconnection to dry well Disconnection to rain garden Other type of disconnection: Last inspection date: Last service date: Type of service contract (if any): Time since last rain > 1" +/-	l l l l ways / Hours		
I.	Contributing Drainage Area			
Y/N	Rooftop contributing drainage area Parking lot contributing drainage area Other contributing drainage area:			
II.	Receiving Area			
Y/N	Improper conveyance to receiving pervice Receiving area encroachment Compaction in receiving area Erosion at inflow points Erosion in flow path Dead vegetation Exposed soil Sediment accumulation Evidence of standing water	ous area		
		1 of 2		

Figure L.3 Impervious Cover Surface Disconnection Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Permeable Pavement Maintenance Inspection Report

Name/Address:		WPD) No
Mailing Address:			Ward:
Owner / Agent:	Telephone:	Lot	Square:
As-Built Plan Available (Y/N) Last Inspection Date:	Last Service Date: Serv	vice Contract (Y/N), Ty	pe:
Permeable Pavement Type: Porous Asphalt	Pervious Concrete	Permeable P	avers
List all other stormwater management facilities on site:			
Review of on-site maintenance logs.			
Surface Condition: Debris/ Sediment AccumulationWeed Accumulation Surface Deformation or Spalling Structural Observations	Repair Needed	ggingSweeping N	eeded
2. Underdrains and Cleanouts: Underdrains Y/N, Number: Observation N Evidence of Subsurface Clogging Inadequate Dra Observations	awdown Standing Water		/Days/Hours
3. Overflow: Over flow Device Y/N, Type: Observations			ied
Inspector Recei	ved By	Date	

Impervious S	Surface Disconnection Maintenanc (continued)	e Inspection Report	
III. Observations			
IV. Signatures			
Owner/Agent:	Inspector:	Date:	_
	2 of 2		

Department of Energy and Environment



Name/Facility Address:		ent Maintenance Inspection Report File/Plan no.
Owner/Agent:		
Mailing Address:		17 64 54
Phone/Email		
Date/Weather		
Maintenance Item	Yes/No/N/A	Comments
	1.	Surface Condition
Clear of		
debris/sediment/weeds Evidence of surface		
clogging		
Sweeping needed		
Surface deformation		
or spalling		
Structure repair		
needed		
	2. Und	erdrains and Cleanouts
Underdrain(s)		
Observation well(s)		
Evidence of surface		
clogging		
Standing water		
Last rain event >1"		Hours / Days
		3. Overflow
Overflow device		
Debris and sediment		
in overflow		
Overflow repair		
		I
needed	Α.	ctions to be Taken:



UF ENERGY & 1200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.4 Permeable Pavement Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Bioretention Practice Maintenance Inspection Report

Sediments/Trash AccumulationFilter Surface CloggingErosion in Practice Inadequate Mulch Thickness or Cover_Outlet: Condition of Outlet Debris/ Sediment in Overflow Repair Needed Underdrains and Cleanouts: Underdrains Observation Wells Number: Evidence of subsurface clogging Inadequate drawdown Standing Water Last Rain Event >1" +/ Days/Hours Observations 3. Plants: Specific Number and Types of Plants in Place Dead or Diseased plants Stakes and Wires Inadequate Watering Observations Note: A qualified professional must treat disease plants. Deficient stakes or wires must be replaced. Dead plants or plants beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days after planting.	Name/Address:		WPD	No.
Owner / Agent:	Mailing Address:			Ward:
Bioretention Type: Traditional Streetscape Tree Pits Planters: Residential: List all other stormwater management facilities on site: Review of on-site maintenance logs 1. Inlets and Drainage Area Stabilization:				
Bioretention Type: Traditional Streetscape Tree Pits Planters: Residential: List all other stormwater management facilities on site: Review of on-site maintenance logs 1. Inlets and Drainage Area Stabilization:	As-Built Plan Available (Y/N) Last Inspection Date:	Last Service Date:	Service Contract (Y/N), Typ	e:
List all other stormwater management facilities on site:				
Inlets and Drainage Area Stabilization:				
Inlet Type (s) Total Number Repair Needed Debris/ Sediment Accumulation Evidence of Erosion in Drainage Area Area Needs Mowing or Clipping Removal Drainage Area Debris Accumulation Observations 2. Bioretention Practice: Sediments/Trash Accumulation Filter Surface Clogging Erosion in Practice Inadequate Mulch Thickness or Cover Outlet: Condition of Outlet Debris/ Sediment in Overflow Repair Needed Underdrains and Cleanouts: Underdrains Observation Wells Number: Evidence of subsurface clogging Inadequate drawdown Standing Water Last Rain Event >1" +/ Days/Hours Observations Observations 3. Plants: Specific Number and Types of Plants in Place Dead or Diseased plants Stakes and Wires Inadequate Watering Observations Note: A qualified professional must treat disease plants. Deficient stakes or wires must be replaced. Dead plants or plants beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days a fler planting.	_			-
Inlet Type (s) Total Number Repair Needed Debris/ Sediment Accumulation Evidence of Erosion in Drainage Area Area Needs Mowing or Clipping Removal Drainage Area Debris Accumulation Observations 2. Bioretention Practice: Sediments/Trash Accumulation Filter Surface Clogging Erosion in Practice Inadequate Mulch Thickness or Cover Outlet: Condition of Outlet Debris/ Sediment in Overflow Repair Needed Underdrains and Cleanouts: Underdrains Observation Wells Number: Evidence of subsurface clogging Inadequate drawdown Standing Water Last Rain Event >1" +/ Days/Hours Observations Observations 3. Plants: Specific Number and Types of Plants in Place Dead or Diseased plants Stakes and Wires Inadequate Watering Observations Note: A qualified professional must treat disease plants. Deficient stakes or wires must be replaced. Dead plants or plants beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days a fler planting.	1. Inlets and Drainage Area Stabilization:			
Sediments/Trash AccumulationFilter Surface CloggingErosion in Practice Inadequate Mulch Thickness or Cover_Outlet: Condition of Outlet Debris/ Sediment in Overflow Repair Needed Underdrains and Cleanouts: Underdrains Observation Wells Number: Evidence of subsurface clogging Inadequate drawdown Standing Water Last Rain Event >1" +/ Days/Hours Observations 3. Plants: Specific Number and Types of Plants in Place Dead or Diseased plants Stakes and Wires Inadequate Watering Observations Note: A qualified professional must treat disease plants. Deficient stakes or wires must be replaced. Dead plants or plants beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days after planting.	Evidence of Erosion in Drainage Area Area Needs M	Mowing or Clipping Removal		
Specific Number and Types of Plants in PlaceDead or Diseased plantsStakes and WiresInadequate Watering Observations Note: A qualified professional must treat disease plants. Deficient stakes or wires must be replaced. Dead plants or plants beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days after planting.	Outlet: Condition of Outlet Underdrains and Cleanouts: Underdrains <u>Y/N</u> , Number Evidence of subsurface clogging Inadequate drawdo	Debris/ Sediment in Overflorer:Observerwn Standing Water	w Repair Needed _ ation Wells <u>Y/N</u> , Number: _	_
beyond treatment must be replaced by plants meeting original specifications. New plants must be watered every day for the first 14 days after planting.				tering
Desired Dr. Det.	beyond treatment must be replaced by plants meeting original			
Inspector Received By Date	Inspector Receive	ed By	Date	

Department of Energy and Environment



Bioretention/Planters Maintenance Inspection Report

Name/Facility Address:		File/Plan no.
Owner/Agent: Ward:		
Mailing Address:		
Phone/Email		
Date/Weather		
Maintenance Item	Yes/No/N/A	Comments
	1. Inlets	s and Drainage Area
Inlet type(s)		
Inlet repair needed		
Pre-treatment clear of		
debris/sediment		
Evidence of erosion in		
drainage area		
Drainage area clear of		
trash/debris/clippings		
Stone weir sediment		
accumulation		
	2. Bio	pretention Facility
Sediments and trash		
accumulation Filter surface clogging		
Overflow clear of debris		
Erosion in facility		
Inadequate mulch		
thickness		
Outlets in good		
condition		
Outlets repair needed		
Underdrains/Observation		
wells/Clean-outs		
Dewaters between		
storms within 48 hours		
		3. Vegetation
Dead or diseased plants		
Stakes and wires		
Inadequate watering		



* * DEPARTMENT
OF ENERGY & 1200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.5 Bioretention Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Filtering System Maintenance Inspection Report

Name/Address: W	PD No
Mailing Address:	Ward:
Owner / Agent: Telephone: Lot:	Square:
As-Built Plan Available (Y/N) Last Inspection Date: Last Service Date: Service Contract (Y/N),	Type:
Structure Type: Cast in Place Prefabricated Name of Plant	
List all other stormwater management facilities on site:	
Review of on-site maintenance logs.	
1. Structural Components and Filter Bed:	
Pretreatment (Y/N), Type: Condition: Chambers <u>Y/N</u> , Number: Condition:	ion:
Filter Bed Condition:Oil/Grease Accumulation Debris Accumulation Eviden	ce of Bypass
Observation Wells (Y/N), Condition: Maintenance Doors (Y/N) , Condition: Manholes (Y/N)	N) Condition:
Valves/Drains (Y/N), Condition: Water Seal (Y/N), Condition: Other	
Inadequate drawdownStanding Water Last Rain Event > 1"+/ Hours/ Days	
Observations	
2. Inlets:	
TypeTotal NumberRepair NeededDebris/Sediment A	Accumulation
Observations	
3. Outlets:	
Over flow Device (Y/N), Type: Debris/ Sediment in Overflow Repo	nir Needed
Observations	
Inspector Received By Date	




Figure L.5 (continued)

Department of Energy and Environment



	Sandfilter	Maintenance Inspection Report		
Name/Facility Address: File/Plan no.				
Owner/Agent: Ward:				
Mailing Address:				
Phone/Email				
Date/Weather				
Maintenance Item	Yes/No/N/A	Comments		
	1. 3	Structural Components		
Observation wells		-		
Maintenance doors				
Manholes				
Inlet/Outlets				
Valves/Drains				
Other				
		2. Inlets		
Inlet Type(s)				
Inlet repair needed				
Inlet clear of				
debris/sediment				
		3. Chambers		
Sediment/debris				
first chamber				
Sediment/debris on				
filter bed				
(2nd chamber)				
Sediment/debris in				
clear well (3rd chamber)				
Water seal				
Oil/Grease				
accumulation				
Debris				
accumulation				
Filter bed condition				
Standing water in				
2 nd chamber				
Evidence of bypass				

*	*	* DEPARTMEN	T
		OF ENERGY	&
		ENVIRONMEN	ıΤ

1 200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.6 Filtering SsystemSandfilter Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Infiltration Practice Maintenance Inspection Report

Name/Address:		WPD No)
Mailing Address:			Ward:
Owner / Agent:	Telephone:	_ Lot	Square:
As-Built Plan Available (Y/N) Last Inspection Date:	Last Service Date: Service C	ontract (Y/N), Type:	
Infiltration Device Type: Dry Well Infiltr	ation Trench Infiltration Basin C	other	
List all other stormwater management facilities on site			
Review of on-site maintenance logs.			
1. Inlets and Drainage Area Stabilization:			
Inlet Type(s)Total Number	Repair Needed Debris/ Sedimen	nt Accumulation	_
Erosion in Drainage Area_Area Needs Mowing/Cli	pping Removal_Drainage Area Debris Accu	mulation_Pretreatme	ent Bypass
Observations			
2. Structural Components and Function:			
Vegetation and Ground Cover Type:		_Surface Erosion Pre	sent? (Y/N)
Condition of Infiltration AreaOb	servation Wells (Y/N), Number:	Condition:	
Inadequate Drawdown Standing Water	Debris/Sediment Accumulation		
Last Rain Event >1" +/ Days/Hours			
Observations			
3. Overflow:			
Over flow Device (Y/N), Type:	Debris/ Sediment in Overflow	Repair Needed	1
Observations			
Inspector Re	ceived By	Date	
mspecioi Ro	cored by	Date	

L-18

Department of Energy and Environment



l l	nfiltration Fac	ilities Maintenance Inspection Report
Name/Facility Addre	ss:	File/Plan no.
Owner/Agent: Ward:		
Mailing Address:		
Phone/Email		
Date/Weather		
Maintenance Item	Yes/No/N/A	Comments
	1.	Inlets and Drainage Area
Inlet Type(s)		
Inlet repair needed		
Inlet clear of		
debris/sediment		
Evidence of erosion		
in drainage area		
Drainage area clear of trash/debris		
Evidence of		
pretreatment bypass		
	2. Struct	ural Components and Function
Vegetation and		Grass/Sod/Media
ground cover type		
Surface erosion		
present Infiltration area in		
good repair		
Observation wells		
in good repair		
Debris and		
sediment present		
Standing water		
Last rain event >1"		Hours / Days
		3. Overflow
Overflow device		
Debris/sediment in		
overflow		
Overflow repair		
needed		

*	*	★ DEPARTMENT
		OF ENERGY &
		ENVIRONMENT

1 200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.7 Infiltration Practice Facilities Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Open Channels Maintenance Inspection Report

Name/Address:	WPD No.
Mailing Address:	Ward:
Owner / Agent:	Square:
As-Built Plan Available (Y/N) Last Inspection Date: Last Service Date: Service Contract (Y/N)), Type:
Type of Open Channel System: Grass Channel Dry Swale Wet Swale Othe	r
List all other stormwater management facilities on site:	<u>_</u>
Review of on-site maintenance logs:	
1. Inlets and Drainage Area Stability:	
Type Total Number Repair Needed Clear of Debris/Sed	liment
Erosion at Inlets Evidence of Pretreatment Bypass Evidence of Erosion in drainage	area
Observations	
2. Open Channel Practice: Debris/ Sediment AccumulationErosion within Practice Inappropriate Ponding of Water Erosion Condition of Check Dams (if applicable) Condition of Underdrain (if applicable) Condition Observations 3. Vegetation: Dead Vegetation Bare Spots Presence of Invasive Species Re-vegetation Observations	of Outlet
Inspector Received By Date	

Actions to be Taken:

Page 2 of 2

Figure L.7 (continued)

Department of Energy and Environment



	Open Chann	el Maintenance Inspection Report
Name/Facility Address	File/Plan no.	
Owner/Agent:	Ward:	
Mailing Address:		
Phone/Email		
Date/Weather		
Maintenance Item	Yes/No/N/A	Comments
	1. I	nlets and Drainage Area
Inlet Type(s)		
Inlet repair needed		
Inlet clear of		
debris/sediment		
Erosion at inlets		
Evidence of erosion		
in drainage area		
Evidence of		
pretreatment bypass		
	2.	Open Channel Facility
Clear of		
debris/sediment		
Erosion within		
facility		
Ponding of water		
Check dams in good		
repair		
Outlet in good		
repair		
		3. Vegetation
Dead vegetation		
Bare spots		
Invasive species		
Re-vegetation		
needed		
		Actions to be Taken:





Figure L.8 Open Channel Systems Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Wet Ponds and Wetlands Maintenance Inspection Report

Name/Address:				WPD No	
Mailing Address:					Ward:
Owner / Agent:		Telephone:	Lot_		Square:
As-Built Plan Available (Y/N)	Last Inspection Date:	Last Service Date:	Service Contract	(Y/N), Type:	
Type of Practice: Wet Pond	Wetland	Underground Detention	Oth	er	
List all other stormwater manage	ement facilities on site:				
Review of on-site maintenance l	ogs				
1. Inlets and Drainage Area St	abilization:				
Inlet Type(s)	Total Number	Repair Needed	_ Debris/ Sediment	Accumulation	1
Erosion in Drainage Area	Drainage Area I	Debris Accumulation	Pretreatment	Bypass	
Observations					
2. Practice Function and Struc	ctural Components:				
Erosion within Practice	Debris/Sediment Accumu	lation Inadequate Wa	ter Level Ex	cessive Algal	Growth
Over flow Device (Y/N), Typ	e: Debris	Sediment in Overflow	Repair Needed		
Observations					
3. Vegetation:					
Dead or Diseased plants Diversity	Inadequate Vegetatio	onLack of Aqua	tic Bench	Lack of Plan	t
Observations					
Inspector	Receive	ed By	Date		

Department of Energy and Environment



Ponds and Wetlands Maintenance Inspection Report			
Name/Facility Address: File/Plan no.			
Owner/Agent: Ward:			
Mailing Address:			
Phone/Email			
Date/Weather			
Maintenance Item	Yes/No/N/A	Comments	
	1. I	nlets and Drainage Area	
Inlet Type(s)			
Inlet repair needed			
Inlet clear of			
debris/sediment			
Erosion in drainage			
area			
Drainage area			
debris accumulation			
Pretreatment bypass			
	2. Facility Fu	nction and Structural Components	
Erosion within			
facility			
Clear of			
debris/sediment			
Inadequate water			
level			
Excessive algal			
growth			
Overflow device			
Debris/sediment in			
overflow			
Overflow repair needed			
needed			
		3. Vegetation	
Dead or diseased			
plants			
Inadequate			
vegetation Lack of aquatic			
bench			
CONCIL			



* * DEPARTMENT
OF ENERGY & 1200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.9 PondsPond and WetlandsWetland Maintenance Inspection Report.Wet

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Storage and Underground Detention Facilities Maintenance Inspection Report

		WPD No
failing Address:		Ward:
wner / Agent:	Telephone:	Lot: Square:
s-Built Plan Available (Y/N) Last Inspect	ion Date: Last Service Date: Serv	rice Contract (Y/N), Type:
ype of Storage Practice: Dry Pond	Underground DetentionOther	
ist all other stormwater management facilit	ties on site:	
eview of on-site maintenance logs.		
Inlets and Drainage Area Stabilization:	:	
Inlet Type (s) Total Num	nberRepair NeededDebris/ S	Sediment Accumulation
Erosion in Drainage Area Dra	ainage Area Debris Accumulation	Pretreatment Bypass
Observations		
Practice Function:		
Inadequate Vegetation and/or Ground Co	ver (if applicable) Surface Erosion in Pra	ctice Debris/Sediment Accumulation
	wer (if applicable) Surface Erosion in Pra g Water Last Rain Event >1	
	g Water Last Rain Event >	
Inadequate DrawdownStanding	g Water Last Rain Event >	
Inadequate DrawdownStanding Observations	g Water Last Rain Event >	
Inadequate Drawdown Standing Observations Structural Components	g Water Last Rain Event >	"+/Days/Hours
Inadequate DrawdownStanding Observations Structural Components: Over flow Device (Y/N), Type:	g Water Last Rain Event >1	"+/Days/Hours v Repair Needed
Inadequate Drawdown Standing Observations Structural Components: Over flow Device (Y/N), Type: Vaults/Chambers (Y/N), Type:	g Water Last Rain Event > l	"+/ Days/Hours v Repair Needed Repair Needed
Inadequate Drawdown Standing Observations Structural Components: Over flow Device (Y/N), Type: Vaults/Chambers (Y/N), Type:	g Water Last Rain Event >	"+/ Days/Hours v Repair Needed Repair Needed

			_
Lack of plant diversity			
	Actions to be Take	n:	1
			_
	Page 2 of 2		
	97 - 01 -		

Figure L.9 (continued)

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



		d Detention Maintenance Inspection Report
Name/Facility Addres	s:	File/Plan no.
Owner/Agent:		Ward:
Mailing Address:		
Phone/Email		
Date/Weather		
Type of practice:		
Maintenance Item	Yes/No/N/A	Comments
	1. Ir	llets and Drainage Area
Inlet type(s)		
Inlet repair needed		
Inlet clear of		
debris/sediment		
Erosion in drainage		
area		
Drainage area debris		
accumulation		
Evidence of		
pretreatment bypass		
		2. Practice Function
Inadequate		
vegetation/ground		
cover		
Surface erosion in		
practice		
Clear of debris/sediment		
Inadequate		
drawdown/standing		
water		
	3. 5	structural Components
Overflow device		
Debris/sediment in		
overflow		
Overflow device		
repair needed		
Vaults and chamber		
Debris/sediment in		
chambers		



* * DEPARTMENT
OF ENERGY & 1200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.10 Storage Practice and Underground Detention Facilities Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Generic Stormwater Management Facilities Maintenance Inspection Report

Name/Address: WPD) No
Mailing Address:	Ward:
Owner / Agent:	Square:
As-Built Plan Available (Y/N) Last Inspection Date: Last Service Date: Service Contract (Y/N), Ty	pe:
Device Type: Hydrodynamic treatment Filtering treatment Retention	
List all other stormwater management facilities on site:	
Review of on-site maintenance logs:	
1. Inlets and Above Ground Condition:	
TypeTotal NumberRepairClear of debris Graded	Areas
Observations	
2. Structure:	
AccessOutletsElbows and ConnectionsVaults and ChambersTrash R	tacks
Observations	
3. Overall Function:	
Oil and Grease Accumulation Sediment Debris Accumulation Last Rain > 1" +/-	Hours/Days
Observations	
Inspector Received By Date	

Vaults/chamber repair needed		
Tepan needed	Actions to be Taken:	

Figure L.10 (continued)

PROPOSED REVISION PROPOSED REVISION

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Stormwater Management Facilities Maintenance Inspection Report

Project	Address:	Plan Numb	or / Filo Numbo	
	Address:			
Owner/	Agent:	Phone:	Lot:	Square:
Y/N 00 00 00 00 00	As-built plan available Service contract Review of on-site maintenance logs Hydrodynamic treatment Filtering treatment Retention Last inspection date: Last service date: Type of service contract (if any): Time since last rain > 1" +/-	Days / Hours		
I.	Inlets and Drainage Area Stabiliz	ation		
Y/N	Inlets need repair Clear of debris Graded areas Inlet type(s): Total number:			
II.	Structure			
Y/N 	Access Outlets Elbows and connections Vaults and chambers Track racks			
III.	Overall Function			
Y/N	Oil and grease accumulation Sediment Debris accumulation			
		1 of 2		

 $\label{eq:Figure L.11 Stormwater Management Facilities $$\frac{Generic Maintenance}{Annual Maintenance}$ Inspection Report.$

Report. GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT Tree Planting and Preservation Maintenance Inspection Report Name/Address: ____ Mailing Address: _____ Ward: ____ ______ Telephone:______ Lot:_____ Square:_____ As-Built Plan Available (Y/N) Last Inspection Date: ____ Last Service Date: ____ Service Contract (Y/N), Type: ____ Tree Type(s): New _____ Preserved : ____ List all other stormwater management facilities on site: Review of on-site maintenance logs._ 1. Tree Condition: Adequately watered ____ Dead/broken/diseased branches pruned ____ Trunk protected ____ Root collar exposed ____ Mower/weed whip damage, vandal damage, animal damage_____ Insect or disease problems____ Observations 2. Mulching: 2-4 inch deep mulch ____ Mulch not against trunk ____ Observations 3. Staking (if needed): Tree age < 1 year: Stakes in place _____ Webbing or ties hampering growth of tree_ Tree age > 1 year: Stakes removed Observations _ Received By

	Stormwater Management Facilities Maintenance Inspection Report (continued) IV. Observations		
1v. Observations			
V. Signatures			
Owner/Agent:	Inspector:	Date:	
	2 of 2		

Figure L.11 (continued)

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Tree Pla	anting and Pre	servation Maintenance Inspection Report
Name/Facility Address	:	File/Plan no.
Owner/Agent:		Ward:
Mailing Address:		
Phone/Email		
Date/Weather		
Maintenance Item	Yes/No/N/A	Comments
		1. Tree Condition
Adequately watered		
Dead/broken/diseased		
branches pruned		
Trunk protected		
Root collar exposed		
Tree damaged		
Insect or disease		
problems		
		2. Mulching
2-4 inch deep mulch		
Mulch not against		
trunk		
		. Staking (if needed)
Tree age < 1 year:		
stakes in place		
Tree age > 1 year: stakes removed		
Webbing or ties hampering growth of		
tree		
400	L,	Actions to be Taken:
	P	Actions to be Taken:

*	*	* DEPARTMENT
		OF ENERGY &
		ENVIRONMENT

1 200 First Street NE, 5th Floor, Washington, DC 20002 | (202) 535-2600 | doee.dc.gov



Figure L.12 Tree Planting and Preservation Maintenance Inspection Report.

GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT



Maintenance Service Completion Inspection Report

Name/Address:	
Owner/Agent:	 WPD No:
Mailing Address:	
Service Providers:	
Maintenance Service Start Date:	
Maintenance Service Completion Date:	
Type of Stormwater Practice Serviced:	
Description of Work:	
Is the maintenance service satisfactory? Yes/No If r	
Inspector R	

GOVERNMENT OF THE DISTRICT OF COLUMBIA

Department of Energy and Environment



Maintenance Service Completion Inspection Report

Name/Address:			
Owner/Agent:		WPD No:	
Mailing Address:			
Service Providers:			
Maintenance Service Start Date:			
Maintenance Service Completion Date: _			
Type of Stormwater Practice Serviced: _			
Description of Work:			
Description of Work.			
Is the maintenance service satisfactory? Y	Yes/No If no, list items to be completed:		
Inspector	Received By	Date	
			_

Figure L.13 Maintenance Service Completion Inspection Report.

Appendix M Tiered Risk Assessment Management: Water Quality End Use Standards

M.1 Tiered Risk Assessment Management (TRAM): Water Quality End Use Standards for Harvested Stormwater for Non-Potable Uses

This work was commissioned by the District of Columbia Department of the Environment (DDOE) to provide a frame work for applicants to follow when proposing a non-potable use of harvested stormwater runoff to comply with site stormwater retention regulations. Suggested water quality standards are drawn from a literature review of the field and rely largely on international guidance developed in Australia and the United Kingdom, guidance has also been drawn from the State of Texas and from the California County of Los Angeles. The proposed application process presented here requires the assessment of contaminates of concerns based on the collection surface(s), along with an assessment of the public health threat for categories of microbial and chemical contaminants. Under this scheme, an applicant is required to consider the potential risk of exposure and related magnitude of human health impacts with exposure. A tiered risk assessment management (TRAM) approach is provided to evaluate site conditions and determine treatment level if needed. If treatment is required this guidance provides a procedure for evaluating any remaining public health risk (residual risk) at the time of the commissioning of treatment practices, as well an ongoing procedure to ensure those practices meet public health standards throughout their maintenance and operation.

M.2 Health Risks

Rainwater collection systems have a long history going back as far as 3000 BC in India. It was used widely for agriculture throughout South East Asia over 2,000 years ago and in early Rome rainwater harvesting systems provided central air conditioning. Although rainwater harvesting has a significant and successful history, its popularity has declined as the large urban central water distribution system has grown. The return to rainwater harvesting in current times is driven largely by two factors, water scarcity and pollution of receiving waters. However, as we reconsider the collection of stormwater for non-potable uses, we must also recognize this can pose health risks. Health risks are due to two principal categories of contaminants—pathogenic microorganisms and toxic chemicals. Although both categories of contaminants need to be evaluated to ensure public health will be protected, microorganisms will typically pose the greatest health risk at most sites where stormwater is harvested for non-potable uses. Microbial hazards include bacteria, viruses, protozoa, and to a lesser extent helminthes. Chemical hazards can include inorganic and organic chemicals, pesticides, potential endocrine disruptors, pharmaceuticals, and disinfection byproducts. Proposals for stormwater harvested for nonpotable uses submitted to DDOE will require an assessment of the public health threat for both categories of contaminants. This assessment starts with an analysis of the likelihood of exposure

and can proceed through risk-based screening to determine if stormwater harvested for non-potable uses will pose a threat to public health.

DDOE cannot anticipate all site conditions within the wide spectrum of projects that may be proposed to harvest stormwater for non-potable uses to comply with District of Columbia stormwater regulations. For this reason, DDOE has developed a tiered risk assessment-management (TRAM) approach that applicants shall follow. Formal risk assessments can be costly, time consuming, and—for many stormwater projects—unnecessary. DDOE developed the TRAM approach to reduce the cost and level of effort associated with preparing the submission of a Stormwater Management Plan (SWMP) that incorporates stormwater harvesting for non-potable uses. The TRAM approach is based on the concept that increasing levels of sophistication, level of effort, and cost of a risk assessment only need to be considered as site conditions warrant. From a risk management perspective, the overarching goal in any project proposing to harvest stormwater for non-potable uses is to demonstrate that public health will be protected when the stormwater project is fully operational.

In addition to providing a cost effective approach for making risk management decisions, the TRAM approach can be used to identify the most cost-effective risk mitigation strategy (should it be necessary). The two types of health risks planners must consider are maximum risk (posed by untreated stormwater) and residual risk (posed by treated stormwater).

Maximum risk is defined as the risk associated with maximum exposure to untreated stormwater. It is the risk posed by stormwater under the intended non-potable use prior to any preventive measure to disinfect or otherwise decontaminate stormwater. Estimating the maximum risk is necessary for DDOE to issue a permit, and it must be based on the specific exposures that are reasonably anticipated for the untreated stormwater. High priority contaminants significantly contributing to the maximum risk should be the primary focus if a treatment plan is required. If the maximum risk is acceptable, no treatment of collected stormwater is necessary. However, if the maximum risk exceeds acceptable levels, stormwater must be treated to reduce health risks to acceptable levels.

DDOE will not be prescriptive with regard to the technology selected to protect public health. However, the threshold criterion for approving a SWMP with harvest for non-potable uses system is ensuring public health will be protected.

DDOE will make a determination on the effectiveness of the risk reduction strategy based on the magnitude of the second type of risk—namely, residual risk. Residual risk is defined as the risk remaining after stormwater has been treated based on the specific types of human exposure associated with the intended stormwater reuse.

For permitting purposes, DDOE will require proof that the residual risk from both microbial and chemical contaminants will be reduced to acceptable levels. The magnitude of residual risk is dependent on the magnitude of the maximum risk (the pretreatment risk) and the efficiency of the risk mitigation technology selected for the project.

M.3 Evaluating the Threat to Public Health

The threat to public health is a function of two site specific criteria—namely, the likelihood of exposure and the magnitude of health risks associated with site specific exposure conditions. Table M.1 through Table M.3 presents a useful matrix that planners can use to evaluate these two primary criteria during project planning. Proposed plans submitted to DDOE should be based on the classification scheme presented in these tables because it will streamline both the process of planning a stormwater project and DDOE's review of the submitted plans.

Table M.1 presents three categories for determining the likelihood of exposure. For some stormwater programs, human exposures will only occur under unusual site conditions. For example, in closed systems where contact with collected stormwater is not anticipated (unless there is a breach in the system), the likelihood of exposure would be classified as unlikely. Under these conditions, stormwater use would not pose a health threat and a treatment system would be unnecessary.

Where exposures are classified as possible or likely, a more detailed analysis of potential maximum health risks for the untreated stormwater will be required. An applicant will identify all proposed collection surfaces to determine potential contaminates of concern (COC). If collection surfaces include any existing surfaces, i.e., contributing drainage areas that exist preproject will remain as part of the final development and will contribute to the proposed rainwater harvest system, sampling of those site conditions may be required to identify COC.

When sampling existing surfaces that are proposed to contribute to the rainwater harvesting system in the proposed development contaminant levels in these samples will be compared with risk based levels that DDOE has derived for a select group of chemicals. Samples will also be screened for microbial threats. Table M.2 presents three categories of risks that roughly characterize maximum risk. Whether stormwater treatment is necessary will depend on the magnitude of maximum risk, which will be quantified with a risk-based screening approach. When contaminant levels are equal to or less than the risk-based levels, the maximum risk is classified as low or acceptable, and stormwater can be used without any treatment. When contaminant concentrations in stormwater are less than ten times the risk based concentration, the maximum risk is characterized as minor and DDOE will use its discretion to decide whether treatment is necessary.

Table M.3 shows the matrix of all possible outcomes for the combined evaluation of the likelihood of exposure and magnitude of health risks. These represent the classification of the health threat. Treatment technologies will not be required for stormwater harvesting projects posing a low threat. DDOE will use professional judgment to determine if moderate threats require a treatment system. Treatment systems will be required for high threats to public health.

Finally, all proposals shall present an analysis of both intended and unintended uses and exposures. While these situations may be rare and unique, they could pose a high risk to a small number of individuals. This could include inadvertent cross connections with drinking water systems and maintenance personnel or children being unintentionally exposed to untreated stormwater. Rainwater harvest proposals must identify how those unintended uses and exposures

will be avoided. Some examples of protective measures include backflow protectors, use of purple pipes and identification stamps, water coloring and signage.

Appendix M Rainwater Harvesting Treatment and Management Requirements

M.1 Introduction

The majority of the information and requirements provided herein are excerpted from the 2017 Water Environment and Reuse Foundation Report: Risk-Based Framework for the Development of Public Health Guidance for Decentralized Non-Potable Water Systems (DNWS Report). In some cases, text from this report has been modified to conform to this guidebook and DOEE's review and inspection procedures.

The purpose of this appendix is to provide information and guidance through a risk-based framework to help designers and DOEE ensure that all rainwater harvesting systems are adequately protective of public health. This appendix identifies pathogen reduction targets that must be met and various treatment systems that can be used to meet the targets. Other considerations, including volatile organic compound (VOC) limits, storage and distribution management, operation and maintenance, and long-term monitoring and reporting requirements, are also discussed.

M.2 Pathogen Reduction Targets

Risk-based pathogen reduction targets have been developed based on analysis of potential human health risks associated with exposure to microbial hazards and are based on a "10⁻⁴ Per Person Per Year Benchmark." This means that the agreed-upon "tolerable" risk level is a probability of infection of 1 in 10,000 people per year. Pathogen reduction targets are expressed in terms of the 95th percentile log₁₀ reduction target (LRT). A log reduction is a mathematical term used to describe the number of living microbes relatively eliminated by disinfection or filtration. A log₁₀ reduction reduces the quantity of living microbes to one-tenth it's previous amount. Therefore, a 1-log₁₀ reduction equates to 90% removal, 2-log₁₀ reduction to 99% removal, 3-log₁₀ reduction to 99.9% removal, and so on. The LRT for the specified pathogen group (i.e. viruses, bacteria, or protozoa) describes the agreed level of risk to individuals. LRTs were developed for each source water and end use addressed in this appendix based on attaining the "tolerable" infection risk. If a system can maintain this level of treatment performance at all times, then the predicted probability of infection across the population will be less than the 1 in 10,000 benchmark for each pathogen 95% of the time.

The LRT for each non-potable use scenario is presented in Table M.1 for healthy adults (values are based on the DNWS Report, although additional uses have been added). A rainwater harvesting system must maintain this level of treatment performance at all times for all three pathogen types: viruses, protozoa, and bacteria. When both general runoff and roof runoff (as

<u>defined below Table M.1)</u> are combined, the reduction targets for general runoff shall apply. Similarly, when multiple uses are proposed, the highest reduction targets shall apply.

 $\begin{array}{ll} \textbf{Table M.1 } \ \underline{\textbf{Likelihood Exposure will Occur}} \underline{\textbf{Ninety-Fifth Percentile Log}_{\underline{10}}} \ \underline{\textbf{Pathogen Reduction}} \\ \underline{\textbf{Targets (LRT) to Meet 10}^4 (infection) \ ppy \ Benchmarks for Healthy \ \underline{\textbf{Adults}}^a} \\ \end{array}$

Descriptor Water	Description of LikelihoodLog ₁₀ , Reduction Targets for 10 ⁻⁴ Per Person Per Year			
Source and Use	<u>Benchmarks</u>			
Unlikely	Exposure could occur only in unusual circumstances Enteric Viruses	Parasitic Protozoa	Enteric Bacteria	
Possible General Runo		Exposure might	occur	
<u>LikelyCooling</u> Towers ^b	Exposure will probably occur_	_	=	
Irrigation	<u>5.0</u>	<u>4.5</u>	4.0	
<u>Indoor Use</u>	<u>5.5</u>	<u>5.5</u>	5.0	
Roof Runoff ^c				
Cooling Towers ^b	=	=		
<u>Irrigation</u>	<u>N/A</u>	Limited data available	3.5	
<u>Indoor Use</u>	<u>N/A</u>	Limited data available	3.5	

a. For the purposes of this appendix, general runoff means precipitation runoff from rain or snowmelt events that flows over land and/or impervious surfaces (e.g., streets, sidewalks, and parking lots). It also includes runoff from roofs or parking garages with frequent public access.

The non-potable uses and LRTs included in Table M.1 assume that human contact with the harvested water will be infrequent and ingestion unintentional. Uses where frequent human contact with the harvested water is intended, like fountains or splash pads, will be considered similar to swimming pools and must meet the standards defined by Section 6408 and 6409 in Chapter 64 of Title 22 of the District of Columbia Municipal Regulations. The remaining sections in this appendix only cover non-potable uses with infrequent human contact. Treatment and monitoring procedures for frequent contact uses will be reviewed on a case-by-case basis.

M.3 Treatment Process

A well-established and accepted concept in modern drinking water and water reuse practices is to attribute the \log_{10} reduction of pathogen groups to specific technologies that are operated within defined limits, coupled with appropriate control points to demonstrate the proper performance of the technology. This is referred to as the \log_{10} reduction value (LRV) and can be compared directly to the LRTs described in Section M.2 above. Various treatment processes and treatment trains can be used to obtain the LRT for each pathogen for a given combination of source water

Merged Cells	
Inserted Cells	
Inserted Cells	
Deleted Cells	
Inserted Cells	
Inserted Cells	

b. The pathogen risks associated with cooling towers and other uses in which there is no public exposure can be controlled by post-treatment management practices rather than initial treatment. There are greater microbial risks from this use due to uncontrolled growth of water-based pathogens (e.g., Legionella pneumophila, Pseudomonas aeruginosa, and non-tuberculous mycobacteria) that may proliferate during prolonged periods of storage.

Management practices are discussed in Section M.5, "Storage and Distribution Management Practices."

c. Roof runoff means precipitation from a rain or snowmelt even that is collected directly from a roof surface not

c. Roof runoff means precipitation from a rain or snownelt event that is collected directly from a roof surface not subject to frequent public access.

and end use. Sections M.3.1 and M.3.2 discuss a range of treatment processes and provide LRVs for each process.

M.3.1 Filtration

The removal of particulate matter, including pathogens, by size exclusion can serve as a barrier to pathogens in water. Filtration is especially important because pathogens can be shielded by or embedded in particulate matter, reducing the effectiveness of subsequent disinfection processes. Typical values for pathogen group \log_{10} reduction by filtration processes are summarized in Table M.2.

Table M.2 Magnitude of Health Risk Typical Values for Pathogen Reduction Using Filtration Processes

Descriptor Barrier	RiskTypical Log ₁₀ Reduction Values			
	<u>Virus</u>	<u>Protozoa</u>	<u>Bacteria</u>	
Slow sand filter	2	4	2	
Dual media filter with coagulant	1	<u>2</u>	1	
Cartridge/bag filter (5-10 microns)	0	0	0	
Insignificant Low or Acceptable LevelsCartridge/bag filter (3 microns or less)		3	0	
MinorCartridge/bag filter (1 micron)	Minor 0	<u>4</u>	0	
Severe-Diatomaceous earth	Major 1	<u>4</u>	2	
<u>Microfilter</u>	1	<u>6</u>	<u>6</u>	
<u>Ultrafilter or Nanofilter</u>	<u>6</u>	<u>6</u>	<u>6</u>	
Reverse osmosis	<u>6</u>	<u>6</u>	<u>6</u>	

M.3.2 Disinfection

Processes for pathogen inactivation include disinfection by chlorine, peracetic acid, ozone, ultraviolet (UV) radiation, advanced oxidation, and pasteurization. Particles in water can inhibit effective disinfection through shading (in the case of UV) and shielding embedded pathogens. Larger particles may require more time for a disinfecting agent to penetrate the particle and reach an embedded pathogen; therefore, for any disinfectant to be effective, particles larger than 10 microns must be removed.

Typical values for the inactivation of pathogens for disinfection processes in filtered water are given in Tables M.3 through M.5. These values serve as a guide to the relative effectiveness of different disinfection technologies and are not for a specific microorganism.

Deleted Cells
Inserted Cells
Inserted Cells

Merged Cells

Inserted Cells

Table M.3 Characterizing Threat to Public Health

<u>Typical Values for Various Levels of the Inactivation of Enteric Virus in Filtered Secondary</u> Effluent with Selected Disinfection Processes

	Magnitude						
Likelihood of ExposureDisinfectant	of Public Health Threat Unit	Dose for Corresponding Log ₁₀ Reduction Value					
Exposure <u>Dismeetune</u>	Insignificant	Minor1 Log ₁₀	Severe-2 Log ₁₀	$3 \operatorname{Log}_{10}$	4 Log ₁₀		
UnlikelyFree chlorine	Low mg•min/L	Low _	Low 1.5–1.8	2.2-2.6	<u>3.0-3.5</u>		
Possible Chloramine a	Low mg•min/L	Moderate _	High370-400	550-600	750-800		
LikelyPeracetic acid	Low mg•min/L	Moderate NA	<u>HighNA</u>	<u>NA</u>	<u>NA</u>		
<u>Ozone</u>	mg•min/L	=	0.25-0.30	0.35-0.45	0.50-0.60		
<u>Ultraviolet radiation</u>	mJ/cm ²	<u>50–60</u>	90-110	140-150	180-200		
Advanced oxidation	mJ/cm ²	10-20	50-60	70-80	110-130		
Pasteurization (60°C)	second	140	280	420	<u>560</u>		

M.4 Applying the Tiered Risk Assessment-Management Approach

DDOE's intent in developing the TRAM approach is to expedite the permitting process and keep investigative costs to a minimum. It is based on the concept that the complexity of investigations should match the complexity of the site and conditions of exposure. DDOE will only require that sufficient information be presented to satisfy the requirement that public health is protected. The level of effort necessary to verify this threshold will depend on site specific characteristics, which will vary from site to site.

The TRAM approach is presented in a risk assessment management decision making framework. Although there are a total of nine steps in this process, proposed plans need only present sufficient analyses to demonstrate public health will be protected. For many sites, the entire nine-step process will not be needed to demonstrate exposure to treated or untreated stormwater will pose low risks. A determination regarding the appropriate course of action can often be made in the first four steps. DDOE believes that the most cost effective approach for project teams is to follow the TRAM, so the complexity, level of effort, and costs of investigation will be a direct function of the site specific conditions instead of a one size fits all preseribed approach.

Figure 1 presents the TRAM decision making framework. There are two important features of this framework that make it cost effective. First, investigative costs (including sampling and analysis) can be minimal for sites where there will be no human exposures to stormwater.

Merged Cells
Inserted Cells
Inserted Cells
Inserted Cells


Appendix M Rainwater Harvesting Treatment and Management Requirements

Second, there are several exit points in the nine-step process at which investigations can be terminated and the proposed plan submitted to DDOE. The overall goal of the TRAM approach is to identify priorities as early as possible in the process to ensure public health will be protected. This requires the following:

- Identifying and documenting contaminant hazards and hazardous events;
- Estimating the likelihood that a hazardous event will occur;
- Estimating the consequences of the hazardous event occurring; and
- Characterizing the overall risk by combining the hazards and hazardous events with their likelihood and consequence.

Depending on the complexity of the site, these requirements may necessitate the following assessments:

- Initial screening level risk assessment;
- An assessment of the maximum risk (in the absence of preventive measures); and
- An assessment of the residual risk (in the presence of preventive measures).



Figurea. Due to interferences with chloro-organic compounds, when chloramine is used as a disinfectant, log₁₀ reductions can only be used if the actual dosage of monochloramine is known, not just the amount of combined chlorine.

b. mg•min/L = Milligram-minutes per liter c. mJ/cm² = Millijoules per square centimeter

Table M.1 TRAM decision-making framework.

Step 8: Conduct Site Investigation.

The goal of the initial site investigation is to identify potential contaminants that could enter the stormwater catchment and to characterize potential human exposures. This information will be used as the baseline investigation for subsequent steps in the TRAM approach. At minimum, the proposed plan must provide a general description of the site and any potential chemical or microbial contamination that may be present. Information should include:

- Site location and map showing all the properties within the proposed stormwater catchment system, in the simplest scenario this identification is the proposed roof area
- Zoning classification of all properties contributing to the stormwater catchment
- Total acreage of the stormwater catchment for the stormwater project

<u>4 Typical Values for Various Levels of the Inactivation of Parasitic Protozoa in Filtered Secondary</u> Effluent with Selected Disinfection Processes

- Description of site property and surrounding areas based on available data and information. In the simplest scenario this is limited to an identification of the proposed roof materials and roof characteristics
- Description of any portion of the site regulated under the Resource Conservation and Recovery Act (RCRA), Superfund Program, or any other environmental investigation by the District of Columbia or the Environmental Protection Agency
- The current status of any orgoing or unresolved Consent Orders, Compliance Agreements, Notices of Violation (NOV), or other activities
- Schematic showing the location of sewer manholes
- Location of any obvious chemical spill residue (e.g., discolored soil, die back of vegetation, etc.)
- Location of all aboveground or underground storage tanks
- Planned future uses of the site

If the site is zoned industrial, and the proposed catchment area contains surfaces other than the a proposed roof area, it will be necessary to conduct a more robust baseline investigation than for other types of properties to determine if chemical or microbial contamination is present. For sites

zoned industrial, all potential chemical contaminants that were used, stored, or released on the property must be identified.

On sites where the catchment area includes surfaces beyond a proposed roof the receiving environment for all stormwater in the catchment must be characterized. All sources of variation due to seasonal and diurnal effects, as well as major rain events, must be characterized. This baseline information is very important because it provides a point of reference for evaluating untreated stormwater. It will also be important to determine whether validation and/or verification sampling or monitoring is warranted.

Stormwater contaminants detected in catchment can be due to both roof water runoff and contamination of soil within the area stormwater will be collected. Therefore, when existing roof areas and other existing surfaces will contribute to the proposed rainwater harvest system the existing roof systems must be inspected, and land use must be characterized as part of the proposal process.

Some of the important roof characteristics include the following:

- Whether vehicular traffic is allowed (i.e., parking structures)
- Whether there are overflow or bleed off pipes from roof mounted appliances, such as air conditioning units, hot water services, and solar heaters that will contribute to the collection area
- Whether any flues or smoke stacks from heaters, boilers, or furnaces could have contaminated roof surfaces
- Whether the roof is covered with lead flashing or exposed areas painted with lead based paints
- Whether the roof is covered with a vegetated roof system

A short narrative of how the property has historically been used must also be provided if the proposed collection areas include existing land surfaces and information is available. This land use description is very important because some land uses have been shown to be associated with high contaminant levels. Land uses of particular interest include the following:

- Industrial land uses can result in either widespread or point sources of contamination due to organic compounds and/or inorganic metals
- Runoff from major roads and freeways with high traffic volumes can contain relatively high levels of hydrocarbons and metals (particularly, lead)
- Residential areas that experience frequent sewer overflows

Plans must describe how the stormwater will be collected, stored, and used. This will provide important exposure information necessary to estimate potential threats to public health. At minimum, the plan must provide:

- How stormwater will be collected
- The total amount of stormwater that will be collected from each source (roof water, parking lots, etc.)

- How stormwater will be stored (aboveground eistern, belowground storage tank, etc.)
- Description of the end use(s) of stormwater (municipal irrigation, spray fountain, pool, etc.)
- List of all types of individuals who could potentially be exposed to stormwater under the intended use(s) (e.g., landscapers, maintenance workers, children, joggers, etc.)
- Age groups for all types of exposed individuals (e.g., children, adults, elderly)
- Estimated time (e.g., hours, days, years) each type of individual could be exposed to stormwater under its intended use
- List of activities the exposed individuals will be engage in on site (recreational, sports, gardening, etc.)
- Type and routes of exposures for all exposed individuals (ingestion of sprays during irrigation, ingestion during car wash, ingestion of fruit and vegetables irrigated with stormwater, etc.)
- List of potential exposures associated with unintended stormwater uses (system malfunction, cross plumbing, etc.)
- List of sensitive populations that may be exposed (children, infirm, invalid, etc.)

The above information will form the basis for determining the likelihood of exposure in the next step and will also be used to characterize specific exposure conditions and routes of exposure in subsequent steps.

Step 9: Determine Likelihood of Exposure.

One of the basic tenets of risk assessment states that, "Where there is no exposure, there is no risk." This truism is applicable even for sites where chemical or microbial contamination is elevated. Accordingly, the first step in the investigation for all stormwater projects is to determine the likelihood of exposure. As was indicated in Table M.1, exposures can be characterized as unlikely, possible, or likely based on reasonable assumption. That is, DDOE's threshold will not be based on the possibility that exposures could occur, but rather on whether it is plausible exposures will occur. Information presented in Step 1 should form the basis for this determination. Making a determination that exposures are unlikely in this step is very important because no stormwater decontamination or disinfection will be required for those projects where exposure is unlikely. Untreated stormwater can be used as it was collected in these cases.

To make a determination that exposures are "unlikely" requires an evaluation of both intended and unintended exposures. An example of unlikely exposure conditions would be a closed system with no intended exposures and less than approximately 50 unintended exposure events per year involving less than 1 milliliter exposure per isolated event. System malfunctions (breaches in the system, pipe bursts per year, tank leakage, cross connections, etc.) are the most likely types of unintended exposures. Likelihood of exposure should be based on the specific end use and the types of individuals who will visit the site.

DECISION POINT 1: Are Exposures Likely?

If the information submitted to DDOE is sufficient to support a determination that exposures are "unlikely," no further study or analysis is required. This is the first exit point in the TRAM

process (as was indicated in Figure 1). On the other hand, if exposure is "likely" or "possible," the investigation must proceed to the next step.

Step 10: Determine Concentration of Contaminants in Stormwater.

When human exposures are likely or possible, the maximum risk must be evaluated based on the concentration of both chemicals and pathogenic organisms. The maximum risk represents the threat to public health associated with potential exposures to untreated stormwater.

All chemicals identified and qualitatively evaluated in Step 1 should be targets in the sampling plan. If the catchment area in which stormwater will be collected is zoned industrial, it is possible that those chemicals identified in the baseline investigation may have contaminated roof water, surface soil, or pavement. For areas considered open space or recreational properties, sampling for chemical contamination can be limited to pesticides.

Table M.4 lists chemicals typically associated with industrial operations, as well as common pesticides. Pathogenic microbes may also be present in collected stormwater, and Table 4 lists the three primary categories of microbial threats to human health, which are bacteria, viruses, and protozoa. Stormwater samples collected in this step should represent the conditions that will occur during a major rain event. Note, however, that the concentrations of chemicals and microbes will be lower after a major rain event compared with a minor rain event due to the dilution effect. Planning for the stormwater sampling event should take into account roof, soil, and solid surface contributions to the stormwater catchment system. All samples submitted for laboratory testing should represent, as closely as possible, the conditions in which untreated stormwater will be stored and used at the site. For example, if collected stormwater will be stored in a cistern shielded from light for several days before it is used, the samples sent for laboratory analysis must be stored under the same conditions (i.e., some temperature under dark conditions to assess growth of microbial pathogens). After replicating site storage conditions, all samples must be sent to an EPA approved laboratory for analysis of all chemicals of interest identified in the baseline investigation.

The sampling locations and number of samples collected at this stage should be based on the size of the catchment area and sources of potential contamination. For example, a non industrial site totaling 2 to 3 acres with only one storage cistern could be adequately represented by taking a minimum of three samples at timed intervals over a holding time of 4 to 5 days. At the other end of the spectrum, a 10 acre site located in an industrial area with several storage cisterns spread out over the site may require sampling from each cistern after moderate and major storm events. Regardless of the type of site, DDOE encourages implementation of the most cost effect approach as the goal is not to fully characterize the site for potential contamination, but rather to determine if the contaminants in collected stormwater pose a health threat.

Sampling results generated in this step should be evaluated in the risk based screening comparison described in the next step.

Table M.4 Chemicals of Interest for Baseline Investigations

Inorganic Metals Disinfectant	Unit Dose for Corresponding Log ₁₀ Reduction				
Aluminum	Chromium	Selenium 1 Log ₁₀	2 Log ₁₀	$3 \operatorname{Log}_{10}$	4 Log ₁₀
Arsenie Free chlorine	Iron mg•min/L	Silver2,000-2,600	<u>NA</u>	<u>NA</u>	NA
Barium Chloramine ^a	Manganesemg•min/L	Tin NA	NA	<u>NA</u>	<u>NA</u>
BerylliumPeracetic acid	Mercurymg•min/L	ZincNA	<u>NA</u>	<u>NA</u>	<u>NA</u>
Bromate Ozone	Molybdenummg•min/L	4.0-4.5	8.0-8.5	12-13	<u>NA</u>
Cadmium Ultraviolet radiation	NickelmJ/cm ²	<u>2–3</u>	<u>5–6</u>	11-12	<u>20–25</u>
Organie Compounds Advanced oxidation	mJ/cm ²	2/3	<u>5–6</u>	<u>10–12</u>	<u>20–25</u>
AcrylamidePasteurization (60°C)	second Hexachlorobutadiene	30 Trichloroethylene	<u>60</u>	<u>90</u>	120
Renzene	Polygromatic hydrocar	Trichloroothana			

(60°C)		F			1			
Benzene		Polyaromatic hydrocarbons Trichloroethane						
Carbon tetrachloride		Polybrominated biphenyls	Trichloroethene					
Chlorobenzene		Polychlorinated biphenyls	Vinyl chl	oride mono	mer			
Benzo[a]pyrene		Tetrachloroethene	Xylene					
Epichlorohydrin		Toluene						
Ethylbenzene		Trichlorobenzenes						
	Pesticides							
Aldicarb		Chlordane						
Aldrin	Diazinon							
Atrazine		Heptachlor						
Pathogenic Microbes								
Bacterium: E. coli								
	Protozoan: Cryptosporidium parvum							

-	Merged Cells
۲	Inserted Cells
Y	Inserted Cells
Y	Merged Cells
1	Inserted Cells
()	Inserted Cells
1	Inserted Cells
	Triscited octis

Inserted Cells
Inserted Cells

Step 11: Compare Stormwater Concentrationsa. Due to interferences with Risk-Based Levels.

To determine whether exposure to untreated stormwaterchloro-organic compounds, when chloramine is a public health threat, maximum risk must be assessed. Determining whether stormwater exposures will pose a threat does not require that a formal risk assessment be conducted. Risk assessmentsused as a disinfectant, \log_{10} reductions can be costly and time consuming to prepare. Instead, it will only be necessary to apply risk based screening, and DDOE has even simplified this step. Screening involves a simple comparisonused if the actual dosage of the chemical and/or microbial concentrations detected in untreated stormwater (inmonochloramine is known, not just the previous step) with acceptable risk based screening levels. Risk based concentrations represent safe exposure levels for chemical or microbial contaminants. They are derived based on the frequency of exposure, amount ingested, and the inherent toxicity of each contaminant of combined chlorine.

Table M.5 lists different types of stormwater use that DDOE anticipates in the District. For each stormwater use, there could be several types of exposure conditions that vary in exposure intensity and duration. For example, individuals engaged in high intensity sports (e.g., baseball, football, soccer, etc.) would have greater exposures to contaminants in stormwater used for irrigation at a municipal park than would someone walking a pet.

<u>b.</u> mg•min/L = Milligram-minutes per liter. <u>c.</u> mJ/cm² = Millijoules per square centimeter

Table M.5 Types of Stormwater Use and Routes of Exposure

Typical Values for Various Levels of the Inactivation of Enteric Bacteria in Filtered Secondary Effluent with Selected Disinfection Processes

Stormwater Use	Route of Exposure	General Description of
		Exposure Conditions
	In gastion of agreed array	Typical watering every other day during
	Ingestion of aerosol spray	half year
Home lawn or garden	Ingestion after contact with plants/grass	Routine indirect ingestion via contact with
spray irrigation	ingestion after contact with plants/grass	plants, lawns, etc.
	Accidental ingestion of stormwater	Infrequent inadvertent ingestion.
	Ingestion via casual contact (picnic,	Infrequent contact with wet grass, picnic
	walking pet)	tables
	Ingestion via low intensity sports (golf,	Typical contact with irrigated
	Frisbee)	plants/grasses
Open space or	Ingestion via high intensity sports	Frequent contact with irrigated sports field
municipal park drip or	(baseball, soccer)	Trequent contact with hingated sports field
spray irrigation	Ingestion by child on playground	Frequent contact with wet surfaces and
	ingestion by clinic on playground	frequent hand to mouth activity
	Public fountain with spray element	Indirect and infrequent ingestion of spray
	Dublic fountain with standing need	Infrequent ingestion of pool water during
	Public fountain with standing pool	hot days
Home garden drip or	T C'	Typical ingestion of small home garden
	Ingestion of irrigated vegetables and fruit	seasonal produce
Home garden drip or spray irrigation	Ingestion of irrigated vegetables and fruit	

Stormwater Use	Route	of Exposure			General Descrip	
Commercial farm produce drip or spray irrigation	Ingestion of irrigat	ed vegetables and	l fruit	Typical produce	ingestion of region	nal commercial
Home car wash spray	Ingestion of	Once a week ca	ı r wash f	or 6 mont	hs <mark>Dose for Corre</mark>	sponding Log ₁₀
application	water and spray			Reducti	on Value	
Commercial car wash spray	Ingestion of water	and spray		Car wasl	h operator exposed	l 5 days per week
Toilet	Ingestion of aerosol spray	1 Log ₁₀	2 Log ₁₀		Flushing 3 times per day3 Log ₁₀	4 Log ₁₀
Washing machine useFree chlorine	Ingestion of spraysmg•min/L	0.4-0.6	0.8	-1.2	Ingestion from 1 load per day1.2–1.8	1.6-2.4
Fire fightingChloramine ^a	Ingestion of water and spraymg•min/L	Firefighter assumed exposed 50 events per year50-70	<u>95-</u>	<u>-150</u>	140–220	200–300
Peracetic acid	mg•min/L	<u>10–25</u>	<u>40</u>	<u>–60</u>	<u>75–125</u>	<u>150–200</u>
<u>Ozone</u>	mg•min/L	<u>0.005–0.01</u> <u>0.01</u>		<u>-0.02</u>	0.02-0.03	0.03-0.04
<u>Ultraviolet radiation</u>	mJ/cm ²	<u>10–15</u> <u>20</u>		<u>-30</u>	30-45	<u>40–60</u>
Advanced oxidation	mJ/cm ²	4-6		-8	<u>8–10</u>	10-12
Pasteurization (60°C)	second	<u>50</u>	1	00	<u>150</u>	200

Table M.6 lists the exposure assumptions that represent different types of stormwater use and the corresponding typical exposure conditions for each use. Project planners should identify the appropriate exposure conditions in this table that most closely match site specific conditions. Stormwater use and the site specific exposure conditions correspond to specific assumptions regarding how individuals will come in contact with untreated stormwater. The two most important criteria are the number of days contact is expected to occur and the volume of stormwater that will be ingested on each of those days.

For example, the first row indicates that an individual watering a lawn or garden is assumed to do so every other day for 6 months and will ingest 0.1 mL of stormwater each time the lawn is watered. While DDOE anticipates that these exposure assumptions will represent the majority of sites, a small number of reuse projects may be unique, and DDOE should be contacted to discuss unique sites. For these projects, planners should either contact DDOE directly to discuss alternative exposure assumptions or select an exposure scenario that is intentionally conservative. Although this may be an overly protective approach, such a comparison would be sufficient proof for DDOE that public health will be protected if the site passed the risk based screen test.

a. Due to interferences with chloro-organic compounds, when chloramine is used as a disinfectant, log₁₀ reductions can only be used if the actual dosage of monochloramine is known, not just the amount of combined chlorine.
 b. mg•min/L = Milligram-minutes per liter

Merged Cells

Merged Cells

Merged Cells

Inserted Cells

Merged Cells

Inserted Cells

Merged Cells

Inserted Cells

Inserted Cells

c. mJ/cm² = Millijoules per square centimeter

M.3.3 Treatment Trains

Most non-potable water systems use a number of unit processes in series to accomplish treatment, known commonly as the "multiple barrier" approach. Multiple barriers are used to improve the reliability of a treatment approach through process redundancy, robustness, and resiliency. When multiple treatment barriers are used to achieve the pathogen LRT, the contribution from each barrier is cumulative.

In addition to these treatment barriers, operational and management barriers are used to ensure that systems are in place to respond to non-routine operation. Treatment barriers can be monitored using sensors and instrumentation for continuous process monitoring. The system should take the treatment train offline automatically in the event of process malfunction.

If each barrier in a treatment train is independent, the LRVs for each process in the treatment train can be added together to obtain the overall treatment train LRV.

M.4 Volatile Organic Compounds

For rainwater harvesting systems that use general runoff from vehicular access areas as a source and will have some level of public exposure risk, the treated water must be tested for the presence of volatile organic compounds (VOCs); however, this does not apply when the water will be used for cooling towers or other "no public exposure" uses. The test must be performed by the system operator prior to commissioning of the system (see Section M.6, "Commissioning") and prior to subsequent DOEE maintenance inspections (see Section M.7, "Operational Monitoring and Reporting"). VOC levels must be below the maximums indicated in Table M.6. If any VOC levels exceed these himts, the rainwater harvesting system must not be utilized until the problem is satisfactorily addressed, and a successful test has been performed. VOC limit exceedances may be addressed through source controls or through provision of additional treatment devices.

Table M.6 Exposure Assumptions Based on Stormwater Use and Exposure Conditions Volatile Organic Compound Maximum Concentrations

Stormwater Use VOC	Rout	Route of Exposure Maximum Concentration Exposure Assum (mg/L) ^a			Assumptions		
					ne Ingested (mL)	Days (per year)	
Home lawn or garden	Ingestion of a	erosol spray				90	\mathbb{L}
spray irrigation Benzene				0.1			
Carbon Tetrachloride					0.5]
Ingestion after cor plants/grass	ntact with	<u>11,2-</u> <u>Dichlorobenzene</u>			90 <u>5.4</u>		4
1,4-Dichlorobenzene					5.4		Īi
Accidental ingestion of	100	<u>+1,1</u> <u>Dichloroethane</u>			14.4		*

Split Cells

Deleted Cells

Split Cells

Split Cells

Deleted Cells

Deleted Cells

Deleted Cells

Deleted Cells

Deleted Cells

Deleted Cells

Deleted Cells

Deleted Cells

Inserted Cells

	stormwater						1	
Open	space, municipal	Ingestion with	casual contact			32	-	Deleted Cells
park c	drip, or spray	picnic, walking	; pet		0.1			Split Cells
	tion1,2				0.1			Copin cens
Dichle	oroethane Ingestion with low	intoncity	1 1.1-				-	
-	sports golf, Frisbe		±1,1- Dichloroethylene		<u> 320.1</u>		<	Deleted Cells
	Ingestion high inte		2.5cis-1,2-		1.520.1			Deleted Cells
	baseball, soccer	J 1	Dichloroethylene		16 28.4			
trans-		Ingestion child	playground		28.4	130		Split Cells
	oroethylene							Deleted Cells
Dichle	<u>oromethane</u>				3.1			Deleted Cells
1,2-D	<u>ichloropropane</u>				12.6			
1,3-D	oichloropropene e				0.2			
<u>Ethyl</u> l	<u>benzene</u>				<u>15.6</u>			
Methy	yl-tert-butyl ether				5.2	5		
Mono	ochlorobenzene				1.7		1	
Styrer					7.7	*		
1.1.2.		Public fountain	with spray element			130	-	Split Cells
	chloroethane	a done rountain	with spray ciement		0.13	130		Deleted Cells
	chloroethylene				6.1			Deleted Cells
Tolue							-	Deleted Cells
		D1-1: - 6			6.8	130	-	
1,2,4-	-Trichlorobenzene	Fuone tountain	with standing pool	$\langle \mathcal{A} \mathcal{X} \rangle$	1.4	•	<	Deleted Cells
				Ingestion		50		Deleted Cells
Home	e garden drip or spra	ay irrigation 1,1,	1-Trichloroethane	irrigated vegetables				Split Cells
				fruit <u>68.2</u>	2		Ì	Deleted Cells
~				Ingestion		140		
	nercial farm produc	e drip or spray is	rrigation-1,1,2-	irrigated vegetables				
Trichi	<u>loroethane</u>			fruit 1.6				
			\cup	Ingestion		24		
Trich!	loroethylene Home	ear wash spray a	pplication	water and				
				spray4.8		250	-	
Comr	mercial car wash spr	-av Trichlorofluo	romethane	Ingestion water and		230		
Comm	meretar ear wash spi	THEMOTORIUS	romemane	spray201.				
				Ingestion	of 0.01	1100		
Toilet	<u>1,1,2-Trichloro-1,2</u>	,2-Trifluoroetha	<u>ne</u>	aerosol				
Wash	ing machine	Ingestion of sp	roxic.	spray 272.		365	_	Deleted Cells
	inyl Chloride	ingestion of sp.	iays		0.011	303		Deleted Cells
				Ingestion	of 20	50		Deleted Cells
Fire fi	ighting Xylenes			water and				
				spray 15.0			4	
C ****	ming pool	Ingestion of wa	ter		200	90		

It should be stressed that although EPA and several state regulatory agencies have developed RSLs (EPA RSLs available at http://www.epa.gov/reg3hwmd/risk/human/rb-concentration_table/equations.htm), these should not be used for stormwater projects. These RSLs apply only to potable drinking water and, because they are overly conservative, many stormwater projects would fail the screen. Stormwater collected in the District must never intentionally or unintentionally be used as a potable drinking water source. Therefore, EPA's RSLs for drinking water, which are based on the assumption that a child and an adult will drink 1 and 2 liters of water per day, respectively, are not applicable to stormwater reuse projects. Furthermore, the drinking water RSL assumes an individual will drink the water 350 days per year for 30 years. This corresponds to 350 to 700 liters of water consumed per year, which is 500 to 1,000 times the amount of stormwater that will be ingested for most projects (as shown in Table M.6). Clearly, drinking water exposure assumptions do not represent typical stormwater reuse exposures and should not be used to screen for the maximum risk.

DDOE has made the risk based screening step easy to use by evaluating the exposure conditions presented in Table M.6, ranking the intensity of each type of exposure and grouping exposures with similar intensity into one of four categories: severe, high, medium, or low. The exposure scenarios (listed in Table M.6) for each of these categories are presented in Table M.7.

Tablea. Values determined by the San Francisco Department of Public Health based on U.S. Occupational Safety and Health Administration Permissible Exposure Limits for 8-hour inhalation exposures to selected VOCs.

M.5 Storage and Distribution Management Practices

To achieve the desired objectives of public health protection, treated water must be properly stored and distributed to prevent compromising the quality of water after treatment. For example, opportunistic pathogens like Legionella could grow in the distribution system, sewage could contaminate treated water, or lead and copper (which are toxic) could leach from piping. Producing adequate quality non-potable water that meets all the pathogen control criteria set forth in this appendix is the first step in ensuring proper public health protection. The final step in quality control is to manage properly 1) storage and distribution systems and 2) the uses of non-potable water.

In rainwater harvesting systems, neither significant or routine ingestion nor direct contact with the treated water product is typically anticipated due to limited exposures to non-potable water. Nevertheless, the occurrence of aerosol inhalation and indirect contact requires the careful management of DNWS storage and distribution systems to control exposures to non-tuberculous mycobacterial and Legionella pathogens. For example, even clean drinking water may allow biofilm growth of Legionella (aerosol pathogen risk) if the water temperature is between 25°C and 45°C and stagnates, resulting in the presence of minimal residual chlorine.

A number of approaches are available to control microbial regrowth in distribution systems, each with varying benefits and drawbacks that depend on the characteristics and use of the system.

Below are some recommended approaches for controlling microbial growth in distribution systems:

- Producing non-potable water low in carbonaceous material and nutrient content. The primary energy source for pathogen regrowth is organic carbon measured as assimilable organic carbon, biodegradable dissolved organic carbon, total organic carbon, and other essential nutrients, including nitrogen (N), phosphorous (P), and iron (Fe); therefore, the primary means to reduce the regrowth potential of pathogens is to provide highly treated water. Reducing the potential for regrowth is more important in large-scale buildings or neighborhood-scale projects where there will be more residence time (creating more opportunities for regrowth) in distribution systems that supply non-potable water.
- Producing highly disinfected non-potable water. Low concentrations of microbes resulting from filtration and advanced means of disinfection have a reduced potential for regrowth if organic carbon levels are low. Otherwise, there may be a need for a residual disinfectant to manage growth in larger community systems that produce aerosols. Post-treatment disinfection with UV radiation is a recommended means of disinfection that does not increase levels of assimilable organic carbon or biodegradable dissolved organic carbon.
- Using non-reactive, biologically stable materials of construction. Avoid the use of corrosive materials or organic materials that tend to protect microorganisms from disinfection and enhance the regrowth environment by the adsorption of organic compounds.
- Maintaining a residual disinfectant. Different disinfectants offer advantages and disadvantages to overall water quality and system management. In general, a higher disinfectant residual provides lower regrowth. Many design and operation considerations are available for each specific system. It is recommended that a free shlorine residual of 0.2 milligrams per liter (mg/L) or monochloramine residual of 2 to 3 mg/L be maintained at or near the point of use to control microbial growth. Chloramine provides a better residual duration as compared to chlorine. Various combinations of UV, chlorine, chloramine, ozone, and hydrogen peroxide are beneficial for specific disinfection goals. Periodic shock treatments with disinfectants and continuous disinfection looping of reservoirs help reduce the potential for regrowth and manage issues with biofilms. Stagnation resulting from dead zones or prolonged periods of zero-flow or low flow that create long residence times and allow disinfectants to dissipate and sediments to deposit result in improved conditions for regrowth and should be avoided.
- Cleaning storage tanks. The required frequency of storage tank cleaning varies depending upon the quality of water stored, detention time in storage, temperature of the water, and nature of the tank. Tanks that are open to the atmosphere require more frequent cleaning.
- Flushing the distribution system. The required frequency of distribution system flushing varies depending upon the quality of water transmitted, detention time in the distribution system, temperature of the water, and nature of the distribution system components. Periodic flushing is a good means of both removing sediments and scouring pipe walls. System design must include means for easily flushing pipes as part of routine maintenance.
- Controlling temperature. Avoid the storage and distribution of non-potable water within 20°C to 45°C to reduce the potential for pathogen regrowth. Otherwise, consider a disinfection residual or point-of-use system, particularly if aerosols are generated.

The rainwater harvesting system designer and Person Responsible for Maintenance each should review published guidelines for the management of Legionella in distribution systems and

implement as appropriate for each specific system. In particular, ANSI/ASHRAE Standard 188-2015 Legionellosis: Risk Management for Building Water Systems (2015) provides guidance on stormwater best management practices (BMPs) for both potable and non-potable water systems. It addresses management program responsibilities, system design, risk analysis, control mechanisms, monitoring, confirmation, and documentation. Although the ASHRAE Standard targets legionellosis, its rationales and approaches are applicable to all pathogens and health risks identified in this appendix.

M.6 Commissioning

In the process of initializing a rainwater harvesting system, the system must be evaluated for leaks in the storage unit and the performance of the components of the treatment and distribution system. A commissioning report of the evaluation is required at the initial startup of the system and anytime the system is brought back online after cleaning, flushing, or a hiatus of use (e.g., winter shutdown).

M.7 Operational Monitoring and Reporting

The Person Responsible for Maintenance, as identified in the Stormwater Management Plan (SWMP), must maintain the rainwater harvesting system in good working condition and assure adequate treatment of the harvested rainwater. All systems, with the exception of those installed in single-family homes, shall include continuous monitoring systems that are capable of determining if the rainwater harvesting system is operating within the design specification, and if all system components of the rainwater harvesting system are functional.

Data logs from continuous monitoring systems must be kept on file and produced upon request from DOEE. In addition, annual reports must be generated that identify the following:

- Significant maintenance activities;
- Treatment modifications;
- Outages and malfunctions (including reasons and durations); and
- Steps taken to mitigate or eliminate recurrence of outages and malfunctions.

If there is a change of personnel—Person Responsible for Maintenance—it is the responsibility, within 15 business days, of the owner of the rainwater harvesting system or her/his agent to update the DOEE Stormwater Database with the name and contact information of the new personnel.

An operation and maintenance manual that includes a schematic drawing of the system, standard operating procedures for the system, and maintenance schedule(s), as well as commissioning reports, field verification reports, and annual reports must be on site and produced upon request from DOEE.

M.8 Field Verification

Field verification is a performance confirmation of a rainwater harvesting system. It can be accomplished by physically observing the collection, storage, and distribution system, and the treatment process components. It can also be conducted using challenge testing, including surrogate microorganisms or other non-biological surrogates and typically involves manual collection of water samples for microbial analysis to check system performance in achieving LRTs. While not specifically required, DOEE construction or maintenance inspections may include field verification testing to ensure that the rainwater harvesting system is achieving its LRTs, and that operational monitoring and control systems are functional.

M.9 Design Report

A design report must be submitted with each rainwater harvesting system that includes, at a minimum, the following:

- Pathogen log₁₀ reduction target (Section M.2);
- Proposed treatment process and associated log₁₀ reduction value (Section M.3)
- Proposed storage and distribution management practices (Section M.4);
- Identification of the Person Responsible for Maintenance (Section M.6).
- Operation and Maintenance Manual (Section M.6); and
- Reliability analysis that identifies the following:
 - How the equipment used to monitor treatment, operations, and water quality enables determination of whether the system is working as planned;
 - How the monitoring and controls of the system will enable the operator or automatic controls to intervene in the event of the production of off-specification water;
 - Remedies and provisions for operation disruption (e.g., power failures, vandalism, and excessive source contamination); and
 - Unauthorized access limitations for the rainwater harvesting and distribution system.

M.10 Treatment Design Examples

M.10.1 Example 1: Rooftop Runoff for Landscape Irrigation


Step 1: Identify the Log₁₀ Reduction Targets for the Reference Pathogen Groups

Since the roof will not allow frequent public access, the water source qualifies as roof runoff rather than general runoff. No LRT is provided for enteric bacteria or parasitic protozoa, but an LRT of 3.5 is defined for enteric bacteria.

Step 2: Select a Treatment Process to Achieve the Log₁₀ Reduction Target

An ozone system with a CT value (the product of concentration and contact time) of 0.04 mg • min/L can achieve 4-log₁₀ reduction of enteric bacteria. However, as all disinfection processes

require removal of particles 10 microns or larger, a 10-micron cartridge filter or similar device will also be necessary (see Figure M.1).



<u>Figure</u> M.7 <u>Categorizing Exposures Based on Stormwater Use: Severe, High, Medium, and Low1</u> Example 1 Treatment Schematic.

Alternative treatment trains that also could meet the required LRT include the following

- Microfiltration (i.e., 6-log₁₀ reduction of bacteria).
- Sand filter with an equivalent effluent particle size distribution of 10 microns, followed by UV radiation with a dose of 40 to 60 mJ/cm² (i.e., 4-log₁₀ inactivation of bacteria).
- Cartridge filtration (10 microns), followed by chlorination with free chlorine with a CT value of 1.6 to 2.4 mg•min/L (i.e., 4-log₁₀ inactivation of bacteria).

Step 3: Determine Storage and Distribution Management Practices

<u>For non-potable water systems, consider the chemical characteristics of roof runoff and storage</u> conditions, as follows:

- Due to its high purity, roof runoff may result in the corrosion of components and fixtures of the metallic distribution system. If any metallic pipe, fittings, solder, or fixtures are used that may be subject to corrosion from contact with corrosive water, then modify the water system or add a corrosion inhibitor to the non-potable water supply.
- If the temperature of water in the non-potable water distribution system exceeds 25°C (which is a condition that could promote the growth of opportunistic pathogens like Legionella), then maintain a free chlorine residual of 0.2 milligrams per liter (mg/L) or chloramine residual of 0.5 mg/L at or near the point of use.

Step 4: Identify Maintenance and Monitoring Requirements and Schedule of Activities

These will vary based on the specific equipment and devices included in each design.

Submit Exposure Classification	Exposure Classification	Route of Exposure
Severe	Swimming pools	Ingestion of water
High	Commercial farm produce drip or spray irrigation	Ingestion of irrigated vegetables and fruit

		Fire fighting	Ingestion of water and spray
		Commercial car wash	Ingestion of water and spray
		Open space or municipal park drip or spray irrigation	Ingestion by child on playground
		Open space or municipal park drip or spray irrigation	Public fountain with standing pool
Medium	Todium	Home garden drip or spray irrigation	Ingestion of irrigated vegetables and fruit
1	wiedrum	Home car wash spray application	Ingestion of water and spray
		Home lawn or garden spray irrigation	Accidental ingestion of stormwater
		Home lawn or garden spray irrigation	Ingestion after contact with plants/grass
	Low	Open space or municipal park drip or spray irrigation	Ingestion via high intensity sports baseball, soccer
		Open space or municipal park drip or spray irrigation	Ingestion via low intensity sports golf, Frisbee
		Open space or municipal park drip or spray irrigation	Public fountain with spray element
		Toilet	Ingestion of aerosol spray
		Home lawn or garden spray irrigation	Ingestion of aerosol spray
		Washing machine use	Ingestion of sprays
		Open space or municipal park drip or spray irrigation	Ingestion with casual contact picnic, walking pet

Project planners should select one of these four categories that best represent site specific conditions. The selection should be based on how stormwater will be used, who will contact the stormwater, and by what route of exposure. For example, stormwater used to fill a swimming pool is ranked "severe" because the frequency of exposure combined with the high rate of ingestion of pool water while swimming is considerably greater than all other exposures. It should be noted that exposure assumptions for formal risk assessments are typically established with worst possible exposure assumptions. While the worst exposure may be hypothetically possible, DDOE expects projects to rely on realistic and common sense expectations. For this reason, detailed and complex "future exposure analyses" are unnecessary. Proposals need only submit sufficient information to allow DDOE to convey to the public that a thorough analysis has been performed and that public health is being protected.

Although exposure assumptions are typically based on broad "what if" hypothetical scenarios in formal risk assessments, DDOE encourages proposals that are based on realistic expectations to determine the most likely threats to public health. DDOE recognizes that, in many cases, the anticipated exposure conditions will be based on subjective judgment rather than on a detailed

complex "future hypothetical exposure" analysis. Accordingly, proposals need only submit sufficient information to show that all potential exposures have at least been considered. This will allow DDOE to convey to the public that a thorough analysis has been performed and that public health is being protected.

In addition to the obvious and planned stormwater use, proposals must also consider inadvertent or unauthorized use of stormwater. That is, while the major focus should be on the intended uses, it is important to consider exposures that could result from inadvertent use of untreated stormwater as it may result in higher than intended exposure to humans and the receiving environment. For example, even though the intended use of stormwater is for purposes other than drinking, such as irrigation of parks and gardens, people may occasionally drink from a recycled water tap by accident. Obviously, a failsafe system must be put in place to prevent this from occurring. However, preventive measures can sometimes be circumvented, and the plan should evaluate the exposure as a low probability event to determine the magnitude of the potential threat to public health in the event of occurrence.

DDOE has derived RSLs for all the chemicals that are routinely detected in environmental media, particularly at industrial sites, which were presented in Table M.4. It is impractical to derive RSLs for all possible combinations of chemicals and for all stormwater uses and exposure conditions, but this list should be the starting point for sampling efforts. However, if the baseline investigation provides sufficient evidence that chemical contamination at the site is unlikely, sampling may be unnecessary. DDOE recognizes that sampling and laboratory analyses can be expensive and time consuming and may not be warranted. For example, if the property is currently and has always been zoned for residential use, there may be no reason to suspect a chemical release has occurred. In this situation, the planner could submit the baseline investigation and justification for a waiver to sample, which DDOE would review and consider.

The RSLs that should be used for risk based screening are presented in Table M.8. These levels represent the acceptable concentrations corresponding to either a cancer risk of 1E-6 or non-cancer hazard index of 1.0. They correspond to the site specific end use of the stormwater and exposure conditions as discussed previously. EPA's risk management framework states that a risk level between 1E-6 and 1E-4 is a discretionary range. The reason DDOE selected a risk-based screening level for cancer risk of 1E-6 is that it is likely that multiple chemicals will be detected for some projects. DDOE will use discretion in setting the acceptable "cumulative" risk level for projects where the individual contaminant levels slightly exceed the concentrations presented in Table M.8.

To use the table, planners only need to identify the column that matches the site specific exposure category and identify the row corresponding to the chemical of interest. That sample concentration is then compared with the RSL. If the sample concentration is below the RSL, it can be concluded stormwater does not pose a threat to human health, and no further action is necessary. If the sample concentration exceeds the RSL, the analysis must continue on to the next step in the TRAM process as described in the next section.

Table M.8 Risk-based Chemical Concentrations for Sites Categorized as Severe, High, Medium, and Low Exposures

Chemical (µg/L)	Drinking	Exposure Category	1
(1.8)	0	1	

Appendix M Rainwater Harvesting Treatment and Management Requirements

	Water	Severe	High	Medium	Low
Acrylamide	4.3E-02	1.6E+00	2.2E+01	5.8E+01	6.3E+02
Aldicarb	3.7E+01	1.3E+03	1.8E+04	4.9E+04	5.3E+05
Aldrin	4.0E-03	1.5E 01	2.0E+00	5.4E+00	5.8E+01
Aluminum	3.7E+04	1.3E+06	1.8E+07	4.9E+07	5.3E+08
Arsenic, Inorganic	4.5E 02	1.6E+00	2.3E+01	6.1E+01	6.6E+02
Atrazine	2.9E 01	1.1E+01	1.5E+02	3.9E+02	4.2E+03
Barium	7.3E+03	2.7E+05	3.7E+06	9.8E+06	1.1E+08
Benzene	4.1E-01	1.5E+01	2.1E+02	5.5E+02	6.0E+03
Benzo[a]pyrene	2.0E-01	7.3E+00	1.0E+02	2.7E+02	2.9E+03
Beryllium	7.3E+01	2.7E+03	3.7E+04	9.8E+04	1.1E+06
Bromate	9.6E-02	3.5E+00	4.8E+01	1.3E+02	1.4E+03
Cadmium	1.8E+01	6.7E+02	9.1E+03	2.5E+04	2.7E+05
Carbon Tetrachloride	4.4E 01	1.6E+01	2.2E+02	5.9E+02	6.4E+03
Chlordane	1.9E 01	6.9E+00	9.5E+01	2.6E+02	2.8E+03
Chlorobenzene	9.1E+01	2.7E+04	3.7E+05	9.8E+05	1.1E+07
Chromium	4.3E 02	4.0E+03	5.5E+04	1.5E+05	1.6E+06
Diazinon	2.6E+01	9.3E+02	1.3E+04	3.4E+04	3.7E+05
Epichlorohydrin	2.1E+00	8.0E+03	1.1E+05	2.9E+05	3.2E+06
Ethylbenzene	1.5E+00	5.5E+01	7.5E+02	2.0E+03	2.2E+04
Heptachlor	1.5E-02	5.5E-01	7.5E+00	2.0E+01	2.2E+02
Hexachlorobutadiene	8.6E-01	3.1E+01	4.3E+02	1.2E+03	1.3E+04
Iron	2.6E+04	9.3E+05	1.3E+07	3.4E+07	3.7E+08
Manganese	8.8E+02	3.2E+04	4.4E+05	1.2E+06	1.3E+07
Mercury	1.1E+01	4.0E+02	5.5E+03	1.5E+04	1.6E+05
Molybdenum	1.8E+02	6.7E+03	9.1E+04	2.5E+05	2.7E+06
Nickel	1.8E+03	6.7E+04	9.1E+05	2.5E+06	2.7E+07
Polybrominated Biphenyls	2.2E 03	8.0E-02	1.1E+00	3.0E+00	3.2E+01
Polychlorinated Biphenyls	5.0E 01	1.8E+01	2.5E+02	6.7E+02	7.3E+03
Selenium	1.8E 02	6.7E+03	9.1E+04	2.5E+05	2.7E+06
Silver	1.8E+02	6.7E+03	9.1E+04	2.5E+05	2.7E+06
Tetrachloroethylene	1.1E-01	4.0E+00	5.5E+01	1.5E+02	1.6E+03
Tin	2.2E+04	8.0E+05	1.1E+07	2.9E+07	3.2E+08
Toluene	2.3E+03	1.1E+05	1.5E+06	3.9E+06	4.3E+07
Trichlorobenzene	2.32103	8.4E+01	1.2E+03	3.1E+03	3.4E+04
Trichloroethane	2.4E 01	8.8E+00	1.2E+02	3.2E+02	3.5E+03
Trichloroethane	9.1E+03	2.7E+06	3.7E+07	9.8E+07	1.1E+09
Trichloroethylene	2.0	7.3E+01	1.0E+03	2.7E+03	2.9E+04
Vinyl Chloride	1.6E 02	5.8E 01	8.0E+00	2.2E+01	2.3E+02
Xylene	2.0E+02	2.7E+05	3.7E+06	9.8E+06	1.1E+08

Chamical (ug/L)	Drinking		Exposure	Category	
Chemical (µg/L)	Water	Severe	High	Medium	Low
Zine	1.1E+01	4.0E+02	5.5E+03	1.5E+04	1.6E+05

Stormwater projects must also include an evaluation of threats from microbial pathogens. Although this can be a complex investigation (there are many hundreds of different microbial pathogens), DDOE has developed a tiered approach to reduce time and costs based on the indicator pathogens *Escherichia coli* (*E. coli*) and *Cryptosporidium parvum* (*C. parvum*). With this approach, planners should first monitor for *E. coli* because it is less expensive to analyze than Cryptosporidium. *E. coli* is termed a reference or indicator microbe because it is associated with human and wildlife fecal waste (it should be noted, however, that no simple statistical correlation exists between *E. coli* and human pathogen concentrations in stormwater). *C. parvum*, however, causes gastrointestinal illness that may be severe and sometimes fatal for people with weakened immune systems (which may include infants, the elderly, and individuals who have AIDs). It will only be necessary to monitor for *C. parvum* if the *E. coli* results exceed the RSLs presented in Table M.9, if the stormwater storage system is large and at ground level, or stormwater is stored in a reservoir.

Table M.9 presents RSLs for *E. coli* that are based on EPA guidance for swimming and wading (Ambient Water Quality Criteria for Bacteria (EPA440/5-84-002 January 1986). The current level that is acceptable for swimming and wading is 160 CFU/100 mL, which corresponds to a risk of developing gastroenteritis of 8 in 1000 and is generally accepted as a safe level by regulatory agencies. This formed the basis for the "severe" category and was also used to derive the RSL for the three other categories using the attenuated exposure assumptions presented in Table M.6. For sites classified as severe exposures, the RSL should be interpreted to mean that when the site sample concentration for *E. coli* < 160 CFU/100 mL, the stormwater is safe for swimming or wading, and no further action is necessary for microbial contaminants. If this RSL is exceeded, however, samples must be collected for the next tier, which involves analyzing for *C. parvum*.

Unlike *E. coli*, no regulatory agency has yet to develop a safe level for *C. parvum* exposure. Although the EPA's recently revised new Long Term 2 Enhanced Surface Water Treatment Rule (LT2 rule; EPA 815 R06 006 Pebruary 2006) stresses the importance of monitoring for *C. parvum* to protect drinking water sources, no exposure specific RSL is available. It should be noted, however, that DDOE's approach for monitoring microbial contaminants is similar to the strategy in the LT2 rule, because DDOE concurs with EPA that a tiered monitoring approach based on *E. coli* and *C. parvum* is the most cost effective strategy for protecting the public from gastrointestinal illness.

Table M.9 presents RSLs for each exposure category for *C. parvum*. These levels were developed based on the WHO approach using Disability Adjusted Life Years (DALYs); they are also consistent with the tolerable levels developed in Australian Guidelines for Water Recycling: Managing Health and Environmental Risks (Phase 2) Stormwater Harvesting And Reuse (July 2009) and are set at 1E 6 risk level.

Table M.9 Risk-Based Microbial Levels for Sites Categorized As Severe, High, Medium, and Low Exposures

Microbial Pathogen	Swimming	Exposure Category				
	Swimming	Severe	High	Medium	Low	
	Escherichia coli (CFU/100 mL)	126 ¹	126	1714	4615	50000
	Cryptosporidium ² (oocysts/L)	NA	0.001	0.016	0.033	0.320

⁴ Ambient Water Quality Criteria for Bacteria (EPA440/5 84 002 January 1986). RSLs correspond to a risk level of 8 in 1,000 of developing a gastrointestinal disease.

The risk based screening results for both chemicals and microbes are considered in the next step.

DECISION POINT 2: Is Maximum Risk for Untreated Stormwater Acceptable?

This step represents the important risk management decision point in the TRAM approach and it is dependent on the previous risk screening comparison. The comparison of chemical and microbiological contaminant levels with RSLs is the only criteria needed to make this determination. This is a pivotal decision, since if the maximum risk is acceptable, no further investigation is necessary, stormwater treatment will not be required, and the proposed plan for no treatment can be submitted to DDOE for review. This represents the second exit point from the TRAM process.

On the other hand, if one or more contaminants tail the risk based screen, action will generally be necessary to lower risks to an acceptable level. The magnitude of the exceedance will be the primary determinant for making risk management decisions. If the exceedance is less than one or two orders of magnitude, DDOE can exercise its discretion about the best path forward and whether a treatment system is necessary. DDOE will rely on factors such as availability of treatment systems, severity of the toxic effect, probability of exposures, and whether measures can be implemented to prevent exposures. DDOE's determination will ultimately be based on a cost benefit evaluation, and the most effective remedy with the lowest cost will be selected.

<u>Step 5:</u> If the appropriate remedy is treatment, planning should proceed to the next step. Design Report and SWMP

M.10.2 Example 2: General Runoff for Indoor Use

Step 1: Identify the Log₁₀ Reduction Targets for the Reference Pathogen Groups

The proposed rainwater harvesting system will capture runoff from two different areas on a rooftop. The first area will have no public access, but the second area includes a patio area that is designed for public access. The combined water from the two areas is therefore considered

² Australian Guidelines for Water Recycling: Managing Health and Environmental Risks (Phase 2) Stormwater Harvesting and Reuse. July 2009. RSLs correspond to a 1E 6 risk level of developing a gastrointestinal disease.

"general runoff," and will need to be treated accordingly. The LRT for both enteric viruses and protozoa is 5.5, and the LRT for enteric bacteria is 5.0.

Step 2: Select a Treatment Process to Achieve the Log₁₀ Reduction Target

An ultrafiltration system can achieve $6 - \log_{10}$ reduction of viruses, protozoa, and bacteria (see Figure M.2).




Figure M.2 Example 2 Treatment Schematic.

The only alternative processes that can also meet the required LRTs are nanofiltration and reverse osmosis.

Step 3: Determine Storage and Distribution Management Practices

For non-potable water systems, consider the chemical characteristics of roof runoff and storage conditions, as follows:

- Due to its high purity, roof runoff may result in the corrosion of components and fixtures of the metallic distribution system. If any metallic pipe, fittings, solder, or fixtures are used that may be subject to corrosion from contact with corrosive water, then modify the water system or add a corrosion inhibitor to the non-potable water supply.
- If the temperature of water in the non-potable water distribution system exceeds 25°C (which is a condition that could promote the growth of opportunistic pathogens like Legionella), then maintain a free chlorine residual of 0.2 milligrams per liter (mg/L) or chloramine residual of 0.5 mg/L at or near the point of use.

Step 4: Identify Maintenance and Monitoring Requirements and Schedule of Activities

These will vary based on the specific equipment and devices included in each design.

Step 5: Submit Design Report and SWMP

M.10.3 Example 3: Roof Runoff for Cooling Towers

Step 1: Identify the Log₁₀ Reduction Targets for the Reference Pathogen Groups

As there is not public exposure to the harvested rainwater, there are no initial treatment requirements. Chlorination may still be required to control the growth of opportunistic pathogens (see Step 2).

Step 2: Determine Storage and Distribution Management Practices

For non-potable water systems, consider the chemical characteristics of roof runoff and storage conditions, as follows:

- Due to its high purity, roof runoff may result in the corrosion of components and fixtures of the metallic distribution system. If any metallic pipe, fittings, solder, or fixtures are used that may be subject to corrosion from contact with corrosive water, then modify the water system or add a corrosion inhibitor to the non-potable water supply.
- If the temperature of water in the non-potable water distribution system exceeds 25°C (which is a condition that could promote the growth of opportunistic pathogens like Legionella), then maintain a free chlorine residual of 0.2 milligrams per liter (mg/L) or chloramine residual of 0.5 mg/L at or near the point of use.

Step 3: Identify Maintenance and Monitoring Requirements and Schedule of Activities

These will vary based on the specific equipment and devices included in each design.

Step 4: Submit Design Report and SWMP.

M.11 References

- San Francisco Department of Public Health (2016). Director's Rules and Regulations Regarding the Operation of Alternate Water Source Systems.
- Sharvelle, S.; Ashbolt, N.; Clerico, E.; Hu tquist, R.; Leverenz, H.; and Olivieri, A. (2017). Risk-Based Framework for the Development of Public Health Guidance for Decentralized Non-Potable Water Systems. Prepared by the National Water Research Institute for the Water Environment & Reuse Foundation. Alexandria, VAWE&RF Project NoSIWM10C15.
- U.S. Environmental Protection Agency (2009). National Primary Drinking Water Regulations EPA 816-F-09-004.

Step 12: Select-Appropriate Treatment Technology to Reduce Contaminants to Acceptable Risk Levels.

Selecting the appropriate remedy will depend on the type(s) of contaminant(s) posing the health threat. For microbial pathogens in small to medium sized stormwater projects, ultraviolet (UV)

disinfection is the most practical and cost effect approach. Although chlorination may also be suitable, protozoa such as *C. parvum* will require a higher Ct value (disinfectant concentration × contact time) because inactivation is more difficult to achieve compared with that for bacteria and viruses.

If chemical contaminants pose an unacceptable risk, it must be determined whether they are soluble or are bound to particles. If they are particulate-bound, it may be necessary to reduce their concentration with filtration, flocculation, or other treatments that reduce suspended solids.

Proposed plans must present the type of treatment selected that will target specific chemical and/or microbial risks. Planning should proceed to the next step.

Step 13: Submit Stormwater "Treatment" Plan to DDOE and Collect Verification Samples.

Proposed plans must provide a full description of the treatment system that is selected to reduce contaminant levels. The operating efficiency and specifications are necessary because verification samples will be used to validate the system is operating as designed.

The design of a monitoring program will be specific to each project, but it must take into account both peak and average rainfall. The point of compliance will be the stormwater in the eatehment rather than separate points across the property because the catchment water represents the average of all contributions because it is likely that one or more individual samples will fail risk-based screening. The extent of sampling required to verify the system is functioning properly will be project specific with more extensive sampling required for projects where a greater number of individuals are exposed to chemicals that are considered more toxic. As a rule of thumb, projects classified as "severe" and "high" will require a slightly more complex sampling design. Also, projects that require a higher log reduction of contaminant levels will receive a greater degree of scrutiny.

Step 14: Compare Treated Stormwater Concentrations with Risk-Based Levels

The log reduction necessary to achieve acceptable risk levels represents the difference between the maximum (untreated stormwater) and residual (treated stormwater) risk. Sample concentrations should be < the target concentrations corresponding to the intended use and exposures, and those target goals are the same RSLs that were presented in Tables N.8 and N.9.

DECISION POINT 3: Residual Risk for Treated Stormwater Acceptable?

This point requires that a decision be made as to whether the treatment system efficiently reduced contaminant levels to acceptable concentrations. If the verification samples indicate the treatment system is performing as designed, the proposal must include the results and conclusions and proceed to the next step. As noted previously, DDOE will use discretion in determining whether the project meets the acceptable "cumulative" risk level for projects where the individual contaminant levels slightly exceed the concentrations presented in Table M.S. For example, DDOE may determine that exceedances do not rise to a level requiring action if the number of potentially exposed individuals is very small. Additionally, DDOE may use its discretion to waive action when an exceedance is less than an order of magnitude above risk-based screening levels.

If the treatment system fails to meet the design specifications and cannot achieve the required risk based acceptable concentrations, the investigation must go back to Step 7 and repeat the subsequent steps of the TRAM process. This requires that either the selected treatment system be modified or an alternate technology selected.

Step 15: Continue Required Monitoring Sampling/Submit Analytical Results to DDOE.

The purpose of a monitoring program is to confirm continued compliance with the required end use water standards. The applicant will submit a post construction monitoring program that will access the ongoing lifecycle compliance including annual verification of performance as well as performance verification after significant maintenance or modifications to the treatment system. Monitoring assesses:

- Overall performance of the systems harvesting stormwater for non-potable uses;
- Quality of the harvested stormwater being supplied or discharged;
- Changes in the receiving environment or exposed populations.

Ultimately, the goal of monitoring is to provide continued assurance that the treatment system is operating at levels specified in the permit and public health is being protected. For example, systems relying on UV radiation for disinfection would need to replace the UV source at manufacturer specified intervals, and monitoring should be conducted soon after the unit is replaced. The original proposal must present a detailed monitoring plan that anticipates routine maintenance or major modification to treatment systems. As a rule of thumb, greater emphasis on monitoring will be necessary for those projects where the exposed population is significant and/or the maximum risks associated with untreated stormwater are significantly above risk-based levels. This monitoring program will be part of the approved SWMP and detailed in the deed of covenants as part of the BMP's long term maintenance obligations.7..7.2

7.37.4 7.57.6

Appendix N Land Cover Designations

N.1 General Notes

The retention standard approach taken in this <u>guidance manualguidebook</u> for on-site stormwater management recognizes the ability of pervious land covers to manage some, or all, of the rainwater that falls on it. This is termed "land abstraction" in this appendix. The concept is discussed as "existing <u>retention</u>" or "<u>pre-project</u> retention" in chapters and appendices related to the off-site retention program. To facilitate the design, review, construction, and enforcement of site-designated land cover, land abstraction has been divided into two types of land covers: natural cover and compacted cover. The preservation and the creation of land covers with either of these designations are treated equally in this guidance manual. The designation of natural cover assumes these lands will generate zero stormwater runoff for a design rain event. The designation of compacted cover assumes these lands will generate 25 <u>percent</u> stormwater runoff for a design rain event. The minimum area threshold for the natural cover designation is 1,500 square feet, with a minimum length of 30 feet. All land cover designations must be recorded in the declaration of covenants.

N.2 Existing Natural Cover Requirements

A site claiming natural cover based on the preservation of existing conditions must ensure conditions remain undisturbed to preserve hydrologic properties equal to or better than meadow in good condition. Preservation areas for natural cover may include the following:

- Portions of residential yards in forest cover that will not be disturbed during construction
- Community open space areas that will not be mowed routinely, but left in a natural vegetated state (can include areas that will be rotary mowed no more than two times per year)
- Utility rights-of-way that will be left in a natural vegetated state (can include areas that will be rotary mowed no more than two times per year)
- Other areas of existing forest and/or open space that will be protected during construction and that will remain undisturbed

N.3 Planting Requirements for the Creation of Natural Cover

- Every 1,500 square feet of created natural area shall be vegetated according to the following options of plant material quantity:
 - 1 native shade tree: 1.5-inch caliper (minimum), or
 - 2 native ornamental trees: 6-foot height (minimum), or
 - ♦ 6 native shrubs: 5—gallon container size (minimum), or
 - 50 native perennial herbaceous plants: 1-gallon container size (minimum), or

- 1 native ornamental tree: 6- to 10-foot height (minimum), and 25 native perennial herbaceous plants: 1-gallon container size (minimum), or
- 3 native shrubs: 5—gallon container size (minimum), and 25 native perennial herbaceous plants: 1—gallon container size (minimum), or
- Steep slope greater than 6 percent grade will require additional plantings, soil stabilization, or a terracing system.
- Whip and seedling stock may be used (when approved by DDOEDOEE) as a site's natural cover creation if a stream bank stabilization opportunity falls within the site's footprint. In this instance, whips or seedlings must be planted at a minimum density of 700 plants per acre, and at least 55-percent% of these plants must remain at the end of the 2-year management period.
- Natural regeneration (i.e., allowing volunteer plants to propagate from surrounding natural cover as a cover creation technique) may be allowed by DDOE, DOEE when 75 percent of the proposed planting area is located within 25 feet of adjoining forest, and the adjoining forest contains less than 20 percent cover of invasive exotic species. In this case, supplemental planting must ensure a density of 400 seedlings per acre.
- All plant materials used must be native to the mid-Atlantic region and must be installed in areas suitable for their growth. Lists of native species of shrubs, grasses, and wildflowers are published in the US Fish and Wildlife Service, (2009,) Native Plants for Wildlife Habitat and Conservation Landscaping: Chesapeake Bay Watershed. There are several websites that may be consulted to select the most appropriate plantings for the District;

+--

- http://www.nps.gov/plants/pubs/nativesMD/pdf/MD CoastalPlain.pdf
- http://www.nps.gov/plants/pubs/nativesMD/pdf/MD Piedmont.pdf
- ◆ http://www.wildflower.org/collections/collection.php?collection=DC
- http://www.nativeplantcenter.net
- https://www.mdflora.org/aboutnatives.html
- https://www.fws.gov/chesapeakebay/bayscapes/bsresources/bs-nativeguides.html
- Plants can be irrigated until established.

N.4 Stormwater Management Plans and Natural Cover

Sites using preservation of existing areas for the natural cover designation shall include on their Stormwater Management Plan (SWMP) a tree and vegetation survey, identification of location, and extent of preservation areas. Depending on the extent of the preservation area DDOE, DOEE may require the SWMP to include a more detailed schedule for retained trees, noting the tree species, tree-size, tree-canopy, tree-condition, and tree location.

The SWMP will include the identification of material and equipment staging areas and parking areas. Material and equipment staging areas and parking areas must be sufficiently offset for preservation areas to ensure no adverse impacts.

For areas maintained as meadow in good condition, the SWMP shall document either the preservation of existing conditions or the creation of meadow conditions. A plan submission claiming meadow preservation will note the existing meadow boundaries and include a field survey of the richness and diversity of existing plant species and the existing soil conditions. A plan submission claiming meadow creation will note the proposed meadow boundaries, the planting and/or seeding species methods, and provide a soil amendments plan as specified in Appendix J_{τ} , "Soil Compost Amendment Requirements."

The 2013 Stormwater Rule (21 DCMR, Chapter 5) requires establishing a buffer of native vegetation within 25 feet of a water body. This can be accomplished by meeting the planting requirements for natural cover as described in Section N.3 or by construction of a living shoreline that meets the requirements identified in the District's Living Shoreline specification. Living shorelines that meet these specifications are classified as natural cover-

N.5 Construction Requirements for Natural Cover Designation

The preservation of lands designated as natural cover,—such as undisturbed portions of yards, community open space, and any other areas designated on a site's SWMP as preserved natural cover,—must be shown outside the limits of disturbance on the site's Soil Erosion and Sediment Control Plan. These areas must be clearly demarcated with signage prior to commencement of construction on the site on the site and with fencing during construction.

The creation of lands designated as natural cover as part of a public right-of-way (PROW) project and on sites where soils were not protected from compaction during construction the soils must be conditioned prior to planting with soil compost amendments as prescribed in Appendix J_{τ} , "Soil Compost Amendment Requirements."

For maximum survivability, planting of trees, shrubs, and herbaceous vegetation for the creation of natural cover should occur only during the fall and early spring (i.e., September—through November and March—through May). The work should be done only under the supervision of someone qualified and skilled in landscape installation (see Section 3.14-, "Tree Planting and Preservation" for details on qualifications). Proper maintenance of the materials after installation will be key in ensuring plants survival. Prior to inspection, all trees and shrubs planted must be alive and in good health, and native grass and wildflower seeds must have been sown at adequate densities and at the right time of year for each species.

Once a natural cover designation has been assigned to a portion of regulated development site, that area will need to be recorded in the declaration of covenants, documented at the site prior to construction activities, protected during construction activities, and permanently protected/maintained for the life of the regulated site.

Root pruning and fertilizing are examples of preconstruction activities. These measures aim to increase the wellbeing of trees and prepare them for higher stress. Prior to beginning construction, temporary devices such as fences or sediment controls are installed and remain throughout the construction phase. Some devices, like retaining walls and root aeration systems may remain permanently. For example, if part of a root system is collapsed by a built road, permanent aeration may be necessary for the tree to remain healthy.

N.6 Maintenance Requirements for Natural Cover Designation

All areas that will be considered natural cover for stormwater purposes must have documentation that prescribes that the area will remain in a natural, vegetated state. Appropriate documentation includes subdivision covenants and restrictions; deeded operation and maintenance agreements and plans; parcels of common ownership with maintenance plans; third-party protective easements within the PROW-or p-maintenance plans; or other documentation approved by DDOE. Natural cover designation must be identified in the site's declaration of covenants. DOEE.

While the goal is to have natural cover areas remain undisturbed, some activities may be prescribed in the appropriate documentation, as approved by DOEE, such as forest management, control of invasive species, replanting and revegetation, passive recreation (e.g., trails), limited bush hogging to maintain desired vegetative community, etc.

N.7 Compacted Cover Designation

The compacted cover designation can apply to all site areas that are disturbed and/or graded for eventual use as managed turf or landscaping. Examples of compacted cover include lawns; portions of residential yards that are graded or disturbed and maintained as turf—_including yard areas; residential utility connections; and PROW. Landscaping areas intended to be maintained as vegetation other than turf within residential, commercial, industrial, and institutional settings are also considered compacted cover if regular maintenance practices are employed.

N.8 Impervious Cover Designation

The impervious cover designation applies to all surface areas that have been compacted or covered with a layer of material that impedes or prevents the infiltration of water into the ground, examples include conventional streets, parking lots, rooftops, sidewalks, pathways with compacted sub-base, and any concrete, asphalt, or compacted gravel surface and other similar surfaces. The surface area of all BMPs, except disconnection areas, are also considered to be impervious cover. For BMPs with ponding, the area of the top of ponding should be considered the BMP surface area.

er simila adred to be add be considered.

PROPOSED PENISION PROPOSED PRO

Appendix O Geotechnical Information Requirements for Underground BMPs

O.1 General Notes Pertinent to All Geotechnical Testing

A geotechnical report is required for all underground stormwater best management practices (BMPs), including infiltration-based practices, filtering systems, and storage practices, as well as stormwater ponds and wetlands. The following must be taken into account when producing this report.

- Testing is to be conducted byat the direction of a qualified professional. This professional shall either be a registered professional engineer, soils scientist, or geologist and must be licensed in the District of Columbia.
- Soil boring or test pit information is to be obtained from at least one location on the site. Additional borings or test pits are required within the proposed BMP facility under three conditions: (1) when the soils or slopes vary appreciably from the findings in the initial boring or test pit, (2) when the ground watergroundwater level is found to be significantly higher than the initial boring or test pit indicated, and (3) when the ground watergroundwater level may adversely affect the performance of the proposed BMP facilities. However, the location, number, and depth of borings or test pits shall be determined by a qualified professional, and be sufficient to accurately characterize the site soil conditions.
- Depth to the ground water table (with 24 hour readings) and estimated depth to the seasonally high ground water table groundwater table with a reading after 24 hours must be included in the boring logs/geotechnical report.
- Laboratory testing must include grain size analysis. Additional tests such as liquid limit and
 plastic limit tests, consolidation tests, shear tests, and permeability tests may be necessary
 where foundation soils or slopes are potentially unstable based on the discretion of the
 qualified professional.
- The geotechnical report must include soil descriptions from each boring or test pit, and the laboratory test results for grain size. Based upon the proposed development, the geotechnical report may also include evaluation of settlement, bearing capacity, and slope stability of soils supporting the proposed structures.
- All soil profile descriptions should provide enough detail to identify the boundary and elevations of any problem (boundary/restrictions) conditions such as fills and seepage zones, type and depth of rock, etc.

In addition to the testing requirements described above, infiltration tests must be performed for all BMPs in which infiltration will be relied upon, including permeable pavement systems, bioretention, infiltration, and dry swales. Specific requirements for infiltration testing are discussed below.

O.2 Initial Feasibility Assessment

The feasibility assessment is conducted to determine whether full-scale infiltration testing is necessary, screen unsuitable sites, and reduce testing costs. However, a designer or landowner may opt to skip the initial feasibility assessment at his or her discretion; and begin with soil borings.

The initial feasibility assessment typically involves existing data, such as the following:

- On-site septic percolation testing, which can establish historic percolation rates, water table, and/or depth to bedrock. Percolation tests are different than tests for coefficient of permeability or infiltration rate;
- Previous geotechnical reports prepared for the site or adjacent properties or
- Natural Resources Conservation Service (NRCS) Soil Mapping.

If the results of initial feasibility assessment show that a suitable infiltration rate (typically greater than $0.5 \, \underline{\text{inches} \underline{\text{inch}}}$ per hour) is possible or probable, then test pits must be dug or soil borings drilled to $\underline{\text{verifydetermine}}$ the $\underline{\text{infiltration rate}}$ -saturated hydraulic conductivity ($\underline{K}_{\text{sat}}$).

O.3 Test Pit/Boring Requirements for Infiltration Tests

- Excavate a test pit or drill a standard soil boring to a depth of 2 feet below the proposed facilityBMP bottom.
- Do not construct, maintain, or abandon a well in a manner that may create a point source or non-point source of pollutants to waters of the District, impair the beneficial uses of waters of the District, or pose a hazard to public health and safety or the environment (21 DCMR, Chapter 18, Section 1801.2). Therefore, if contaminated soil or materials indicative of contamination are noticed at the site, in accordance with 21 DCMR, Chapter 18, Section 1802.4, and 1832.2, stop work, report the findings to DOEE Inspections and Enforcement Division, undertake any Department-ordered corrective actions, and obtain a DCRA well construction building permit to properly abandon the borehole in accordance with 21 DCMR §§ 1831.4 through 1831.6 and 1831.8 through 1831.14.
- Determine depth to the groundwater table (if within 2 feet of proposed <u>BMP</u> bottom), and the estimated seasonally high groundwater table.
- Determine Unified Soil Classification (USC) System and/(USCS) or United SatesStates
 Department of Agriculture (USDA) textures at the proposed bottom and 4to 2 feet below the bottom of the BMP.
- Determine depth to bedrock (if within 2 feet of proposed <u>BMP</u> bottom).
- The Include the soil description must include in all soil horizons. Perform the infiltration test at the proposed bottom of the practice BMP. If any of the soil horizons below the proposed bottom of the infiltration practice (within 2 feet) appear to be a confining layer, additional

infiltration tests must be performed on this layer (or layers), following the procedure described below.

• The location of the test pits or borings shall correspond to the BMP locations; a. A map or plan that clearly and accurately indicates the locations(s) of the test pits or soil borings must be provided with the geotechnical report.

At least 1 test pit must be dug or encased soil boring drilled for each proposed infiltration-based BMP. For larger practices, additional test pits or soil borings are required for infiltration testing, as described in Table O.1 below.

Table O.1 indicates the number of test pits or soil borings and subsequent infiltration tests that must be performed per BMP. In cases where multiple BMPs are proposed in one area with generally uniform conditions, a circular shape that fully encompasses all of the BMPs may be substituted for the "area of practice" that determines the number of required infiltration tests.

Area of Practice	Minimum Number of Test Pits/Soil Borings		
< 1,000	1		
1,000–1,999	2		
2,000–9,999	3		
≥ 10,000	Add 1 test pit/soil boring for each additional ±0510,000 ft ² of BMP.		

When one test pit or boring is required, it must be located as near to the testing area as possible. When more than one test pit or boring is necessary for a single BMP or area, the pit or boring locations must be equally spaced throughout the proposed BMP area-of the practice, as directed by the qualified professional. The reported infiltration ratesaturated hydraulic conductivity for a BMP shall be the median or geometric mean (area-weighted average) of the observed results from the soil boring-or test pit locations.

O.4 Infiltration Testing Requirements

The following tests are acceptable for use in determining soil infiltration rates. The geotechnical report shall include a detailed description of the test method and published source references:

Constant Head Bore-Hole Infiltration Tests (also referred to as bore-hole permeameter tests and constant-head well permeameter tests). These types of tests determine saturated hydraulic conductivity (coefficient of permeability) by measuring the rate of water flow to a borehole. Analytical solutions utilize principles of Darcy's Law, borehole geometry, and head (or multiple heads) of water in determining saturated hydraulic characteristics. Where the soil characteristics meet all of the above described requirements for infiltration BMPs, the hydraulic gradient element of Darcy's Law is often estimated as 1 for determining infiltration rate.

One published standard developed by the United States Bureau of Reclamation for this method is USBR 7300-89. Some of the commercially available equipment is listed below:

- Amoozemeter
- Guelph Permeameter
- Johnson Permeameter
- Maryland Stormwater Design Manual, Appendix D.1 Testing Requirements for Infiltration, Bioretention, and Sand FilerFilter Subsoils, as modified below. The data obtained from this infiltration testing procedure shall be used to calculate the saturated hydraulic conductivity (see Section O.5)-, "Saturated Hydraulic Conductivity Calculations").
 - 1. Install solid casing in the boring or test pit to the proposed BMP bottom or other required test depth (i.e. confining layer encountered within 2 feet below the BMP bottom). When installing casing, drive the casing between 3 to 5 inches below the test surface to promote a good casing-to-soil seal.
 - 2. Remove any smeared, soiled surfaces, and provide a natural soil interface into which water may infiltrate. Remove all loose material from the casing. At the tester's/tester or registered professional's discretion, a 2-inch layer of coarse sand or fine gravel may be placed to protect the bottom from scouring and sediment. Fill the casing with clean, potable water 24 inches above the test surface (24 inches of head), and allow to presoak for 24 hours.
 - 3. Protect the open borehole with suitable cover such as a sanitary well cap and steel plate with surrounding sandbags to prevent the introduction of surface water runoff, trash, debris, and other pollutants.
 - 3.4. Twenty-four hours later, refill the casing with approximately 24 inches of clean water (24 inches of head), and monitor the water level for 1 hour, recording the depth of water at the beginning and end of the test.
 - 4.5_Repeat step 34 (filling the casing each time) three additional times, for a total of four observations. At the registered professional's discretion, the saturated hydraulic conductivity calculations may be performed based on the values recorded during the average of the four readings or the last observation. The testing interval can be increased at the discretion of the registered professional.

All soil borings and test pits shall be properly backfilled after conclusion of the tests. A person shall not construct, maintain, or abandon a well in a manner that may create a point source or non-point source of pollutants to waters of the District, impair the beneficial uses of waters of the District, or pose a hazard to public health and safety or the environment (21 DCMR, Chapter 18, Section 1801.2). To prevent a soil boring from becoming a conduit for stormwater or other contaminants to enter groundwater and create a low-permeability seal against vertical fluid migration, follow these steps:

1. Using a positive displacement technique, inject a sodium-based bentonite slurry through a tremie pipe at least 1 inch in diameter starting at the bottom of the borehole. The slurry shall be composed of 2 pounds of sodium-based bentonite powder to 1 gallon of water.

- 2. If the borehole is too narrow to accommodate a tremie pipe or the borehole is less than 10 feet deep, slowly place uncoated, medium-sized, sodium-based bentonite chips in the borehole to create a 2-foot lift of chips measured from the bottom of the borehole.
- 3. Tamp down the bentonite chips to prevent bridging.
- 4. Using a ratio of 1 gallon of water to 12.5 pounds of bentonite chips, add potable water to the borehole and allow 15 to 30 minutes to elapse to ensure proper hydration of the bentonite chips.
- 5. Adjust these instructions as necessary in accordance with the manufacturer's instructions, providing that the resulting seal will have an effective hydraulic conductivity of no more than 1×10^{-7} cm/s.
- 6. The process should be repeated until the boring is filled 1 to 2 feet from the ground surface
- 7. The remainder of the borehole should be backfilled with material to match the surrounding cover and must not include the use of a coal-tar product.

Further details are provided in 21 DCMR §§ 1831.4 through 1831.6 and 1831.8 through 1831.14.

An infiltration test does not require ground water quality protection approval a well permit in accordance with the current well construction, maintenance, and abandonment regulations set forth in 21 DCMR, Chapter 18 if the following apply:

- The test is conducted to a depth of fifteen 15 feet or less below the ground surface, and
- A Professional Engineer licensed in the District of Columbia certifies the ratehydraulic conductivity and that the test was carried out in compliance with this guidance and accepted professional standards.

Note: If the infiltration testing procedure reveals smells or visual indications of soil or groundwater contamination then the boring or test hole must be filled in accordance with wellhead protection best practices, unless laboratory analysis determines groundwater or soil is not contaminated, as defined in the District of Columbia Brownfield Revitalization Act of 2000, as amended (D.C. Official Code §§ 8-631 et seq).

O.5 Saturated Hydraulic Conductivity Calculations

To convert the field infiltration measurements to a saturated hydraulic conductivity value (K_{sat}), the following calculations must be performed.

$$K_{sat} = \frac{\pi D}{11(t_2 - t_1)} \times \ln(\frac{H_1}{H_2})$$

where:

 K_{sat} = saturated hydraulic conductivity (in/hr) D = casing diameter (in) (minimum 4 inches)

 t_2 = recorded end time of test (hr)

 t_1 = recorded beginning time of test (hr) H_1 = head in casing measured at time t_1 (ft) H_2 = head in casing measured at time t_2 (ft)

This equation was adapted by the U.S. Bureau of Reclamation in 1975 from Lambe and Whitman, 1969.

O.6 Infiltration Restrictions

If a Phase I Environmental Site Assessment determines that identifies a Recognized Environmental Concern at a site indicating that site contamination is likely, or present; or if DDOEDOEE is aware of upgradient or downgradient contaminant plumes, the presence of a brownfield or historic hotspot uses use, such as any of the following current or previously existing leaking underground storage tanks (LUSTs), gas stations, or asphalt plants, previous uses, then an impermeable liner must be used for BMPs, and infiltration is restricted, prohibited.

- Leaking underground storage tank (LUST);
- Above ground storage tanks (AST);
- Gas stations;
- Vehicle maintenance or repair facility;
- Dry cleaner;
- Transformer sub-station;
- Waste transfer or holding facility;
- Print shop;
- Chemical storage warehouse;
- Illicit hazardous wastes generator;
- Greenhouse with unlined floor;
- Septic system;
- Cement or asphalt plant; or
- Dump or landfill.


If an ASTM Phase II Environmental Site Assessment is performed, based on a DOEE-approved workplan in accordance with 21 DCMR, Chapter 19, Section 1901.1 and a qualified professional DOEE reviews the results and determines that the use of stormwater infiltration-based practices will not increase the likelihood of BMPs may impact on-site contamination by the following means, then an impermeable liner must be used for BMPs, and infiltration is prohibited:

- Spreading of contamination vertically or horizontally at the site;
- Increasing on-site groundwater contamination, infiltration is not restricted. by leaching contaminants from the soil;

- Causing or enhancing contaminant migration to go offsite;
- Interfering with contaminant remedial activities;
- Decreasing or reversing the natural degradation of contaminants; or
- Causing a pollutant discharge to a surface water body.

If <u>DOEE concludes</u> there is no evidence of a <u>history of contamination, Recognized</u> Environmental Condition based on ASTM Phase I and II Environmental Site Assessments conducted in accordance with 21 DCMR § 1901.1, and there is no current site use that could result in the foreseeable creation of a Recognized Environmental Concern, then impermeable

liners are not required, and infiltration is not restricted.



See Figure O.1 for a graphic depiction of the process for determining infiltration restrictions.




Figure O.1 Infiltration restrictions related to site contamination.

Appendix P Stormwater Hotspots

P.1 Stormwater Hotspots

Stormwater hotspots are defined as commercial, industrial, institutional, municipal, or transport-related operations that produce higher levels of stormwater pollutants, and/or present a higher potential risk for spills, leaks₂ or illicit discharges. The following operations are classified as stormwater hotspots operations in the District of Columbia:

- H-1 Vehicle Maintenance and Repair
- H-2 Vehicle Fueling
- H-3 Vehicle Washing
- H-4 Vehicle Storage
- H 5 Outdoor Materials Loading and Unloading
- H-65 Outdoor or Bulk Material Storage

If any of the above operations are expected to occur in areas that will receive rainfall or runoff on the proposed site for which a Stormwater Management Plan (SWMP) is required, the Stormwater Hotspot Cover Sheet must be completed. Further, if a Construction General Permit Stormwater Pollution Prevention Plan (SWPPPCGPSWPPP) was not required or the SWPPPCGPSWPPP does not cover operational pollution prevention practices, then the Stormwater Hotspot Checklist must be submitted with the SWMP.

This appendix contains the following information:

- Stormwater Hotspot Cover Sheet
- Stormwater Hotspot Checklist
- Hotspot operation pollution prevention profile sheets for operations H-1 through H-65

PROPOSED REVISION PROPOSED REVISION

P.2 Stormwater Hotspot Cover Sheet



GOVERNMENT OF THE DISTRICT OF COLUMBIA

District Department of the Energy and Environment 1200 First Street NE, Fifth Floor, Washington DC 20002

Stormwater Hotspot Cover Sheet

Project Name:
Applicant Name:
Date:
Please indicate the appropriate hotspot operations for your project (check all that apply). If none apply check N/A.
Hotspot Operations:
Vehicle Maintenance and Repair (H-1)
Vehicle Fueling (H-2)
Vehicle Washing (H-3)
Vehicle Storage (H-4)
—Outdoor Materials Loading and Unloading (H-54)
Outdoor or Bulk Material Storage (H-65)
N/A
If "N/A" is checked, please include this sheet only with plan submittal.
Otherwise, please indicate which of the following items are being included with the submittal of the Stormwater <u>management Management</u> Plan (SWMP). Note: If a <u>SWPPP_CGPSWPPP</u> has not been completed or the <u>SWPPP_CGPSWPPP</u> does not cover operational pollution prevention practices, then the Stormwater Hotspot Checklist must be completed for the <u>SWMPsubmittalSWMP submittal</u> to be considered complete.
$\underline{\hspace{1cm}} A completed Construction General Permit Stormwater Pollution Prevention Plan \\ \underline{\hspace{1cm}} (\underline{SWPPP_{CGP}}\underline{SWPPP})$

___ A completed Stormwater Hotspot Checklist

PROPOSED REVISION PROPOSED REVISION

P.3 Stormwater Hotspot Checklist

Stormwater Hotspot Checklist

Instructions: Complete the following site information:

	Requirement	Description
Site Description	List the type of facility and facility address	.05
Site Operations	Describe the operations to be conducted on-site.	
Receiving Waters	Name(s) of the receiving water(s). If drains to a municipal storm sewer system, include ultimate receiving waters.	Q-V
Site Materials	Significant materials to be stored on-site (specify indoor or outdoor storage)	
Stormwater Management Practices	List the stormwater management practicesBMPs being used to treat runoff from the site. Where appropriate, include description of design modifications appropriate for treatment of hotspot runoff (i.e., bioretention area with impermeable liner and underdrain).	
Spill Prevention and Response	Describe methods to prevent spills along with clean-up and notification procedures.	
Employee Education Program	Description of employee orientation and education program.	

Instructions: Fill in the appropriate page number(s) from the site plans where the following site elements are clearly indicated.

Site elements Elements	Site Plan Sheet Number(s)	Check if N/A	Approved (for official use only)	
Material loading and access areas				
Material storage and handling areas				
Cleaning and maintenance areas				
Vehicle or machinery storage areas			(2)	
Vehicle or machinery maintenance/service areas			7	
Treatment or disposal areas for significant materials				
Hazardous waste storage areas				
Areas of outdoor manufacturing				
Stormwater management calculations				
Drainage Contributing drainage area outline for eac stormwater inlet or structure	h			
Stormwater management practicesBMPs				
Stormwater managementBMP maintenance				
inspectionschedules and agreements Spill Prevention and Response Kits				
Facility inspection agreements for inspections of areas where potential spills of significant materials or industrial activities can impact stormwater				
For official use only:				
J				

PROPOSED REVISION PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION REPORTS AND ADMINISTRATION OF THE PROPOSED REVISION ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION ADMINISTRATION OF THE PROPOSED REVISION ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION AND ADMINISTRATION OF THE PROPOSED REVISION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION AND ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION AND ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMINISTRATION ADMIN

Instructions: Complete this table only if operation H-1 was checked on Page ΘP .2.

١	H-1 Ve	hicle Maintenance and Repair Operati	ons	
	Description of Operation			
	Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
	Provide locations for recycling collection of used antifreeze, oil, grease, oil filters, cleaning solutions, solvents, batteries, and hydraulic and transmission fluids			2/
	Cover all vehicle and equipment repair areas with a permanent roof of or canopy.		(0)	
•	Connect outdoor vehicle storage areas to a separate stormwater collection system with an oil/grit separator-or, sand filter, or other accepted pretreatment device or BMP.	\$\frac{1}{2}		
	Designate a specific location for outdoor maintenance activities that is designed to prevent stormwater pollution (paved, away from storm drains, and with stormwater containment measures)	SIL		
	Stencil or mark storm drain inlets with "No Dumping, Drains to" message	R		

	For official use only:	
Date of Submission:	Reviewed by:	
Date Received:	Reviewed on:	Plan Accepted: Y/N
_		

Instructions: Complete this table only if operation H-2 was checked on Page $\underline{\mathcal{GP}}$.2.

	H-2 Vehicle Fueling		
Description of Operation			
Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
Cover fueling stations with a canopy or roof to prevent direct contact with rainfall.			1
Design fueling pads to prevent the run-on of stormwater and pretreat any runoff with an oil/grit separator-or-a, sand filter, or other accepted pretreatment device or BMP.		, C	0,
Locate storm drain inlets away from the immediate vicinity of the fueling area			
Stencil or mark storm drain inlets with "No Dumping, Drains to" message.	Q-1		
Pave fueling stations with concrete rather than asphalt			

For official use only:			
Date of Submission:	Reviewed by:		
Date Received:	Reviewed on:	Plan Accepted: Y / N	

Instructions: Complete this table only if operation H-3 was checked on Page $F\underline{P}$.2.

H-3 Vehicle Washing			
Description of Operation			
Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
Include flow-restricted hose nozzles that automatically turn off when left unattended.			
Provide a containment system for washing vehicles such that wash water does not flow into storm drain system.			O_{ℓ}
Label storm drain inlets with "No Dumping, Drains to" signs to deter disposal of wash water in the storm drain system.			
Design facilities with designated areas for indoor vehicle washing where no other activities are performed (e.g., fluid changes or repair services).	2		

For official use only:			
Date of Submission:	Reviewed by:		
Date Received:	Reviewed on:	Plan Accepted: Y/N	

Instructions: Complete this table only if operation H-4 was checked on Page $\underline{\mathcal{GP}}$.2.

Description of Operation			
Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
abel storm drain inlets with "No Dumping, Drains to" nessage Design liquid storage areas with impervious surfaces und secondary containment.			S
HMinimize stormwater runoff from the fleet run-on by covering storage area must receive pretreatment via an oil/grit reparatorareas with a permanent ranopy or sand filter roof.		16	
Untreated stormwater from the Teet storage area may not be Hischarged off site.			
Connect outdoor vehicle storageSlope containment areas to a separate stormwater collection system drain with an oil/grit separatora positive control (lock, valve, or sand filerplug) that leads to the sanitary sewer (if permitted) or to a holding tank.	SKO		
Provide permanent cover for building materials stored outside. Direct runoff away from building material storage areas.	00		
nstall a high-level alarm on torage tanks to prevent werfilling.	08-		

For official use only:

Date of Submission:	Reviewed by:	
	Reviewed on:	Plan Accepted: Y/N



Instructions: Complete this table only if operation H-5 was checked on Page $\underline{\mathcal{GP}}$.2.

H-5 Loading and UnloadingH-5 Outdoor or Bulk Material Storage			
Description of Operation	(Include methods of storage, usage, treatment, and disposal.)		
Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
Design liquid storage areas with impervious surfaces and secondary containment Grade the designated loading and unloading to prevent run-on or pooling of stormwater.			0
Minimize stormwater run on by covering storageCover the loading and unloading areas with a permanent canopy or roof.		10	
Slope containment areas to a drain with a positive control (lock, valve, or plug) that leads to the sanitary sewer (if permitted) or to a holding tank Install an automatic shutoff valve to interrupt flow in the event of a liquid spill.			
Provide permanent cover for building materials stored outside install a high-level alarm on storage tanks to prevent overfilling.	205		
Direct runoff away from building material storage areas Pave the loading and unloading area with concrete rather than asphalt.	00		
Install a high level alarm on storage tanks to prevent overfillingPosition roof downspouts to direct stormwater away from loading and unloading areas.			
For official use only:			
Date of Submission:	Reviewed by:		
Date Received:	Reviewed on:	Plan Accep	ted: Y / N



PROPOSED REVISION

Instructions: Complete this table only if operation H-6 was checked on Page Q.2.

	H-6 Outdoor or Bulk Material Storage		
Description of Operation	(include methods of storage, usage, treatment, and dis	posal).	
Requirement	Description of pollution prevention mechanism or BMP to be implemented	Site Plan Sheet Number(s)	Approved (for official use only)
Grade the designated loading/unloading to prevent run on or pooling of stormwater			
Cover the loading/unloading areas with a permanent canopy or roof			
Install an automatic shutoff valve to interrupt flow in the event of a liquid spill	.()`		
Install a high level alarm on storage tanks to prevent overfilling			
Pave the loading/unloading area with concrete rather than asphalt			
Position roof downspouts to direct stormwater away from loading/unloading areas	2		
	\O_*		
	For official use only:		
Date of Submission: Date Received:	Reviewed by:	Plan Accep	pted: Y / N
	3		

PROPOSED REVISION PROPOSED REVISION REV

P.4 Hotspot Operation Pollution Prevention Profile Sheets

The following profile sheets include the following:

- H-1 Vehicle Maintenance and Repair
- H-2 Vehicle Fueling
- H-3 Vehicle Washing
- H-4 Vehicle Storage
- H-5-Outdoor Materials Loading and Unloading
- H-65 Outdoor or Bulk Material Storage

PROPOSED PENISION PROPOSED PRO

	Hotspot Source Area: Vehicles	
H-l	VEHICLE MAINTENANCE AND REPAIR	

Description

PROPOSED PENISION PROPOSED PRO

H-1 Vehicle Maintenance and Repair

Vehicle maintenance and repair operations can exert a significant impact on water quality by generating toxins such as solvents, waste oil, antifreeze, and other fluids. Often, vehicles that are wrecked or awaiting repair can be a stormwater hotspot if leaking fluids are exposed to stormwater runoff (Figure P.1). Vehicle maintenance and repair can generate oil and grease, trace metals, hydrocarbons, and other toxic organic compounds. Table 1



Figure P.1 Vehicle yard.

The following summarizes a series of simple pollution prevention techniques for vehicle maintenance and repair operations that can prevent stormwater contamination. You are encouraged to consult Consult the Resources section of this sheet to getbelow for a more comprehensive review of pollution prevention practices for vehicle maintenance and repair operations.

Application

Avoid hosing down work or fueling areas.

- Clean all spills immediately using dry cleaning techniques.
- Collect used antifreeze, oil, grease, oil
 filters, cleaning solutions, solvents,
 batteries, and hydraulic and transmission
 fluids, and recycle with appropriate
 agencies.
- Conduct all vehicle and equipment repairs indoors or under a cover (if done outdoors).
- Connect outdoor vehicle storage areas to
 a separate stormwater collection system
 with an oil/grit separator that discharges
 to a dead holding tank, the sanitary
 sewer, or a stormwater treatment
 practice.
- Designate a specific location for outdoor maintenance activities that is designed to prevent stormwater pollution (i.e., paved, away from storm drains, and with stormwater containment measures).
- Inspect the condition of all vehicles and equipment stored outdoors frequently.
- Use tarps, ground cloths, or drip pans beneath vehicles or equipment being repaired outdoors to capture all spills and drips.
- Seal service bay concrete floors with an impervious material so cleanup can be done without using solvents. Do not wash service bays to outdoor storm drains.
- Store cracked batteries in a covered secondary containment area until they can be disposed of properly.
- Wash parts in a self-contained solvent sink rather than outdoors.

Pollution prevention practices should be applied to any facility that maintains or repairs vehicles in a subwatershed. Examples include car dealerships, body

shops, service stations, quick lubes, school bus depots, trucking companies, and fleet maintenance operations at larger industrial, institutional, municipal, or transport-related operations. Repair facilities are often clustered together, and

are a major priority for subwater shed

pollution prevention.

Table 1: Pollution Prevention Practices for Vehicle Maintenance and Repair Activities

- Avoid hosing down work or fueling areas
- Clean all spills immediately using dry cleaning techniques
- Collect used antifreeze, oil, grease, oil filters, cleaning solutions, solvents, batteries, hydraulic
 and transmission fluids and recycle with appropriate agencies
- Conduct all vehicle and equipment repairs indoors or under a cover (if done outdoors)
- Connect outdoor vehicle storage areas to a separate stormwater collection system with an oil/grit separator that discharges to a dead holding tank, the sanitary sewer or a stormwater treatment practice
- Designate a specific location for outdoor maintenance activities that is designed to prevent stormwater pollution (paved, away from storm drains, and with stormwater containment measures)
- Inspect the condition of all vehicles and equipment stored outdoors frequently
- Use a tarp, ground cloth, or drip pans beneath vehicles or equipment being repaired outdoors to capture all spills and drips
- Seal service bay concrete floors with an impervious material so cleanup can be done without using solvents. Do not wash service bays to outdoor storm drains
- Store cracked batteries in a covered secondary containment area until they can be disposed of properly
- * Wash parts in a self-contained solvent sink rather than outdoors

Primary Training Targets

Owners, fleet operation managers, service managers, maintenance supervisors, mechanics and other employees are key targets for training.

Feasibility

Pollution prevention techniques for vehicle repair facilities broadly apply to all regions and climates. These techniques generally rely on changes to basic operating procedures, after an initial inspection of facility operations. The inspection relies on a standard operations checklist that can be completed in a few hours.

Implementation Considerations

Employee training is essential to successfully implement vehicle repair pollution prevention practices. The connection between the storm drain system and local streams should be emphasized so that employees understand why any fluids need to be properly disposed of. It is also important to understand the demographics of the work force; in some communities, it may require a multilingual education program. See Table P.1 for employee training implementation considerations.

Cost—Employee training is generally inexpensive, since training can be done using posters, pamphlets, or videos. Structural practices can vary based on what equipment is required. For instance, solvent sinks to clean parts can cost from \$1,500 to \$15,000, while spray cabinets may cost more than \$50,000. In addition, proper recycling/disposal of used or spilled fluids usually requires outside contractors that may increase costs.

Table P.1 Pollution Prevention Considerations for Vehicle Maintenance and Repair

Consideration	Description			
Primary Targets for Employee Training	Owners, fleet operation managers, service managers, maintenance supervisors, mechanics, and other employees are key targets for training.			
Feasibility of Prevention Techniques	Pollution prevention echniques for vehicle repair facilities broadly apply to all regions and climates. These techniques generally rely on changes to basic operating procedures, after an initial inspection of facility operations. The inspection relies on a standard operations checklist that can be completed in a few hours.			
Cost	Employee training is generally inexpensive, since training can be done using posters, pamphlets, or videos. Structural practices can vary based on what equipment is required. For instance, solvent sinks to clean parts can cost from \$1,500 to \$15,000, while spray cabinets may cost more than \$50,000. In addition, proper recycling/disposal of used or spilled fluids usually requires outside contractors that may increase costs.			

Resources

Stormwater Management Manual for Western Washington: Volume IV -- Source Control BMPs. http://www.cey.wa.gov/biblio/9914.html

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: Industrial and Commercial. http://www.cabmphandbooks.com/

Coordinating Committee For Automotive Repair (CCAR) Source: US EPA CCAR-GreenLink®, the National Automotive Environmental Compliance Assistance Center CCAR-GreenLink® Virtual Shop http://www.ccar_greenlink.org/

Auto Body Shops Pollution Prevention Guide. Peaks to Prairies Pollution Prevention Information Center. http://peakstoprairies.org/p2bande/autobody/abguide/index.cfm

<u>California Stormwater Quality Association. 2003 California Stormwater BMP Handbook:</u> <u>Industrial and Commercial. http://www.cabmphandbooks.com/</u>

<u>City of Los Angeles Bilingual Poster of BMPs for Auto Repair Industry.</u> http://www.lastormwater.org/wp-content/files_mf/bmp_auto_poster_8.5x14.pdf

<u>City of Santa Cruz. Best Management Practices for Vehicle Service Facilities (in English and Spanish).</u> http://www.cityofsantacruz.com/home/showdocument?id=6038

<u>Coordinating Committee For Automotive Repair (CCAR) Source: US EPA CCAR-GreenLink®, the National Automotive Environmental Compliance Assistance Center CCAR-GreenLink® Virtual Shop http://www.ccar-greenlink.org/</u>

Massachusetts Office of Technical Assistance (OTA). Crash Course for Compliance and Pollution Prevention Toolbox.

 $\underline{\text{http://www.mass.gov/eea/grants-and-tech-assistance/education-and-training/education-and-outreach/ota-publications/guidance-docs/crash-course.html}$

Model Urban Runoff Program: A How-To Guide for Developing Urban Runoff Programs for Small Municipalities. http://www.swrcb.ca.gov/water_issues/programs/stormwater/murp.shtml

<u>Stormwater Management Manual for Western Washington: Volume IV -- Source Control BMPs.</u> http://www.ecy.wa.gov/biblio/9914.html

US EPA. Facility Regulatory Tour: Vehicle Maintenance. https://www.fedcenter.gov/assistance/facilitytour/vehicle/

H-2 Vehicle Fueling

PROPOSED REVISION PROPOSED REVISION

City of Santa Cruz. Best Management
Practices for Vehicle Service Facilities (in
English and Spanish).

http://www.cityofsantacruz.com/Modules/ShowDocument.aspx?documentid=5989

City of Los Angeles Bilingual Poster of BMPs for Auto Repair Industry.

http://www.lastormwater.org/wp_content/files_mf/bmp_auto_poster_8.5x14.pd f



Hotspot Source Area: Vehicles

H-2

VEHICLE FUELING



Description

Spills at vehicle fueling operations have the potential to directly contribute oil, grease, and gasoline to stormwater, and can be a significant source of lead, copper-and, zinc, and petroleum hydrocarbons. Delivery of pollutants to the storm drain can be sharply reduced by well-designed fueling areas and improved operational procedures. The risk of spills depends on whether the fueling area is covered and has secondary containment. The type, condition, and exposure of the fueling surface can also be important. Table 4The following describes common pollution prevention practices for fueling operations. Consult the Resources section below for a more comprehensive review of pollution prevention practices for vehicle fueling.

- Maintain an updated spill prevention and response plan on premises of all fueling facilities.
- Cover fueling stations with a canopy or roof to prevent direct contact with rainfall.
- Design fueling pads for large mobile equipment to prevent the run-on of stormwater and collect any runoff in a dead-end sump.
- Keep suitable cleanup materials on the premises to promptly clean up spills.
- Install slotted inlets along the perimeter of the "downhill" side of fueling stations to collect fluids and connect the drain to a waste tank or stormwater treatment practice. The collection system should

<u>have a shutoff valve to contain a large</u> <u>fuel spill event.</u>

- Locate storm drain inlets away from the immediate vicinity of the fueling area.
- <u>Clean fuel-dispensing areas with dry</u> <u>cleanup methods. Never wash down</u> <u>areas before dry cleanup has been done.</u>



Figure 1: Covered Retail Gas Operation
Without Containment for Potential
Ensure that wash water is collected and
disposed of in the sanitary sewer system
or approved stormwater treatment
practice.

Pave fueling stations with concrete rather than asphalt.

Protect above ground fuel tanks using a containment berm with an impervious floor of Portland cement. The containment berm should have enough capacity to contain 110

Application

- % of the total tank volume.
- Use fuel-dispensing nozzles with automatic shutoffs, if allowed.

 Consider installing a perimeter sand filter to capture and treat any runoff produced by the station.

These practices can be applied to any facility that dispenses fuel. Examples include retail gas stations, bus depots, marinas, and fleet maintenance operations (Figure 4<u>P.2</u>). In addition, these practices also apply to temporary above-ground

fueling areas for construction and earthmoving equipment. Many fueling areas are usually present in urban subwatersheds, and they tend to be clustered along commercial and highway corridors. These hotspots are often a priority for subwatershed source control.



Figure P.2 Covered Retail Gas Operation Without Containment for Potential Spills.

Employee training is essential to successfully implement vehicle fueling pollution prevention practices. See Table P.2 for employee training implementation considerations.

Table P.2 Pollution Prevention Considerations for Fueling Operation Areas

Consideration	<u>Description</u>	
Primary Targets for Employee Training	Training efforts should be targeted to owners, operators, attendants, and petroleum wholesalers.	
Table 1: PollutionFeasibility of Prevention Practices For Fueling Operation AreasTechniques	Vehicle fueling pollution prevention practices apply to all geographic and climatic regions. The practices are relatively low-cost, except for structural measures that are installed during new construction or station remodeling.	
Fueling Area Covers	Maintain-Fueling areas can be covered by installing an updated spill prevention overhanging roof or canopy. Covers prevent exposure to rainfall and response plan on premises of allare a desirable amenity for retail fueling facilities (see Profile Sheet H 7) Cover station customers. The area of the fueling stations with a eanopycover should exceed the area where fuel is dispensed. All downspouts draining the cover or roof should be routed to prevent direct contact with rainfall	

Inserted Cells

Inserted Cells

	 Designdischarge across the fueling pads forarea. If large mobile equipment to prevent the run on ofmakes it difficult to install covers or roofs, fueling islands should be designed to prevent stormwater run-on through grading, and collect any runoff in a from the fueling area should be directed to a dead-end sump Retrofit underground storage tanks with spill containment and overfill prevention systems Keep suitable cleanup materials on the premises to promptly clean up spills Install slotted inlets along the perimeter of the "downhill" side of fueling stations to collect fluids and connect the drain to a waste tank or stormwater treatment practice. The collection system should have a shutoff valve to contain a large fuel spill event Locate storm drain inlets away from the immediate vicinity of the fueling area Clean fuel dispensing areas with dry cleanup methods 	
	* Clean fuel-dispensing areas with dry cleanup methods. Never wash down areas before dry cleanup has been done. Ensure that wash water is collected and disposed of in the sanitary sewer system or approved stormwater treatment practice * Pave fueling stations with concrete rather than asphalt * Protect above ground fuel tanks using a containment berm with an impervious floor of Portland coment. The containment berm should have enough capacity to contain 110 percent of the total tank volume * Use fuel-dispensing nozzles with automatic shutoffs, if allowed Consider installing a perimeter sand filter to capture and treat any runoff produced by the station	
Surfaces	Fuel dispensing areas should be paved with concrete; the use of asphalt should be avoided, unless the surface is sealed with an impervious sealant. Concrete pads used in fuel dispensing areas should extend to the full length that the hose and nozzle assembly can be pulled, plus an additional foot.	
Grading	Fuel dispensing areas should be graded with a slope that prevents ponding and is separated from the rest of the site by berms, dikes, or other grade breaks that prevent run-on of urban runoff. The recommended grade for fuel dispensing areas is 2%–4%.	
Cost	Costs to implement pollution prevention practices at fueling stations will vary, with many of the costs coming upfront during the design of a new fueling facility. Once a facility has implemented, the ongoing maintenance costs should be low.	

Primary Training Targets

'raining efforts should be targeted to owners, perators, attendants, and petroleum wholesalers

Feasibility

Vehicle fueling pollution prevention practices apply to all geographic and climatic regions. The practices are relatively low cost, except Resources for structural measures that are installed during new construction or station remodeling.

Implementation Considerations

Fueling Area Covers — Fueling areas can be covered by installing an overhanging roof or canopy. Covers prevent exposure to rainfall and are a desirable amenity for retail fueling station customers. The area of the fueling cover should exceed the area where fuel is dispensed. All downspouts draining the cover or roof should be routed to prevent discharge across the fueling area. If large equipment makes it difficult to install covers or roofs, fueling islands should be designed to prevent stormwater run on through grading, and any runoff from the fueling area should be directed to a dead end sump.

Surfaces -

<u>Alachua County, FL Best Management</u> <u>Practices for Controlling Runoff from Gas</u> <u>Stations</u>

 $\frac{http://www.alachuacounty.us/Depts/EPD/Do}{cuments/WaterResources/Gas\%20Stations.p} \\ df$

Fuel dispensing areas should be paved with concrete the use of asphalt should be avoided, unless the surface is sealed with an impervious sealant.

Concrete pads used in fuel dispensing areas should extend to the full length that the hose and nozzle assembly can be pulled, plus an additional foot.

Grading—Fuel dispensing areas should be graded with a slope that prevents ponding, and separated from the rest of the site by berms, dikes or other grade breaks that prevent run on of urban runoff. The recommended grade for fuel dispensing areas is 2–4 percent (CSWQTF, 1997).

Cost Costs to implement pollution prevention practices at fueling stations will vary, with many of the costs coming upfront during the design of a new fueling facility. Once a facility has implemented the, ongoing maintenance costs should be low.

Resources

Best Management Practice Guide – Retail Gasoline Outlets. Prepared by Retail Gasoline Outlet Work Group.

http://www.waterboards.ca.gov/rwqcb4/water_issues/programs/stormwater/municipal/los_angeles_ms4/tentative/rgo%20bmp%20guide 03-97_.pdf

Stormwater Management Manual for
Western Washington: Volume IV - Source
Control BMPs.
http://www.ecv.wa.gov/biblio/9914.html

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: New Development and Redevelopment.

http://www.cabmphandbooks.com/ http://www.cabmphandbooks.com/

City of Los Angeles, CA Best Management
Practices for Gas Stations
http://www.lacitysan.org/watershed_protect
on/pdfs/gasstation.pdf

City of Dana Point Tips for the Automotive Industry

http://www.danapoint.org/Modules/ShowDocument.aspx?documentid=3309

Alachua County, FL Best Management
Practices for Controlling Runoff from Gas
Stationshttp://www.alachuacounty.us/Depts/
EPD/Documents/WaterResources/Gas%20S
tations.pdf

California Stormwater Regional Control
Board Retail Gasoline Outlets: New
Development Design Standards For
Mitigation Of Stormwater Impacts
http://www.waterboards.ca.gov/rwqcb4/water-issues/programs/stormwater/municipal/los-angeles-ms4/tentative/rgopaper.pdf

http://www.waterboards.ca.gov/rwqcb4/water_issues/programs/stormwater/municipal/los_angeles_ms4/tentative/rgopapersupplement_12-01_.pdf

Canadian Petroleum Products Institute Best Management Practices Stormwater Runoff from Petroleum Facilities
http://canadianfuels.ca/userfiles/file/CPPI%20-
20-
<

City of Monterey (CA). Posters of Gas Station BMPs.

<u>City of Los Angeles, CA Best Management</u> <u>Practices for Gas Stations</u> <u>http://www.lacitysan.org/watershed_protection/pdfs/gasstation.pdf</u>

<u>City of Dana Point Tips for the Automotive</u> <u>Industry</u>

http://www.danapoint.org/Modules/ShowDocument.aspx?documentid=3309

Pinole County, CA Typical Stormwater
Violations Observed in Auto Facilities and
Recommended Best Management
Practices (BMPs)
http://www.ci.pinole.ca.us/publicworks/downloads/AutoStormwater.pdf

	Hotspot Source Area: Vehicles	1
H-3	VEHICLE WASHING	

Description

Source Control BM

PROPROSELLA Stormwater Management Manual for Western Washington: Volume IV -- Source Control BMPs. http://www.ecy.wa.gov/biblio/9914.html

H-3 Vehicle Washing

Vehicle washing pollution prevention practices apply to many commercial, industrial, institutional, municipal, and transport-related operations. Vehicle wash water may contain sediments, phosphorus, metals, oil and grease, and other pollutants that can degrade water quality. When vehicles are washed on impervious surfaces such as parking lots or industrial areas, dirty wash water can contaminate stormwater that ends up in streams.

Application

Improved washing practices can be used at any facility that routinely washes vehicles. Examples include commercial car washes, bus depots, car dealerships, rental car companies, trucking companies, and fleet operations. In addition, washing dump trucks and other construction equipment can be a problem. Washing operations tend to be unevenly distributed within urban subwatersheds. Vehicle washing also occurs in neighborhoods, and techniques to keep wash water out of the storm drain system are discussed in the car washing profile sheet (N-11). Table 1 reviews The following provides some of the pollution prevention techniques available for hotspot vehicle washing operations. Consult the Resources section below for a more comprehensive review of pollution prevention practices for vehicle washing.

Primary Training Targets

Owners, fleet managers, and employees of operations that include Wash vehicles at indoor car washes are the primary training target.

Feasibility

- that recycle, treat, or convey. Vehicle washing practices can be applied to all regions and climates. Vehicle washing tends to occur more frequently in summer months and in drier regions of the country. Sound vehicle washing practices are not always used at many sites because operators are reluctant to change traditional cleaning methods. In addition, the cost of specialized equipment to manage high volumes of wash water can be too expensive for small businesses to the sanitary sewer system.
- Use biodegradable, phosphate-free, waterbased soaps.
- Use flow-restricted hose nozzles that automatically turn off when left unattended.
- Wash vehicles on a permeable surface or a washpad that has a containment system.
- Prohibit discharge of wash water into the storm

Table 1: Pollution Prevention Practices for Vehicle Washing

- Wash vehicles at indoor car washes that recycle, treat or convey wash water to the sanitary sewer system
- Use biodegradable, phosphate free, waterbased soaps
- Use flow restricted hose nozzles that automatically turn off when left unattended
- Wash vehicles on a permeable surface or a washpad that has a containment system
- Prohibit discharge of wash water into the storm drain system or ground by using temporary berms, storm drain covers, drain plugs or other containment system
- Label storm drains with "No Dumping" signs to deter disposal of wash water in the storm drain system
- Pressure and steam clean off site to avoid runoff with high pollutant concentrations
- Obtain permission from sewage treatment facilities to discharge to the sanitary sewer

drain system or ground by using temporary berms, storm drain covers, drain plugs, or other containment system.

- Label storm drains with "No Dumping" signs to deter disposal of wash water in the storm drain system.
- Pressure and steam clean offsite to avoid runoff with high pollutant concentrations.
- Obtain permission from sewage treatment facilities to discharge to the sanitary sewer.

Recording action, and should

P-27

Implementation Considerations

The ideal practice is to wash all vehicles at commercial car washes or indoor facilities that are specially designed for washing operations. Table 2The following offers some tips for indoor car wash sites:

- Facilities should have designated areas for indoor vehicle washing where no other activities are performed (e.g., fluid changes or repair services).
- Indoor vehicle wash areas should have floor drains that receive only vehicle washing wastewater (not floor washdown or spill removal wash waters) and be connected to a holding tank with a gravity discharge pipe, to a sump that pumps to a holding tank, or to an oil/grit separator that discharges to a municipal sanitary sewer.
- The floor of indoor vehicle wash bays should be completely bermed to collect wash water.
- Aromatic and chlorinated hydrocarbon solvents should be eliminated from vehicle-washing operations.
- Vehicle-washing operations should use vehicle rinse water to create new wash water using recycling systems that filter and remove grit.

Table 2: Tips for Indoor Car Wash Sites (Adapted from U.S. EPA. 2003)

 Facilities should have designated areas for indoor vehicle washing where no other activities are performed (e.g., fluid changes When washing operations are conducted outside, a designated wash area should have the following characteristics:

 Paved with an impervious surface, such as Portland cement concrete.

- Bermed to contain wash water.
- Sloped so that wash water is collected and discharged to the sanitary sewer system, holding tank, or dead-end sump.
- Operated by trained workers to confine washing operations to the designated wash area.

Outdoor vehicle washing facilities should use pressurized hoses without detergents to remove most dirt and grime. If detergents are used, they should be phosphate-free to reduce nutrient loading. If acids, bases, metal brighteners, or degreasing agents are used, wash water should be discharged to a treatment facility, sanitary sewer, or a sump. In addition, waters from the pressure washing of engines and vehicle undercarriages must be disposed of using the same options.

or repair services)

- * Indoor vehicle wash areas should have floor drains that receive only vehicle washing wastewater (not floor washdown or spill removal wash waters) and be connected to a holding tank with a gravity discharge pipe, to a sump that pumps to a holding tank, or to an oil/grit separator that discharges to a municipal sanitary sewer
- The floor of indoor vehicle wash bays should be completely bermed to collect wash water
- Aromatic and chlorinated hydrocarbon solvents should be eliminated from vehicle-washing operations
- Vehicle washing operations should use vehicle rinse water to create new wash water through the use of recycling systems that filter and remove grit.

Discharge to pervious areas may be an option for washing operations that generate small amounts of relatively clean wash water (water only—__no soaps, no steam cleaning). The clean wash water should be directed as sheet flow across a vegetated area to infiltrate or evaporate before it enters the storm drain system. This option should be exercised with caution, especially in environmentally sensitive areas or protected groundwater recharge areas.

The best way to avoid stormwater contamination during washing operations is to drain the wash water to the sanitary sewer system. Operations that produce high volumes of wash water should consider installing systems that connect to the sewer. Other options for large and small operations include containment units to capture the wash water prior to transport away for proper disposal (Figure 4P.3). If vehicles must be washed on an impervious surface, a storm drain filter should be used to capture solid contaminants.

Cost—The cost of using vehicle washing practices can vary greatly and depends on the size of the operation (Table 3). The cost of constructing a commercial grade system connected to the sanitary sewer can exceed \$100,000. Disposal fees and frequency of washing can also influence the cost.



Training costs can be minimized by using educational materials available from local governments, professional associations or EPA's National Compliance Assistance Centers



(http://www.assistancecenters.net/).

Figure P.3 Containment System Preventing Wash Water from Entering the Storm Drain.

Employee training is essential to successfully implement vehicle washing pollution prevention practices. See Table P.3 for employee training implementation considerations.

Table P.3 Pollution Prevention Considerations for Vehicle Washing Areas

Temporary, portable containment systems can be shared by several companies that cannot afford specialized companies that cannot afford specialized

п		
	Consideration	<u>Description</u>
	Primary Targets for Employee Training	Owners, fleet managers, and employees of operations that include car washes are the primary training target.
	Feasibility of Prevention Techniques	Vehicle washing practices can be applied to all regions and climates. Vehicle washing tends to occur more frequently in summer months and in drier regions of the country. Sound vehicle washing practices are not always used at many sites because operators are reluctant to change traditional cleaning methods. Additionally, the cost of specialized equipment to manage high volumes of wash water can be too expensive for small businesses. Improved vehicle washing practices are relatively simple to implement and are very effective at preventing stormwater contamination. Training is essential to get owners and employees to adopt these practices, and should be designed to overcome cultural and social barriers to improved washing practices. Table 3: Sample Equipment Costs for Vehicle Washing Practices
	Cost	The cost of using vehicle-washing practices can vary greatly and depends on the size of the operation (Table P.4). The cost of constructing a commercial grade system connected to the sanitary sewer can exceed \$100,000. Disposal fees and frequency of washing can also influence the cost.

Inserted Cells

Training costs can be minimized by using educational materials available from local governments, professional associations, or EPA's National Compliance Assistance Centers (http://www.assistancecenters.net/). Temporary, portable containment systems can be shared by several companies that cannot afford specialized equipment independently.

Table P.4 Sample Equipment Costs for Vehicle Washing Practices

Item	Cost	
Bubble Buster	\$2,000–\$2,500*	
Catch basin insert	\$65*	
Containment mat	\$480-\$5,840**	
Storm drain cover (24-in. drain)	\$120-**	
Pump	\$75-\$3,000**	
Water dike/ berm (20 ft)	\$100.00-**	
Wastewater storage container	\$50-\$1,000+**	701
Source: *U.S. EPA, 1992 -**Robins	son, 2003	

Resources

EPA FedSite Facility Regulatory Tour: http://www.fedcenter.gov/assistance/facilitytour/vehicle/washing/

Alachua County BMP for Outdoor Car Washing.

http://www.alachuacounty.us/Depts/EPD/WaterResources/StormwaterPollutionAndSolutions/Re ducing%20Stormwater%20Pollution%20Documents/Carwash%20BMP.pdf

<u>California Stormwater Quality Association. 2003 California Stormwater BMP Handbook:</u> Industrial and Commercial. http://www.cabmphandbooks.com/

Figure 1: Containment System Preventing Wash Water from Entering the Storm Drain

EPA FedSite Facility Regulatory Tour:

http://www.fedcenter.gov/assistance/facilitytour/vehicle/washing/

Kitsap County Sound Car Wash Program. http://www.kitsapgov.com/sswm/carwash.htm.

Robinson, C., Proprietor, "Latimat" portable wastewater containment system. Personal Communication June 2, 2003. http://www.latimat_systems.htm

Washington Department of Ecology. 1995. Vehicle and Equipment Wash Water Discharges: Best Management Practices Manual. Olympia, Washington. http://www.ecy.wa.gov/pubs/95056.pdf

U.S. Environmental Protection Agency. Pollution Prevention/Good Housekeeping for Municipal Operations. http://cfpub2.epa.gov/npdes/stormwater/menuofbmps/poll-18.cfmhttp://water.epa.gov/polwaste/npdes/swbmp/Pollution-Prevention-Good-Housekeeping-for-Municipal-Operatators.cfmhttp://cfpub2.epa.gov/npdes/swbmp/Pollution-Prevention-Good-Housekeeping-for-Municipal-Operatators.cfm

<u>U.S. EPA. 1992. Storm Water Management for Industrial Activities: Developing Pollution Prevention Plans and Best Management Practices. US EPA Office of Wastewater Management. Washington, D.C. EPA 832-R-92-006</u>



H-4 Outdoor Materials Loading and Unloading

U.S. EPA. 1992. Storm Water Management for Industrial Activities: Developing Pollution Prevention Plans and Best Management Practices. US EPA Office of Wastewater Management. Washington, D.C. EPA 832-R-92-006.

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: Industrial and Commercial. http://www.cabmphandbooks.com/

Description

Parking lots and vehicle storage areas can introduce sediment, metals, oil and grease, and trash into stormwater runoff. Simple pavement sweeping, litter control, and stormwater treatment practices can minimize pollutant export from these hotspots. Table 1 provides a list of simple pollution prevention practices intended to prevent or reduce the discharge of pollutants from parking and vehicle storage areas.

Application

Pollution prevention practices can be used at larger parking lots located within a subwatershed. Examples include regional malls, stadium lots, big box retail, airport parking, car dealerships, rental car companies, trucking companies, and fleet operations (Figure 1). The largest, most heavily used parking lots with vehicles in the poorest condition (e.g., older cars or wrecked vehicles) should be targeted first.

This practice is also closely related to parking lot maintenance source controls, which are discussed in greater detail in profile sheet H-11.

Primary Training Targets

Owners, fleet operation managers, and property managers that maintain parking lots are key training targets.



Figure 1: Retail Parking Lot

Table 1: Pollution Prevention Practices for Parking Lot and Vehicle Storage Area

Parking Lots

- Post signs to control litter and prevent patrons from changing automobile fluids in the parking lot (e.g., changing oil, adding transmission fluid, etc.)
- Pick up litter daily and provide trash receptacles to discourage littering
- Stencil or mark storm drain inlets with "No Dumping, Drains to _____" message
- Direct runoff to bioretention areas, vegetated swales, or sand filters
- Design landscape islands in parking areas to function as bioretention areas
- Disconnect rooftop drains that discharge to paved surfaces
- Use permeable pavement options for spillover parking (Profile sheet OS-11 in Manual 3)
- Inspect catch basins twice a year and remove accumulated sediments, as needed
- Vacuum or sweep large parking lots on a monthly basis, or more frequently
- Install parking lot retrofits such as bioretention, swales, infiltration trenches, and stormwater filters (Profile sheets OS 7 through OS 10 in Manual 3)

Vehicle Storage Areas

- Do not store wrecked vehicles on lots unless runoff containment and treatment are provided
- Use drip pans or other spill containment measures for vehicles that will be parked for extended periods of time
- Use absorbent material to clean up automotive fluids from parking lots

Feasibility

Sweeping can be employed for parking lots that empty out on a regular basis.

Mechanical sweepers can be used to remove small quantities of solids. Vacuum sweepers should be used on larger parking lot storage areas, since they are superior in picking up deposited pollutants (see Manual 9). Constraints for sweeping large parking lots include high annual costs, difficulty in controlling parking, and the inability of current sweeper technology to remove oil and grease. Proper disposal of swept materials might also represent a limitation.

Implementation Considerations

The design of parking lots and vehicle storage areas can greatly influence the ability to treat stormwater runoff. Many parking areas are landscaped with small vegetative areas between parking rows for aesthetic reasons or to create a visual pattern for traffic flow. These landscaped areas can be modified to provide stormwater treatment in the form of bioretention (Figure 2).



Figure 2: Parking Lot Island Turned Bioretention

Catch basin cleanouts are also an important practice in parking areas. Catch basins within the parking lot should be inspected at least twice a year and cleaned as necessary. Cleanouts can be done manually or by vacuum truck. The cleanout method selected depends on the number and size of the inlets present (see Manual 9).

Most communities have contractors that can be hired to clean out catch basins and vacuum sweep lots. Mechanical sweeping services are available, although the cost to purchase a new sweeper can exceed \$200,000. Employee training regarding spill prevention for parking areas is generally low cost and requires limited staff time.

Resources

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: Industrial and Commercial http://www.cabmphandbooks.com/

Stormwater Management Manual for Western Washington: Volume IV -- Source Control BMPs. WA Dept. of Ecology http://www.ecy.wa.gov/biblio/9914.html

ea: Outdoor Materials

D UNLOADING



Description

Outdoor loading and unloading normally takes place on docks or terminals at many commercial, industrial, institutional, and municipal operations. Materials spilled or leaked during this process can either be carried away in stormwater runoff or washed off when the area is cleaned. As a result, many different pollutants can be introduced into the storm drain system, including sediment, nutrients, trash, organic material, trace metals, and an assortment of other pollutants. A number of Many simple and effective pollution prevention practices can be used at loading and unloading areas to prevent runoff contamination, as shown in Table 1 listed below. Consult the Resources section below for a more comprehensive review of pollution prevention practices for outdoor materials loading and unloading.

Application

- Use seals, overhangs, or door skirts on docks and terminals to prevent contact with stormwater.
- Avoid loading and unloading materials in the rain.

Table 1: Pollution Prevention Practices for Loading and Unloading Areas

- Avoid loading/unloading materials in the rain
- Close adjacent storm drains during loading/unloading operations
- Surround the loading/unloading area with berms or grading to prevent run on or pooling of stormwater. If
 possible, cover the area with a canopy or roof
- Ensure that a trained employee is always present to handle and cleanup spills
- Inspect the integrity of all containers before loading/unloading.
- Inspect equipment such as valves, pumps, flanges, and connections regularly for leaks, and repair as needed.
- Install an automatic shutoff valve to interrupt flow in the event of a catastrophic liquid spill
- Install a high level alarm on storage tanks to prevent overfilling
- Pave the loading/unloading area with concrete rather than asphalt
- Place drip pans or other temporary containment devices at locations where leaks or spills may occur, and always use pans when making and breaking connections
- Position roof downspouts to direct stormwater away from loading/unloading areas and into bioretention areas
- Prepare and implement an Emergency Spill Cleanup Plan for the facility (see Profile Sheet H 7)
- Sweep loading/unloading area surfaces frequently to remove material that could otherwise be washed off by stormwater
- Train all employees, especially fork lift operators, on basic pollution prevention practices and post signs
- Use seals, overhangs, or door skirts on docks and terminals to prevent contact with rainwater.
- Close adjacent storm drains during loading and unloading operations.
- Surround the loading and unloading area with berms or grading to prevent run-on or pooling of stormwater. If possible, cover the area with a canopy or roof.
- Ensure that a trained employee is always present to handle and clean up spills.
- Inspect the integrity of all containers before loading and unloading.
- Inspect equipment such as valves, pumps, flanges, and connections regularly for leaks, and repair as needed.
- Install an automatic shutoff valve to interrupt flow in the event of a catastrophic liquid spill.
- Install a high-level alarm on storage tanks to prevent overfilling.

7.11Appendix P Stormwater Hotspots

- Pave the loading and unloading area with concrete rather than asphalt.
- Place drip pans or other temporary containment devices at locations where leaks or spills may occur, and always use pans when making and breaking connections.
- Position roof downspouts to direct stormwater away from loading and unloading areas and into stormwater treatment facilities.
- Prepare and implement an Emergency Spill Cleanup Plan for the facility.
- Sweep loading and unloading area surfaces frequently to remove material that could otherwise be washed off by stormwater.
- Train all employees, especially fork lift operators, on basic pollution prevention practices and post signs.

While nearly every commercial, industrial, institutional, municipal, and transport-related site has a location where materials or products are shipped or received, the risk of stormwater pollution is greatest for operations that transfer high volumes of material or liquids, or unload potentially hazardous materials. Some notable examples to look for in a subwatershed include distribution centers, grocery stores, building supply outlets, lawn and garden centers, petroleum wholesalers, warehouses, landfills, ports, solid waste facilities, and maintenance depots (Figure 4P.4). Attention should also be paid to industrial operations that process bulk materials and any operations regulated under industrial stormwater NPDES permits.

Primary Training Targets

Owners, site managers, facility engineers, supervisors, and employees of operations with loading/unloading facilities are the primary training target.

Feasibility



Figure P.4 Unloading Area of Warehouse.

Loading/unloading pollution prevention

practices can be applied in all geographic and climatic regions, and work most effectively at preventing sediment, nutrients, toxic materials, and oil from coming into contact with stormwater runoff or runon. Few impediments exist to using this practice, except for the cost to retrofit existing loading and unloading areas with covers or secondary containment.

Implementation Considerations

<u>Loading/ and</u> unloading pollution prevention practices should be integrated into the overall stormwater pollution prevention plan for a facility. Employee training should focus on proper techniques to transfer materials, using informational signs at loading docks and material handling sites and during routine safety meetings. <u>See Table P.5 for employee training implementation considerations.</u>

Cost Costs to implement loading/unloading pollution prevention practices consist of one time construction costs to retrofit new or existing loading areas, but annual maintenance costs are relatively low thereafter. Exceptions include industries that elect to use expensive hir pressure or vacuum systems for loading/unloading facilities, which can also be expensive to maintain (U.S. EPA, 1992). Ongoing costs include employee training and periodic monitoring of loading/unloading activities.



Figure 1: Loading/Unloading Area of Warehouse

<u>Table P.5 Pollution Prevention Considerations</u> <u>for Loading and Unloading Areas</u>

Consideration	<u>Description</u>
Primary Targets of Employee Training	Owners, site managers, facility engineers, supervisors, and employees of operations with loading and unloading facilities are the primary training target.
Feasibility of Prevention Techniques	Loading and unloading pollution prevention practices can be applied in all geographic and climatic regions, and work most effectively at preventing sediment, nutrients, toxic materials, and oil from encountering stormwater runoff or run-on. Few impediments exist to using this practice, except for the cost to retrofit existing loading and

	unloading areas with covers or secondary containment.
Cost	Costs to implement loading and unloading pollution prevention practices consist of one-time construction costs to retrofit new or existing loading areas; annual maintenance costs are relatively low thereafter. Exceptions include industries that elect to use air pressure or vacuum systems for loading and unloading facilities, which can also be expensive to maintain (U.S. EPA, 1992). Ongoing costs include employee training and periodic monitoring of loading and unloading activities.

Resources

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: Industrial and Commercial. http://www.cabmphandbooks.com/

City of Los Angeles, CA Reference Guide
For Stormwater Best Management Practices
http://www.lacitysan.org/watershed_protection/pdfs/bmp_refguide.pdf

Stormwater Management Manual for Western Washington: Volume IV -- Source Control BMPs. WA Dept. Manual for Western Washington: Volume IV - Source Control BMPs. WA Dept. of Ecology 99-14 http://www.ecy.wa.gov/biblio/9914.html

U.S. EPA. 1992. Storm Water Management for Industrial Activities: Developing Pollution Prevention Plans and Best Management Practices. US EPA Office of Wastewater Management. Washington, D.C. EPA 832-R-92-006.

Ventura County Flood Control District Clean Business Program Fact Sheet

http://www.vcstormwater.org/index.php/clean-business-fact-sheets

Business Best Management Practices Stormwater Bmp #3— Shipping/Receiving/Loading Docks

City of Los Angeles, CA Reference Guide For Stormwater Best Management Practices

	Hotspot Source Area: Outdoor Materials	
H-6	OUTDOOR STORAGE	



Description

PROPOSED REVISION PROPOSED REVISION REPORT OF THE PROPOSED REVISION REPORT OF THE PROPOSED REVISION REVISION REPORT OF THE PROPOSED REVISION REVISION REVISION REPORT OF THE PROPOSED REVISION R

H-5 Outdoor or Bulk Material Storage

Protecting outdoor storage areas is a simple and effective pollution prevention practice for many commercial, industrial, institutional, municipal, and transport-related operations. The underlying concept is to prevent runoff contamination by avoiding contact between outdoor materials and rainfall (or runoff).stormwater. Unprotected outdoor storage areas can generate a wide range of stormwater pollutants, such as sediment, nutrients, toxic materials, and oil and grease (see Figure 4P.5).



Figure P.5 Mulch Stored Outdoors at a Garden Center.

Materials can be protected by installing covers, secondary containment, and other structures to prevent accidental release. Outdoor storage areas can be protected on a temporary basis (tarps or plastic sheeting) or permanently through structural containment measures (such as roofs, buildings, or concrete berms). Table 1. The following summarizes pollution prevention practices available for outdoor storage areas. Consult the Resources section below for a more comprehensive review of pollution prevention practices for outdoor or bulk material storage.

Application

- Emphasize employee education regarding storage area maintenance.
- Keep an up-to-date inventory of materials stored outdoors, and try to minimize them.
- Store liquids in designated areas on an impervious surface with secondary containment.
- Inspect outdoor storage containers regularly to ensure they are in good condition.
- Minimize stormwater run-on by enclosing storage areas or building a berm around them.

- Slope containment areas to a drain with a positive control (lock, valve, or plug) that leads to the sanitary sewer (if permitted) or to a holding tank.
- Schedule regular pumping of holding tanks containing stormwater collected from secondary containment areas.

Many businesses store materials or products outdoors. The risk of stormwater pollution is greatest for operations that store large quantities of liquids or bulk materials at sites that are connected to the storm drain system. Several notable operations include nurseries and garden centers, boat building/repair, auto recyclers/body shops, building supply outlets, landfills, ports, recycling centers, solid waste and composting facilities, highway maintenance depots, and power plants. Attention should also be paid to industrial operations that process bulk materials, which are often regulated under industrial stormwater NPDES permits.

Primary Training Targets

Owners, site managers, facility engineers, supervisors, and employees of operations with loading/unloading facilities are the primary training target.

Feasibility

Outdoor storage protection can be widely applied in all regions and climate zones, and requires routine monitoring by employees. Most operations have used covering as the major practice to handle outdoor storage protection (U.S. EPA, 1999). The strategy is to design and maintain outdoor material storage areas so that they:

- Reduce exposure to stormwater and prevent runon
- Use secondary containment to capture spills
- Can be regularly inspected
- Have an adequate spill response plan and cleanup equipment

Table 1: Pollution Prevention Practices for Protecting Outdoor Storage Areas

- Emphasize employee education regarding storage area maintenance
- Keep an up to date inventory of materials stored outdoors, and try to minimize them
- Store liquids in designated areas on an impervious surface with secondary containment
- Inspect outdoor storage containers regularly to ensure that they are in good condition
- Minimize stormwater run on by enclosing storage areas or building a berm around them
- Slope containment areas to a drain with a positive control (lock, valve, or plug) that leads to the sanitary sewer (if permitted) or to a holding tank
 - Schoolula regular purpling of holding tanks containing stormwater collected from secondary containment



Figure 1: Mulch Stored Outdoors at a Garden Center



Figure 2: Secondary Containment of Storage Drums Behind a Car Repair Shop

Implementation Considerations

Covers—The use of impermeable covers is an effective pollution prevention practice for non hazardous materials.

Covers can be as simple as plastic sheeting or tarps, or more elaborate roofs and canopies. Site layout, available space, affordability, and compatibility with the covered material all dictate the type of cover needed for a site. In addition, the cover should be compatible with local fire and building codes and OSHA workplace safety standards. Care should be taken to ensure that the cover fully protects the storage site and is firmly anchored into place.

Secondary Containment Secondary containment is designed to contain possible spills of liquids and prevent stormwater run on from entering outdoor storage areas. Secondary containment structures vary in design, ranging from berms and drum holding areas to specially designed solvent storage rooms (Figure 2).

Secondary containment can be constructed from a variety of materials, such as concrete curbs, earthen berms, plastic tubs, or fiberglass or metal containers. The type of material used depends on the substance contained and its resistance to weathering. In general, secondary containment areas should be sized to hold 110 percent of the volume of the storage tank or container unless other containment sizing regulations apply (e.g., fire codes).

If secondary containment areas are uncovered, any water that accumulates must be collected in a sanitary sewer, a stormwater treatment system, or a licensed disposal facility. Water quality monitoring may be needed to determine whether the water is contaminated and dictate the method of disposal. If the stormwater is clean, or an on site stormwater treatment practice is used, a valve should be installed in the containment dike so that excess stormwater can be drained out of the storage area and directed either to the storm drain (if clean) or into the stormwater treatment system (if contaminated). The valve should always be kept closed except when stormwater is drained, so that any spills that occur can be effectively contained. Local sewer authorities may not allow discharges from a large containment area into the sewer system, and permission must be obtained

sanitary sewer system are prohibited, containment should be provided, such as a holding tank that is regularly pumped out.

Employee training on outdoor storage pollution prevention should focus on the activities and site areas with the potential to pollute stormwater and the proper techniques to manage material storage areas to prevent runoff contamination. (see Table P.6). Training can be conducted

through safety meetings and the posting of on-site informational signs. Employees should also know the on-site person who is trained in spill response.

 $\frac{Cost-Many\ storage\ protection\ practices\ are\ relatively\ inexpensive\ to\ install\ (Table\ 2\underline{Table\ P.6}}{Pollution\ Prevention\ Considerations\ for\ Outdoor\ Storage\ Areas}$

Actual costs depend on the size of the storage area and the nature of the pollution prevention practices. Other factors are whether practices are temporary or permanent and the type of materials used for covers and containment. Employee training can be done in connection with other safety training to reduce program costs. Training costs can also be reduced by using existing educational materials from local governments, professional associations or from EPA's National Compliance Assistance Centers (http://www.assistancecenters.net).

Resources

Consideration	<u>Description</u>
Primary Targets for Employee Training	Owners, site managers, facility engineers, supervisors, and employees of operations with outdoor storage facilities are the primary training target.
Feasibility of Prevention Techniques	Outdoor storage protection can be widely applied in all regions and climate zones and requires routine monitoring by employees. Many operations have used covering as the major practice to handle outdoor storage protection. The strategy is to design and maintain outdoor material storage areas so that they comply with the following: Reduce exposure to stormwater and prevent run-on. Use secondary containment to capture spills. Can be regularly inspected. Have an adequate spill response plan and cleanup equipment.
Covers	The use of impermeable covers is an effective pollution prevention practice for non-hazardous materials. Covers can be as simple as plastic sheeting or tarps, or more elaborate roofs and canopies. Site layout, available space, affordability, and compatibility with the covered material all dictate the type of cover needed for a site. In addition, the cover should be compatible with local fire and building codes and OSHA workplace safety standards. Care should be taken to ensure that the cover fully protects the storage site and is firmly anchored into place.

7.11Appendix P Stormwater Hotspots

Consideration	<u>Description</u>
Secondary Containment	Secondary containment is designed to contain possible spills of liquids and prevent stormwater run-on from entering outdoor storage areas. Secondary containment structures vary in design, ranging from berms and drum holding areas to specially designed solvent storage rooms (see Figure P.6). Secondary containment can be constructed from a variety of materials, such as concrete curbs, earthen berms, plastic tubs, or fiberglass or metal containers. The type of material used depends on the substance contained and its resistance to weathering. In general, secondary containment areas should be sized to hold 110% of the volume of the storage tank or container unless other containment sizing regulations apply (e.g., fire codes). If secondary containment areas are uncovered, any water that accumulates must be collected in a sanitary sewer, a stormwater treatment system, or a licensed disposal facility. Water quality monitoring may be needed to determine whether the water is contaminated and dictate the method of disposal. If the stormwater is clean, or an on-site stormwater treatment practice is used, a valve should be installed in the containment dike so that excess stormwater can be drained out of the storage area and directed either to the storm drain (if clean) or into the stormwater is drained, so that any spills that occur can be effectively contained. DC Water may not allow discharges from a large containment area into the sewer system, and permission must be obtained before discharging. If discharges to the sanitary sewer system are prohibited, containment should be provided, such as a holding tank that is regularly pumped out.
Cost	Many storage protection practices are relatively inexpensive to install (Table P.7). Actual costs depend on the size of the storage area and the nature of the pollution prevention practices. Other factors include whether practices are temporary or permanent and the type of materials used for covers and containment. Employee training can be done in connection with other safety training to reduce program costs. Table 2: Sample Equipment Costs for Outdoor Storage Protection Training costs can also be reduced by using existing educational materials from local governments professional associations, or from EPA's National Compliance Assistance Centers (http://www.assistancecenters.net).

Inserted Cells

Figure P.6 Secondary Containment of Storage Drums Behind a Car Repair Shop.

Table P.7 Sample Equipment Costs for Outdoor Storage Protection

Storage Protection Device	Cost
Concrete Slab (6") inches)	\$3.50 to \$5.00 per -ft ²
Containment Pallets	\$50 to \$350 based on size and #number of barrels to be stored
Storage buildings Buildings	\$6 to \$11 per -ft ²
Tarps & Canopies	\$25 to \$500 depending on size of area to cover

Sources: Costs were derived from a review of Ferguson et al., 1997 and numerous websites that handle proprietary spill control or hazardous material control products

Resources

<u>Alameda Countywide Clean Water Program Outdoor Storage of Liquid Materials</u> <u>http://alamedaca.gov/go-green/clean-water-resources</u>

California Stormwater Quality Association. 2003 California Stormwater BMP Handbook: Industrial and Commercial. http://www.cabmphandbooks.com/

<u>California Stormwater Quality Association Factsheet: Outdoor Storage of Raw Materials</u> https://www.casqa.org/

EPA Office of Wastewater Management Storm Water Management Fact Sheet: Coverings http://www.epa.gov/owm/mtb/covs.pdf

<u>Ferguson, T., R. Gigac, M. Stoffan, A. Ibrahim, and H. Aldrich. 1997. Rouge River National Wet Weather Demonstration Project. Wayne County, MI.</u>

Rouge River National Wet Weather Demonstration Project. Wayne County, MI. http://www.rougeriver.com/proddata/catalog7ad4.html?category=overview#PI-PAPER-01.00

Storm Water Management Fact Sheet: Coverings. USEPA, Office of Water, http://water.epa.gov/scitech/wastetech/upload/2002-06-28-mtb covs.pdf

Ferguson, T., R. Gigac, M. Stoffan, A. Ibrahim, and H. Aldrich. 1997. Rouge River National Wet Weather Demonstration Project. Wayne County, MI.

California Stormwater Quality Association Factsheet: Outdoor Storage of Raw Materials http://www.cabmphandbooks.com/Documents/Municipal/SC 33.pdf Alameda Countywide Clean Water Program Outdoor Storage of Liquid Materials http://www.cityofalamedaca.org/getdoc.cfm?id=123

Washtenaw County, MI Community Partners for Clean Streams Fact Sheet Series #1: Housekeeping Practices

http://www.ewashtenaw.org/government/drain commissioner/dc webWaterQuality/dc cpcs/cpc s-handbook/cpcs-series-1-housekeeping-practices.pdpdf



Appendix Q Pollution Prevention Through Good Housekeeping

Q.1 Pollution Prevention

This appendix is meant to complement Appendix P Stormwater Hotspots and an Erosion and Sediment Control Plan (ESCP), but not reiterate EPA's Construction General Permit requirements. These notes shall appear as stamped notes on Stormwater Management Plans (SWMPs) where land disturbance is greater than 5,000 square feet and less than one1 acre. These notes shall constitute a minimum Stormwater Pollution Prevention Plan (SWPPPmin) and provide guidance on good housekeeping practices to prevent potential construction—site pollutants from interacting with stormwater.

Q.2 Stormwater Management Plan (SWMP) Good Housekeeping Stamp Notes

Fuels and Oils. On-site refueling will be conducted in a dedicated location away from access to surface waters. Tanks fabricated with double walls do not require an additional bermed area. Install containment berms and—for secondary containments around refueling areas and storage tanks. Spills will be cleaned up immediately and contaminated soils disposed of in accordance with all federal and District of Columbia regulations. Petroleum products will be stored in clearly labeled tightly sealed containers. All vehicles on—site will be monitored for leaks and receive regular preventive maintenance activities. Any asphalt substances used on—site will be applied according to manufacturer's recommendations. Spill kits will be included with all fueling sources and maintenance activities.

Solid Waste. No solid materials shall be discharged to surface water. Solid materials including building materials, garbage, and paint debris shall be cleaned up daily and deposited into dumpsters, which will be periodically removed and deposited into a landfill. A cover is required for all dumpsters when the dumpster is not actively being loaded with waste materials.

Abrasive Blasting. Water blasting, sandblasting, and other forms of abrasive blasting on painted surfaces built prior to 1978 may only be performed if an effective containment system prevents dispersal of paint debris.

Fertilizer. Fertilizers will be applied only in the minimum amounts recommended by the manufacturer, worked into the soil to limit exposure to stormwater, and stored in a covered shed. Partially used bags will be transferred to a sealable bin to avoid spills.

Paint and Other Chemicals. All paint containers and curing compounds will be tightly sealed and stored when not required for use. Excess paint will not be <u>dischargesdischarged</u> to the storm sewers, but will be properly disposed of according to manufacturer's recommendations. Spray guns will be cleaned on a removable tarp. Chemicals used on—site are kept in small quantities

and in closed containers undercover and kept out of direct contact with stormwater. As with fuels and oils, any inadvertent spills will be cleaned up immediately and disposed of according federal and District of Columbia regulations.

Concrete. Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash on—site, except in a specially designated concrete disposal area. Form release oil for decorative stone work will be applied over a pallet covered with an absorbent material to collect excess fluid. The absorbent material will be replaced and disposed of properly when saturated.

Water Testing. When testing and—or cleaning water supply lines, the discharge from the tested pipe will be collected and conveyed to a completed stormwater conveyance system for ultimate discharge into a stormwater best management practice (BMP).

Sanitary Waste. Portable lavatories located on—site will be <u>services serviced</u> on a regular basis by a contractor. Portable lavatories will be located in an upland area away from direct contact with surface waters. Any spills occurring during servicing will be cleaned immediately and contaminated soils disposed of in accordance with all federal and District of Columbia regulations.

Appendix R Integrated Pest Management

R.1 Integrated Pest Management

This appendix is in support of the District of Columbia's legislation B19-745, The Anacostia Waterfront Environmental Standards Amendment Act of 2012. This legislation requires regulated projects in the AWDZ governed by this legislation to receive a DDEE/DOEE">DDEE/DOEE approved Integrated Pest Management Plan (see Figure R.1 for a sample plan).

Integrated Pest Management (IPM) is an approach that applies biological, cultural, mechanical, and chemical controls to manage pests at acceptable levels. The following are general guidelines to encourage <u>a_more_considered</u> use of fertilizers, herbicides, and pesticides.

R.2 Components of an Integrated Pest Management Plan

- 1. Identification. Identify the Pestpest and Understand understand its Life Cycle life cycle. Correctly identify the pest to determine an appropriate control strategy. For assistance with pest identification, contact the Maryland Home & Garden Information Center at Maryland Cooperative Extension.
- 2. When to take Take Action. Insects are an integral part of the local ecology and; thus, their presence alone should not be reason for taking action. First, monitor pest numbers and determine if preventative maintenance measures can be employed to remediate the situation. Take action only when alternative preventative methods are no longer feasible and when pest activity threatens the long-term health of the plant.

3. Prevention in Design

- (a) Choose the right plant for the right location.
- (b) This means assessing species Assess species' suitability to site soils, moisture, wind, and sun exposure. Well-selected species require less maintenance.
- (c) Select plant species and cultivars resistant to disease.
- (d) Select a diverse plant palate to ensure on goingongoing survival of remaining plant material.
- (e) Inspect delivered plant material at the nursery and again prior to installation.
- (f)(e) Material delivered from the nursery may carry pathogens or insects. Inspect all plant material at the nursery and again prior to installation. Reject any material that is diseased.
- **4. Prevention in Maintenance and Construction.** Proper cultural management practices can reduce plant stress and thus decrease their susceptibility to pests. Prior to applying pesticide or herbicides, consider your current landscape management practices. Soils are the foundation for healthy plants. As such; it is important to provide: the proper moisture, fertility, organic matter, and drainage.

- (a) **Soil** testing Testing. Submit a soil sample to a soil testing laboratory for analysis. The results will determine the appropriate soil amendments to be applied.
- (b) **Fertilizers**. Organic fertilizers are derived <u>from</u> natural sources such as: cottonseed meal, blood meal, fish emulsion, and manure. Slow-release inorganic fertilizers supply nutrients over the growing season with less nutrient loss than quick-release fertilizers. Fertilizer grade and rate should be selected and applied only as <u>determined by</u> test results <u>indicate</u>. Apply fertilizer only as <u>indicated by a soil test</u>. Do not apply fertilizer prior to a heavy rainfall event and do not apply between December and February.
- (c) **Trees and shrubs**. Place mulch underneath the root zone of trees and shrubs to reduce competition with turf and weeds for water and nutrients. Topdress planting beds with compost to improve soil structure, biological activity, and fertility.
- (d) Lawn areas Areas. Increased mowing height can reduce weed germination, as less by limiting the amount of sunlight that reaches the soil level. Topdressing with organic matter increases soil moisture and enables turf to withstand drought conditions. Regular monitoring and over-seeding of bare spots prevents weed establishment. After mowing, grass clippings should be left in-place. These above-mentioned strategies will reduce symptoms of disease and weed pressure, thus decreasing herbicide and fertilizer usage.
- **5. Develop a Treatment Plan.** When pest activity exceeds acceptable levels, choose a control method appropriate to observed conditions. This may include biological, cultural, mechanical, and chemical controls.
 - (a) **Biological** <u>control</u>. Uses the introduction of a predator. Introduce additional natural predators where existing populations are too few to effectively control pests. Consult with your local Cooperative Extension office <u>prior to introducing any biological</u> controls.
 - (b) **Cultural** control. Uses pruning and removal of Prune and remove diseased branches. Sanitize all tools after use. Properly amend soils and irrigate plantings as necessary.
 - (c) **Mechanical** <u>control</u>. Conduct weeding by hand, tool, or heat solarization. Remove insect pests by hand or using traps.
 - (d) **Chemical** <u>control</u>. Uses non-toxic, non-residual pesticide or herbicide products where necessary.
 - Narrow-spectrum contact pesticides target the pest directly and preserve beneficial predator species. Broad-spectrum pesticides also eliminate beneficial predators and thus the natural controls on pest populations. Only certified individuals can apply restricted-use pesticides.
 - Insecticidal soap and horticultural oils. Insecticidal soaps are used to penetrate the
 insect's outer covering, causing the cells to collapse. Horticultural oils, on the other
 hand, coat and suffocate the offending insect.
 - Application timing is used to To maximize effectiveness, apply pesticides at the appropriate point in the life cycle for of the pest. Herbicide application also requires consideration for of the seasonal growth pattern for of the targeted weed.

Sample Form for an Integrated Pest Management Plan





GOVERNMENT OF THE DISTRICT OF COLUMBIA DISTRICT DEPARTMENT OF THE ENVIRONMENT WATERSHED PROTECTION DIVISION INSPECTION AND ENFORCEMENT BRANCH

Integrated Pest Management Plan

This document/submission will serve as your IPM plan. It must be printed and distributed to the owner of the property and to any person or company who is given responsibility for on-site pest management, landscaping, or facility maintenance (i.e. homeowners, property managers, maintenance companies). Per the Stormwater Management Plan that this IPM plan supports, the owner of the property and their agents are Legally required to comply with this plan.

Integrated pest management (IPM) is a continuous system of controlling pests (weeds, diseases, insects or others) in which pests are identified, action thresholds are considered, all possible control options are evaluated and selected control(s) are implemented. Control options which include biological, cultural, manual, mechanical and chemical methods are used to prevent or remedy unacceptable pest activity or damage. Choice of control option(s) is based on effectiveness, environmental impact, site characteristics, worker/public health and safety, and economics. IPM takes advantage of all appropriate pest management options.

PROJECT INFORMATION

ILECTINI ONVIATION	
Project Name	
Street Number:	
Street Name	
Zip Code	
Email Address:	
Project Developer Information (Name & Tit	le
Contact	
Com pany	
Address	
Phone	
Fax	
JUSTIFICATION FOR IPM PLAN	

JUSTIFICATION FOR IPM PLAN
Ordinance Requirement

Yes No

res 140

This development is a publically owned, privately developed property within the boundaries of the Anacostia Watershed Development Zone

 The property requires a Certificate of Occupancy and falls within the regulations of Green Area Ratio.

1



GOVERNMENT OF THE DISTRICT OF COLUMBIA DEPARTMENT OF ENERGY AND ENVIRONMENT INSPECTION AND ENFORCEMENT DIVISION CONSTRUCTION AND MAINTENANCE BRANCH

Integrated Pest Management Plan

This document/submission will serve as your integrated pest management (IPM) plan. It must be printed and distributed to the owner of the property and to any person or company who is given responsibility for on-site pest management, landscaping, or facility maintenance (i.e. homeowners, property managers, maintenance companies). Per the Stormwater Management Plan (SWMP) that this IPM plan supports, the owner of the property and their agents are legally required to comply with this plan.

IPM is a continuous system of controlling pests (weeds, diseases, insects, or others) where pests are identified, action thresholds are considered, all possible control options are evaluated, and selected control(s) is implemented. Control options (biological, cultural, manual, mechanical, and chemical methods) are used to prevent or remedy unacceptable pest activity or damage. Choice of control option(s) is based on effectiveness, environmental impact, site characteristics, worker/public health and safety, and economics. IPM takes advantage of all appropriate pest management options.

PROJECT INFORMATION

Project Name:
Street Number:
Street Name:
Zip Code:
Email Address:
Project Developer Information (Name & Title)
Contact:
Company:
Address:
Phone:
Fax:
HISTIEICATION FOR IDM DLAN

JUSTIFICATION FOR IPM PLAN

Ordinance Requirement

Yes No

0 0

This development is a publically owned, privately developed property within the boundaries of the Anacostia Watershed Development Zone.

C The property requires a Certificate of Occupancy and falls within the regulations of Green Area Ratio.

1

Figure R.1 Sample form for an Integrated Pest Management Plan.

Environmen	ntal Criteria Manu	ual requirement
		ed LID stormwater management structures, please refer to the DDOE
		maintenance requirements)
		, ,
Critical Env	ironmental Featu	ires and Buffers (List any that exist - must be
shown on t	the site plan)	
Yes	No	
0	0	Streambank
0	0	Wetland
Other		
	DI INDOCADE DECE	S I COLUTION S
	D LANDSCAPE PEST	s and SOLUTIONS In Information Center offers regionally appropriate guidelines for
		nance and control of landscape pests. Refer to the following guidelines in
the Marylan	d Home & Garden	Information Center: http://extension.umd.edu/hgic.
Charles II have		have used the suidelines in the Manuford Harry & Condend to Survey
Center webs		I have read the guidelines in the Maryland Home & Garden Information
П		
Insects		
Invasiv	es	
Lawns		
Plant D	Diagnostics	
Soils		
Trees 8	& Shrubs	
Weeds		
ADDITIONAL IPM	1 SUBMITTAL REQU	JIREMENTS – SITES WITH GREEN AREA RATIO OBLIGATION
		tio requirements, submit the IPM plan within Green Area Ratio drawings for
The same of the sa		ing in your submitted plans:
		indscape management activities for the below categories. gory describing: materials, methods, preventative maintenance, and pest
		applies to each CATEGORY listed below. To protect our water resources, you are
		least toxic options before using chemical treatment applications.
		A section was a
	Soil preparation	submittal in IPM plan:
:	Use of compost	
	Plant replacemen	t
	Irrigation	
	Weed control	
	Insect/disease con	ntrol s or invasive species
•	COTTO OF FIOXICU	a or in reasive apedies
		2
		-

FigureR
Environmental Criteria Manual requirement (If site has existing or planned BMP stormwater management structures, refer to the DOEE Stormwater Management Guidebook for maintenance requirements.)
Critical Environmental Features and Buffers (List any that exist - must be shown on the site plan)
Yes No
C Streambank
C C Wetland
Other
ANTICIPATED LANDSCAPE PESTS and SOLUTIONS The Maryland Home and Garden Information Center offers regionally appropriate guidelines for preventative landscape maintenance and control of landscape pests. Refer to the following guidelines in the Maryland Home & Garden Information Center: http://extension.umd.edu/hgic.
Check all boxes to indicate you have read the guidelines in the Maryland Home & Garden Information Center website.
Insects
Invasives
Lawns
Plant Diagnostics
Soils
Trees & Shrubs
Weeds
ADDITIONAL IPM SUBMITTAL REQUIREMENTS – SITES WITH GREEN AREA RATIO OBLIGATION Where applicable to Green Area Ratio requirements, submit the IPM plan within Green Area Ratio drawings for review by DOEE. Include the following in the submitted plans: Seasonal schedule of all landscape management activities for the below categories. A paragraph for each category describing the following: materials, methods, preventative maintenance, and pest management practices as applies to each CATEGORY listed below. To protect our water resources, you are required to start with the least toxic options before using chemical treatment applications.
CATEGORIES required for submittal in the IPM plan: Soil preparation Use of compost Plant replacement Irrigation Weed control Insect/disease control Control of noxious or invasive species
2

Figure	R.1	(continued)	

MAINTENANCE DOCUMENTATION

The property owner will maintain records of all Service Provider visits and pest control treatments for at least three (3) years. Information regarding pest management activities will be made available to the public at the property owner's administrative office. Requests to be notified of pesticide applications may also be made to this office. All guardians will be informed of their option to receive notification of all pesticide applications at enrollment and once annually.

Maintain the following records for all pesticide, herbicide, and fertilizer application.

- For pesticide and herbicide application:
 - Target pest and description of infestation severity
 - Prevention activities and non-chemical methods applied prior to chemical control
 - Type and quantity of pest/weed control used
 - Location of pesticide or herbicide application
 - Date of treatment application
 - Name and certification number of pesticide applicator
 - Application equipment used
 Summary of results
- For fertilizer application:
 - Landscape type (lawn, ornamental planting beds, trees, other)
 - Location of fertilizer application within site
 - Soil report from lab with nutrient analysis and application recommendations
 - Fertilizer product description, including: product name, grade
 - Application rate (lb/1000 ft²)

 - Date of fertilizer application
 Name of individual applicator and associated landscape business
 - Summary of results

PROGRAM OUTREACH TO PROPERTY OWNER

	the owner(s) of the property that they are required to apply less- ns as described by the <u>Maryland Home & Garden Information Cel</u> extension.umd.edu/hgic.	
declaration of covenants. If this is be an element included in the pro	IPM Plan, I am aware that this IPM plan is required to be filed as a government property where covenants are not filed then this I jects SWMP maintenance partnership agreement or memorandustruments requiring the use of IPM on this site.	PM plan must
By checking all boxes, I certify th Pest Management strategy for th	at I have read the requirements listed here and agree to carry or se above-listed property	ut an Integrated
Signature	Date:	

3

FigureR		
	MAINTENANCE DOCUMENTATION The property owner will maintain records of all Service Provider visits and pest control treatments for at least 3 years. Information regarding pest management activities will be made available to the public at the property owner's administrative office. Requests to be notified of pesticide applications may also be made to this office. All guardians will be informed of their option to receive notification of all pesticide applications at enrollment and once annually.	
	Maintain the following records for all pesticide, herbicide, and fertilizer application. • For pesticide and herbicide application:	
	Target pest and description of infestation severity Prevention activities and non-chemical methods applied prior to chemical control Type and quantity of pest/weed control used Location of pesticide or herbicide application Date of treatment application Name and certification number of pesticide applicator Application equipment used Summary of results For fertilizer application: Landscape type (lawn, ornamental planting beds, trees, other) Location of fertilizer application within site Soil report from lab with nutrient analysis and application recommendations Fertilizer product description including product name and grade Application rate (lb/1000 ft²) Date of fertilizer application Name of individual applicator and associated landscape business Summary of results	
	PROGRAM OUTREACH TO PROPERTY OWNER	
	Developer agrees to inform the owner(s) of the property that they are required to apply less-toxic, non-chemical pest management options as described by the Maryland Home & Garden Information Center. IPM guidelines can be found at http://extension.umd.edu/hgic. As the person preparing the IPM Plan, I am aware that this IPM plan is required to be filed as an exhibit in the declaration of covenants. If this is a government property or a project where covenants are not filed then this IPM plan must be an element included in the project's SWMP (and/or Green Area Ratio) maintenance partnership agreement or memorandum of understanding. These are legal instruments requiring the use of IPM on this site.	
	By checking all boxes, I certify that I have read the requirements listed here and agree to carry out an Integrated Pest Management strategy for the above-listed property	
	Signature: Date:	
	3	

Figure R.1 (continued)



Appendix S Proprietary Practices Approval Process

S.1 Proprietary Practice Consideration Overview

This appendix provides details on the DOEDOEE approval process for the use of a proprietary stormwater best management practice (BMP). If a proposed BMP is not listed in Chapter 3-of the DOOE, "Stormwater Best Management GuidebookPractices (BMPs)" of this guidebook, or deviates significantly from the specifications listed in this Guidebookguidebook, an application with or prior certified approvals sufficient to demonstrate compliance with the stormwater performance standards of the District's stormwater program must be submitted to DOOEDOEE. To differentiate between a traditional stormwater BMP, a proprietary practice, or manufactured BMP, the term Manufactured Treatment Device (MTD) will be utilized for the class of practices that require an approval from DOOEDOEE.

DOCEDOEE recognizes the value of innovative stormwater pollutant removal technologies, especially in the ultra-urban landscape of the District, where available site area is limited and often constrained by utilities and other factors. However, DDOEDOEE also acknowledges that the resources required to develop and implement a testing program for the purposes of evaluating the performance of new MTDs are beyond the current capacity of DOE's Stormwater Management DOEE's Regulatory Review Division. Further, DDOEDOEE recognizes that there are other state and potentially national programs being developed to provide for this testing. Therefore, until such time that DDOEDOEE develops a MTD performance testing and verification program, DDOEDOEE will accept performance testing and compliance with the New Jersey Department of Environmental Protection's (NJDEP) Protocol for Total Suspended Solids Removal as outlined in this Appendixappendix.

S.2 Types of Manufactured Treatment Devices

There are numerous MTDs currently available. The various configurations and stormwater treatment objectives represented by this general category of stormwater BMPs will continue to evolve and expand along with stormwater regulations and land development trends. It is not expected that a standard categorization of MTDs here can accommodate this growing industry. However, in order to best address the current regulations and foreseeable regulatory framework, the following represents the types of MTDs and performance goals that will be considered by DDDE's DOEE's stormwater program:

Hydrodynamic Treatment Devices. The term "hydrodynamic" has been used to describe a family of MTDs that rely on a wet chamber or manhole to encourage gravity separation or dynamic settling of solids during flow conditions (as opposed to quiescent settling within vaults or chambers sized comparably to wet ponds). In most cases the total area of the wet chamber has been reduced through the application of dynamic settling, or vortex (as borrowed from technology applied to remove coarse solids from combined sewer overflows). The term "hydrodynamic" has therefore been loosely applied to the entire category of practices that are designed to achieve physical settling within a small treatment area, with or

without a vortex component. DDOEDOEE considers these practices to be applicable as pretreatment devices to be placed in series upstream of a primary (filtering) MTD or a retention or pollutant removal practice included in Chapter 3, "Stormwater Best Management Practices (BMPs)" of this Guidebookguidebook. Pretreatment is typically an essential element of the primary BMP's performance and designed maintenance interval and therefore no additional retention or pollutant removal credit is awarded.

- **Filtering Treatment Devices.** A broad category of MTDs utilize a filter media contained within an engineered structure. In some cases, the filter media itself may be the proprietary product, while others may also include the media container (cartridges, tubes, etc.), and/or the overall structure geometry and hydraulic components as the proprietary product. When necessary, DDOEE will determine if the design, sizing, filter media, or other characteristics deviate significantly from the specifications listed in this Guidebookguidebook and therefore requires an approval.
- Retention Devices. The current category of retention devices is limited to storage chambers, vaults, perforated pipes, and other forms of supplemental storage volume. These devices generally serve to supplement a primary retention practice such as infiltration, bioretention, etc., by providing additional storage within or adjacent to the practice. Alternatively, these devices may also supplement a pollutant removal practice by creating additional runoff storage volume. In either case, the devices are not considered treatment MTDs. Rather, these storage elements allow the primary BMP to capture and retain or treat a larger volume of runoff and are therefore considered part of the primary BMP, and not an additional treatment mechanism. Therefore, no additional pollutant removal is credited.

S.3 Proprietary Practice Approval Process – Background

DDOEDOEE has reviewed different testing protocols and state sponsored MTD performance verification programs. In general, the evaluation and approval of MTD performance has traditionally been based on a combination of field monitoring and a rigorous review of the resulting data. While the consensus is that there is no substitute for field monitoring through the seasonal variations in rainfall, pollutant loading, temperature, and other factors to evaluate the performance of a stormwater BMP, there is anecdotal evidence that these studies can take a long time, be very expensive, and in some cases, be inconclusive.

The process and experience in New Jersey was derived from a multi-state testing protocol and reciprocity agreement: The Technology Acceptance Reciprocity Partnership (TARP, 2003). TARP refers to a testing protocol that outlines the standard methods and procedures to be employed when testing a stormwater MTD. The concept was based on the belief that if a manufacturer followed the TARP protocol to test the MTD, then the data would be acceptable to all the partner states. The New Jersey Department of Environmental Protection (NJDEP), in partnership with the New Jersey Corporation for Advanced Technology (NJCAT), is a TARP member state that has developed a formal evaluation and acceptance process for MTDs. Unfortunately, the "reciprocity" element of the process did not evolve primarily due to the different partner states having established different treatment objectives and performance goals. The New Jersey program established TSS as the treatment objective, while other states included nutrients or other parameters in addition to TSS.

The MTD performance certification program in New Jersey, implemented by NJDEP and NJCAT, provides a continuous evaluation of the effectiveness of the testing and verification protocol and, in an effort to establish a more reliable and consistent process, are currently transitioning to a prescriptive laboratory testing protocol. The laboratory testing of filter products may be supplemented by optional field testing to demonstrate system longevity and corresponding expected maintenance intervals.

The new protocol, entitled "New Jersey Department of Environmental Protection Process for Approval of Use for Manufactured Treatment Devices January 25, 2013" (NJDEP₂ 2013a), requires that MTD's obtain Verification through NJCAT. The NJCAT Verification process, entitled "Procedure for Obtaining Verification of a Stormwater Manufactured Treatment Device from New Jersey Corporation for Advanced Technology January 25, 2013" (NJCAT₂ 2013), and the NJDEP protocol can be found on NJDEP's website, -http://www.nistormwater.org/treatment.html.

The new protocol includes a formal transition process that recognizes existing MTD certification and allows sufficient time for recertification under the new protocol. In addition, the new NJ protocol remains consistent with the DDEE stormwater program's treatment objectives (TSS) and performance goals (80-percent% reduction). To allow for the use of effective MTDs in the District immediately and include an opportunity to transition to a more reliable and consistent testing protocol, DDEE will accept the existing NJDEP certifications, and implement the same expiration schedule of those existing certifications and accompanying verification/certification renewal as required by NJDEP's new protocol. DDEE will apply the District's SWRv treatment requirements (1.2-inch rainfall, or when over treating overtreating, up to 1.7-inch rainfall) to the specific MTD unit sizing formula as verified and certified by NJCAT and NJDEP, respectively.

S.4 MTD Current Approval Status

<u>DDOEDOEE</u> will accept MTDs for use in the District that have a current NJDEP verification/certification as conditioned upon those items referenced in Transition for Manufactured Treatment Devices dated July 15, 2011 (NJDEP, 2011) as follows:

- —All MTDs that have a MTD Laboratory Test Certification for 80-percent% TSS removal will be approved for use by DDO2 until the NJDEP published certification expiration date (determined in conjunction with NJDEP's January 25, 2013 adoption of the new testing protocols; NJDEP 2013b).
- All MTD's that have a MTD Laboratory Test Certification for 50 percent TSS removal will be approved for use by DDOE for pretreatment upstream of MTDs and, on a case by case basis, upstream of applicable practices listed in Chapter 3DOEE until the NJDEP published certification expiration date (determined in conjunction with NJDEP's January 25, 2013 adoption of the new testing protocols; NJDEP 2013e, 2013b);
- All <u>MTDsMTD's</u> that have a MTD <u>FieldLaboratory</u> Test Certification for <u>80 percent50%</u> TSS removal will be approved for use by <u>DDOEDOEE</u> for pretreatment upstream of <u>MTDs</u> and, on a case by case basis, upstream of applicable practices listed in Chapter 3, "Stormwater Best Management Practices (BMPs)" until the NJDEP published certification

- expiration date (determined in conjunction with NJDEP's January 25, 2013 adoption of the new testing protocols; NJDEP, 2013c);
- All MTDs that have a MTD Field Test Certification for 80% TSS removal will be approved
 for use by DOEE until the NJDEP published certification expiration date (determined in
 conjunction with NJDEP's January 25, 2013 adoption of the new testing protocols; NJDEP,
 2013b).

All manufacturers seeking acceptance for use in the District based on certification by NJDEP must submit evidence of NJDEP Verification/Certification (Certification Letter) and documentation representing how the MTD design and sizing is affected by the application of the District's stormwater performance standards as detailed in Chapter 2, "Minimum Control Requirements" and as compared to that of the NJDEP. The application of a specific MTD sizing criteria or model on a given development site must be rated for a Treatment Flow Rate (as defined by the new-2013 protocol) equal to or greater than or equal to the District's Stormwater Retention Volume (SWRv) design storm peak flow rate. Refer to Appendix H. "Acceptable Hydrologic Methods and Models" for guidance on the computational methodology for computing the District's SWRv design peak flow rate. Developers and consultants may review available products that have been certified by the NJDEP and select the one most appropriate for their site. For most recent MTD approvals consult NJDEP website -http://www.njstormwater.org/treatment.html.

S.5 MTD Approval Status Renewal

Prior to the expiration of the NJDEP verification/certification, as noted in <u>Section S.ection S.4</u>, all MTDs that wish to continue to be accepted for water quality treatment in the District shall formally request acceptance by <u>DDOEDOEE</u> and submit evidence of approval through NJDEP's 2013 MTD Laboratory Test Certification/Verification process.

S.6 MTD Application Fees

Submission of evidence of verification/certification through NJDEP's MTD Certification Program does not require a review fee. However, any requests for acceptance of an MTD for other treatment parameters, including but not limited to pathogens, metals, oil and grease, or runoff volume may be subject to alternate submittal requirements and a review fee commensurate with the services required for reviewing and approving the MTD.

S.7 References

MDE. 2011. Facts About Maryland's Stormwater Program & Proprietary Practices. Maryland Department of the Environment. Available at:

The National Environmental Laboratory Accreditation Conference (NELAC) Institute (TNI) Available at: http://www.nelac-institute.org/

New Jersey Corporation for Advanced Technology (NJCAT) Technology Verification Program and Testing Protocols available at: http://www.njcat.org/

- NJCAT 2013. Procedure for Obtaining Verification of a Stormwater Manufactured Treatment Device from New Jersey Corporation for Advanced Technology January 25, 2013. Available at: http://www.njstormwater.org/pdf/njcat-mtd-process-1-25-13.pdf
- New Jersey Department of Environmental Protection (NJDEP) 2011 Transition for Manufactured Treatment Devices, July 15, 2011. <u>Available at: Available at: http://www.njstormwater.org/pdf/mtd-certification-process-7-13.pdf</u>
- NJDEP 2013a. Process for Approval of Use for Manufactured Treatment Devices January 25, 2013 Available at: http://www.njstormwater.org/pdf/njdep-mtd-process-1-25-13.pdf
- NJDEP 2013b. Laboratory Protocol to Assess Total Suspended Solids Removal by a Filtration Manufactured Treatment Device January 25, 2013. Available at: http://www.njstormwater.org/pdf/filter-protocol-1-25-13.pdf
- NJDEP 2013c. Laboratory Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device January 25, 2013. A vailable at: http://www.njstormwater.org/pdf/hds-protocol-1-25-13.pdf
- TARP. 2003. Stormwater Best Management Practice Demonstrations (TARP Tier II Protocols). The Technology Acceptance Reciprocity Partnership. Available at: http://www.dep.state.pa.us/dep/deputate/pollprev/techservices/tarp/pdffiles/Tier2protocol.pdf
 Available at: http://www.mass.gov/eea/docs/dep/water/laws/i-thru-z/swprotoc.pdf
- U.S. EPA. 2002. Guidance for Quality Assurance Project Plans. United States Environmental Protection Agency. EPA QA/G-5. Available at: http://www.epa.gov/quality/gs docs/g5-final.pdf_Available at: https://www.epa.gov/quality/guidance-quality-assurance-project-plans-epa-qag-5
- U.S. EPA. 2006. Data Quality Assessment: Statistical Methods for Practitioners. United States Environmental Protection Agency. EPA QA/G-9S. Available at: https://www.epa.gov/quality/guidance-data-quality-assessment

PROPOSED PENISION PROPOSED PRO

Appendix T Underground Sand Filter Design Example

Design of underground sand filters requires proper application of a number of equations to ensure the resulting stormwater best management practice (BMP) provides adequate treatment for the design storm. This appendix illustrates the step-by-step process for designing a three-chamber underground sand filter (see Figure T.1 for sand filter schematic).

Data Required

- Storm frequency = 15 years
- Time of concentration = Tc = 6 minutes
- From District rainfall intensity duration frequency curve:
 - Intensity, i = 7.56 inches per hour

Assumptions

- The site is a parking lot with area, $A = 10,000 \text{ ft}^2$.
- The sand filter will outfall to a storm sewer.
- The distance is 50 feet from the sand filter's invert-out to the storm sewer pipe connection.
- The invert of the city storm sewer = 92 feet at the proposed connection point (note: allow a 2% slope in the pipe connecting the invert-out of the sand filter to the city storm sewer invert).
- The contributing drainage area (CDA) is 100% impervious.
- One half of the SWRv (based or a 1.2-inch storm) must be treated by the sand filter.




Figure T.1 Sand filter schematic with steps shown.

The following steps show how to calculate the sand filter dimensions.

Step 1: Determine Design Invert Elevations

<u>Determine the final surface elevation, invert in, invert out, and bottom invert elevation of the structure.</u>

- Invert in = 98 feet
- Invert out = 93 feet or higher (based on 2% slope for 50 feet to city storm sewer connection)

Actual head difference available within the filter between invert-in and invert-out is

$$98 \text{ ft} - 93 \text{ ft} = 5 \text{ ft}$$

- Assume inflow pipe diameter = 1 foot
- Assume over the crown pipe cover = 2 feet
- Final surface elevation above sand filter = 98 ft + 2 ft + 1 ft = 101 ft
- Minimum depth of filter layer (Section 3.7.4): df-min = 1 foot

Step 2: Peak Discharge Calculation for Bypass Flow

The District uses the 15-year storm (with Tc = 6 minutes) for post-development runoff.

Using the Rational Method:

$$Q_{v15} = C \times I \times A$$

<i>Op</i> ₁₅	=	bypass peak flow (cfs)
C	=	runoff coefficient = 1.0
I	=	rainfall intensity = 7.56 in./hr
A	=	drainage area = 0.23 acres
Tc	=	time of concentration (used in selecting rainfall intensity) = 6 min

$$Q_{p15} = 1.0 \times 7.56 \frac{\text{in}}{\text{hr}} \times 0.23 \text{ ac} = 1.74 \text{ cfs}$$

Step 3: Determine Design Volume

The Stormwater Retention Volume (SWRv) is determined by Equation 2.1:

Equation 2.1 Stormwater Retention Volume

$$SWRv = \frac{P \times [(Rv_I \times I) + (Rv_C \times C) + (Rv_N \times N)] \times 7.48}{12}$$

SWRv .	= volume required to be retained (gallons)
<u>P</u>	= selection of District rainfall event varies based on regulatory
	trigger:
	• 90th percentile (1.2 inches) for major land-disturbing activity,
	• 85th percentile (1.0 inch) for major substantial improvement
	activity in the AWDZ and governed by the Anacostia
	Waterfront Environmental Standards Amendment Act of 2012,
	• 80th percentile (0.8 inch) for other major substantial
	improvement activities
Rv_I	= runoff coefficient for impervious cover (0.95)

I	= impervious cover surface area (ft ²)
Rv_C	= runoff coefficient for compacted cover (0.25)
<u>C</u>	= compacted cover surface area (ft ²)
Rv_N	= runoff coefficient for natural cover (0.00)
N	= natural cover surface area (ft ²)
7.48	= conversion factor, converting cubic feet to gallons
12	= conversion factor, converting inches to feet

$$SWRv = \frac{1.2 \times [(0.95 \times 10,000) + (0.25 \times 0) + (0.00 \times 0)] \times 7.48}{12}$$
= 7,106 gallons (950 cubic feet)

In this example, the sand filter must treat half the SWRv, so the design volume is 3,553 gallons, or 475 cubic feet.

Step 4: Determine the Required Ponding Volume

Use the following equation:

Equation 3.9 Required Ponding Volume for Filtering Practices

$$V_{ponding} = 0.50 \times DesignVolume$$

where:

<u>Vponding</u> = storage volume required prior to filtration (ft³) <u>DesignVolume</u> = design storm volume (ft³)

$$V_{ponding} = 0.50 \times 475 \text{ ft}^3 = 238 \text{ ft}^3$$

As shown in Equation 3.9, the total ponding volume must be at least 50% of the design volume. The ponding volume consists of two components:

- Pretreatment volume, which must be at least 25% of the design volume (at least 50% of the ponding volume)
- Temporary ponding volume above the pretreatment level in the first chamber and above the filter media in the second chamber

The pretreatment volume must be at least 25% of the **design volume**, so in this example, at least 119 cubic feet must be captured in the first chamber for pretreatment. The remaining ponding volume should be provided as temporary ponding above the pretreatment level in the first chamber and above the filter media in the second chamber.

Step 5: Determine the First Chamber Dimensions

This step will be iterative with Step 6 below, as the depth of the first chamber will be equal to the filter media depth (*df*) selected in Step 6.

First Chamber Pretreatment Volume:

$$V_1 = L_1 \times W \times (d_f + 1)$$

V_I	=	permanent pretreatment volume of first chamber = 119 ft^3
$\overline{L_1}$	=	length of first chamber (ft)
W	_	width of chamber (ft) use 6 feet

 d_f+1 = depth of permanent pretreatment, use 2 feet for df from Step 6 plus 1 foot for underdrain and pea gravel depths

therefore:

$$L_1 = \frac{V_1}{W \times (d_f + 1)} = \frac{119 \text{ ft}^3}{6 \text{ ft} \times (2 \text{ ft} + 1 \text{ ft})} = 6.61 \text{ ft}$$

Use: $L_1 = 7$ ft

With L_l equal to 7 feet, the permanent pretreatment volume is 126 cubic feet. This means that at least 112 cubic feet must be provided in temporary ponding above the first and second chamber.

Step 6: Determine Sand Filter Area (SA_{filter})

Solving Equation 3.8 below will require an iterative solution to determine the best combination of height of water (*hf*), filter depth (*df*) and area of the filter *SA*_{filter} that lead to the required ponding volume.

Equation 3.8 Minimum Filter Surface Area for Filtering Practices

$$SA_{filter} = \frac{DesignVolume \times d_f}{k \times (h_{avg} + d_f) \times t_d}$$

where:

SA _{filter}	= area of the filter surface (ft^2)	
DesignVolume	= design storm volume, typically the $SWRv$ (ft ³)	
d_f	= filter media depth (thickness) (ft), with a minimum of 1 ft	
<u>k</u>	= coefficient of permeability (ft/day) (3.5 ft/day for partially clogge	d
	sand)	
h_f	= height of water above the filter bed (ft), with a maximum of 5 ft	
h_{avg}	= average height of water above the filter bed (ft), one half of the	
	filter height (hf)	
<u>t</u> _d	allowable drawdown time (1.67 days)	
_		

With a filter depth of 2 feet and a height of water of 1.1 feet:

$$SA_{filter} = \frac{475 \text{ ft}^3 \times 2 \text{ ft}}{3.5 \frac{\text{ft}}{\text{day}} \times (0.55 \text{ ft} + 2 \text{ ft}) \times 1.67 \text{ days}} = 64 \text{ ft}^2$$

A surface area of 64 square feet will yield 70 cubic feet of temporary ponding volume above the filter and 46 cubic feet of temporary ponding volume above the 6-foot by 7-foot first chamber, for a total of 116 cubic feet—enough to meet the 112-cubic-foot temporary ponding requirement.

Step 7: Check Design Inverts

$$D = h_f + d_f + 1 \text{ ft}$$

where:

D	=	depth of filter chamber (from bottom of filter to bypass pipe outl	let
		invert) (ft)	
h_f	=	height of water above filter bed, which vertical distance between	1
-		top of filter layer and bypass pipe outlet invert = 1 feet	
d_f	=	depth of filter layer (ft) = 2 feet	
1 ft	=	additional depth for underdrain and pea gravel layers	

Note: *D* must be equal to or smaller than the difference between the invert in and invert out (5 feet).

$$D = 1.1 \text{ ft} + 2 \text{ ft} + 1 \text{ ft} = 4.1 \text{ ft}$$

The result of 4.1 feet is less than 5 feet, which is good.

Step 8: Determine Size of Bypass Pipe

Determine the capacity of the bypass pipe:

$$D = \left[\frac{2.16 \times n \times Q_{p15}}{\sqrt{S}}\right]^{0.375}$$

where:

$$\begin{array}{lll} \underline{D} & = & \text{estimated bypass pipe diameter (ft)} \\ \underline{n} & = & \text{Manning s roughness coefficient} = 0.011 \\ \underline{O_{p15}} & = & \text{bypass peak flow (cfs)} = 1.74 \text{ cfs} \\ \underline{S} & = & \text{pipe slope} = \text{assume } 0.5\% = 0.005 \\ \end{array}$$

$$D = \left[\frac{2.16 \times 0.011 \times 1.74}{\sqrt{0.005}} \right]^{0.375} = 0.82 \text{ ft}$$

Use: D = 1 ft (12 in.)

Step 9: Determine Submerged Weir Opening in First Chamber

Since the weir opening in the first chamber is submerged, the orifice equation is used to calculate the dimensions of the weir opening:

$$Q_{p15} = C \times A_{wl} \times \sqrt{2gh_{max}}$$

therefore:

$$A_{wl} = \frac{Q_{p15}}{C \times \sqrt{2gh_{max}}}$$

where:

A_{wI}		area of weir opening in first chamber (ft ²) = $h_{wl} \times l_{wl}$
h_{wI}	=	weir height, assume 1 foot
l_{wI}	=	weir length (ft)
<u>Q</u> _{p15}	=	bypass peak flow (cfs) = 1.74 cfs
C		0.6
g		gravitational acceleration (32.2 ft/s ²)
h_{max}	=	hydraulic head above the center line of weir (ft)
	=	[(invert in - invert out) – $(h_{wl}/2)$]
	_	[(98 ft - 95 ft) - 0.5 ft] - 2.5 ft

$$A_{wl} == 0.23 \text{ ft}^2 = h_{wl} \times l_{wl}$$

$$l_{wl} = \frac{A_{wl}}{h_{w;}} = \frac{0.23 \text{ ft}^2}{1 \text{ ft}} = 0.23 \text{ ft}$$

The minimum requirement is 0.23 ft.

Note: Assume 50% of the weir opening is clogged, therefore, use the following:

$$l_{wl} = 2 \times \left(\frac{A_{wl}}{h_{w;}}\right) = 2 \times \left(\frac{0.23 \text{ ft}^2}{1 \text{ ft}}\right) = 0.46 \text{ ft}$$

Use: $I_{w1} = 0.5 \text{ ft}$

Step 10: Structure Dimensions (Internal Only)

Second Chamber:

$$A_f = L_2 \times W$$

$\underline{A_f} =$	surface area of filter layer (second chamber) = 64 ft^2
L_2 =	length of filter layer (second chamber) (ft)
$\underline{\overline{W}} =$	width of chamber, use 6 feet

Appendix T Underground Sand Filter Design Example

$$L_2 = \frac{A_f}{W} = \frac{64 \text{ ft}^2}{6 \text{ ft}} = 10.7 \text{ ft}$$

<u>Use: $L_2 = 11 \text{ ft}$ </u>

First Chamber determined in Step 5:

L_{l}	=	7	ft
\overline{W}	=	6	ft

Third Chamber:

Select L_3 , length of third chamber = 3 ft

therefore:

Length of structure, $L = L_1 + L_2 + L_3 = 7$ ft + 11 ft + 3ft = 21 ft

Total inner height inside sand filter:

 \underline{Dt} = depth of filter chamber (Step 7) + inflow pipe diameter + free board

Dt = 5 ft + 1 ft + 2 ft = 8 ft

Appendix U Site Drainage Area and BMP Design Diagrams

U.1 Design Diagram Overview

Section U.2 Site Drainage Area Diagrams illustrates how to determine a project's Site Drainage Areas (SDAs) when designing a Stormwater Management Plan (SWMP). Section U.3, "Determining When BMP Performance is Considered to be On-Site" illustrates how to determine whether the retention, treatment, and storage volumes achieved by a stormwater best management practice (BMP) should be considered "on-site" in determining compliance with performance requirements for the project.

<u>Each diagram is intended to illustrate conceptual designs. The diagrams are not intended to illustrate preferred design options and are not drawn to scale.</u>

U.2 Site Drainage Area Diagrams

As described in Chapter 2, "Minimum Control Requirements," an SDA is the area that drains to a point of discharge (or sheet flow) from the site. These diagrams may be used to assist in defining SDAs. Each diagram represents a project with more than one discharge point. In many cases, a site will only have one discharge point, resulting in one SDA.

The following diagrams can be used to determine SDA boundaries based on the type of project:

<u>Projects Disturbing a Single Lot.</u> Each point of discharge (or sheet flow) will be determined <u>based on the boundary of the lot.</u>

Projects Disturbing Many Lots (including common plans of development). Each point of discharge (or sheet flow) will be determined based on the external boundaries of all lots. The internal lot boundaries between the disturbed lots may be disregarded when determining SDA points of discharge (or sheet flow).

<u>Projects Occurring on Campuses.</u> Each point of discharge (or sheet flow) will be determined based on the boundary of the limit of disturbance (LOD) and/or Major Substantial Improvement activity.

Figure U.1 shows the determination of SDA boundaries for projects occurring on a single lot. The site boundary is the same as the lot boundary, so each SDA is based on the point of departure or sheet flow from the lot (and not the LOD for the project). In SDA 1, although there are two points of discharge from the LOD, these pipes come together within the site and exit the site from a single point of departure, making it one SDA. Individual discharge points from the site that connect to a common pipe outside the lot are considered separate SDAs.






Figure U.1 Site Drainage Areas on a single lot.

Figure U.2 shows the determination of SDA boundaries for project occurring on multiple lots. The site boundary is the same as the external boundaries of the group of disturbed lots. The LOD and any internal lot boundaries are not considered in determining the SDA boundaries. For example, although stormwater may cross from one lot to another before departing the site, these

are not considered separate SDAs. Individual discharge points from the site that connect to a common pipe outside the lots are considered separate SDAs.




Figure U.2 Site Drainage Areas on projects with multiple lots.

Figure U.3 shows the determination of SDA boundaries on a campus. Each SDA is defined based on the point of departure or sheet flow from the LOD, rather than campus boundaries.

<u>Individual discharge points from the LOD that connect to a common pipe outside the LOD are considered separate SDAs.</u>




Figure U.3 Site Drainage Areas on campuses.

U.3 Determining When BMP Performance is Considered to be On-Site

Appendix U Site Drainage Area and BMP Design Diagrams

This section illustrates BMP design scenarios and clarifies whether the retention, treatment, and storage volumes achieved by a BMP may be considered "on-site" in determining compliance with performance requirements for the project. For simplicity, these diagrams only depict whether a single BMP's performance may be considered on-site. The project must comply with all other regulatory requirements. This may include minimum performance requirements for SDAs or design of additional BMPs.

These diagrams assume that the BMPs depicted meet all other design requirements specified in this guidebook. For simplicity in illustrating these design scenarios, each diagram assumes there is only one SDA. Each diagram evaluates a single BMP, but additional BMPs may be necessary to meet the site's performance requirements.

BMPs may achieve a retention, treatment, or storage volume that cannot be used to meet on-site performance requirements. In these cases, the volume that meets on-site performance requirements is proportional to the volume of runoff received by the BMP from qualifying contributing drainage area (CDA), as depicted in the design scenario. The volume that is not considered on-site may be eligible for SRC certification according to Chapter 7, "Generation, Certification, Trading, and Retirement of Stormwater Retention Credits" of this guidebook.

<u>Project Disturbing a Single Lot.</u> Figure U.4 through Figure U.12 depict design scenarios that are applicable to projects that disturb a single lot.

Projects Disturbing Many Lots (including common plans of development). Figure U.13 through Figure U.22 depict design scenarios that are applicable to projects that disturb many lots. In these examples, all of the disturbed lots are reviewed by DOEE on a single SWMP. This may be applicable for common plans of development. As the lots are developed under a common plan, the project's performance requirements and compliance may be calculated jointly. However, the SWMP and covenant should state the portion of the performance requirement that is calculated for each lot. If at some point in the future, some of the lots are redeveloped or a BMP maintenance issue arises, each lot may be responsible for achieving compliance with its own portion of the performance requirements.

<u>Projects Occurring on Campuses.</u> Figure U.23 through Figure U.27 depict design scenarios that are applicable to projects that occur on campuses (universities, hospitals, or similar properties).

<u>Projects Occurring in the Public Right-of-Way (PROW)</u>. Figure U.28 through Figure U.32 depict design scenarios that are applicable to projects, or portions of projects, that occur in the <u>PROW</u>.

Shared BMPs. In some cases, DOEE may approve the use of a shared BMP between two or more SWMPs. A shared BMP may meet on-site requirements for each SWMP that has CDA to the shared BMP, as shown in Figure U.33. The portion of the volume achieved by the shared BMP that meets on-site requirements for a project is proportional to the runoff volume received from the site where that project is occurring. Shared BMPs must be entered into the Stormwater Database and represented on the SWMP as directed by DOEE, identifying the CDA to the shared BMP from each site.

When a shared BMP is used, each project may have a maintenance obligation for the BMP and its CDA. If so, each SWMP and declaration of covenants must show this responsibility for maintaining the shared BMP. Furthermore, the SWMP and Declaration must show that if, at some point in the future, stormwater management is no longer provided by the shared BMP, the site is responsible for managing stormwater either on site or through a combination of on-site and off-site retention.




Figure U.4 shows that if a BMP and its entire CDA are within the LOD, any retention or treatment volume achieved by the BMP may meet on-site requirements.




Figure U.4 Single lot: BMP and CDA are entirely within the LOD.

Figure U.5 shows that if a BMP is within the LOD and the entire CDA is within the lot that is being disturbed, any retention or treatment volume achieved by the BMP may meet on-site requirements.




Figure U.5 Single lot: CDA is partially outside the LOD, but within the lot.

Figure U.6 shows that if a BMP's CDA includes any area from the PROW, any retention or treatment volume achieved may partially meet on-site requirements.




Figure U.6 Single lot: CDA is partially in the PROW.

Figure U.7 shows that if a BMP's CDA includes any area from an adjacent lot that is not part of the project, any retention or treatment volume achieved by the BMP may partially meet on-site requirements.




Figure U.7 Single lot: CDA includes area on an adjacent lot.

Figure U.8 shows that if a BMP is installed outside the LOD, and receives no runoff from the LOD, it may be considered voluntary and generate SRCs. However, no retention or treatment volume achieved may meet on-site performance requirements. If the applicant wishes to use the BMP to meet on-site requirements, refer to Figure U.9.




Figure U.8 Single lot: BMP and CDA are entirely outside the LOD.

Figure U.9 shows that if a BMP is installed outside the LOD for a project, any retention or treatment volume achieved by the BMP may meet on-site requirements if the BMP's surface is considered part of the LOD. Performance requirements are calculated for this additional LOD. If the applicant wishes to install the BMP voluntarily without increasing the LOD, refer to Figure U.8.




Figure U.9 Single lot: BMP and CDA are outside primary LOD.

Figure U.10 shows that if a BMP is installed outside the LOD for a project, but receives runoff from within the LOD, DOEE will also consider the surface of the BMP to be part of the LOD. Performance requirements are calculated for this additional LOD. Any retention or treatment achieved by the BMP may meet on-site requirements.




Figure U.10 Single lot: BMP is outside primary LOD; CDA includes area within primary LOD.

Figure U.11 shows that planting trees within the LOD may meet on-site requirements. Land disturbance associated with tree planting is considered part of the LOD for the project.

Alternatively, trees may be planted outside of the LOD to generate SRCs without increasing the LOD, but these trees will not meet on-site requirements.

Planting volun	tary trees o	n adjacent lots or in the PROW may be SRC-eligible	9
Lot Boundary		LOD	
Planting voluntary trees outside the LOD may be SRC-eligible		Planting trees within the LOD	
LOD Planting to within the meets on requirem	LOD -site	meets on-site requirements	
Legend	utornal houndar	v of lat/s)/sampus/RROW	
		y of lot(s)/campus/PROW ce and substantial improvement for the project	
,		his area meet on-site requirements	
	lanting trees in t e SRC-eligible	his area may not meet on-site requirements but may	

Figure U.11 Single lot: Tree planting.

<u>Figure U.12</u> shows that preserving trees anywhere within the LOD may meet on-site requirements. Generally, preserving trees outside the LOD does not provide a retention volume.




Figure U.12 Single lot: Tree preservation

<u>Figure U.13 shows that if a BMP and its entire CDA are within the LOD, any retention or treatment volume achieved by the BMP may meet on-site requirements for all lots.</u>




Figure U.13 Many lots: BMP and CDA are entirely within the LOD.

<u>Figure U.14 shows that if a BMP is within the LOD and the entire CDA is within the disturbed lots, any retention or treatment volume achieved by the BMP may meet on-site requirements for all lots.</u>




Figure U.14 Many lots: CDA is partially outside the LOD, but within the disturbed lots.

Figure U.15 shows that if a BMP's CDA includes any area from the PROW, the retention or treatment of runoff from the PROW does not meet on-site requirements.




Figure U.15 Many lots: CDA is partially in the PROW.

<u>Figure U.16</u> shows that if a BMP's CDA includes any area from an adjacent lot that is not part of the project, the retention or treatment of runoff from the adjacent lot does not meet on-site requirements.




Figure U.16 Many lots: CDA includes area on an adjacent lot.

Figure U.17 shows that if a BMP is installed outside the LOD on one of the disturbed lots, and receives no runoff from the LOD, it may be considered voluntary and generate SRCs. However, no retention or treatment volume achieved may meet on-site requirements. If the applicant wishes to use the BMPs to meet on-site requirements, refer to Figure U.23.




Figure U.17 Many lots: BMP and CDA are entirely outside the LOD.

Figure U.18 shows that if a BMP is installed on an adjacent lot that is not part of the project, it may be considered voluntary and generate SRCs. However, no retention or treatment volume achieved by the BMP may meet on-site requirements. If the applicant wishes to use this BMP to meet on-site requirements, refer to Figure U.19.




Figure U.18 Many lots: BMP and CDA are on an adjacent, undisturbed lot.

Figure U.19 shows that if a BMP is installed outside the LOD for a project on one of the disturbed lots, any retention or treatment volume achieved by the BMP may meet on-site requirements if the BMP's surface is considered part of the LOD. Performance requirements are calculated for this additional LOD. If the applicant wishes to install the BMPs voluntarily without increasing the LOD, refer to Figure U.17.




Figure U.19 Many lots: BMP and CDA are outside primary LOD.

Figure U.20 shows that if a BMP is installed outside the LOD for a project, but receives runoff from within the LOD, DOEE will also consider the surface of the BMP to be part of the LOD. Performance requirements are calculated for this additional LOD. Any retention or treatment achieved by the BMP may meet on-site requirements.




Figure U.20 Many lots: BMP is outside primary LOD; CDA includes area within primary LOD.

Figure U.21 shows that planting trees inside the LOD may meet on-site requirements. Land disturbance associated with tree planting is considered part of the LOD for the project. Alternatively, trees may be planted in these areas voluntarily to generate SRCs without increasing the LOD, but these trees will not meet on-site requirements.




Figure U.21 Many lots: Tree planting.

Figure U.22 shows that preserving trees anywhere within the LOD may meet on-site requirements. Generally, preserving trees outside the LOD does not provide a retention volume.

Lot Boundar			
_	rees anywhere outside es not provide retention volume	Preserving trees anywhere outside the LOD does not provide retention volume	
LOD		Preserving trees within the LOD meets on-site requirements for all lots	
Legend			
	External boundary of lot(s)/campus/PROW		
	Internal boundary of lot(s)/campus/PROW		
LOD	Limit of disturbance and substantial improvement for the project		
	Preserving trees in this area may meet on-site requirements		

Figure U.22 Many lots: Tree preservation.

<u>Figure U.23 shows that if a BMP and its entire CDA are within the LOD, any retention or treatment volume achieved by the BMP may meet on-site requirements.</u>




Figure U.23 Campus: BMP and CDA are entirely within the LOD.

Figure U.24 shows that if a BMP's CDA includes any area from outside the LOD, any retention or treatment volume achieved by the BMP may partially meet on-site requirements.




Figure U.24 Campus: CDA is partially outside the LOD.

Figure U.25 shows that if a BMP is installed outside the LOD, and receives no runoff from the LOD, it may be considered voluntary and generate SRCs. However, no retention or treatment volume achieved may meet on-site requirements. If the applicant wishes to use these BMPs to meet on-site requirements, refer to Figure U.29.




Figure U.25 Campus: BMP and CDA are entirely outside the LOD.

Figure U.26 shows that planting trees anywhere within the LOD may meet on-site requirements. Land disturbance associated with tree planting is considered part of the LOD for the project. Alternatively, trees may be planted in elsewhere on the campus, outside the LOD, to voluntarily to generate SRCs without increasing the LOD, but these trees will not meet on-site requirements.




Figure U.26 Campus: Tree planting.

<u>Figure U.27 shows that preserving trees anywhere within the LOD may meet on-site</u> requirements. Generally, preserving trees outside the LOD does not provide a retention volume.




Figure U.27 Campus: Tree preservation.

Figure U.28 shows that if a BMP and its entire CDA are within the LOD, any retention or treatment volume achieved by the BMP may meet PROW requirements.




Figure U.28 PROW: BMP and CDA are entirely within the LOD.

<u>Figure U.29 shows that if the BMP is within the LOD and its entire CDA is within the PROW,</u> any retention or treatment volume achieved by the BMP may meet PROW requirements.




Figure U.29 PROW: CDA is partially outside the LOD, but within the PROW.

Figure U.30 shows that if the BMP is within the LOD and its CDA includes an adjacent lot, any retention or treatment volume achieved by the BMP may meet PROW requirements. Retention of the 1.2-inch storm from the PROW must be achieved prior to receiving runoff from adjacent lots. BMPs located in the PROW cannot meet on-site requirements for adjacent lots, even if the CDA includes adjacent lot.




Figure U.30 PROW: CDA is partially in an adjacent lot.

Figure U.31 shows that planting trees within the LOD may meet PROW requirements. Land disturbance associated with tree planting is considered part of the LOD for the project. Alternatively, trees may be planted in these areas voluntarily to generate SRCs without increasing the LOD.




Figure U.31 PROW: Tree planting.

Figure U.32 shows that preserving trees within the LOD may meet PROW requirements. Generally, preserving trees outside the LOD does not provide a retention volume.




Figure U.32 PROW: Tree preservation.

<u>Figure U.33 shows how the retention or treatment achieved by a shared BMP may meet on-site requirements for many SWMPs.</u>




Figure U.33 Shared BMPs.

PROPOSED PENISION PROPOSED PRO

Appendix TAppendix V Resources

The following documents provide more detailed information on many aspects of BMPbest management practice (BMP) design than is found in this Guidebookguidebook. These resources may be useful for those looking to develop greater understanding of individual BMPs or stormwater design in general. Recommendations in these resources may be used to inform BMP designs; however, where conflicts occur between these resources and the Guidebookthis guidebook, the requirements of the Guidebookthis guidebook prevail.

- American Association of State Highway and Transportation Officials (AASHTO). 1993.

 AASHTO Guide for Design of Pavement Structures, 4th Edition with 1998 Supplement. Washington, D.C.
- Arendt, R. G. 1996. Conservation design for subdivisions. A practical guide to creating open space networks. Washington, DC: Island Press. 184 p.
- ASTM International. 2006. <u>E2400 / E2400M-06(2015)e1</u>, Standard Guide for Selection, Installation, and Maintenance of Plants for Green (Vegetated) Roof Systems. <u>Standard E2400 06</u>. ASTM, International. West Conshohocken, PA. available online: http://www.astm.org/Standards/E2400.htm.
- <u>, 2015, www.astm.org</u> Brown, M.L., and R.G. Brown. 1984. Herbaceous Plants of Maryland. Port City Press, Baltimore, MD.
- Brown, Melvin L., and R.G. Brown. 1984. Woody Plants of Maryland. Port City Press, Baltimore, MD.
- City Press, Baltimore, MD. Cabell Brand Center. 2009. Virginia Rainwater Harvesting Manual, Version 2.0. Salem, VA.

 https://www.radford.ed
 u/content/dam/departments/administrative/Sustainability/Documents/Rainwater-Manual.pdf
- Cappiella, K., T. Schueler, and T. Wright. 2005. Urban Watershed Forestry Manual. Part 1: Methods for Increasing Forest Cover in a Watershed. NA-TP-04-05. USDA Forest Service, Northeastern Area State and Private Forestry. Newtown Square, PA.
- Cappiella, K., T. Schueler and T. Wright. 2006. Urban Watershed Forestry Manual: Part 2: Conserving and Planting Trees at Development Sites. USDA Forest Service. Center for Watershed Protection. Ellicott City, MD.
- Center for Watershed Protection. 1998. Better site design: a handbook for changing development rules in your community. Ellicott City, MD. 174 p.
- Chollak, T. and P. Rosenfeld. 1998. Guidelines for Landscaping with Compost-Amended Soils. City of Redmond Public Works. Redmond, WA. Available online at:

- www.redmond.gov/common/pages/UserFile.aspx?fileId=14766Available online at: http://www.redmond.gov/common/pages/UserFile.aspx?fileId=14766
- Claytor, R. and T. Schueler. 1996. Design of Stormwater Filtering Systems. Chesapeake Research Consortium and the Center for Watershed Protection. Ellicott City, MD. http://www.cwp.org/online-watershed-library?view=docmanhttps://owl.cwp.org/
- Das, Braja M. 1990. Principle of Geotechnical Engineering Second Edition. PWS-KENT Publishing Company. Boston, MA.
- District of Columbia Department of Transportation (DDOT). Design and Engineering Manual 2009.
 - http://de.gov/DC/DDOT/Projects+and+Planning/Standards+and+Guidelines/Design+and+Engineering+Manual2017. https://ddot.dc.gov/publication/ddot-design-and-engineering-manual-2017
- <u>District of Columbia Department of Transportation (DDOT). Green Infrastructure Standards</u> 2014. https://ddot.dc.gov/publication/ddot-green-infrastructure-standards-2014
- District of Columbia Department of Transportation (DDOT). Public Realm Design Manual 2011. http://dc.gov/DC/DDOT/Projects+and+Planning/Standards+and+Guidelines/Public+Realm+Design+Manualhttps://ddot.dc.gov/PublicRealmDesignManual
- District of Columbia Water and Sewer Authority.2009. D.C. Project Design Manual Volume 3 Infrastructure Design. Washington DC.
 - http://www.dewater.com/business/permits/DCWater_Project_Design_Manual.pdfhttps://www.w.dewater.com/sites/default/files/Project%20Design%20Manual%20Volume%203%20Infrastructure%20Design.pdf
- Doherty, K.; Bloniarz, D.; Ryan, H. 2003. Positively the pits: successful strategies for sustainable streetscapes. Tree Care Industry 14(11): 34-42.
 - www.umass.edu/urbantree/publications/pits.pdfhttp://www.umass.edu/urbantree/publications/pits.pdf (Accessed 2006).
- Dunnett, N. and N. Kingsbury. 2004. Planting Green Roofs and Living Walls. Timber Press. Portland, Oregon.
- Environmental Services City of Portland, 2008, Green Streets Construction Guide. Portland, OR. https://www.portlandoregon.gov/bes/article/228860 https://www.portlandoregon.gov/bes/article/228860
- Gilman, E. F. 1997. Trees for urban and suburban landscapes. Albany, NY: Delmar Publishers.
- Hairston-Strang, A. 2005. Riparian forest buffer design and maintenance. Annapolis: Maryland Department of Natural Resources.
 - $\frac{http://www.dnr.state.md.us/forests/download/rfb_design\&maintenance.pdf\underline{http://dnr.marylan}}{d.gov/forests/Pages/publications.aspx}$

- Hathaway, J.M. and Hunt, W.F. 2006. Level Spreaders: Overview, Design, and Maintenance. Urban Waterways Design Series. North Carolina Cooperative Extension Service. Raleigh, NC. Available online:
 - http://www.bae.ncsu.edu/stormwater/PublicationFiles/LevelSpreaders2006.pdfAvailable online: http://chesapeakestormwater.net/wp-content/uploads/downloads/2012/01/LevelSpreaders2006.pdf
- Hightshoe, G.L., 1988. Native Trees, Shrubs, and Vines for Urban and Rural America. Van Nostrand Reinhold, New York, NY.
- Hirschman, D., L. Woodworth and S. Drescher. 2009. Technical Report: Stormwater BMPs in Virginia's James River Basin: An Assessment of Field Conditions & Programs. Center for Watershed Protection. Ellicott City, MD.
- Hunt, W., M. Burchell, J. Wright and K. Bass. 2007. "Stormwater Wetland Design Update: Zones, Vegetation, Soil and Outlet Guidance." Urban Waterways. North Carolina State Cooperative Extension Service. Raleigh, NC.
- Hunt, W.F. III and W.G. Lord. 2006. "Bioretention Performance, Design, Construction, and Maintenance." North Carolina Cooperative Extension Service Bulletin. Urban Waterways Series. AG-588-5. North Carolina State University. Raleigh, NC.
- Jackson, N. 2007. Design, Construction and Maintenance Guide for Porous Asphalt Pavements. National Asphalt Pavement Association. Information Series 131. Lanham, MD. www.hotmix.comhttp://www.asphaltpavement.org/index.php.
- Low Impact Development Center. 2003. Guideline for Soil Amendments. Available online at: ..
- Luckett, K. 2009. Green Roof Construction and Maintenance. McGraw-Hill Companies, Inc.
- Maryland—National Capital Park & Planning Commission. 1998. Native Plants of Prince George's County, Maryland 1997–1998. Maryland—National Capital Park & Planning Commission, Riverdale, MD.
- New Jersey Corporation for Advanced Technology (NJCAT) Technology Verification Program and Testing Protocols available at: -andhttp://www.njcat.org/ and http://www.njstormwater.org/treatment.html
- New Jersey Department of Environmental Protection (NJDEP), 2009a. Protocol for Manufactured Filtration Devices for Total Suspended Solids Based on Laboratory Analysis Dated August 5, 2009, Revised December 15, 2009. New Jersey Department of Environmental Protection. https://www.njstormwater.org/pdf/filter-protocol-12-15-09.pdf
- NJDEP, 2009b. Protocol for Total Suspended Solids Removal Based on Field Testing Amendments to TARP Protocol Dated August 5, 2009, Revised December 15, 2009. New Jersey Department of Environmental Protection. https://www.njstormwater.org/pdf/field-protocol-12-15-09.pdf

- NJDEP 2011 Transition for Manufactured Treatment Devices, July 15, 2011. Available at: http://www.njstormwater.org/pdf/mtd-certification-process-7-13.pdf
- North Carolina Division of Water Quality (NCDWQ). 2010. Level Spreader-Vegetated Filter Strip System. Stormwater Best Practices Manual. Raleigh, NC.
 - http://portal.ncdenr.org/c/document_library/get_file?uuid=5d698f00-caaa-4f64-ac1f-d1561b4fd53d&groupId=38364
- Palone, R. S.; Todd, A. H., eds. 1998. Chesapeake Bay riparian handbook: a guide for establishing and maintaining riparian forest buffers. NA-TP-02-97. Radnor, PA: USDA Forest Service, Northeastern Area State and Private Forestry.
- Pennsylvania State University. 1999. A guide to preserving trees in development projects.
 University Park, PA: Penn State College of Agricultural Sciences, Cooperative Extension. 27 p.
- "Precipitation-Frequency Atlas of the United States" NOAA Atlas 14, Volume 2, Version 3.0, G. M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley, NOAA, National Weather Service, Silver Spring, Maryland, 2006.

 http://hdse.nws.noaa.gov/hdse/pfds/https://hdsc.nws.noaa.gov/hdse/pfds/
- Pitt, R., 1994, Small Storm Hydrology. University of Alabama Birmingham. Unpublished manuscript. Presented at design of stormwater quality management practices. Madison, WI, May 17-19 1994.
- Reed, P.B. Jr., 1988. National List of Species That Occur in Wetlands: Northeast. U.S. Fish and Wildlife Service, St. Petersburg, FL.
- Roa-Espinosa. 2006. An Introduction to Soil Compaction and the Subsoiling Practice. Technical Note. Dane County Land Conservation Department. Madison, Wisconsin.
- Schueler, Thomas R. 1987. Controlling Urban Runoff: A Practice Manual for Planning and Designing Urban BMPs. Department of Environmental Programs. Metropolitan Washington Council of Governments. Prepared for: Washington Metropolitan Water Resources Planning Board. Washington, DC.
- Schueler, Thomas R. 1992. Design of Stormwater Wetland Systems. Metropolitan Washington Council of Governments. Washington, DC.
- Schueler, T. R. 1995. Site planning for urban stream protection. Ellicott City, MD: Center for Watershed Protection. 232 p.
- Schueler, T.; Brown, K. 2004. Urban stream repair practices. Version 1.0. Manual 4 of the Urban Subwatershed Restoration Manual Series. Ellicott City, MD: Center for Watershed Protection.
- Smith, D. 2006. Permeable Interlocking Concrete Pavement-selection design, construction and maintenance. Third Edition. Interlocking Concrete Pavement Institute. Herndon, VA.

- Snodgrass, E. and L. Snodgrass. 2006. Green Roof Plants: a resource and planting guide. Timber Press. Portland, OR.
- Sturm, Paul, Chris Swann, and Deb Caraco. 2000. Impacts of Urbanization on Receiving Waters. Center for Watershed Protection. Ellicott City, MD.
- U.S. Department of Agriculture (USDA). 1954. Handbook of channel design for soil and water conservation. SCS-TP-61. Washington, DC. Available online: http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1044529.pdf online: https://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1044529.pdf
- U.S. Fish and Wildlife Service, 2009. Native Plants for Wildlife Habitat and Conservation Landscaping: Chesapeake Bay Watershed.

http://www.nps.gov/plants/pubs/chesapeake/pdf/chesapeakenatives.pdfhttps://www.fws.gov/Chesapeakebay/pdf/NativePlantsforWildlifeHabitatandConservationLandscaping.pdf

- U.S. Fish and Wildlife Service, 2001. Native Plants for Wildlife Habitat and Conservation Landscaping, Maryland: Coastal Plain. http://www.fws.gov/chesapeakebay/bayscapes/bsresources/bs-nativeguides.html
- U.S. Fish and Wildlife Service, 2001. Native Plants for Wildlife Habitat and Conservation Landscaping, Maryland: Piedmont Region.

http://www.nps.gov/plants/pubs/nativesMD/pdf/MD-Piedmont.pdfhttps://www.fws.gov/chesapeakebay/bayscapes/bsresources/bsnativeguides.html

- Virginia Department of Conservation and Recreation (VA DCR). 1999. Virginia Stormwater Management Handbook, first edition.
- "Washington D.C. Recommended." NPIN: Recommended Native Plants. The University of Texas at Austin, Lady Bird Johnson Wildflower Center, n.d. Web. 11 July 2013. <a href="http://www.wildflower.org/collections/collection.php?collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wildflower.org/collection=DChttps://www.wild
- Weiler, S. and K. Scholz-Barth. 2009. Green Roof Systems: A Guide to the Planning, Design, and Construction of Landscapes over Structure. Wiley Press. New York, NY.

PROPOSED PENISION PROPOSED PRO

Appendix UAppendix W Definitions

<u>Advanced Design (AD)</u> – Detailed design for an area of a project described explicitly in the <u>following:</u>

- (a) Stage Two (2) planned unit development (PUD) application to the District of Columbia Zoning Commission;
- (b) Application for design review under the Capitol Gateway Overlay District to the District Zoning Commission; and
- (c) Final design submission to the National Capital Planning Commission (NCPC)
- Affordable Housing A single-family or two-family house that is built to be offered for tent or for sale for residential occupancy below market value and is made available to, and affordable to, a household whose income is equal to, or less than, eighty percent (80%) of the Area Median Income calculation provided by the United States Department of Housing and Urban Development.
- **Anacostia Waterfront Development Zone (AWDZ)** the following areas of the District of Columbia, as delineated on a map in the DDOE's DOEE's Stormwater Management Guidebook (Figure 2.1):
 - (a) Interstate 395 and all rights-of-way of Interstate 395, within the District, except for the portion of Interstate 395 that is north of E Street, S.W., or S.E.;
 - (b) All land between that portion of Interstate 395 that is south of E Street, S.W., or S.E., and the Anacostia River or Washington Channel;
 - (c) All land between that portion of Interstate 695, and all rights of way, that are south of E Street, S.W. or S.E., and the Anacostia River;
 - (d) The portion of Interstate 295 that is north of the Anacostia River, within the District, and all rights-of-way of that portion of Interstate 295;
 - (e) All land between that portion of Interstate 295 that is north of the Anacostia River and the Anacostia River;
 - (f) The portions of:
 - The Anacostia Freeway that is north or east of the intersection of the Anacostia Freeway and Defense Boulevard and all rights-of-way of that portion of the Anacostia Freeway;
 - Kenilworth Avenue that extend to the northeast from the Anacostia Freeway to Eastern Ave; and
 - Interstate 295, including its rights-of-way, that is east of the Anacostia River and that extends to the southwest from the Anacostia Freeway to Defense Boulevard.

- (g) All land between those portions of the Anacostia Freeway, Kenilworth Avenue, and Interstate 295 described in -(f) and the Anacostia River;
- (h) All land that is adjacent to the Anacostia River and designated as parks, recreation, and open space on the District of Columbia Generalized Land Use Map, dated January 2002, except for the land that is:
 - North of New York Avenue, N.E.;
 - East of the Anacostia Freeway, including rights-of-way of the Anacostia Freeway;
 - East of the portion of Kenilworth Avenue that extends to the northeast from the Anacostia Freeway to Eastern Avenue;
 - East of the portion of Interstate 295, including its rights-of-way, that is east of the Anacostia River and that extends to the southwest from the Anacostia Freeway to Defense Boulevard, but excluding the portion of 295 and its rights-of-way that go to the northwest across the Anacostia River;
 - Contiguous to that portion of the Suitland Parkway that is south of Martin Luther King, Jr. Avenue; or
 - South of a line drawn along, and as a continuation both east and west of the center line of the portion of Defense Boulevard between Brookley Avenue, S.W., and Mitscher Road, S.W.;
- (i) All land, excluding Eastern High School, that is:
 - Adjacent to the land described in (h);
 - West of the Anacostia River; and
 - Designated as a local public facility on the District of Columbia Generalized Land Use Map, dated January 2002;
- (j) All land that is:
 - South or east of that portion of Potomac Avenue, S.E., between Interstate 295 and 19th Street, S.E.; and
 - West or north of the Anacostia River;
- (k) The portion of the Anacostia River within the District; and
- (1) The Washington Channel.
- Anacostia Waterfront Development Zone Site -(AWDZ site) A site within the Anacostia Waterfront Development Zone (AWDZ) that undergoes a major regulated project that is publicly owned or publicly financed.
- **Animal confinement area** An area, including a structure, used to stable, kennel, enclose, or otherwise confine animals, not including confinement of a domestic animal on a residential property.
- **Applicant** A person or their agent who applies for approval pursuant to this chapter.

- **As-built plan** A set of architectural, engineering, or site drawings, which sometimes include including specifications that certify, describe, delineate, or present details of a completed construction project.
- Athletic playing fields Compacted land cover and synthetic surfaces that are constructed primarily for use for athletic activities at public parks and schools. Compacted land cover and synthetic surfaces for which athletic activities are not the primary use are not considered athletic playing fields, unless these areas are necessary to support use of an adjacent area that is primarily used for athletic activities. Synthetic surfaces must have a minimum surface permeability of at least 10 inches per hour, in accordance with ASTM F2898 Standard Test Method for Permeability of Synthetic Turf Sports Field Base Stone and Surface System by Non-confined Area Flood Test Method.
- **Best management practice (BMP)** Structural or non-structural practice that minimizes the impact of stormwater runoff on receiving waterbodies and other environmental resources, especially by reducing runoff volume and the pollutant loads carried in that runoff.
- **Buffer** An area along a stream, river, or other natural feature that provides protection for that feature.
- **Building permit** Authorization for construction activity issued by the District of Columbia Department of Consumer and Regulatory Affairs.
- **Clearing** The removal of trees and brush from the land excluding the ordinary mowing of grass, pruning of trees or other forms of long-term landscape maintenance.
- Combined sewer overflow (CSO) The discharge of untreated effluent into a water body as a result of the combined volume of stormwater and sanitary water exceeding the capacity of the combined sewer system and wastewater treatment plant.
- <u>Combined sewer system (CSS)</u> Sewer system in which stormwater runoff is conveyed together with sanitary wastewater through sewer lines to a wastewater treatment plant.
- **Common plan of development** _ Multiple, separate, and distinct land-disturbing, substantial improvement, or other construction activities taking place under, or to further, a single, larger plan, although they may be taking place at different times on different schedules.
- Compacted cover An area of land that is functionally permeable, but where permeability is impeded by increased soil bulk density as compared to natural cover, such as through grading, construction, or other activity and will require regular human inputs such as periodic planting, irrigation, mowing, or fertilization. Examples include landscaped planting beds, lawns, or managed turf.
- **Conservation area** <u>An</u> area with a natural cover designation set aside to receive stormwater runoff as part of an impervious surface disconnection practice.

Construction — Activity conducted for the <u>following</u>:

- (a) Building, renovation, modification, or razing of a structure; or
- (b) Movement or shaping of earth, sediment, or a natural or built feature.

Contributing drainage area (CDA) – Area contributing runoff to a BMP.

Control measure — Technique, method, device, or material used to prevent, reduce, or limit discharge.

Critical area stabilization — Stabilization of areas highly susceptible to erosion, including down-slopes and side-slopes, through the use of brick bats, straw, erosion control blanket mats, gabions, vegetation, and other control measures.

Cut — An act by which soil or rock is dug into, quarried, uncovered, removed, displaced, or relocated and the conditions resulting from those actions.

Demolition — The removal of part or all of a building, structure, or built land cover.

Department The District Department of the Environment or its agent.

Detention – Controlling the peak discharge rate of stormwater from a site.

Dewatering — Removing water from an area or the environment using an approved technology or method, such as pumping.

Director — The Director of the District-Department of the Energy and Environment-(DOEE).

District — The District of Columbia.

Drainage area Area contributing runoff to a single point.

DOEE's submittal database – An online platform managed by DOEE and accessible to the public that the Department uses to receive applications and make approval determinations.

Easement — A right acquired by a person to use another person's land for a special purpose.

Electronic media — Means of communication via electronic equipment, including the internet.

Erosion — The process by which the ground surface, including soil and deposited material, is worn away by the action of wind, water, ice, or gravity.

Excavation — An act by which soil or rock is cut into, dug, quarried, uncovered, removed, displaced, or relocated and the conditions resulting from those actions.

Existing retention—Retention on a site, including by each existing best management practice (BMP) and land cover, before retrofit of the site with installation of a new BMP or land cover.

- **Exposed area** Land that has been disturbed or land over which unstabilized soil or other erodible material is placed.
- **Grading** Causing disturbance of the earth, including excavating, filling, stockpiling of earth materials, grubbing, root mat or topsoil disturbance, or any combination of them.
- Green Area Ratio (GAR) The ratio of the weighted value of landscape elements to land area, as it relates to an increase in the quantity and quality of environmental performance of the urban landscape as defined in the Zoning regulation (Title 11 DCMR) Chapter 34. Details are provided under a separate and unique DDOE guidance manual zoning regulation (Chapter 34 of Title 11 of the District of Columbia Municipal Regulations). The GAR Guidebook is available at https://doee.dc.gov/service/green-area-ratio-overview.
- Impervious cover A surface area which that has been compacted or covered with a layer of material that impedes or prevents the infiltration of water into the ground, examples include conventional streets, parking lots, rooftops, sidewalks, pathways with compacted sub-base, and any concrete, asphalt, or compacted gravel surface and other similar surfaces.

Infiltration — The passage or movement of surface water through the soil profile.

Land cover — Surface of land that is impervious, compacted, or natural.

- **Land-cover change** Conversion of land cover from one type to another, typically in order to comply with a requirement of this chapter or to earn certification of a Stormwater Retention Credit- (SRC).
- Land-disturbing activity Movement of earth, land, or sediment that disturbs the land surface and the related use of pervious land to support that movement. This Land-disturbing activity includes stripping, grading, grubbing, trenching, excavating, transporting, and filling of land, as well as the use of pervious adjacent land for movement and storage of construction vehicles and materials. Land-disturbing activity does not include repaving or remilling that does not expose the underlying soil.
- **Low impact development (LID)** A land-planning and engineering-design approach to manage stormwater runoff within a development footprint. It emphasizes conservation, the use of on-site natural features, and structural best management practices stormwater BMPs to store, infiltrate, evapotranspire, retain, and detain rainfall as close to its source as possible with the goal of mimicking the runoff characteristics of natural cover.

Maintenance agreement – See Section 5.4.2-, "Maintenance Agreement.."

Maintenance contract – See "maintenance agreement."

Maintenance responsibility – See Section-, "5.4.1 Maintenance Responsibility-."

Maintenance plan – Planned scheduled maintenance for the life of the BMP.

Maintenance schedule – See "maintenance plan"..."

- **Maintenance standards** Detailed maintenance plan laid out in Exhibit C within Declaration of Covenants Covenants.
- **Major land-disturbing activity** Activity that disturbs, or is part of a common plan of development that disturbs, five thousand 5,000 square feet (5,000 ft²) or greater of land area, except that multipleand either:
 - (a) Any portion of the pre-project land cover is natural; or
 - (b) 2,500 square feet or greater of the post-project land cover is impervious or BMP area

<u>Multiple</u> distinct <u>projectsareas</u> that each disturb less than 5,000 \(\pm^2\)square feet of land and that are in separate, non-adjacent sites do not constitute a major land-disturbing activity.

- Major regulated project A major land-disturbing activity or a major substantial improvement activity.
- Major substantial improvement activity Substantial improvement activity and associated land-disturbing activity, including such activities that are part of a common plan of development, for which the combined footprint of improved building and land-disturbing activity is 5,000 square feet or greater—, and either:
 - (a) Any portion of the pre-project land cover is natural; or
 - (b) 2,500 square feet or greater of the post-project land cover is impervious or BMP area.

A major substantial improvement activity may include a substantial improvement activity that is not associated with land disturbance.

- **Market value of a structure** Assessed value of the structure for the most recent year, as recorded in the real property assessment database maintained by the District of Columbia's Office of Tax and Revenue.
- Natural cover Land area that is dominated by vegetation and does not require regular human inputs such as irrigation, mowing, or fertilization to persist in a healthy condition. Examples include forest, meadow, or pasture.
 - Non-structural BMP-Nonstructural best management practice A land use, development, or management strategy that minimizes to minimize the impact of stormwater runoff, including conservation of natural cover or disconnection of impervious surface.
 - **Off-site retention** Use of a Stormwater Retention Creditstormwater retention credit (SRC) or payment of in-lieu fee in order to achieve an Off Site Retention Volumeoff-site retention volume under these regulations.

- Off-Site Retention Volumesite retention volume (Offv) A portion of a required Stormwater Retention Volumestormwater retention volume or required Water Quality Treatment Volumewater quality treatment volume that is not retained on—site.
- **On-site retention** Retention of a site's stormwater on that site or via conveyance to a shared best management practice stormwater BMP on another site.
- **On-site stormwater management** Retention, detention, or treatment of stormwater on—site or via conveyance to a shared best management practice stormwater BMP.
- Original Stormwater Retention Credit (SRC) owner A person who is indicated as the proposed SRC owner in an application to the Department DOEE for the certification of an SRC. The proposed SRC owner becomes the original SRC owner upon the Department's DOEE's certification of the SRC.
- **Owner** The person who owns real estate or other property, or that person's agent.
- **Peak discharge** The maximum rate of flow of water at a given point and time resulting from a storm event.
- Permeable athletic track A surface, including a surface made of synthetic material, located at a school or public park that is used for athletic purposes including biking, running, and walking, and that allows the infiltration of water into the ground. The track must have a minimum surface permeability of at least 10 inches per hour in accordance with the ASTM F2898 Standard Test Method for Permeability of Synthetic Turf Sports Field Base Stone and Surface System by Non-confined Area Flood Test Method.
- Permeable playground surface A surface, including a surface made of synthetic material, located under a playground area at a school or public park, that allows the infiltration of water into the ground. The playground surface must have a minimum surface permeability of at least 10 inches per hour, in accordance with ASTM F2898 Standard Test Method for Permeability of Synthetic Turf Sports Field Base Stone and Surface System by Non-confined Area Flood Test Method.
- **Person** A legal entity, including an individual, partnership, firm, association, joint venture, public or private corporation, trust, estate, commission, board, public or private institution, cooperative, the Government of the District of Columbia and its agencies, and the federal government and its agencies.
- **Pervious Area** area Area with a compacted cover designation set aside to receive stormwater runoff as part of an impervious surface disconnection practice.
- **Post-development** Describing conditions that may be reasonably expected to exist after completion of land development activity on a site.
- **Practice** A system, device, material, technique, process, or procedure that is used to control, reduce, or eliminate an impact from stormwater; except where the context indicates its more typical use as a term describing a custom, application, or usual way of doing something.

- Preconstruction meeting The mandatory meeting occurring prior to any construction, including the owner, the designer, the installer, and the DDOEDOEE inspector. This meeting must contain an on-site component to evaluate the SWMP against existing site conditions. This should include, at a minimum, a visual examination of land cover types, the tree preservation plan, boundaries of the contributing drainage areaCDA(s), the existing inlet elevation(s) to ensure they conform to original design.
- **Predevelopment** Describing conditions of meadow land and its relationship to stormwater before human disturbance of the land.
 - <u>Preproject Pre-project Describing conditions, including land covers, on a site that exist at before the time that construction described in a Stormwater Management Plan is submitted to DDOEhas begun.</u>

Publicly owned or publicly financed project — A project that is defined as follows:

- (a) That is District-owned or District-instrumentality owned;
- (b) Where at least fifteen percent (15%) of a project's total cost is District-financed or District-instrumentality financed; or
- (c) That includes a gift, lease, or sale from District-owned or District instrumentality-owned property to a private entity.
- Public right-of-way (PROW) The surface, the air space above the surface (including air space immediately adjacent to a private structure located on public space or in a public right-of-way), and the area below the surface of any public street, bridge, tunnel, highway, railway track, lane, path, alley, sidewalk, or boulevard.
- Public space All the publicly owned property between the property lines on a street, park, or other public property as such property lines are shown on the records of the District, and.

 This includes any roadway, tree space, sidewalk, or parking between such property lines, but it excludes adjacent parks and other public property that is not associated with the public right-of-way.
- **Raze** The complete removal of a building or other structure down to the ground <u>or to its</u> foundation.
- **Responsible person** Construction personnel knowledgeable in the principles and practices of soil erosion and sediment control and certified by a Department-approved soil erosion and sedimentation control training program to assess conditions at the construction site that would impact the effectiveness of a soil-erosion or sediment-control measure on the site.
- **Retention** Keeping a volume of stormwater runoff on—site through infiltration, evapotranspiration, storage for non-potable use, or some combination of these.
- **Retention capacity** The volume of stormwater that can be retained by a best management practicestormwater BMP or land cover.

- **Retention failure** Failure to retain a volume of stormwater for which there is an obligation to achieve retention, including retention that an applicant promises to achieve in order to receive Department DOEE-certified Stormwater Retention Credits (SRCs). Retention failure may result from a failure in construction, operation, or maintenance; a change in stormwater flow; or a fraud, misrepresentation, or error in an underlying premise in an application.
- **Retrofit** A best management practicestormwater BMP or land cover installed in a previously developed area to improve stormwater quality or reduce stormwater quantity relative to current conditions.
- **Runoff** That portion of precipitation (including snow-melt) which that travels over the land surface, and also from rooftops, either as sheetflow or as channel flow, in small trickles and streams, into the main water courses.
- **Sediment** Soil, including soil transported or deposited by human activity or the action of wind, water, ice, or gravity.
- **Sedimentation** The deposition or transportation of soil or other surface materials from one place to another as a result of an erosion process.
- Shared best management practice (S—A stormwater BMP)—A best management practice (BMP), or combination of BMPs, providing stormwater management for stormwater conveyed from another site or sites.
- <u>Single- or two-family house</u> An individual house, townhouse, or rowhouse designed and used for occupancy by one or two families. An individual house, townhouse, or rowhouse that has been physically altered for use by more than one or two families is not considered a single-or two-family house.
- Site A tract, lot, or parcel of land, or a combination of tracts, lots, or parcels of land for which development is undertaken as part of a unit, sub-division, or project. The mere divestiture of ownership or control does not remove a property from inclusion in a site.
- Site drainage area Drainage Area (SDA) The area that drains to a point on a site from which stormwater discharges. Throughout this guidance and in accompanying calculator spreadsheets this is referred to as from the drainage area(s) withinsite to a single discharge point or sheet flows from a single area off the limits of disturbance. The use of DA to indicate SDA, or a subset of SDA, is commonsite.
- **Soil** All earth material of whatever origin that overlies bedrock and may include the decomposed zone of bedrock whichthat can be readily excavated by mechanical equipment.
- Soil Erosion and Sediment Control Plan A set of drawings, calculations, specifications, details, and supporting documents related to minimizing or eliminating erosion and off-site sedimentation caused by stormwater on a construction site. It includes information on construction, installation, operation, and maintenance.

- **Soils report** A geotechnical report addressing all soil erosion and sediment control-related soil attributes, including but not limited to site soil drainage and stability.
- Storm sewer A system of pipes or other conduits which that carries or stores intercepted surface runoff, street water, and other wash waters, or drainage, but excludes domestic sewage and industrial wastes.
- Stormwater Flow of water that results from runoff, snow melt runoff, and surface runoff and drainage.
 - Stormwater Fee Discount The program that will allow District water and sewer ratepayers to apply for a discount of up to fifty five percent (55 %) of the DDOE Stormwater Fee that appears on their DC Water bill. To be eligible for a discount, ratepayers must have installed Best Management Practices (BMPs) that retain or prevent stormwater runoff. The program rules are defined in Title 21, Water and Sanitary, Chapter 5, Water Quality and Pollution, of the DCMR sections 557 through 563. Details are provided under a separate and unique DDOE guidance manual.
 - Stormwater management A system to control stormwater runoff with structural and nonstructural best management practicesnonstructural stormwater BMPs, including the following: (a) quantitative control of volume and rate of surface runoff and (b) qualitative control to reduce or eliminate pollutants in runoff.
- Stormwater Management Guidebook (SWMG) The current manual published by DOEDOEE, and available on DOEE's website, containing design criteria, specifications, and equations to be used for planning, design, and construction, operations operation, and maintenance of a site and each best management practice stormwater BMP on the site.
- **Stormwater Management Plan (SWMP)** A set of drawings, calculations, specifications, details, and supporting documents related to the management of stormwater for a site. A SWMP includes information on construction, installation, operation, and maintenance.
- **Stormwater Pollution Prevention Plan (SWPPP)** A document that identifies potential sources of stormwater pollution at a construction site, describes practices to reduce pollutants in stormwater discharge from the site, and may identify procedures to achieve compliance.
- Stormwater Retention Credit (SRC) One gallon (1 gal.) of retention eapacity for one (1) year, as certified by DDOE. An SRC may also be referred to as a RainReC. DOEE.
- **Stormwater Retention Credit ceiling** Maximum retention for which <u>DDOEDOEE</u> will certify an SRC, calculated using the <u>SWRv-Stormwater Retention Volume</u> equation with P equal to 1.7 inches.
- **Stormwater Retention Volume (SWRv)** Volume of stormwater from a site for which the site is required to achieve retention.
- Stripping An activity which that removes or significantly disturbs the vegetative surface cover including clearing, grubbing of stumps and rock mat, and top soil removal.

- **Substantial improvement** A repair, alteration, addition, or improvement of a building or structure, the cost of which equals or exceeds fifty percent (50%) of the market value of the structure before the improvement or repair is started.
- Structural <u>stormwater</u> best management practice A practice engineered to minimize the impact of stormwater runoff, including a bioretention, green roof, permeable <u>paving</u> <u>systempavement</u>, system to capture stormwater for non-potable uses, etc.
- **Supplemental review** A review that <u>DDOEDOEE</u> conducts after the review it conducts for a first <u>re-submission</u> of a plan.
- **Swale** A narrow low-lying stretch of land which that gathers or carries surface water runoff.
- **Total suspended solids (TSS)** The entire amount of organic and inorganic particles dispersed in water. TSS is measured by several methods, which entail measuring the dry weight of sediment from a known volume of a subsample of the original.
- **Waste material** Construction debris, dredged spoils, solid waste, sewage, garbage, sludge, chemical wastes, biological materials, heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial or municipal waste.

W.1 References

ASTM F2898-11, Standard Test Method for Permeability of Synthetic Turf Sports Field Base
Stone and Surface System by Non-confined Area Flood Test Method, ASTM International,
West Conshohocken, PA, 2011, www.astm.org